



# ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

## DETAILED PROJECT REPORT FOR FDR



Name of the Road :-

Construction of road from Verdi to PWD  
Mahadalit Tola Md. Khurshid House of  
Nagendar Paswan in Chaundali Panchayat  
under the Katra Block

|                       |                    |       |     |
|-----------------------|--------------------|-------|-----|
| DISTRICT              | Muzaffarpur        |       |     |
| DIVISION              | Muzaffarpur East-2 |       |     |
| BLOCK                 | Katra              |       |     |
| Damage LENGTH OF ROAD | :                  | 0.025 | KM  |
| CONSTRUCTION COST     | :                  | 3.020 | Lac |

Submitted By :- Executive Engineer  
RWD Work Division Muzaffarpur East-2

GENERAL ABSTRACT

Name of Road Construction of Road from Vardi to P.W.D  
Mahadalit Tola Md. Khurshid House of  
Nagendar Paswan in Chaundali Panchayat  
under the Katra Block

District Muzaffarpur

Block Katra

Division Muzaffarpur East-2

Damage length

| Sl no                          | DESCRIPTION      | AMOUNT (LAKHS)  |
|--------------------------------|------------------|-----------------|
| 1                              | Brick-Bats       | 297792.53       |
| 2                              | Local Sand       | 4224.45         |
| 3                              | HP               | <del>0.00</del> |
| 4                              | Cement Bag       | <del>0.00</del> |
|                                | GARAND SUB TOTAL | 302016.98       |
| TOTAL COST OF PROJECT IN LACS= |                  | 302016.98       |

Rs 3.02 lacs

*[Signature]*  
A.E. 12/11/24

*[Signature]*  
12/11/24

Post facto technical sanctioned for Rs. 3.02 lacs  
(True lacs two thousand) only

*[Signature]* 15/11/24  
Superintending Engineer  
Rural Works Department  
Work Circle, Muzaffarpur  
*[Signature]* 15/11/24

Name of Road-

Construction of Road from Vardi to P.W.D  
Mahadalit Tola Md. Khurshid House of  
Nagendar Paswan in Chaundali Panchayat  
under the Katra Block

Block-

Katra

| Measurement for Suppling of Brick Bats |          |     |               |              |                     |                   |                         |                   |
|----------------------------------------|----------|-----|---------------|--------------|---------------------|-------------------|-------------------------|-------------------|
| S. No                                  | Chainage | Nos | Length<br>(M) | Width<br>(M) | Av.<br>Width<br>(M) | Thicknes<br>s (M) | Av.<br>Thickness<br>(M) | Quantity<br>(Cum) |
| 1                                      |          | 1   | 7.50          |              | 4.1                 |                   | 2.00                    | 61.50             |
| 2                                      |          | 1   | 13.00         |              | 6.0                 |                   | 2.10                    | 163.80            |
| Total (Cum) :-                         |          |     |               |              |                     |                   |                         | 225.30            |

  
Assistant Engineer,  
Rural Works Department,  
Work Sub Division, Katra  
Muzaffarpur East-2

  
Executive Engineer,  
Rural Works Department,  
Work Division,  
Muzaffarpur East-2


Name of Road-

Construction of Road from Vardi to P.W.D  
Mahadalit Tola Md. Khurshid House of  
Nagendar Paswan in Chaundali Panchayat  
under the Katra Block

Block-

Katra

| Measurement for Supplying of Local Sand |          |     |               |              |                     |                   |                         |                   |
|-----------------------------------------|----------|-----|---------------|--------------|---------------------|-------------------|-------------------------|-------------------|
| S. No                                   | Chainage | Nos | Length<br>(M) | Width<br>(M) | Av.<br>Width<br>(M) | Thicknes<br>s (M) | Av.<br>Thickness<br>(M) | Quantity<br>(Cum) |
| 1                                       |          | 1   | 7.50          |              | 4.1                 |                   | 0.15                    | 4.61              |
| 2                                       |          | 1   | 13.00         |              | 6.0                 |                   | 0.15                    | 11.70             |
| Total (Cum) :-                          |          |     |               |              |                     |                   |                         | 16.31             |

  
Assistant Engineer,  
Rural Works Department,  
Work Sub Division, Katra  
Muzaffarpur East-2

  
Executive Engineer,  
Rural Works Department,  
Work Division,  
Muzaffarpur East-2

**Construction of Road from Vardi to P.W.D  
Mahadalit Tola Md. Khurshid House of  
Nagendar Paswan in Chaundali Panchayat**

**Name of Work**

| Sl no        | SDB Sl<br>No | MORD<br>Ref No | Description                                                                                                                                                                                                                               | Unit | QUANTITY | RATE    | AMOUNT<br>(In Rs.) |
|--------------|--------------|----------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----------|---------|--------------------|
| 1            |              |                | Providing brick bats including spreading laying hand packing and compacting with C.I. Hammer in layers not exceeding 75 mm thick including cost of light barriers, danger signals, chowkidar, taxes, royalty etc. all complete job as per | M3   | 225.30   | 1321.76 | 297792.53          |
| 2            |              |                | Supplying, Laying and spreading Local Sand at work site including all cost of Tax and Royalties etc.                                                                                                                                      | M3   | 16.31    | 258.97  | 4224.45            |
| 3            |              |                | Providing and laying sand bags with filling of local sand in empty cement bags, stitching including all cost of Tax and Royalties etc..                                                                                                   | No   | 0.00     | 29.19   | 0.00               |
| 4            |              |                | Providing and Laying Reinforced Cement Concrete Pipe NP3 1000 mm dia as per desing in Single Row                                                                                                                                          | M    | 0.00     | 2240.61 | 0.00               |
| <b>Total</b> |              |                |                                                                                                                                                                                                                                           |      |          |         | <b>302016.98</b>   |

A.E  
12/11/24

A.E  
12/11/24