



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :-

SHAHPUR MOR to DAKRAMA SIMAN

DISTRICT	Muzaffarpur		
DIVISION	Muzaffarpur East-2		
BLOCK	Aurai		
Damage LENGTH OF ROAD	:	0.020	KM
CONSTRUCTION COST	:	0.922	Lac

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-2

GENERAL ABSTRACT

Name of Road SHAHPUR MOR to DAKRAMA SIMAN

District Muzaffarpur

Block Aurai

Division Muzaffarpur East-2

Damage length

Sl no	DESCRIPTION	AMOUNT (LAKHS)
1	Brick-Bats	90329.08
2	Local Sand	1946.16
3	HP	0.00
4	Cement Bag	0.00
	GARAND SUB TOTAL	92275.24
TOTAL COST OF PROJECT IN LACS=		92275.24

Shan
14/11/24
A.E.

Rs 92,300.00
Shan
12/11/24

Post facto technical sanctioned for Rs. 92,300.00
(Rs. Ninety two thousand three hundred) only

Shan 11/11/24
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur
Shan 15/11/24

Name of Road-

SHAHPUR MOR to DAKRAMA SIMAN

Block-

Aurai

Measurement for Supplying of Brick Bats								
S. No	Chainage	Nos	Length (M)	Width (M)	Av. Width (M)	Thicknes s (M)	Av. Thickness (M)	Quantity (Cum)
1		1	3.00		1.50		1.40	6.30
2		1	3.00		4.00		1.40	16.80
3		1	3.00		1.30		1.20	4.68
4		1	3.50		3.80		1.20	15.96
5		1	4.10		4.00		1.50	24.60
Total (Cum) :-								68.34



Assistant Engineer,
Rural Works Department,
Work Sub Division, Aurai
Muzaffarpur East-2




Executive Engineer,
Rural Works Department,
Work Division,
Muzaffarpur East-2

Name of Road- SHAHPUR MOR to DAKRAMA SIMAN

Block- Aurai

Measurement for Supplying of Local Sand								
S. No	Chainage	Nos	Length (M)	Width (M)	Av. Width (M)	Thickness (M)	Av. Thickness (M)	Quantity (Cum)
1		1	3.00		1.50		0.15	0.68
2		1	3.00		4.00		0.15	1.80
3		1	3.00		1.30		0.15	0.59
4		1	3.50		3.80		0.15	2.00
5		1	4.10		4.00		0.15	2.46
Total (Cum) :-								7.52


Assistant Engineer,
Rural Works Department,
Work Sub Division, Aurai
Muzaffarpur East-2


Executive Engineer,
Rural Works Department,
Work Division,
Muzaffarpur East-2

Name of Work

SHAHPUR MOR to DAKRAMA SIMAN

Sl no	SDB Sl No	MORD RefNo	Description	Unit	QUANTITY	RATE	AMOUNT (In Rs.)
1			Providing brick bats including spreading laying hand packing and compacting with C.I. Hammer in layers not exceeding 75 mm thick including cost of light barriers, danger signals, chowkidar, taxes, royalty etc. all complete job as per specification and direction of E/I including carriage cost of bricks	M3	68.34	1321.76	90329.08
2			Supplying, Laying and spreading Local Sand at work site including all cost of Tax and Royalties etc.	M3	7.52	258.97	1946.16
3			Providing and laying sand bangs with filling of local sand in empty cement bags, stitching including all cost of Tax and Royalties etc..	No	0.00	29.19	0.00
4			Providing and Laying Reinforced Cement Concrete Pipe NP3 1000 mm dia as per desing in Single Row	M	0.00	2240.61	0.00
Total							92275.24

Shahpur
A.E

12.11.21
Shahpur