



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

BIHAR RURAL ROADS PROJECT

Bihar Rural Road Development Agency (BRRDA)

DETAILED PROJECT REPORT

YEAR 2024-25

FDR

VOLUME- I

STATE :- BIHAR
DISTRICT :- Sitamarhi
BLOCK :- Belsand

NAME OF ROAD :- Detail Estimate For Restoration of L084-Hasaur PMGSY Path To Siropatti SC North Tola (VR67)

TOTAL LENGTH OF ROAD :- 2.331 KM

Actual length of Damage Road 0.181 km

TOTAL COST OF CONSTRUCTION :- Rs. 0.990 Lacs

TOTAL COST OF PROJECT :- Rs. 0.990 Lacs

SUBMITTED BY:
EXECUTIVE ENGINEER
RWD (W) DIVISION, BELSAND
SITAMARHI

INSPECTION REPORT FOR MOTORABLE WORK

Name of PIUs :- EE, RWD, Works Division, Beland

Name of Block / Road :- LO84 - Hasaur PMGSY Path to Sirapatti
Sc North Tola (NR67) under beland Block

A. For Road

1. Damage location / Chainage :- 26.394443, 25.379606

2. Damage Length :- 0.180 km

3. Nature of Damage (Length Wise)

(i) Breach :- 0.180 km

(ii) Crust Damage :-

(iii) Only Flank Damage

Whether Traffic Fully / Partially obstructed :- Fully obstructed

4. Details of Restoration :-

(i) Material Being Used in Restoration :- Brick Bats, Rabbish, Bamboo

(ii) Equipment / Tools Being used in Restoration Work :- JCB, Tractor, Roller

(iii) Restored Length

In open Area :- 0.180 km

In Habitation Area :-

(iv) If Restoration Work Done in habitation Area give Reason :-

B. For Bridge (Size of Bridge / Culvert)

(1) Damage Location / Chainage :-

(2) No. of Span Damage :-

(3) Length of Span :-

(4) Nature of Damage (Pier/Abutment/
Wing Wall/ Approach Road Damage) :-

(5) Details of Restoration :-

(i) Material Being Used in Restoration :-

(ii) Equipment / Tools Being used in Restoration Work :-

(iii) Restored Length

Overall Grade of restoration Work (Satisfactory/Unsatisfactory) :- Satisfactory


Signature of Inspector
Executive Engineer
Rural Works Department
Works Division, Sheohar

तकनीकी प्रतिवेदन


पथ का नाम :- LO84-Hasaur PMGSY Path to Sirpatti
प्रखंड :- Belsand
योजना शीर्ष :- 2245/FDR
पथ की लंबाई :- 2.331 km
क्षतिग्रस्त पथांश की लंबाई :- 0.181 km
प्राक्कलित राशि :- 0.990 Lacs
प्राधिकार :-

प्रस्तुत प्राक्कलन शीर्ष 2245/FDR अंतर्गत LO84-Hasaur PMGSY Path to Sirpatti Path to Sirpatti SC North Tola (VR 67) पथ के वर्ष 2024 में आये बाढ़ से क्षतिग्रस्त हो जाने के कारण यातायात को चालू (Motorable) रखने के लिए कुल रू०- 0.990 Lacs मात्र का तैयार किया गया है।

उक्त पथ के द्वाराको एकल संपर्कता प्राप्त है। बागमति नदी का बाँध काटने के फलस्वरूप पथ में बहुत स्थलों पर कटाव हुआ था जिसके कारण उक्त बसावट तक पहुँचना संभव नहीं हो पा रहा था। अतएव यातायात को अविलम्ब बहाल करने हेतु क्षतिग्रस्त पथांश में Brick Bats एवं Rabbish का उपयोग कर आकस्मिक मरम्मत कार्य करते हुए पथ को चालू किया गया है। विभागीय निदेशानुसार किये गए कार्य का Geotagged फोटोग्राफ एवं ड्रोन विडियोग्राफी MIS पर Upload किया गया है। पथ के पुनर्स्थापन कार्य का प्राक्कलन कार्य स्थल के अनुरूप है एवं तकनीकी अनुमोदन अपेक्षित है।


14/11/24
कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा.....बेलसंड


14/11/24
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल.....बेलसंड


14/11/24
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बेलसंड

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :

Detail Estimate For Restoration of ~~Hasaur to Daryapur Road~~

LO84 - Hasaur PMCSY

Path to sirpatti Se North Tola (VR67)

DISTRICT

Sitamarhi

BLOCK

Belsand

LENGTH OF APPROACH ROAD

2.331 KM

LENGTH OF EFFECTED ROAD

0.181

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Supplying fitting and fixing in position split Bamboo woven chanchary	0.2290
2	Labour for cutting 62mm to 75mm dia bamboo piles in size	0.0000
3	Labour for cutting 62mm to 75mm dia bamboo Runner	0.0000
4	Supplying of nariyal coir	0.1824
5	Providing fitting and fixing split bamboo woven chachari	0.0000
6	Labour filling empty cement bag with local sand, stitching the bags and placing	0.0000
7	Sand filling in foundation trench	0.0000
8	Providing and Laying Of Brick Bat obtained from chimney	0.5311
9	Providing Rabbish including spreading laying	0.0479
	Sub Total:--	0.990
	TOTAL COST OF PROJECT IN LACS =	0.990

J.E

A.E

E.E

T/S (provisional) is accorded with for Rs 99,000 (Ninety thousand only)

अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल सीतामढ़ी
Page 1 15/11/2024
15-11-24

Detail Estimate For Restoration of L084-Hasaur PMGSY Path To Siropatti SC North Tola (VR67)

Sl.no	Name Of work	NO	Lengt h in M	Breadt h in M	Depth in M	Total Length		Amount in RS
						Quantity	Unit Rate	
1	Providing bricks bats including spreading laying hand packing and compacting with C.I hammer in layers not exceeding 75 mm thick including cost of light barrier,danger signals,chowkidar tax royalty etc all complate job as per specification and direction of E/I including carriage cost of bricks							
		1 x	10.20 x	0.50 x	0.60 =	3.06	M3	
		1 x	11.80 x	0.60 x	0.70 =	4.96	M3	
		1 x	8.00 x	0.45 x	0.80 =	2.88	M3	
		1 x	7.50 x	0.40 x	0.50 =	1.50	M3	
		1 x	9.20 x	0.45 x	0.45 =	1.86	M3	
		1 x	9.70 x	0.45 x	0.60 =	2.62	M3	
		1 x	15.00 x	0.55 x	0.80 =	6.60	M3	
		1 x	10.20 x	0.45 x	0.45 =	2.07	M3	
		1 x	14.60 x	0.45 x	0.55 =	3.61	M3	
		1 x	18.60 x	0.40 x	0.65 =	4.84	M3	
		1 x	14.10 x	0.40 x	0.60 =	3.38	M3	
		1 x	8.00 x	0.20 x	0.70 =	1.12	M3	
		1 x	25.60 x	0.65 x	0.50 =	8.32	M3	
		1 x	18.00 x	0.70 x	0.55 =	6.93	M3	
		TOTAL				53.75	M3	
	Brick Bats Quantity	80% x	53.75	=		43.00	M3	1235.23
2	Providing roadbits including spreading laying hand packing and compacting with C.I hammer in layers not exceeding 75 mm thick including cost of light barrier,danger signals,chowkidar tax royalty etc all complate job as per specification and direction of E/I							
	(20% Of items no 1)	20% x	53.75	=		10.75	M3	445.84
3	Supplying fitting and fixing in position spior Bamboo woven chanchary with 20SWG G.I etc all complete job (75mm dia and 6 meter to 8 meter Long) all complate job as per specification and direction of E/I							
	Pile	62	3.50	=		217.00	m	
		54	3.50	=		189.00	m	
		48	3.50	=		168.00	m	
		9	3.50	=		31.50	m	
						605.50		
	runner	3	115.00	=		345.00	m	32.765
	Supplying of Nariyal coir							19839.2075
								8.86
								3056.7
		1	35.00	=		35.00	kg	521.00
		TOTAL						18235.00
		Total						Rs 99035.35
								Rs 99035.35
								Say Rs 99035.00

[Signature]
J.E
RWD Belsand

[Signature]
A.E
RWD Belsand

[Signature]
E.E
RWD Belsand

Rural Works Department, Govt. of Bihar



Welcome:-PIUBelsand
Wing:-CE-6,Darbhanga
Circle:-Sitamarhi
Division:-Belsand
No Of Visit:-46

Home Road-Cutting Request User,Menu and Profile Entry Forms Project Views MIS Reports QMC Reports Scheduled List Zone Reports

Schedule Change Request Contractors Debar Class 1 Road Format Time Extension Contractors Black List NEW MR Contractor Revoke

Flood/Rain Damage Roads Poorak Core Network Crash Inspection Contractor Emergent Repair User Registration NEW MR Allotment Road / Bridge Allotment

NEW MR Observation Offline Inspection Left Habitation Survey Routine Inspection Bridge Aproach CM Janta Darbar POP Inauguration Tools Inspection

DPR RoadPavement BRRMS Report Review Report Road Cutting Bridge Details NEWMR INS. Report

Flood/Rain Damaged Road/Bridge Report

Chief Engineer: CE-6,Darbhanga

Circle Sitamarhi

Division Belsand

FDR Fin Year 2024-25

Show Data

Download in Excel

Details of Road & Bridge

11/15/24, 3:57 PM

8	CE- 6,Darbhanga	Sitamari	Sitamari	Belsand	Belsa nd	Bagmati Bandh to Ramni Pmg sy Road	MMGSY- NDB(BRICS)-I	Completed	Yes	0.4	0.400	20.00	The road surface is fully submerged. Road & Flank Damage	2024-25
9	CE- 6,Darbhanga	Sitamari	Sitamari	Belsand	Belsa nd	L082- Bharwari Ghat To Maulanagar West Tola (VR65)	PMGSY	Completed	Yes	0.684	0.430	15.00	The road surface is fully submerged. Road & Flank Damaged	2024-25
10	CE- 6,Darbhanga	Sitamari	Sitamari	Belsand	Belsa nd	L084-Hasaur PMGSY Path To Siropatti SC North Tola (VR67)	PMGSY	Completed	Yes	2.331	2.000	35.00	The road surface is fully submerged. Road & Flank Damage	2024-25
11	CE- 6,Darbhanga	Sitamari	Sitamari	Belsand	Belsa nd	MADHCOL - JHAFARPUR	PMGSY	Completed	Yes	1.14	1.100	32.00	The road surface is fully submerged. Road & Flank Damaged	2024-25
12	CE- 6,Darbhanga	Sitamari	Sitamari	Belsand	Belsa nd	MAHOLANGER MOTHERSA BHANDH - MAHOLANGER REO ROAD	PMGSY	Completed	Yes	1.11	1.100	10.00	Road & Flank Damaged.	2024-25
13	CE- 6,Darbhanga	Sitamari	Sitamari	Belsand	Belsa nd	PACHNOUR - NANAURA	PMGSY	Completed	Yes	3.19	2.800	45.00	The road surface is fully submerged. Road & Flank Damage	2024-25
14	CE- 6,Darbhanga	Sitamari	Sitamari	Belsand	Belsa nd	SIROPATTI - BATUA VIA	PMGSY	Completed	Yes	7.648	2.000	55.00	Road & Flank Damaged	2024-25
15	CE- 6,Darbhanga	Sitamari	Sitamari	Belsand	Belsa nd	SUKHI PRIMARY SCHOOL - KHARKA BHAND	PMGSY	Completed	Yes	0.66	0.625	25.00	The road surface is fully submerged. Road & Flank	2024-25