

तकनीकी प्रतिवेदन

पथ का नाम:- los2 - Bhargawn to mustai

प्राक्कलित राशि:-

प्रमंडल का नाम:-झंझारपुर।

अंचल का नाम:-मधुबनी।

योजना का नाम:-F.D.R 2245


प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक में los2 - Bhargawn to mustai पथ के लिए तैयार किया गया है जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/जलजमाव Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था। फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़े/मिट्टी/स्थानीय बालु से भरकर उसका संपीडन किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवेदक लाभांश छोड़कर) पर तैयार किया गया है। यह कार्य लोकहित एवं जनहित में अत्यावश्यक है। अतः इस प्राक्कलन की स्वीकृति अपेक्षित है।


कनीय अभियंता


सहायक अभियंता


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, झंझारपुर।

INSPECTION REPORT FOR MOTORABLE WORK

Name of PIUs :- Ruid, Jharkapur	
Name of Block/Road :- Madhepur / 652 - Bhargawanto mustan	
A. For Road	
1. Damage Location/Chainage :- 640m, 1500m	
2. Damage Length :- 119m	
3. Nature of Damage (Length Wise)	(i) Breach :- 119m
	(ii) Crust Damage :-
	(iii) Only Flank Damage :-
whether traffic fully/Partially obstructed :- Fully	
4. Details of Restoration :-	
(i) Material Being Used in Restoration :- Brick Vats	
(ii) Equipment/Tools Being Used in Restoration Works :- JCB & Tractor.	
(iii) Restored Length	In open Area :- open
	In habitation Area :-
(iv) If Restoration work done in habitation Area give Reason :-	
B. For Bridge (Size of Bridge/Culvert)	
(1) Damage Location/Chainage :-	
(2) No. of Span Damage :-	
(3) Length of Span :-	
(4) Nature of Damage (Pier/Abutment/Wing Wall/Approach Road Damage) :-	
(5) Details of Restoration :-	
(i) Material Being Used in Restoration :-	
(ii) Equipment/Tools Being Used in Restoration Works :-	
(iii) Restored Length :-	
Overall Grade of Restoration work (Satisfactory/Unsatisfactory) :-	

24/11/24
J.E

24/11/24
Executive Engineer
 Rural Works Department
 Works Division, Jaynagar
 (Official Seal)

General Abstract of Cost

Division- Jhanjharpur

Block- Madhepur

Name of Road- L052- Bhargawan to Mushahari

1	2	3	4	5	6
Si. No.	Name of item	Unit	Quantity as per measurement	Rate	Amount
1	Providing and filling brick bats in damaged embankment and crust including cost of brick bats and labour, all complete job as per specification.	cum	422.64	1239.00	523650.96
Rs.-					523650.96
Add 18% GST Rs.-					0.00000
Add 1% L.C. Rs.-					0.00000
Add S.F. Rs.- (col.4*900.00@10%)					0.00000
Total Rs.-					523650.96
Say Rs.-					523651.00

Samir
08/11/24
Junior Engineer
RWD works section

Assistant Engineer
RWD works sub div.

Qul
15/11/24
Executive Engineer
RWD Jhanjharpur

असंख्य संस्थापक अभिभाग, ग्रामीण कार्य विभाग
की प्रमत्तन - जमाना के द्वारा दिनांक :- 14.11.2024
के प्राप्त और प्रत्येक के जानाई में -

Technically Sanctioned (provisional) for
Rs. 523651.00 (Rupees Five Lakh twenty
three thousand six hundred fifty one only)

ANIL
15/11/24
Superintending Engineer:
R.W.D. Works Circle
Madhubani

Qul
15/11/24
E.O.

ANIL
15/11/24
TA

Measurement of restoration of crust and embankment with brick bats

FDR 2024-25

Name of Road:- L052- Bhargawan to Mushahari

Division- Jhanjharpur

Block- Madhepur

1	2	3	4	5	6	7
CH. In km	Nos.	Length(m)	Width(m)	Avg. Width	Thickness	Quantity(cum)
0.64	3	30	$(4.2+3.8+4+3.8+3.95)/5$	3.95	$(0.4+0.6+1.45+0.8+1.25)/5$	319.95
0.64	1	14	$(4.2+3.8+4+3.8+3.95)/5$	3.95	$(0.4+0.6+1.45+0.8+1.25)/5$	49.77
1.5	1	15	$(5+4.8+4)/3$	4.6	$(0.5+0.8+1.0)/3$	52.923
						422.643


06/11/2024
Junior Engineer

RWD works Section

Assistant Engineer
RWD works Sub Div.


06/11/2024

Executive Engineer
RWD Jhanjharpur

Analysis of Rates (FORMAT F8)

Sl. No.	SDB Sl. No.	MORD Ref No.	DESCRIPTION	Unit	Quantity	Rate	Amount in Rs
1	6.6.1 WRD Bihar		Labour for laying dry graded Jhama Khoa or stone filter under Brick Pitching or Boulder Pitching in slope or apron including light ramming etc.all complete as per approved design,specification and Direction of E/I Unit = Per Cum Taking output = 2.832 Cum a) Labour Mazdoor (Unskilled) b) Overheads @ 2.5 % Cost for 2.832 cum Rate per cum =	Nos	3.00	320.00	960.00 0.00 960.00 338.98
			Rate Per Km.	Cum			339.00
2	1.40	RCD	Cost of Haulage excluding Loading & Unloading Haulage of materials by tractor excluding cost of loading, unloading and stacking. Unit = t.km Taking output 3.6 t load and lead 10 km =36 t.km Case-I : Surfaced Road Speed with load: 15 km per hour Speed while returning empty: 25 km per hour a) Machinery Tractor 3.6 t capacity Time taken for onward Haulage with load Time taken for Empty return trip b) Overheads @ 2.5 % Cost for 36 t-km = a+b+c Rate per cum = (a+b) /36	hour hour	0.40 0.29	550.00 550.00	220.00 159.50 0.00 379.50 10.54
			Rate Per Km.	Cum			10.50
3			Cost of Haulage excluding Loading & Unloading Haulage of materials by tractor excluding cost of loading, unloading and stacking. Unit = t.km Taking output 3.6 t load and lead 10 km =36 t.km Case-II: Unsurfaced Gravel Road. Speed with load: 12 km per hour Speed while returning empty: 20 km per hour a) Machinery Tractor 3.6 t capacity Time taken for onward Haulage with load Time taken for Empty return trip b) Overheads @ 2.5 % Cost for 36 t-km = a+b+c Rate per cum = (a+b) /36	hour hour	0.833 0.500	550.00 550.00	458.15 275.00 0.00 733.15 7.33
			Rate Per Km.	Cum			7.30
4			Cost of Haulage excluding Loading & Unloading Haulage of materials by tractor excluding cost of loading, unloading and stacking. Unit = t.km Taking output 3.6 t load and lead 10 km =36 t.km Case-III : Katcha Track and Track in River Bed/Nallah Bed and Choe Bed. Speed with load: 10 km per hour Speed while returning empty: 15 km per hour a) Machinery Tractor 3.6 t capacity Time taken for onward Haulage with load Time taken for Empty return trip b) Overheads @ 2.5 % Cost for 36 t-km = a+b+c Rate per cum = (a+b) /36	hour hour	1.000 0.667	550.00 550.00	550.00 366.85 0.00 916.85 9.17
			Rate Per Km.	Cum			9.20

Analysis of Rates (FORMAT F8)

Sl. No.	SDB Sl. No.	MORD Ref No.	DESCRIPTION	Unit	Quantity	Rate	Amount in Rs
5	1.10	RCD	Loading and Unloading of Stone Boulder/Stone aggregates/Sand/Kanker/Moorum. Placing tractor at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip Unit = cum Taking output = 2.25 cum Time required for i) Positioning of tractor at loading point ii) Loading by front end loader 1 cum bucket capacity @ 25 cum per hour Total a) Labour Mate Mazdoor for loading and unloading a) Machinery Tractor 3.6 t capacity Front end-loader 1 cum bucket capacity @ 25 cum/hour Overheads @ 2.5 % Cost for 2.25 cum = a+b+c Rate per cum = (a+b+c) / 2.25				
				1 Min			
				5 Min			
				6 Min			
			a) Labour	day	0.03	434.00	13.02
			Mate	day	0.72	320.00	230.40
			Mazdoor for loading and unloading				
			a) Machinery				
			Tractor 3.6 t capacity	hour	0.10	550.00	55.00
			Front end-loader 1 cum bucket capacity @ 25 cum/hour	hour	0.083	1220.00	101.26
			Overheads @ 2.5 %				0.00
			Cost for 2.25 cum = a+b+c				399.68
			Rate per cum = (a+b+c) / 2.25				177.64
			Unloading will be done manually			say	177.64
6		A	Supplying for Brick Bats (With OH) Basic Rate of Brick Bat Over Heads @ 2.5 % Total Cost Surface Lead Katcha Track and Track in River Bed/Nallah Bed and Choe Bed. Factor (3.6/2.25)	Cum	1.00	900.00	900.00
							0.00
							900.00
		B	Carriage with OH (1.6 x 7 x 10.80) + (1.6 x 1 x 9.40) + 182.08	KM	7		
				KM	1		
				Cum	1.6		
		C	Cost fo Labour for pitching and light Ramming as per WRD SOR 6.6.1 (With OH)				0.00
							339.00
			Total Cost (A+B+C)				1239.00
1	9.30	1100	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row Providing and laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material in single row 1000 MM DIA Unit =m Taking output =7.5 m (3 pipes of 2.5 m length each) a) Material I) Sand at site ii) Cement at site iii) RCC pipe NP 3 pipe including collar at site b) Labour Mate				
(II)				cum	0.040	3103.37	124.13
				ton	0.030	6185.96	185.58
				m	7.50	5100.00	38250.00
				day	0.09	434.00	39.06
				day	0.25	400.00	100.00
			Mason (1st class)				
			Mazdoor (Unskilled)	day	2.000	320.00	640.00
			Overheads @ 2.5 %				0.00
			d) Contractor's profit @ 10% on (a+b+c)				0.00
			Cost for 7.5m = (a+b+c+d)				39338.77
			Rate per m = (a+b+c+d)/7.5				5245.17
			Total Cost	m			5245.17