



# ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

## DETAILED PROJECT REPORT FOR FDR



Name of the Road :- Shivdiyal Rai Khet to Middle School  
Mushari Tola Hue Ambdker Nagar

|                       |                    |       |     |
|-----------------------|--------------------|-------|-----|
| DISTRICT              | Muzaffarpur        |       |     |
| DIVISION              | Muzaffarpur East-2 |       |     |
| BLOCK                 | Aurai              |       |     |
| Damage LENGTH OF ROAD | :                  | 0.050 | KM  |
| CONSTRUCTION COST     | :                  | 4.872 | Lac |

Submitted By :- Executive Engineer  
RWD Work Division Muzaffarpur East-2

**GENERAL ABSTRACT**

Name of Road      Shivdityal Rai Khet to Middle School  
District            Mushari Tola Hue Ambuker Nagar  
Block                Muzaffarpur  
Division            Aurai  
Division            Muzaffarpur East-2  
Damage length

| Sl no                          | DESCRIPTION      | AMOUNT (LAKHS)  |
|--------------------------------|------------------|-----------------|
| 1                              | Brick-Bats       | 480139.89       |
| 2                              | Local Sand       | 7157.67         |
| 3                              | HP               | 0.00            |
| 4                              | Cement Bag       | <del>0.00</del> |
|                                | GARAND SUB TOTAL | 487297.57       |
| TOTAL COST OF PROJECT IN LACS= |                  | 487297.57       |

*Sham*  
12/11/24  
A.E

B. 4.87 lakhs  
*[Signature]*  
12/11/24


Post facto technical sanctioned for B. 4.87 lakhs  
i.e. four lakhs Eighty seven thousand only

*[Signature]* 11/11/24  
Superintending Engineer  
Rural Works Department  
Work Circle: Muzaffarpur  
15/11/24

Name of Road- Shivdiyal Rai Khet to Middle SchoolMushari Tola Hue Ambdker Nagar  
Block- Aurai

| Measurement for Suppling of Brick Bats |          |     |               |              |                     |                   |                         |                   |
|----------------------------------------|----------|-----|---------------|--------------|---------------------|-------------------|-------------------------|-------------------|
| S. No                                  | Chainage | Nos | Length<br>(M) | Width<br>(M) | Av.<br>Width<br>(M) | Thicknes<br>s (M) | Av.<br>Thickness<br>(M) | Quantity<br>(Cum) |
| 1                                      |          | 1   | 21.00         |              | 3.76                |                   | 1.80                    | 142.13            |
| 2                                      |          | 1   | 27.00         |              | 3.90                |                   | 2.10                    | 221.13            |
| Total (Cum) :-                         |          |     |               |              |                     |                   |                         | 363.26            |

  
Assistant Engineer,  
Rural Works Department,  
Work Sub Division, Aurai  
Muzaffarpur East-2

  
Executive Engineer,  
Rural Works Department,  
Work Division,  
Muzaffarpur East-2



Name of Road-

Shivdiyal Rai Khet to Middle SchoolMushari Tola Hue Ambdker Nagar

Block-

Aurai

| Measurement for Supplying of Local Sand |          |     |               |              |                     |                   |                         |                   |
|-----------------------------------------|----------|-----|---------------|--------------|---------------------|-------------------|-------------------------|-------------------|
| S. No                                   | Chainage | Nos | Length<br>(M) | Width<br>(M) | Av.<br>Width<br>(M) | Thicknes<br>s (M) | Av.<br>Thickness<br>(M) | Quantity<br>(Cum) |
| 1                                       |          | 1   | 21.00         |              | 3.76                |                   | 0.15                    | 11.84             |
| 2                                       |          | 1   | 27.00         |              | 3.90                |                   | 0.15                    | 15.80             |
| Total (Cum) :-                          |          |     |               |              |                     |                   |                         | 27.64             |

*[Signature]*  
12/11/24

Assistant Engineer,  
Rural Works Department,  
Work Sub Division, Aurai  
Muzaffarpur East-2

*[Signature]*  
12/11/24

Executive Engineer,  
Rural Works Department,  
Work Division,  
Muzaffarpur East-2

Name of Work

Shivdiyal Rai Khet to Middle School[Mushari Tola Hue Ambdker Nagar

| Sl no | SDB Sl No | MORD RefNo | Description                                                                                                                                                                                                                                                                                                    | Unit | QUANTITY | RATE    | AMOUNT<br>(In Rs.) |
|-------|-----------|------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----------|---------|--------------------|
| 1     |           |            | Providing brick bats including spreading laying hand packing and compacting with C.I. Hammer in layers not exceeding 75 mm thick including cost of light barriers, danger signals, chowkidar, taxes, royalty etc. all complete job as per specification and direction of E/I including carriage cost of bricks | M3   | 363.26   | 1321.76 | 480139.89          |
| 2     |           |            | Supplying, Laying and spreading Local Sand at work site including all cost of Tax and Royalties etc.                                                                                                                                                                                                           | M3   | 27.64    | 258.97  | 7157.67            |
| 3     |           |            | Providing and laying sand bangs with filling of local sand in empty cement bags, stitching including all cost of Tax and Royalties etc..                                                                                                                                                                       | No   | 0.00     | 29.19   | 0.00               |
| 4     |           |            | Providing and Laying Reinforced Cement Concrete Pipe NP3 1000 mm dia as per desing in Single Row                                                                                                                                                                                                               | M    | 0.00     | 2240.61 | 0.00               |
| Total |           |            |                                                                                                                                                                                                                                                                                                                |      |          |         | 487297.57          |

Sham  
12/11/24  
A.E

Shivdiyal Rai Khet to Middle School[Mushari Tola Hue Ambdker Nagar