

तकनीकी प्रतिवेदन

पथ का नाम

:- ~~Sahiya~~ Sahiya 989 thana kaithi to kharbani to 19

प्रखंड

:- Bathnaha.

योजना शीर्ष

:- MM457.

पथ की लंबाई

:- 2.55 KM.

क्षतिग्रस्त पथांश की लंबाई

:- 19.00 M.

प्राक्कलित राशि

:- 1,78,069 = ₹

प्राधिकार

:-

प्रस्तुत प्राक्कलन शीर्ष 2245/FDR अंतर्गत Sahiya 989 thana kaithi to kharbani to 19. पथ के वर्ष 2024 में आये बाढ़ से क्षतिग्रस्त हो जाने के कारण यातायात को चालू (Motorable) रखने के लिए कुल ₹0- 1,78,069 = ₹ मात्र का तैयार किया गया है।

उक्त पथ के द्वारा को एकल संपर्कता प्राप्त है। बागमति नदी का बाँध काटने के फलस्वरूप पथ में बहुत स्थलों पर कटाव हुआ था जिसके कारण उक्त बसावट तक पहुँचना संभव नहीं हो पा रहा था। अतएव यातायात को अविलम्ब बहाल करने हेतु क्षतिग्रस्त पथांश में Brick Bats एवं Rabbish का उपयोग कर आकस्मिक मरम्मत कार्य करते हुए पथ को चालू किया गया है। विभागीय निदेशानुसार किये गए कार्य का Geotagged फोटोग्राफ एवं ड्रोन विडियोग्राफी MIS पर Upload किया गया है। पथ के पुनर्स्थापन कार्य का प्राक्कलन कार्य स्थल के अनुरूप है एवं तकनीकी अनुमोदन अपेक्षित है।

R Patel
15/11/24

कनीय अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशाखा Bathnaha.

Himes
15/11/24

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल Bathnaha.

Ani
15/11/24

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमंडल, सीतामढ़ी

DETAILED ESTIMATE FOR F.D.R.

General Abstract of Cost

Name of Road

Length of Road

Block

DISTRICT

: SAHIYARA THANA KAITHAHI TO KHARBANI TOLA
: 2.500
: BATHNAHA
: SITAMARHI

S.No.	Particulars	Total Cost (in Lakh)
1	Total Cost for Motorable Roads	1,78,069.00 1,87,042.00
	Total Cost of Road Repair	1,78,069.00 1,87,042.00
	Say	1,78,069.00 1,87,042.00

R Patel
14/11/24
JE JE
RWD BATHNAHA

Vino
15/11/2024
AE
RWD BATHNAHA

Ani
15/11/24
EE
RWD Sitamarhi

T/S (Provisional) is accorded for Rs. 1,78,069.00
(Rupees one Lakh Seventy eight thousands sixty nine
only).

Vino
15/11/2024
अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंशल सीतामढ़ी
Vishud
15-11-24

Schedule of Quantity

NAME OF WORK ;SAHIYARA THANA KAITHHI TO KHARBANI TOLA

BATHNAKA
Block Sonbarsa

S.No	DESCRIPTION OF ITEMS	QTY	UNIT	RATE	AMOUNT
1	Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to acheive required density with all complete as per the direction of engineer in charge.	125.97			0.00
	Less 20% for Voids	-25.19			
		100.78	Cum	1626.71	163933.73
2	Providing Rabbishs including spreading laying hand packing and compacting with C.I hammer in layers not exceeding 75 mm thick including cost of light barrier,danger signals,chowkidar tax royalty etc all complite job as per specification and direction of E/I				
	Taking 20% of Brick Qty for Rabbish	25.19	Cum	561.16 560.00	14135.62 14108.64
3	Drone video recording(3 times)	3.00	Nos	3000.00	9000.00

Total ~~1,87,042.37~~
Say ~~1,87,042.00~~

~~1,78,069.00~~

Rpapee
14/11/24
JE

Vinod
15/11/2024
AE

Ans
15/11/24
EE

Details of Measurement of ditches filled by brick bats and rabbish

NAME OF WORK ;SAHIYARA THANA KAITHHI TO KHARBANI TOLA

Record ENTRY

	Length (in meter)	Width(in meter)	Depths (in meter)	Volume (Cum)
AT CH-1000M	19.0	5.1	1.30	125.97
Total				125.97 (Cum)

Total (in Cum) 125.97 Cum

Rpall
15/11/24
JE

Vimal
15/11/2024
A.E

Ami
15/11/24



Welcome:- Seditamathi
Wing:- CE-6, Darbhanga
Circle:- Sitamarhi
Division:- HQ
No Of Visit:-

Rural Works Department, Govt. of Bihar

Home Road-Cutting Request User Menu and Profile Entry Forms Project Views MIS Reports QMC Reports Scheduled List Zone Reports Contractors Debar Time Extension
NEW MR Contractor Revoke Flood/Rain Damage Roads Crash Inspection Contractor NEW MR Allotment Road / Bridge Allotment NEW MR Observation Offline Inspection
Left Habitation Survey Routine Inspection Bridge Approach CM Janta Darbar POP Inauguration DPR Road Pavement BRIMS Report Review Report Bridge Details
NEWMR INS. Report

Flood/Rain Damaged Road/Bridge Report

Chief Engineer: CE-6, Darbhanga

Circle Sitamarhi

Division Sitamarhi

FDR Fin Year 2024-25

Show Data Download in Excel

Details of Road & Bridge															Start Po		
Sino	Wing	Circle	District	Division	Block	Road/Bridge Name	Scheme Name	Status (Comp./Ongoing)	Is Maintenance (Y/N)	Length (In Km)	Approximate Damage Length During Flood(In Km)	Restoration Amount (In Lakh)	Remarks	FDR Fin Year	Type (R/B)	Latitude	Lc
1	CE-6,Darbhanga	Sitamarhi	Sitamarhi	Sitamarhi	Bathn aha	L021 -Mahadewa to Mahadewa (VR3)	PMGSY	Completed	Yes	2.06	0.060	5.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.724909	85
2	CE-6,Darbhanga	Sitamarhi	Sitamarhi	Sitamarhi	Bathn aha	PMGSY path belahi jayram to belahi	MMGSY[SC]	Completed	Yes	0.95	0.030	5.00	NO NEED FOR TEMPORARY	2024-25	Road	26.705395	85

3	CE- 6, Darbhanga	Sitamarni	Sitamarni	Sitamarni	Bathna	chamar tola WEST sahyara thana katahi path to kharban tola	MMGSY[Gen]	Completed	Yes	2.55	0.050	20.00	RESTORATION O/E/FLOW AND OLD CULVERT COLLAPSE at ch 1km	2024-25	Road	26.710942	8
4	CE- 6, Darbhanga	Sitamarni	Sitamarni	Sitamarni	Bathna	PMGSY Path Singhorehiya To Mahadevmath Singrahiya	MMGSY[Gen]	Completed	Yes	1.175	0.070	5.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.719577	8
5	CE- 6, Darbhanga	Sitamarni	Sitamarni	Sitamarni	Bathna	pmgsy path narha mahadev math to gaachi tola narha	MMGSY[SC]	Completed	Yes	2.1	0.030	4.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.674602	8
6	CE- 6, Darbhanga	Sitamarni	Sitamarni	Sitamarni	Bathna	pmgsy path trikauliya to kumhar tola trikauliya	MMGSY[SC]	Completed	Yes	1.6	0.020	6.00	over flow and cut at 2 diff ch	2024-25	Road	26.667982	8
7	CE- 6, Darbhanga	Sitamarni	Sitamarni	Sitamarni	Bathna	Narha Brahm Sthan to Musahari Naya Tola	MMGSY[SC]	Completed	Yes	3.7	0.170	12.00	cut at 3 diff ch and overflow	2024-25	Road	26.665319	8
8	CE- 6, Darbhanga	Sitamarni	Sitamarni	Sitamarni	Bathna	pmgsy path to gajharwa rajpoo tola gaaharwa	MMGSY[Gen]	Completed	Yes	1	0.020	2.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.710617	8
9	CE- 6, Darbhanga	Sitamarni	Sitamarni	Sitamarni	Dumra	N.H-77 Nahar Chowk To Rajanager(Kabristan Tola)	MMGSY[Gen]	Completed	Yes	0.9	0.050	5.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.574168	8
10	CE- 6, Darbhanga	Sitamarni	Sitamarni	Sitamarni	Dumra	Lagma Chowk to Bell Road	MMGSY OLD	Completed	Yes	4	0.030	25.00	lakhandeye river side flank and some portion road crust is damage	2024-25	Road	26.504517	8
11	CE- 6, Darbhanga	Sitamarni	Sitamarni	Sitamarni	Major ganj	House of Bharat Thakur To link Road	GTSNY	Completed	Yes	0.21	0.030	5.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.756878	8
12	CE- 6, Darbhanga	Sitamarni	Sitamarni	Sitamarni	Major ganj	Marpa sirpail/Basbitta bazar) to belwa paradi	MMGSY[Gen]	Completed	Yes	1.125	0.100	5.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.768214	8
13	CE- 6, Darbhanga	Sitamarni	Sitamarni	Sitamarni	Major ganj	House Of Badri Paswan to House Of Ram Narayan Jha	MMGSY[SC]	Completed	Yes	0.5	0.020	5.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.756761	8
14	CE- 6, Darbhanga	Sitamarni	Sitamarni	Sitamarni	Major ganj	Basbitta - Rasalpur Path	PMGSY-NEA	Completed	Yes	4.1	0.300	32.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.756878	8
15	CE- 6, Darbhanga	Sitamarni	Sitamarni	Sitamarni	Parhar	Kharwa To Kharwa Muslim Tola	MMGSY[Gen]	Completed	Yes	1.5	0.030	20.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.789749	8
16	CE- 6, Darbhanga	Sitamarni	Sitamarni	Sitamarni	Parhar	bara to bhumihar tola	MMGSY[SC]	Completed	Yes	1.7	0.090	40.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.665107	8
17	CE- 6, Darbhanga	Sitamarni	Sitamarni	Sitamarni	Riga	L044 to Bin Tola Tak	MMGSY[SC]	Completed	Yes	1.15	0.200	5.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.682159	8