



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :- L053-Amnaur T04 To Bahuara (VR30)

DISTRICT	Muzaffarpur		
DIVISION	Muzaffarpur East-2		
BLOCK	Aurai		
Damage LENGTH OF ROAD	:	0.035	KM
CONSTRUCTION COST	:	11.729	Lac

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-2

GENERAL ABSTRACT

Name of Road **L053-Amnaur T04 To Bahura (VR30)**
 District **Muzaffarpur**
 District **Muzaffarpur**
 Block **Aurai**
 Division **Muzaffarpur East-2**
 Damage length

Sl no	DESCRIPTION	AMOUNT (LAKHS)
		1154689.54
1	Brick-Bats	7011.61
2	Local Sand	11193.30 11203.05
3	HP	0.00
4	Cement Bag	1172904.20
	GARAND SUB TOTAL	1172904.20
TOTAL COST OF PROJECT IN LACS=		11,72,894.45

[Signature]
 12/11/24
 A.E

[Signature]
 12/11/24
 Say B. 11.73 lacs

Post facto technical Sanctioned for B. 11.73 lacs
 (B. Eleven lacs seventy three thousand) only

[Signature] 15/11/24
 Superintending Engineer
 Rural Works Department
 Work Circle, Muzaffarpur
 15/11/24

Name of Road- L053-Amnaur T04 To Bahuara (VR30)

Block- Aurai

Measurement for Supplying of Brick Data								
S. No	Chainage	Nos	Length (M)	Width (M)	Av. Width (M)	Thickness (M)	Av. Thickness (M)	Quantity (Cum)
1		1	16.00		5.50		3.20	281.60
		1	18.50		5.00		6.40	592.00
Total (Cum) :-								873.60


Assistant Engineer,
Rural Works Department,
Work Sub Division, Aurai
Muzaffarpur East-2


Executive Engineer,
Rural Works Department,
Work Division,
Muzaffarpur East-2

Name of Road- L053-Amnaur T04 To Bahuara (VR30)

Block- Aurai

Measurement for Supplying of Local Sand								
S. No	Chainage	Nos	Length (M)	Width (M)	Av. Width (M)	Thickness (M)	Av. Thickness (M)	Quantity (Cum)
1		1	16.00		5.50		0.15	13.20
		1	18.50		5.00		0.15	13.88
Total (Cum) :-								27.08

Assistant Engineer,
Rural Works Department,
Work Sub Division, Aurai
Muzaffarpur East-2

Executive Engineer,
Rural Works Department,
Work Division,
Muzaffarpur East-2

Name of Road-
Block-

L053-Amnaur T04 To Bahuara (VR30)

Aurai

Measurement for Supplying of HP

S. No	Chainage	Nos	Length (M)	Width (M)	Av. Width (M)	Thicknes s (M)	Av. Thickness (M)	Quantity (Cum)
1		2	2.50		0.0		0.00	5.00
Total (Cum) :-								5.00

Assistant Engineer,
Rural Works Department,
Work Sub Division, Aurai
Muzaffarpur East-2

Executive Engineer,
Rural Works Department,
Work Division,
Muzaffarpur East-2

L053-Amnaur T04 To Bahuara (VR30)

Name of Work

Sl no	SDB Sl No	MORD Ref No	Description	Unit	QUANTITY	RATE	AMOUNT (In Rs.)
1			Providing brick bats including spreading laying hand packing and compacting with C.I. Hammer in layers not exceeding 75 mm thick including cost of light barriers, danger signals, chowkidar, taxes, royalty etc. all complete job as per specification and direction of E/I including carriage cost of bricks	M3	873.60	1321.76	1154689.54
2			Supplying, Laying and spreading Local Sand at work site including all cost of Tax and Royalties etc.	M3	27.08	258.97	7011.61
3			Providing and laying sand bags with filling of local sand in empty cement bags, stitching including all cost of Tax and Royalties etc..	No	0.00	29.19	0.00
4			Providing and Laying Reinforced Cement Concrete Pipe NP3 1000 mm dia as per desing in Single Row	M	5.00	2240.61 2238.66	11203.05 11,193.30
Total							1172904.20

1172,894.45

Sham
12/11/24
A.E

Sham
12/11/24
A.E

S.