

DETAILED PROJECT REPORT FOR FDR

Name of the Road :- Pupari Janewali Balia More Se High School Hote Hue to Mehsaul Suman Tak

DISTRICT	Muzaffarpur		
DIVISION	Muzaffarpur East-2		
BLOCK	Aurai		
Damage LENGTH OF ROAD	:	0.040	KM
CONSTRUCTION COST	:	3.286	Lac

**Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-2**

GENERAL ABSTRACT

Name of Road Puparl Janewall Balla More Se High School Hote Hue to Mehsaul Suman
Tuk
District Muzaffarpur
Block Aurai
Division Muzaffarpur East-2
Damage length

Sl no	DESCRIPTION	AMOUNT (LAKHS)
1	Brick-Bats	326078.19
2	Local Sand	2602.65
3	HP	0.00
4	Cement Bag	0.00
	GARAND SUB TOTAL	328680.84
TOTAL COST OF PROJECT IN LACS=		328680.84

Say b 3.29 lakhs

Sham
14/11/24
A.E

Sham
12.11.24

Post facto technical sanctioned for b. 3.29 lakhs
(b. Three lakhs twenty nine thousand) only

Sham 15/11/24
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur

Sham
15/11/24

Name of Road- Pupari Janewali Balia More Se High School Hote Hue to Mehsaul Suman Tak
Block- Aurai

Measurement for Supplying of Brick Bats								
S. No	Chainage	Nos	Length (M)	Width (M)	Av. Width (M)	Thickness (M)	Av. Thickness (M)	Quantity (Cum)
1		1	8.00		2.50		3.90	78.00
2		1	7.00		2.00		3.80	53.20
3		1	8.00		1.50		3.60	43.20
4		1	8.00		1.50		3.40	40.80
5		1	6.00		1.50		3.50	31.50
Total (Cum) :-								246.70

Sham
12/11/24
Assistant Engineer,
Rural Works Department,
Work Sub Division, Aurai
Muzaffarpur East-2


Sham
12/11/24
Executive Engineer,
Rural Works Department,
Work Division,
Muzaffarpur East-2

Name of Road- Pupari Janewali Balia More Se High School Hote Hue to Mehsaul Suman Tak

Block- Aurai

Measurement for Supplying of Local Sand								
S. No	Chainage	Nos	Length (M)	Width (M)	Av. Width (M)	Thicknes s (M)	Av. Thickness (M)	Quantity (Cum)
1		1	8.00		2.50		0.15	3.00
2		1	7.00		2.00		0.15	2.10
3		1	8.00		1.50		0.15	1.80
4		1	8.00		1.50		0.15	1.80
5		1	6.00		1.50		0.15	1.35
Total (Cum) :-								10.05


Assistant Engineer,
Rural Works Department,
Work Sub Division, Aurai
Muzaffarpur East-2


Executive Engineer,
Rural Works Department,
Work Division,
Muzaffarpur East-2

Name of Work

Pupari Janewali Balia More Se High School Hote Hue to Mehsaul Suman Tak

Sl no	SDB Sl No	MORD Ref No	Description	Unit	QUANTITY	RATE	AMOUNT (In Rs.)
1			Providing brick bats including spreading laying hand packing and compacting with C.I. Hammer in layers not exceeding 75 mm thick including cost of light barriers, danger signals, chowkidar, taxes, royalty etc. all complete job as per specification and direction of E/I including carriage cost of bricks	M3	246.70	1321.76	326078.19
2			Supplying, Laying and spreading Local Sand at work site including all cost of Tax and Royalties etc.	M3	10.05	258.97	2602.65
3			Providing and laying sand bangs with filling of local sand in empty cement bags, stitching including all cost of Tax and Royalties etc..	No	0.00	29.19	0.00
4			Providing and Laying Reinforced Cement Concrete Pipe NP3 1000 mm dia as per desing in Single Row	M	0.00	2240.61	0.00
Total							328680.84

Suman
12/11/24
A.E

Suman
12/11/24
A.E