



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :- T01-Sahila Rampur to Narma

DISTRICT	Muza ff arpur		
DIVISION	Muza ff arpur East-2		
BLOCK	Bochaha		
Damage LENGTH OF ROAD	:	0.060	KM
CONSTRUCTION COST	:	17.740	Lac

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-2

GENERAL ABSTRACT

Name of Road T01-Sahila Rampur to Narma

District Muzaffarpur

Block Hochaha

Division Muzaffarpur East-2

Damage length

Sl no	DESCRIPTION	AMOUNT (LAKHS)
1	Brick-Bats	1751629.13
2	Local Sand	10698.05
3	HP	0.00
4	Cement Bag	11676.00
	GARAND SUB TOTAL	1774003.18
TOTAL COST OF PROJECT IN LACS=		1774003.18

J.E

A.E

B. 17.74 lacs

Post facto technical sanctioned for B. 17.74 lacs
(Seventeen lacs Seventy four thousand) only

11/11/24
Superintending Engineer
Rural Works Department
Work Circle Muzaffarpur
15/11/24

Name of Road- T01-Sahila Rampur to Narma

Block- Bochaha

Measurement for Supplying of Brick Bats								
S. No	Chainage	Nos	Length (M)	Width (M)	Av. Width (M)	Thickness (M)	Av. Thickness (M)	Quantity (Cum)
1		1	54.00		5.1		4.81	1325.22
Total (Cum) :-								1325.22


Assistant Engineer,
Rural Works Department,
Work Sub Division, Bochaha
Muzaffarpur East-2



Executive Engineer,
Rural Works Department,
Work Division,
Muzaffarpur East-2

Name of Road- T01-Sahila Rampur to Narma

Block- Bochaha

Measurement for Supplying of Rabish

S. No	Chainage	Nos	Length (M)	Width (M)	Av. Width (M)	Thicknes s (M)	Av. Thicknes (M)	Quantity (Cum)
1		1	54.00		5.1		0.15	41.31
Total (Cum) :-								41.31


Assistant Engineer,
Rural Works Department,
Work Sub Division, Bochaha
Muzaffarpur East-2


Executive Engineer,
Rural Works Department,
Work Division,
Muzaffarpur East-2


Name of Road-


T01-Sahila Rampur to Narma

Block-

Bochaha

Measurement for Supplying of Sand bag								
S. No	Chainage	Nos	Length (M)	Width (M)	Av. Width (M)	Thicknes s (M)	Av. Thickness (M)	Quantity (n)
1		400	0.00		0.0		0.00	400.00
Total (Cum) :-								400.00


Assistant Engineer,
Rural Works Department,
Work Sub Division, Bochaha
Muzaffarpur East-2


Executive Engineer,
Rural Works Department,
Work Division,
Muzaffarpur East-2

Name of Work

T01-Sahila Rampur to Narma

Sl no	SDB SI No	MORD Ref No	Description	Unit	QUANTITY	RATE	AMOUNT (In Rs.)
1			Providing brick bats including spreading laying hand packing and compacting with C.I. Hammer in layers not exceeding 75 mm thick including cost of light barriers, danger signals, chowkidar, taxes, royalty etc.all complete job as per specification and direction of E/I including carriage cost of bricks	M3	1325.22	1321.76	1751629.13
2			Filling in Local Sand as per drawing and technical specification Clause 305.3.9	M3	41.31	258.97	10698.05
3			Providing and laying sand bangs with filling of local sand in empty cement bags, stitching including all cost of Tax and Royalties etc..	No	400.00	29.19	11676.00
4			Providing and Laying Reinforced Cement Concrete Pipe NP3 1000 mm dia as per desing in Single Row	M	0.00	2240.61	0.00
Total							1774003.18


 A.E.


 A.E.