



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :- NH-77 Se Gopalpur Sarachiya Bandh Tak

DISTRICT	Muzaffarpur		
DIVISION	Muzaffarpur East-2		
BLOCK	Aurai		
Damage LENGTH OF ROAD	:	0.100	KM
CONSTRUCTION COST	:	24.348	Lac

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-2

GENERAL ABSTRACT

Name of Road NH-77 Se Gopalpur Sarachlyn Bandh Tak
District Muzaffarpur
Block Aurai
Division Muzaffarpur East-2
Damage length

Sl no	DESCRIPTION	AMOUNT (LAKHS)
1	Brick-Bats	2412145.91
2	Local Sand	22711.02
3	HP	0.00
4	Cement Bag	0.00
	GARAND SUB TOTAL	2434856.93
TOTAL COST OF PROJECT IN LACS=		2434856.93

Rs. 24.35 lacs

J.E

A.E

Post facto technical sanctioned for Rs. 24.35 lacs
(Rs. Twenty four lacs thirty five thousand) only

[Signature] 17/11/21
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur

[Signature]
15/11/21

GENERAL ABSTRACT

Name of Road NH-77 Se Gopalpur Sarachiya Bandh Tak
District Muzaffarpur
Block Aurai
Division Muzaffarpur East-2
Damage length

Sl no	DESCRIPTION	AMOUNT (LAKHS)
1	Brick-Bats	2412145.91
2	Local Sand	22711.02
3	HP	0.00
4	Cement Bag	0.00
	GARAND SUB TOTAL	2434856.93
TOTAL COST OF PROJECT IN LACS=		2434856.93

Rs. 24.35 lakhs

J.E

A.E


Post facto technical sanctioned for Rs. 24.35 lakhs
(Rs. Twenty four lakhs thirty five thousand) only


Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur

Name of Road- NH-77 Se Gopalpur Sarachiya Bandh Tak

Block- Aurai

Measurement for Supplying of Brick Bats								
S. No	Chainage	Nos	Length (M)	Width (M)	Av. Width (M)	Thicknes s (M)	Av. Thickness (M)	Quantity (Cum)
1		1	15.00		3.65		2.70	147.83
2		1	10.00		3.60		2.50	90.00
3		1	16.00		5.50		3.00	264.00
4		1	2.50		3.70		2.50	23.13
5		1	2.00		4.00		2.60	20.80
6		1	6.00		5.25		4.00	126.00
7		1	15.00		6.50		4.20	409.50
8		1	15.00		1.35		2.80	56.70
9		1	15.00		1.75		2.60	68.25
10		1	15.00		1.90		3.00	85.50
11		1	14.00		1.35		3.00	56.70
12		1	15.00		2.00		3.00	90.00
13		1	15.00		2.05		2.60	79.95
14		1	15.00		1.70		3.00	76.50
15		1	15.00		1.75		3.00	78.75
16		1	15.00		2.05		2.80	86.10
17		1	15.00		1.50		2.90	65.25
Total (Cum) :-								1824.95


Assistant Engineer,
Rural Works Department,
Work Sub Division, Aurai
Muzaffarpur East-2


Executive Engineer,
Rural Works Department,
Work Division,
Muzaffarpur East-2

Name of Road-

NH-77 Se Gopalpur Sarachiya Bandh Tak

Block-

Aurai

Measurement for Supplying of Local Sand

S. No	Chainage	Nos	Length (M)	Width (M)	Av. Width (M)	Thickness (M)	Av. Thickness (M)	Quantity (Cum)
1		1	15.00		3.65		0.15	8.21
2		1	10.00		3.60		0.15	5.40
3		1	16.00		5.50		0.15	13.20
4		1	2.50		3.70		0.15	1.39
5		1	2.00		4.00		0.15	1.20
6		1	6.00		5.25		0.15	4.73
7		1	15.00		6.50		0.15	14.63
8		1	15.00		1.35		0.15	3.04
9		1	15.00		1.75		0.15	3.94
10		1	15.00		1.90		0.15	4.28
11		1	14.00		1.35		0.15	2.84
12		1	15.00		2.00		0.15	4.50
13		1	15.00		2.05		0.15	4.61
14		1	15.00		1.70		0.15	3.83
15		1	15.00		1.75		0.15	3.94
16		1	15.00		2.05		0.15	4.61
17		1	15.00		1.50		0.15	3.38
Total (Cum) :-								87.70

Sham
12/11/24
Assistant Engineer,
Rural Works Department,
Work Sub Division, Aurai
Muzaffarpur East-2

Muzaffarpur
12/11/24
Executive Engineer,
Rural Works Department,
Work Division,
Muzaffarpur East-2

Name of Work NH-77 Se Gopalpur Sarachiya Bandh Tak

Sl no	SDB SI No	MORD Ref No	Description	Unit	QUANTITY	RATE	AMOUNT (In Rs.)
1			Providing brick bats including spreading laying hand packing and compacting with C.I. Hammer in layers not exceeding 75 mm thick including cost of light barriers, danger signals, chowkidar, taxes, royalty etc.all complete job as per specification and direction of E/I including carriage cost of bricks	M3	1824.95	1321.76	2412145.91
2			Supplying, Laying and spreading Local Sand at work site including all cost of Tax and Royalties etc.	M3	87.70	258.97	22711.02
3			Providing and laying sand bags with filling of local sand in empty cement bags, stitching including all cost of Tax and Royalties etc..	No	0.00	29.19	0.00
4			Providing and Laying Reinforced Cement Concrete Pipe NP3 1000 mm dia as per desing in Single Row	M	0.00	2240.61	0.00
Total							2434856.93

Shourav
A.E

Shourav
A.E