



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

BIHAR RURAL ROADS PROJECT

Bihar Rural Road Development Agency (BRRDA)

Head :- F.D.R.

YEAR (2024-25)

STATE :- BIHAR

DICTRICT :- MADHEPURA

BLOCK :- ALAMNAGAR

DIVISION :- UDAKISHANGANJ

DETAILED ESTIMATE FOR TEMPORARY RESTORATION OF ROAD FROM T04 -BAJRAHA TO LAUKA.

Actual Length of Road	=	2.000 Km
Flood affected Length of Road	:-	0.080 Km
TOTAL COST OF PAVEMENT	:-	Rs. 40,17,578.16
TOTAL PROJECT COST	:-	Rs. 40,17,578.16

Submitted By:
Executive Engineer
RWD (W) Division, Udakishanganj

Prepared By:
Executive Engineer
RWD (W) Division, Udakishanganj

प्रशासनिक प्रतिवेदन

पथ का नाम : T04 Bajraha to Lauka

पथ की लंबाई :- 2.00 K.M

प्राक्कलित राशि : 40,17,578=00

प्रमंडल का नाम : उदाकिशुनगंज

अंचल का नाम : अछेपुरा

योजना शीर्ष : F.D.R

योजना वर्ष : 2024-25

प्रस्तुत प्राक्कलन विभागीय पत्रांक-

89

दिनांक- 18.10.24

के आदेशानुसार पथ में कराये गये यातायात पुनर्स्थापना कार्य के निमित्त तैयार की गयी है।

यह प्राक्कलन खाद प्रभावित पथ को मोटेमूल्य कार्य के लिए तैयार की गई है। वर्ष 2024 में आयी प्रलयकारी बाढ़/आतिवृष्टि के कारण पथ कई जगहों पर क्षतिग्रस्त हो गया था जिसके कारण आवागमन अवरुद्ध हो गई थी। जिसमें अस्थायी यातायात पुनर्स्थापन कार्य किया गया है।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनुसूचित दर पर, जो संवेदक तालांश को छोड़कर था, उसे प्रावधान करते हुए तैयार किया गया है।

अतः किये गये कार्यों के भुगतान हेतु प्राक्कलन की प्रशासनिक स्वीकृति अपेक्षित है।


11/11/24


कनीय अभियंता
ग्रामीण कार्य विभाग

कार्य प्रशाखा-आलमनगर

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल आलमनगर


11/11/24

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमंडल उदाकिशुनगंज

Inspection Report for Flood Damage work

Date:-

- 1 Name of PIUs :- UdaKishunganj
2 Name of Block/Road :- Alam Nagar]- Tod Bajraha to Lauka

A. For Road

- 1 Damage Location/Chainage :- Multiple Location (1.920 - 2.00) K.M
2 Damage Length :- 0.080
3 Nature of damage :- Damage due to flood
4 Details of Restoration Works :-
i Material being used in Restoration works:- Bricks batd bambaspile, Ecbag, Runner
ii Equipments/Tools being used in Restoration works :- Tractor manual Means
iii Procedure taken up in Restoration works :- Immergent work
iv Restored Length :- 0.080 K.M
Restoration make take up to completed
to restore traffic Bricksbat Filled
in ditch & Levelled.

B. For Bridge

- 1 Damage Location/Chainage :- 0
2 Damage Length :-
3 Nature of damage :-
4 Details of Restoration Works :-
i Material being used in Restoration works:-
ii Equipments/Tools being used in Restoration works :-
iii Procedure taken up in Restoration works :-
iv Restored Length :-

Signature of

JE

AE

EE

Signature
Executive Engineer
(Name of Inspector)
R.W.D (W) Div, Madhapura

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :- DETAILED ESTIMATE FOR TEMPORARY RESTORATION OF ROAD FROM T04 -BAJRAHA TO LAUKA.

DIVISION :- UDAKISHANGANJ


BLOCK :- ALAMNAGAR

Actual Length of Road :- 2.000 Km

Flood Affected Length of Road :- 0.080 Km


Sr. No.	Description	Amount (In Rs.)
1	Brick Bats=	
2		28,03,910.80
3	Bamboo Pilling=	34,035.41
4	Bamboo Runner=	1,957.35
5	Supply of Bamboo=	26,988.31
	Empty Cement Bag=	3,85,337.67
	Total Cost of Restoration=	32,52,229.54
6	Add:-Labour Cess @1% amt. =	32,522.30
7	Add:GST@18% on amt. =	5,85,401.32
8	Add:S.F.@ 10% on Material =	1,47,425.00
TOTAL RESTORATION COST OF THE PROJECT IN LACS=		40,17,578.16


Junior Engineer
RWD (W) Division, Udakishanganj


Assistant Engineer
RWD (W) Division, Udakishanganj


Executive Engineer
RWD (W) Division, Udakishanganj

Provisional T.S. accorded Rs. 40,17,578 = Rupees (Forty Lakh seventy thousand Five hundred seventy Eight) only


13.11.24
अधीक्षण अभियंता
ग्रामीण एवं विभाग
काम