



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

BIHAR RURAL ROADS PROJECT

Bihar Rural Road Development Agency (BRRDA)

Head :- F.D.R.

YEAR (2024-25)

STATE :- BIHAR

DICTRICT :- MADHEPURA

BLOCK :- ALAMNAGAR

DIVISION :- UDAKISHANGANJ

**DETAILED ESTIMATE FOR TEMPRORY RESTORATION OF
ROAD FROM L025-T05 SONAMUKHI TO MURAUT.**

Actual Length of Road	=	1.825 Km
Flood affected Length of Road	:-	0.040 Km
TOTAL COST OF PAVEMENT	:-	Rs. 16,70,392.65
TOTAL PROJECT COST	:-	Rs. 16,70,392.65

Submitted By:
Executive Engineer
RWD (W) Division, Udakishanganj

Prepared By:
Executive Engineer
RWD (W) Division, Udakishanganj

प्रशासनिक प्रतिवेदन

पथ का नाम : ^{Tos} सोनामुखी से मुरौत

पथ की लंबाई 1.825 K.M

प्राक्कलित राशि : 16,70,392=10

प्रमंडल का नाम : उदाकिशुनगंज

अंचल का नाम : मधेपुरा

योजना शीर्ष : F.D.R

योजना वर्ष : 2024-25

प्रस्तुत प्राक्कलन विभागीय पत्रांक- 89 दिनांक- 18.10.24
के आदेशानुसार पथ में कराये गये यातायात पुनर्स्थापना कार्य के निमित्त तैयार की
गयी है।

यह प्राक्कलन बाढ़ प्रभावित पथ को मौसमसूचक कार्य के लिए तैयार
की गई है। वर्ष 2024 में आयी प्रलयकारी बाढ़/आतिवृष्टि के कारण पथ कई जगहों पर
क्षतिग्रस्त हो गया था जिसके कारण आयागमन अवरुद्ध हो गई थी। जिसमें अस्थाई यातायात
पुनर्स्थापन कार्य किया गया है।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनुसूचित दर पर, जो संवेदक लागाना
को छोड़कर था, उसे प्रावधान करते हुए तैयार किया गया है।

अतः किये गये कार्यों के भुगतान हेतु प्राक्कलन की प्रशासनिक स्वीकृति अपेक्षित है।



कनीय अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशाखा- आलमनगर

सहायक अभियंता
ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल आलमनगर


कार्यपालक अभियंता
ग्रामीण कार्य विभाग

कार्य प्रमंडल उदाकिशुनगंज

Inspection Report for Flood Damage work

Date:-

1 Name of PIUs :- Uda Kishunganj

2 Name of Block/Road :- Alamnagar / Restoration of road from L025-T05
Sonamukhi to Muraut

A. For Road

1 Damage Location/Chainage :- Multiple Location (0-0.040) K.M

2 Damage Length :- 0.040 K.M

3 Nature of damage :- Damage due to flood

4 Details of Restoration Works :-

i Material being used in Restoration works:- Brick bats, bamboo Pile Runner, E.C bag

ii Equipments/Tools being used in Restoration works :- Tractor manual Means

iii Procedure taken up in Restoration works :- Immergent work

iv Restored Length :- Restoration make take up to
Completed to Restore traffic
Brick bats Filled in the ditch &
Levelled.

B. For Bridge

1 Damage Location/Chainage :-

2 Damage Length :-

3 Nature of damage :-

4 Details of Restoration Works :-

i Material being used in Restoration works:-

ii Equipments/Tools being used in Restoration works :-

iii Procedure taken up in Restoration works :-

iv Restored Length :-

Signature of


12.11.24
JE

AE

EE


19.11.24
Signature
Executive Engineer
(R.W.D (W) Div., Madhapura)

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :- DETAILED ESTIMATE FOR TEMPORARY
RESTORATION OF ROAD FROM L025-T05
SONAMUKHI TO MURAUT.

DIVISION :- UDAKISHANGANJ

BLOCK :- ALAMNAGAR

Actual Length of Road :- 1.825 Km

Flood Affected Length of Road :- 0.040 Km

Sr. No.	Description	Amount (In Rs.)
1	Brick Bats=	8,03,203.62
2	Bamboo Pilling=	12,763.28
3	Bamboo Runner=	734.01
4	Supply of Bamboo=	10,120.62
5	Empty Cement Bag=	5,36,717.65
	Total Cost of Restoration=	13,63,539.17
6	Add:-Labour Cess @1% amt. =	13,635.39
7	Add:GST@18% on amt. =	2,45,437.05
8	Add:S.F.@ 10% on Material =	47,781.04
TOTAL RESTORATION COST OF THE PROJECT IN LACS		16,70,392.65


11/11/24

Junior Engineer

RWD (W) Division, Udakishanganj


11/11/24

Assistant Engineer


RWD (W) Division, Udakishanganj


11/11/24

Executive Engineer

RWD (W) Division, Udakishanganj

Provisional T.S. accorded for Rs 16,70,392 = 16 Lakhs 70,392 Rupees
(Sixteen Lakh seventy thousand Three hundred Ninety Two)
only


13.11.24
अधीक्षक अभियंता
ग्रामीण कार्य विभाग
नर्मदा अंचल, मधेपुरा