



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

BIHAR RURAL ROADS PROJECT

Bihar Rural Road Development Agency (BRRDA)

Head :- F.D.R.

YEAR (2024-25)

STATE :- BIHAR
DISTRICT :- MADHEPURA
BLOCK :- ALAMNAGAR
DIVISION :- UDAKISHANGANJ

DETAILED ESTIMATE FOR TEMPORARY RESTORATION OF ROAD FROM MALA BASA SE FULAUT TAK.

Actual Length of Road	=	3.350 Km
Flood affected Length of Road	:-	0.250 Km
TOTAL COST OF PAVEMENT	:-	Rs. 60,20,166.81
TOTAL PROJECT COST	:-	Rs. 60,20,166.81

Submitted By:
Executive Engineer
RWD (W) Division, UdaKishanganj

Prepared By:
Executive Engineer
RWD (W) Division, UdaKishanganj

प्रशासनिक प्रतिवेदन

पथ का नाम : माला वासा से फुलौत

पथ की लंबाई 3.350 K.M

प्राक्कलित राशि : 60,20,166=100

प्रगंडल का नाम : उदाकिशुनगंज

अंघल का नाम : मधेपुरा

योजना शीर्ष : F.D.R

योजना वर्ष : 2024-25

प्रस्तुत प्राक्कलन विभागीय पत्रांक-

89


दिनांक- 18.10.24

के आदेशानुसार पथ में कराये गये यातायात पुनर्स्थापना कार्य के निमित्त तैयार की गयी है।

यह प्राक्कलन व्यापक प्रभावित पथ को मोटे-मूल् कार्य के लिए तैयार की गई है। वर्ष 2024 में आयी प्रलयकारी बाढ़/आतिवृष्टि के कारण पथ कई जगहों पर क्षतिग्रस्त हो गया था जिसके कारण आयागमन अवरुद्ध हो गई थी। जिसमें अस्थाई यातायात पुनर्स्थापन कार्य किया गया है।


प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनुसूचित दर पर, जो संवेदक लागू होने के छोड़कर था, उसे प्रावधान करते हुए तैयार किया गया है।

अतः किये गये कार्यों के भुगतान हेतु प्राक्कलन की प्रशासनिक स्वीकृति अपेक्षित है।



कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा-आलमनगर

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रगंडल आलमनगर


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रगंडल उदाकिशुनगंज

Inspection Report for Flood Damage work

Date:-

1 Name of PIUs :- Udakishunganj

2 Name of Block/Road :- Alamnagar 1 Mala Baba to ~~Badhot~~ Fulaut tal

A. For Road Mala Baba to Fulaut tal

1 Damage Location/Chainage :- Multiple Location (2.50-2.750) km

2 Damage Length :- 0.250 km

3 Nature of damage :- Damage due to flood

4 Details of Restoration Works :-

i Material being used in Restoration works:- Brickbats, bamboo Pile, E.C bag, Runner

ii Equipments/Tools being used in Restoration works :- Tractor, manual means

iii Procedure taken up in Restoration works :-

iv Restored Length :- 0.250 km

Restoration make take up to completed to restore traffic
Brickbat Filled in ditch & Levelled

B. For Bridge

1 Damage Location/Chainage :-

2 Damage Length :-

3 Nature of damage :-

4 Details of Restoration Works :-

i Material being used in Restoration works:-

ii Equipments/Tools being used in Restoration works :-

iii Procedure taken up in Restoration works :-

iv Restored Length :-

Signature of

JE

AE

EE

Signature
Executive Engineer
(Name of Inspector)
R.W.B (W) Div. Madhopura

SUMMARY OF COST ESTIMATE FOR THE PROJECT

DETAILED ESTIMATE FOR TEMPORARY
NAME OF ROAD :- RESTORATION OF ROAD FROM MALA BASA SE
FULAUT TAK.

DIVISION :- UDAKISHANGANJ

BLOCK :- ALAMNAGAR

Actual Length of Road :- 3.350 Km


Flood Affected Length of Road :- 0.250 Km

Sr. No.	Description	Amount (In Rs.)
1	Brick Bats=	27,11,676.90
2	Bamboo Pilling=	66,475.41
3	Bamboo Runner=	4,587.54
4	Supply of Bamboo=	56,169.42
5	Empty Cement Bag=	20,81,549.62
	Total Cost of Restoration=	49,20,458.88
6	Add:-Labour Cess @1% amt. =	49,204.59
7	Add:GST@18% on amt. =	8,85,682.60
8	Add:S.F.@ 10% on Material =	1,64,820.74
TOTAL RESTORATION COST OF THE PROJECT IN LACS		60,20,166.81


11/11/24


Junior Engineer

RWD (W) Division, Udakishanganj


11/11/24

Assistant Engineer

RWD (W) Division, Udakishanganj


11.11.24

Executive Engineer

RWD (W) Division, Udakishanganj

Provincial T.S. accorded For Rs 60,20,166 = 60 Rupees (Sixty
Lakh Twenty thousand one hundred Sixty Six) only


13.11.24

अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, मधेपुरा