

तकनीकी प्रतिवेदन

पथ का नाम : फतेहपुर सरकरपुर भरपा बेनाही कन्होली
प्रखंड : ~~कन्होली गारु~~ ~~भरपा~~ ~~बेनाही~~ ~~कन्होली~~
योजना शीर्ष : ~~सोनबरसा~~ ~~PMGSY.~~
पथ की लंबाई : 8.3 किलोमीटर
क्षतिग्रस्त पथांश की लंबाई :- 0.0290 Km.
प्राक्कलित राशि :- Rs. 67419=00
प्राधिकार :-

प्रस्तुत प्राक्कलन शीर्ष 2245/FDR अंतर्गत फतेहपुर सरकरपुर भरपा बेनाही कन्होली गारु पथ के वर्ष 2024 में आये बाढ़ से क्षतिग्रस्त हो जाने के कारण यातायात को चालू (Motorable) रखने के लिए कुल रू0- 67,419=00 (Rupees Sixty seven thousand four hundred and Nineteen) मात्र का तैयार किया गया है।

उक्त पथ के द्वारा भासर को एकल संपर्कता प्राप्त है। बागमति नदी का बाँध काटने के फलस्वरूप पथ में बहुत स्थलों पर कटाव हुआ था जिसके कारण उक्त बसावट तक पहुँचना संभव नहीं हो पा रहा था। अतएव यातायात को अविलम्ब बहाल करने हेतु क्षतिग्रस्त पथांश में Brick Bats एवं Rabbish का उपयोग कर आकस्मिक मरम्मत कार्य करते हुए पथ को चालू किया गया है। विभागीय निदेशानुसार किये गए कार्य का Geotagged फोटोग्राफ एवं ड्रोन विडियोग्राफी MIS पर Upload किया गया है। पथ के पुनर्स्थापन कार्य का प्राक्कलन कार्य स्थल के अनुरूप है एवं तकनीकी अनुमोदन अपेक्षित है।

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा.....

15/11/24
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल. सोनबरसा

15/11/24
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, सीतामढ़ी

DETAILED ESTIMATE FOR F.D.R.

General Abstract of Cost

Name of Road : Fatehpur Sarbarpur Marpa Betahi Kanhauli Bhasar Path
Length of Road : 8.30 Km
Block : Sonbarsa
DISTRICT : SITAMARHI

S.No.	Particulars	Total Cost (in Lakh)
1	Total Cost for Motorable Roads	79,923.00
	Total Cost of Road Repair	79,923.00
	Say	79,923.00

[Signature]
JE
RWD Sonbarsa

[Signature]
AE
RWD Sonbarsa

[Signature]
EE
RWD Sitamarhi

Is (provisioned) is accorded for Rs 67,419.00
(Rs. sixty seven thousand four hundred ninteen only)

[Signature]
15/11/24
अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल सीतामढ़ी
[Signature]
15.11.24

Schedule of Quantity

Name Of Work : Fatehpur Sarbarpur Marpa Betahi Kanhauli Bhasar Path Block Sonbarsa

S.No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	OF ITEMS				
1	Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to acheive required density with all complete as per the direction of engineer in charge.	47.70			0.00
	Less 20% for Voids	-9.54		1626.71	
		38.16	Cum	1698.60	64818.58
2	Providing Rabbishs including spreading laying hand packing and compacting with C.I hammer in layers not exceeding 75 mm thick including cost of light barrier,danger signals,chowkidar tax royalty etc all complite job as per specification and direction of E/I				
	Taking 20% of Brick Qty for Rabbish	9.54	Cum	560.16 639.90	5344.00 6104.65
3	Drone video recording(3 times)	-3.00	Nos	3000.00	9000.00 67419

Total 79,923.22

Say 79,923.00

Sumar
15/11/24
JE

Sumar
15/11/24
AE

Sumar
15/11/24
EE

67,419.00

Details of Measurement of ditches filled by brick bats and rabbish

Name Of Work : Fatehpur Sarbarpur Marpa Betahl Kanhauli Bhasar Path

Record ENTRY

	Length (in meter)	Width(in meter)	Depths (in meter)	Volume
at Ch- 725m	16.0	2.0	0.90	28.80
	9.0	2.0	0.90	16.20
	4.0	1.5	0.45	2.70
Total				47.70

Total (in Cum) 47.70 Cum

Kumar
15/11/24
7.2

[Signature]
15/11/24

Ani
15/11/24

Rural Works Department, Govt. of Bihar



Welcome: **Sesitamadhi**
Wing:-CE-6, Darbhanga
Circle:-Sitamarhi
Division:-HQ
No Of Visit:-

- Home
- Road-Cutting Request User,Menu and Profile
- Entry Forms
- Project Views
- MIS Reports
- QMC Reports
- Scheduled List
- Zone Reports
- Contractors Debar
- Time Extension
- NEW MR
- Contractor Revoke
- Flood/Rain Damage Roads
- Crash Inspection
- Contractor
- NEW MR Allotment
- Road / Bridge Allotment
- NEW MR Observation
- Offline Inspection
- Left Habitation Survey
- Routine Inspection
- Bridge Approach
- CM Jania Darbar
- POP
- Inauguration
- DPR
- Road Pavement
- BRRMS Report
- Review Report
- Bridge Details
- NEW MR INS. Report

Flood/Rain Damaged Road/Bridge Report

Chief Engineer: Circle Division FDR Fin Year

Details of Road & Bridge															Start Po		
SINo	Wing	Circle	District	Division	Block	Road/Bridge Name	Scheme Name	Status (Comp./Ongoing)	Is Maintenance (Y/N)	Length (In Km)	Approximate Damage Length During Flood(In Km)	Restoration Amount (In Lakh)	Remarks	FDR Fin Year	Type (R/B)	Latitude	Lc
1	CE-Darbhanga	Sitamarhi	Sitamarhi	Sitamarhi	Bathn aha	L021-Mahadewa to Mahadewa (VR3)	PMGSY	Completed	Yes	2.06	0.060	5.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.724909	81
2	CE-Darbhanga	Sitamarhi	Sitamarhi	Sitamarhi	Bathn aha	PMGSY path belahi jayram to belahi	PMGSY[SC]	Completed	Yes	0.95	0.030	5.00	NO NEED FOR TEMPORARY	2024-25	Road	26.705395	81

18	CE-6, Darbhanga	Sitamarhi	Sitamarhi	Sitamarhi	Riga	pwd path rampur gangoli to ghinriya tola	MMGSY[SC]	Completed	Yes	2.491	0.200	5.00	OVERFLOW and cut	2024-25	Road	26.619773	8%
19	CE-6, Darbhanga	Sitamarhi	Sitamarhi	Sitamarhi	Riga	Riga Bhabita Path - From Riga to Helampur, Via Budhwara, Najarpur, Sonar	PMGSY-NEA	Completed	Yes	7.5	0.500	6.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.704061	8%
20	CE-6, Darbhanga	Sitamarhi	Sitamarhi	Sitamarhi	Riga	Mohanpur - Bhabdeopur Path	PMGSY-NEA	Completed	Yes	2.25	0.500	1.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.603846	8%
21	CE-6, Darbhanga	Sitamarhi	Sitamarhi	Sitamarhi	Sonb arsa	Maharani Asthan to Mohchaati zamirashahi ke ghar	MMGSY[SC]	Completed	Yes	2.9	0.080	40.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.793878	8%
22	CE-6, Darbhanga	Sitamarhi	Sitamarhi	Sitamarhi	Sonb arsa	MRL01-Sonbarsa Rajwara REO to Inderwa	PMGSY-II	Completed	Yes	7.14	0.010	10.00	OLD BRIDGE COLLAPSE ON BANKE RIVER	2024-25	Road	26.822508	8%
23	CE-6, Darbhanga	Sitamarhi	Sitamarhi	Sitamarhi	Sonb arsa	ITAHARWADULARPUR - MURAHACHHATAUNA FDR	FDR	Completed	Yes	5.83	0.040	8.00	ON GOING	2024-25	Road	26.797413	8
24	CE-6, Darbhanga	Sitamarhi	Sitamarhi	Sitamarhi	Sonb arsa	NH-77 to Bin tola	MMGSY[SC]	Completed	Yes	0.695	0.100	40.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.727487	8%
25	CE-6, Darbhanga	Sitamarhi	Sitamarhi	Sitamarhi	Sonb arsa	ARARIA - INDARWA-II	PMGSY	Completed	Yes	2.805	0.090	30.00	OVERFLOW and CUT	2024-25	Road	26.792848	8%
26	CE-6, Darbhanga	Sitamarhi	Sitamarhi	Sitamarhi	Sonb arsa	L059-Lakhandei Pul to Mushahari Tola (VR60)	PMGSY	Completed	Yes	2.47	0.040	10.00	OVERTOPPING and cut	2024-25	Road	26.794733	8%
27	CE-6, Darbhanga	Sitamarhi	Sitamarhi	Sitamarhi	Sonb arsa	RAMMAGAR RASALPUR - Chirri N.H 77	PMGSY	Completed	Yes	1.49	0.100	40.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.83094	8%
28	CE-6, Darbhanga	Sitamarhi	Sitamarhi	Sitamarhi	Sonb arsa	FATHEPUR SARBEPUR - MARPA BETAHI KANHAULI BHASHAR PATH	PMGSY	Completed	Yes	8.72	0.050	20.00	OVERTOPPING and cut	2024-25	Road	26.803553	8%
29	CE-6, Darbhanga	Sitamarhi	Sitamarhi	Sitamarhi	Sonb arsa	Sonbarsa to Bhutahi via Rajwara and Lokhar	Other	On Going	No	22.4	0.060	10.00	OLD BRIDGE COLLAPSE ON BANKE RIVER and OVERTOPPING & cut	2024-25	Road	26.812507	8%