

तकनीकी प्रतिवेदन

पथ का नाम

प्रखंड

योजना शीर्ष

पथ की लंबाई

क्षतिग्रस्त पथांश की लंबाई

प्राक्कलित राशि

प्राधिकार

:- PWD pun Rampur gangoli to Jhingri tola

:- Riga

:- mrrg sy (50

:- 2.431

:- 013me

:- 710350 = w

प्रस्तुत प्राक्कलन शीर्ष 2245/FDR अंतर्गत PWD pun Rampur gangoli to Jhingri tola पथ के वर्ष 2024 में आये बाढ़ से क्षतिग्रस्त हो जाने के कारण यातायात को चालू (Motorable) रखने के लिए कुल रू०- 710350 = w. मात्र का तैयार किया गया है।

उक्त पथ के द्वारा को एकल संपर्कता प्राप्त है। बागमति नदी का बाँध काटने के फलस्वरूप पथ में बहुत स्थलों पर कटाव हुआ था जिसके कारण उक्त बसावट तक पहुँचना संभव नहीं हो पा रहा था। अतएव यातायात को अविलम्ब बहाल करने हेतु क्षतिग्रस्त पथांश में Brick Bats एवं Rabbish का उपयोग कर आकस्मिक मरम्मत कार्य करते हुए पथ को चालू किया गया है। विभागीय निदेशानुसार किये गए कार्य का Geotagged फोटोग्राफ एवं ड्रोन विडियोग्राफी MIS पर Upload किया गया है। पथ के पुनर्स्थापन कार्य का प्राक्कलन कार्य स्थल के अनुरूप है एवं तकनीकी अनुमोदन अपेक्षित है।

Xmar

कनीय अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशाखा

12.11.24

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल

12.11.24

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमंडल, सीतामढ़ी

DETAILED ESTIMATE FOR F.D.R.

General Abstract of Cost

Name of Road : PWD Path Rampur Gangoli to Jhingri tola
Length of Road : 2.491 Km
Block : Riga
DISTRICT : SITAMARHI

S.No.	Particulars	Total Cost (in Lakh)
1	Total Cost for Motorable Roads	71035/- 83,715.00
	Total Cost of Road Repair	71035/- 83,715.00
	Say	71035/- 83,715.00

Kumar
12/11/24
JE
RWD ~~Sambarsa~~ Riga

M
12.11.24
AE
RWD ~~Sambarsa~~ Riga

Ani
15/11/24
EE
RWD Sitamarhi

[Signature]
12.11.24
AE

Is (provision) is accorded for Rs 71,035=-
(Rs seventy one thousand thirty five only)

[Signature]
15/11/2024
अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल सीतामढ़ी
[Signature]
15.11.24

Schedule of Quantity

Name Of Work : PWD Path Rampur Gangoli to Jhingri tola

Block Riga

S.No	OF ITEMS	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1		Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to acheive required density with all complete as per the direction of engineer in charge.	50.25			0.00
		Less 20% for Voids	-10.05			
			40.20	Cum	1626.71 1698.60	65,394.93 68283.72
2		Providing Rabbishs including spreading laying hand packing and compacting with C.I hammer in layers not exceeding 75 mm thick including cost of light barrier,danger signals,chowkidar tax royalty etc all complite job as per specification and direction of E/I				
		Taking 20% of Brick Qty for Rabbish	10.05	Cum	561.16 639.90	5639.66 6431.00
3		Drone video recording(3 times)	3.00	Nos	3000.00	9000.00
Total Say						71,034.6 83,714.72 83,715.00 71035.00

[Signature]
12/11/24
JE

[Signature]
12.11.24
AE

[Signature]
15/11/24
EE

[Signature]
12.11.24

Details of Measurement of ditches filled by brick bats and rabbish

Name Of Work : PWD Path Rampur Gangoli to Jhingri tola

Record ENTRY

Record ENTRY					
		Length (in meter)	Average Width(in meter)	Avg depth	Volume
Chainage 1.20 Km		6.5	1.50	2.00	19.50
		3.00	1.00	0.50	1.50
		15	2.50	0.15	5.63
		25	2.50	0.15	9.38
		20	2.50	0.15	7.50
		18	2.50	0.15	6.75
					50.25

Total (in Cum) 50.25

Sunay
12/11/24
702

[Signature]
12.11.24
A.E.

Ani
15/11/24
EE



Welcome:-SEsitamadhi
Wing:-CE-6,Darbhanga
Circle:-Sitamarhi
Division:-HQ
No Of Visit:-

Rural Works Department, Govt. of Bihar

Home Road-Cutting Request User,Menu and Profile Entry Forms Project Views MIS Reports QMC Reports Scheduled List Zone Reports Contractors Debar Time Extension
NEW MR Contractor Revoke Flood/Rain Damage Roads Crash Inspection Contractor NEW MR Allotment Road / Bridge Allotment NEW MR Observation Offline Inspection
Left Habitation Survey Routine Inspection Bridge Approach CM Janta Darbar POP Inauguration DPR Road/Pavement BRRMS Report Review Report Bridge Details
NEWMR INS Report

Flood/Rain Damaged Road/Bridge Report

Chief Engineer: CE-6,Darbhanga

Circle Sitamarhi

Division Sitamarhi

FDR Fin Year 2024-25

Show Data

Download in Excel

Details of Road & Bridge															Start Po		
SINO	Wing	Circle	District	Division	Block	Road/Bridge Name	Scheme Name	Status (Comp./Ongoing)	Is Maintenance (Y/N)	Length (In Km)	Approximate Damage Length During Flood(In Km)	Restoration Amount (In Lakh)	Remarks	FDR Fin Year	Type (R/B)	Latitude	Lc
1	CE-6,Darbhanga	Sitamarhi	Sitamarhi	Sitamarhi	Batnaha	LO21-Mahadewa to Mahadewa (VR3)	PMGSY	Completed	Yes	2.06	0.060	5.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.724909	8°
2	CE-6,Darbhanga	Sitamarhi	Sitamarhi	Sitamarhi	Batnaha	PMGSY path belahi jayram to belahi	PMGSY[SC]	Completed	Yes	0.95	0.030	5.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.705395	8°

18	CE- 6, Darbhanga	Sitamari	Sitamari	Sitamari	Riga	pwd path rampur gangoli to jhinriya tola	MMGSY[SC]	Completed	Yes	2.491	0.200	5.00	OVERFLOW and cut	2024-25	Road	26.619775	8:
19	CE- 6, Darbhanga	Sitamari	Sitamari	Sitamari	Riga	Riga Basbitta Path - From Riga to Heliampur, Via Budhiwara, Najampur, Sonar	PMGSY-NEA	Completed	Yes	7.5	0.500	6.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.704061	8:
20	CE- 6, Darbhanga	Sitamari	Sitamari	Sitamari	Riga	Mohampur - Bhabdeoour Path	PMGSY-NEA	Completed	Yes	2.25	0.500	1.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.603846	8:
21	CE- 6, Darbhanga	Sitamari	Sitamari	Sitamari	Sonb arsa	Maharani Asthan to Mohchaati zamirastheki ke ghar	MMGSY[SC]	Completed	Yes	2.9	0.080	40.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.783878	8:
22	CE- 6, Darbhanga	Sitamari	Sitamari	Sitamari	Sonb arsa	MRL01-Sonbarsa Rajwara REO to Inderwa	PMGSY-II	Completed	Yes	7.14	0.010	10.00	OLD BRIDGE COLLAPSE ON BANKE RIVER	2024-25	Road	26.822508	8:
23	CE- 6, Darbhanga	Sitamari	Sitamari	Sitamari	Sonb arsa	ITAHARWADULARPUR - MURAHACHHATAUNA FDR	FDR	Completed	Yes	5.83	0.040	8.00	ON GOING	2024-25	Road	26.787418	8
24	CE- 6, Darbhanga	Sitamari	Sitamari	Sitamari	Sonb arsa	NH-77 to Bin tola	MMGSY[SC]	Completed	Yes	0.695	0.100	40.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.727487	8:
25	CE- 6, Darbhanga	Sitamari	Sitamari	Sitamari	Sonb arsa	ARARIA - INDIRAWA-II	PMGSY	Completed	Yes	2.805	0.090	30.00	OVERFLOW and CUT	2024-25	Road	26.782848	8:
26	CE- 6, Darbhanga	Sitamari	Sitamari	Sitamari	Sonb arsa	LOS9-Lakhandel Pul to Mushahar tola (VR60)	PMGSY	Completed	Yes	2.47	0.040	10.00	OVERTOPPING and cut	2024-25	Road	26.794733	8:
27	CE- 6, Darbhanga	Sitamari	Sitamari	Sitamari	Sonb arsa	RAMNAGAR RASALPUR - Chilir N.H.77	PMGSY	Completed	Yes	1.49	0.100	40.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.83094	8:
28	CE- 6, Darbhanga	Sitamari	Sitamari	Sitamari	Sonb arsa	FATHERPUR SAREBPUR - MARPA BETTAH KANHAIL BHASHAR PATH	PMGSY	Completed	Yes	8.72	0.050	20.00	OVERTOPPING and cut	2024-25	Road	26.808553	8:
29	CE- 6, Darbhanga	Sitamari	Sitamari	Sitamari	Sonb arsa	Sonbarsa to Bhutahi via Rajwara and Lokhar	Other	On Going	No	22.4	0.060	10.00	OLD BRIDGE COLLAPSE ON BANKE RIVER and OVERTOPPING & cut	2024-25	Road	26.812507	8: