

तकनीकी प्रतिवेदन

पथ का नाम

प्रखंड

योजना शीर्ष

पथ की लंबाई

क्षतिग्रस्त पथांश की लंबाई

प्राक्कलित राशि

प्राधिकार

इटहरवा दुल्लापुर से दतौना
CH: - 850m to 880m
सोनबरसा
FDR
2.25Km
0.060Km
Rs. 620,752

प्रस्तुत प्राक्कलन शीर्ष 2245/FDR अंतर्गत

इटहरवा दुल्लापुर से दतौना

पथ के वर्ष 2024 में आये बाढ़ से क्षतिग्रस्त हो जाने के कारण

यातायात को चालू (Motorable) रखने के लिए कुल रू०-

620,752-00 (दुल्लापुर, वीरहापुर)

5,080,827 = 0

समाप्त बाक) मात्र का तैयार किया गया है।

उक्त पथ के द्वारा

मुल्हा दतौना

को एकल

संपर्कता प्राप्त है। बागमति नदी का बाँध काटने के फलस्वरूप पथ में बहुत स्थलों पर कटाव हुआ था जिसके कारण उक्त बसावट तक पहुँचना संभव नहीं हो पा रहा था। अतएव यातायात को अविलम्ब बहाल करने हेतु क्षतिग्रस्त पथांश में Brick Bats एवं Rabbish का उपयोग कर आकस्मिक मरम्मत कार्य करते हुए पथ को चालू किया गया है। विभागीय निदेशानुसार किये गए कार्य का Geotagged फोटोग्राफ एवं ड्रोन विडियोग्राफी MIS पर Upload किया गया है। पथ के पुनर्स्थापन कार्य का प्राक्कलन कार्य स्थल के अनुरूप है एवं तकनीकी अनुमोदन अपेक्षित है।

Xumar
15/11/24

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा

15/11/24

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल

15/11/24

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, सीतामढ़ी

SPECTION REPORT FOR MOTORABLE WORK

AIUs :- Sri Avinash Kumar, O.R. L. W.D. S/Hamarla
of Block / Road :- ITdara Dularpur to Chorda chetana

A. For Road

1. Damage location / Chainage :- Lat - 26.757448 Long - 85.48417 CH - 85010880

2. Damage Length :- 0.030 km

3. Nature of Damage (Length Wise)

(i) Breach :-

(ii) Crust Damage :- 0.030 km

(iii) Only Flank Damage

Whether Traffic Fully / Partialiy obstructed :- partially obstructed

4. Details of Restoration :-

(i) Material Being Used in Restoration :- Source bds, Laksh, bamboo

(ii) Equipment / Tools Being used in Restoration Work :- T.C.B, Tractor

(iii) Restored Length

In open Area :-

In Habitation Area :-

(iv) If Restoration Work Done in habitation Area give Reason :-

B. For Bridge (Size of Bridge / Culvert)

(1) Damage Location / Chainage :-

(2) No. of Span Damage :-

(3) Lenth of Span :-

(4) Nature of Damage (Pier/Abuttment/
Wing Wall/ Approach Road Damage) :-

(5) Details of Restoration :-

(i) Material Being Used in Restoration :-

(ii) Equipment / Tools Being used in Restoration Work :-

(iii) Restored Length

Overall Grade of restoration Work (Satisfactory/Unsatisfactory) :-


Signature of Inspector
(Official Seal)

DETAILED ESTIMATE FOR F.D.R.

General Abstract of Cost

Name of Road : ltharwa Dularpur to Murha Chatauna at Chainage 850m to 880m
 Length of Road : 5.83 Km
 Block : Sonbarsa
 DISTRICT : SITAMARHI

S.No.	Particulars	Total Cost (in Lakh)
1	Total Cost for Motorable Roads	-620752.00
	Total Cost of Road Repair	-620752.00
	Say	-620752.00

X4MAY
 15/11/24
 JE
 RWD Sonbarsa

AD
 15/11/24
 AE
 RWD Sonbarsa

AD
 15/11/24
 EE
 RWD Sitamarhi

T/S (Provisional) is accorded for Rs. 50,80,827.00

[Rupees five lakh eighty thousand eight hundred twenty seven only]

* *T/S (Provisional) is accorded for Rs. 5,88,904.00*
[Rupees five lakh eighty eight thousands, Nine hundreds four only].

MS
 अधीक्षण अभियंता
 ग्रामीण कार्य विभाग
 कार्य अंचल सीतामढ़ी
 15/11/2024
Q. Kishan
 15.11.24

Schedule of Quantity

Name Of Work : Itharwa Dularpur to Murha Chatauna at Chainage 850m to Block Sonbarsa
80m

No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to acheive required density with all complete as per the direction of engineer in charge.	405.00			0.00
	Less 20% for Voids	-81.00		1626.71	527054.04
		324.00	Cum	1698.60	550346.40
2	Providing Rabbishs including spreading laying hand packing and compacting with C.I hammer in layers not exceeding 75 mm thick including cost of light barrier,danger signals,chowkidar tax royalty etc all complite job as per specification and direction of E/I				
	Taking 20% of Brick Qty for Rabbish	81.00	Cum	560.18 639.90	51831.90 51831.90
3	Providing Bamboo (6m to 8m, 75mm dia)	60.00	Nos	274.62 459.56	16477.20 9573.60
4	Drone video recording(3 times)	3.00	Nos	3000.00	9000.00 5080.827.24
				Total Say	620,751.90 620,752.00 5,88,904.00 5,88,904.00

[Signature]
15/11/24
JE

[Signature]
15/11/24
AE

[Signature]
15/11/24
EE

Details of Measurement of ditches filled by brick bats and rubbish

Name Of Work : Itharwa Dularpur to Murha Chatauna at Chainage 850m to 880m.

Record ENTRY

	Length (in meter)		Width(in meter)	Average Width(in meter)	Area
at Chainage 850m to 880m	2x30 =	60.00	3m+ 1.5m	2.25	135.00

Depths Measured	Avg Depth
3	3

Volume= (Avg Depth x Avg Area)= 405.00 Cum

Total (in Cum) 405.00 Cum

Kumar
15/11/24
A.E.

[Signature]
15/11/24
A.E.

Aw
15/11/24

Rural Works Department, Govt. of Bihar



Welcome:-SESitamadhi
Wing:-CE-6,Darbhanga
Circle:-Sitamarhi
Division:-HQ
No Of Visit:-

- Home Road-Cutting Request User Menu and Profile Entry Forms Project Views MIS Reports QMC Reports Scheduled List Zone Reports Contractors Debar Time Extension
- NEW MR Contractor Revoke Flood/Rain Damage Roads Crash Inspection Contractor NEW MR Allotment Road / Bridge Allotment NEW MR Observation Offline Inspection Bridge Details
- Left Habitation Survey Routine Inspection Bridge Approach CM Jania Darbar POP Inauguration DPR RoadPavement BRMS Report Review Report
- NEWMR INS. Report

Flood/Rain Damaged Road/Bridge Report

Chief Engineer: CE-6,Darbhanga

Circle Sitamarhi

Division Sitamarhi

FDR Fin Year 2024-25

Show Data Download in Excel

Details of Road & Bridge															Start Po

20	CE- 6, Darbhanga	Sitamathi	Sitamathi	Sitamathi	Riga	pwd path rampur gangoli to jhinriya tola	MMGSY[SC]	Completed	Yes	2.491	0.200	5.00	OVERFLOW and cut	2024-25	Road	26.619775	8;
21	CE- 6, Darbhanga	Sitamathi	Sitamathi	Sitamathi	Riga	Riga Baspitra Path - From Riga to Helampur, Via Budhiwara, Najarpur, Sonar	PMGSY-NEA	Completed	Yes	7.5	0.500	6.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.704061	8;
22	CE- 6, Darbhanga	Sitamathi	Sitamathi	Sitamathi	Riga	Mohanpur - Bhabdeepur Path	PMGSY-NEA	Completed	Yes	2.25	0.500	1.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.603846	8;
23	CE- 6, Darbhanga	Sitamathi	Sitamathi	Sitamathi	Sonb arsa	Maharani Asthan to Mohchaati zaminrashekh ke ghar	MMGSY[SC]	Completed	Yes	2.9	0.080	40.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.783878	8;
24	CE- 6, Darbhanga	Sitamathi	Sitamathi	Sitamathi	Sonb arsa	MRLD1-Sonbarsa Rajwara REO to Indervra	PMGSY-II	Completed	Yes	7.14	0.010	10.00	OLD BRIDGE COLLAPSE ON BANKE RIVER	2024-25	Road	26.822508	8;
25	CE- 6, Darbhanga	Sitamathi	Sitamathi	Sitamathi	Sonb arsa	ITAHARWADULARPUR MURAHACHHATAUNA FDR	FDR	Completed	Yes	5.83	0.040	8.00	ON GOING	2024-25	Road	26.787418	8;
26	CE- 6, Darbhanga	Sitamathi	Sitamathi	Sitamathi	Sonb arsa	NH-77 to Bin tola	MMGSY[SC]	Completed	Yes	0.695	0.100	40.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.727487	8;
27	CE- 6, Darbhanga	Sitamathi	Sitamathi	Sitamathi	Sonb arsa	ARARUA - INDIRWA- II	PMGSY	Completed	Yes	2.805	0.090	30.00	OVERFLOW and CUT	2024-25	Road	26.782848	8;
28	CE- 6, Darbhanga	Sitamathi	Sitamathi	Sitamathi	Sonb arsa	L059-Lakhadei Pul to Mushahon Tola (VR60)	PMGSY	Completed	Yes	2.47	0.040	10.00	OVERTOPPING and cut	2024-25	Road	26.794733	8;
29	CE- 6, Darbhanga	Sitamathi	Sitamathi	Sitamathi	Sonb arsa	RANINAGAR RASALPUR - Chitr N.H 77	PMGSY	Completed	Yes	1.49	0.100	40.00	NO NEED FOR TEMPORARY RESTORATION	2024-25	Road	26.83094	8;
30	CE- 6, Darbhanga	Sitamathi	Sitamathi	Sitamathi	Sonb arsa	FATHEPUR SARBEPUR - NARPA BETAI KANHAUL BHASHAR PATH	PMGSY	Completed	Yes	8.72	0.050	20.00	OVERTOPPING and cut	2024-25	Road	26.808553	8;
31	CE- 6, Darbhanga	Sitamathi	Sitamathi	Sitamathi	Sonb arsa	Sonbarsa to Bhutahi via Rajwara and Lokhar	Other	On Going	No	22.4	0.060	10.00	OLD BRIDGE COLLAPSE ON BANKE RIVER and OVERTOPPING & cut	2024-25	Road	26.812507	8;