

कार्यपालक अभियंता का कार्यालय,
ग्रामीण कार्य विभाग, कार्य प्रमंडल,
मुजफ्फरपुर पूर्वी-1

पत्रांक 2710 अक

दिनांक 4/11/24

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग, कार्य प्रमंडल,
मुजफ्फरपुर पूर्वी-1

सेवा में,

अपर मुख्य कार्यपालक पदाधिकारी-सह-सचिव
बिहार ग्रामीण पथ विकास अभिकरण,
बिहार पटना।

विषय: शीर्ष राज्य योजना (नाबार्ड) अंतर्गत वित्तीय वर्ष 2024-25 में अनुरक्षण मद में व्यय हेतु आवंटन की मांग।

महाशय,

उपर्युक्त विषय प्रासंगिक पत्र के संबंध में शीर्ष राज्य योजना (नाबार्ड) अंतर्गत वित्तीय वर्ष 2024-25 में अनुरक्षण मद में व्यय हेतु संलग्न विवरणी के अनुसार 117441.00 (एक लाख सतरह हजार चार सौ एकतालिस) रुपये का आवंटन उपलब्ध कराने की कृपा की जाये ताकि किये गये कार्यों का भुगतान किया जा सके।

अनुलग्नक:- यथोक्त

विश्वासभाजन

4/11/24
कार्यपालक अभियंता
ग्रामीण कार्य विभाग, कार्य प्रमंडल,
मुजफ्फरपुर पूर्वी-1

राज्य योजना (नाबार्ड) अंतर्गत पथों में पंचवर्षीय अनुरक्षण अधियाचना प्रपत्र

राज्य योजना (नोड) अर्थात् न																									
क्र० सं०	कार्य प्रमंडल का नाम	योजना का नाम	एकराशनामा के अनुसार प्रावधानित राशि वर्षवार					कुल राशि (लाख में)	व्यय की राशि वर्षवार					कुल राशि (लाख में)	प्रशासनिक स्वीकृति की राशि एवं प्रसंग (लाख में)	पंचवर्षीय अनुरक्षण की राशि सहित अनुमोदित परिमाण विपत्र की राशि (लाख में)	अनुरक्षण हेतु प्रशासनिक स्वीकृति का पत्रांक/दिनांक	मूल निर्माण कार्य करने की वास्तविक तिथि	वर्तमान अधियाचित राशि					कुल अधियाचित राशि (लाख में)	
			प्रथम वर्ष राशि (लाख में)	द्वितीय वर्ष राशि (लाख में)	तृतीय वर्ष राशि (लाख में)	चतुर्थ वर्ष राशि (लाख में)	पंचम वर्ष राशि (लाख में)		प्रथम वर्ष राशि (लाख में)	द्वितीय वर्ष राशि (लाख में)	तृतीय वर्ष राशि (लाख में)	चतुर्थ वर्ष राशि (लाख में)	पंचम वर्ष राशि (लाख में)						प्रथम वर्ष राशि (लाख में)	द्वितीय वर्ष राशि (लाख में)	तृतीय वर्ष राशि (लाख में)	चतुर्थ वर्ष राशि (लाख में)	पंचम वर्ष राशि (लाख में)		
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26
											</														

- 1 कार्य विवरणों के अनुरूप पूर्ण कर लिया गया है।
- 2 पथ में MGNUL/ROM/IE से संबंधित कोई सुधार प्रतिवेदन लंबित नहीं है।
- 3 अनुमोदित परिमाण विपत्र की कुल राशि प्रशासनिक स्वीकृति की राशि से 20% अधिकतम सीमा के भीतर है साथ ही अनुमोदित परिमाण विपत्र के मदों का विस्तार का विचलन भी 20% से ज्यादा नहीं है।
- 4 अनुमोदित - प्रशासनिक स्वीकृति का पत्र, अनुमोदित परिमाण विपत्र एवं एकराशनामा की अभिप्रमाणित प्रति।


 कार्यपालक अभियंता,
 ग्रामीण कार्य विभाग, कार्य प्रमंडल,
 मुजफ्फरपुर पूर्वी-1
 21.11.2019

बिहार सरकार
ग्रामीण कार्य विभाग

पत्रांक - मु0 अ0-4 (मु0)-नाबार्ड-03-39/2017

/पटना, दिनांक-

प्रेषक,

संजय कुमार, भा0प्र0से0

अपर सचिव।

सेवा में,

महालेखाकार, बिहार

वीरचन्द पटेल पथ, पटना।

आंतरिक वित्तीय सलाहकार द्वारा
अनुपचारिक रूप से प्रामाणिक

विषय:- योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परिव्यय-103-ग्राम विकास-राज्य योजना-0105-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना)-उपशीर्ष के अन्तर्गत बिहार राज्य के विभिन्न जिलों में (परिशिष्ट-1 के रूप में संलग्न सूची के अनुरूप) कुल 87 पथ निर्माण योजनाओं पर पथवार प्रशासनिक स्वीकृति प्रदान करने के संबंध में।

महाशय,

निदेशानुसार योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परिव्यय-103-ग्राम विकास-राज्य योजना-उप शीर्ष-0105-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना)-उप शीर्ष के अन्तर्गत बिहार राज्य के विभिन्न जिलों में (परिशिष्ट-1 के रूप में संलग्न सूची के अनुरूप) कुल 87 पथ निर्माण योजनाओं जिसकी लम्बाई 84.766 कि०मी० एवं राशि रू० 53.3065967 करोड़ (तिरपन करोड़ तीस लाख पैसठ हजार नौ सौ सड़सठ रू० मात्र) है-हेतु पथवार प्रशासनिक स्वीकृति प्रदान की जाती है।

परिशिष्ट-1

नाबार्ड संपोषित योजना अन्तर्गत वित्तीय वर्ष 2017-18 के लिए प्रशासनिक अनुमोदित योजनाओं की सूची :-								
Sl No.	District	Works Division	Block	MMGSY CNCPL No.	Name of Road	Length (K.M)	TA Amount (In Lacs)	Amount Lac/K.M
1	2	3	4	5	6	7	8	9
1	Patna	Patna	Fatuha	S038	Saidpur Chandasi Path to Yamanpura	0.555	38.482	69.3369369
2	Patna	Patna	Khushrupur	S04	NH-30 se 100m Aage (Nagarnausa Taraf) to Harijan Tola	0.515	36.039	69.9786408
3	Patna	Patna	Daniyawan	S06	NH-30A Jodhan Bigha	0.525	34.848	66.3771429
4	Patna	Danapur	Maner	S030	Maner-Haldichapra Road to Dhajawa tola	1.00	69.86850	69.8685
5	Patna	Danapur	Bihta	S042	Bihta Bikram Road to Kanchanpur Yadav Tola	1.10	68.48430	62.2584545
6	Patna	Masaurhi	Punpun	S03	Pothi Bripur Path to Parthu main Road Mahadalit tola.	1.00	59.90840	59.9084
7	Patna	Masaurhi	Masaurhi	S033	Nadaul Bhagwanganj Path to Nadauna.	0.35	20.92597	59.7884857
8	Patna	Masaurhi	Dhanarua	S024	Sewai Mode to Tadwan	2.10	127.44	60.6857143
9	Patna	Paliganj	Naubatpur	S020	Bari Tairaila to Bedulli	1.06	65.80	62.0754717
10	Patna	Paliganj	Dulhin Bazar	S016	Pali Masaurhi Road to Shihi Takiya (Nawada)	1.10	61.53	55.9363636
11	Patna	Paliganj	Naubatpur	S014	Gonwan Palu Chhitani Road to Navadinan	0.55	30.90	56.1818182
12	Patna	Paliganj	Bikram	S026	Tiluchak Sundarpur road to Taripur	0.3	22.80250	76.008
13	Lakhisarai	Lakhisarai	Chanan	S024	PMGSY Malya to South Manihi tola Malya	0.720	40.774	56.6305556

Sl. No.	District	Works Division	Block	MMGSY CNCPL No.	Name of Road	Length (K.M)	TA Amount (In Lacs)	Amount Lac/K.M
1	2	3	4	5	6	7	8	9
14	Lakhisarai	Lakhisarai	Lakhisarai	S013	T012 ODR to SaaroBaro Harijan Tola	1.125	68.519	60.9057778
15	Lakhisarai	Lakhisarai	Ramgarh Chowk	S015	L033 to Ramnagar	0.790	46.503	58.864557
16	Lakhisarai	Lakhisarai	Suryagarha	S031	L049 Sahur to Jagira	0.620	39.752	64.116129
17	Lakhisarai	Lakhisarai	Halsi	S011	Sethna Salaunza Nahar Road to Baajitpur.	1.610	78.99	49.0621118
18	Lakhisarai	Lakhisarai	Pipariya	S01	Middle School Diyara Pipariya to Karari Pipariya.	1.865	135.95	72.895442
19	Lakhisarai	Lakhisarai	Ramgarh Chowk	S02	L056 to Bhamariya Manjhi Tola	1.600	93.44	58.40
20	Katihar	Katihar	Hasanganj	S01	Madarsa Chowk to Bagghabari	1.05	67.296	64.0914286
21	Katihar	Katihar	Hasanganj	S012	T01 to Naga Tola	0.575	38.608	67.1443478
22	Sheikhpura	Sheikhpura	Barbigha	S005	Barbugha Toy path Terarpur more to Saraiya.	0.936	56.075	59.909188
23	Sheikhpura	Sheikhpura	Chewara	S038	Ekray Path to Kemra Mushari	0.745	48.460	65.0469799
24	Sheikhpura	Sheikhpura	Sheikhpura	S010	Mehus Chimani par to Maniauri via Nawada	0.730	43.348	59.3808219
25	Supaul	Triveniganj	Triveniganj	S129	PWD Parsahi sadak Kuwar Yadav ke ghar to Parsahi Mohan Yadav Tola tak.	0.846	60.76	71.820331
26	Chapra	Chapra-2	Jalalpur	S016	Bangra to Bangra -4.	1.195	68.715	57.5020921
27	Chapra	Chapra-2	Jalalpur	S054	Dhenki to Devbariya tak.	0.500	28.174	56.348
28	Chapra	Chapra-2	Lahladpur	S049	Purusotampur Sonia PMGSY Kishanpur Lauaar Panchayat Bhawan se Bhatbaliya khas.	0.515	39.073	75.8699029
29	Chapra	Chapra-1	Garkha	S057	Dhanaura High School to Dhanaura Jaggu Singh ke ghar tak.	0.39	31.015	79.525641
30	Chapra	Chapra-1	Sadar Chapra	S036	Middle School Fakuli to Umdha.	1.055	58.328	55.2872038
31	Chapra	Chapra-1	Sadar Chapra	S019	Mathiya Gramin Sadak to Hasanpurva Chhat Talab tak.	0.700	44.519	63.5985714
32	Chapra	Madhaura	Amnaur	S062	Raipura Mura PMGSY Path to Hakama Paschim Tola.	0.97	68.439	70.5556701
33	Chapra	Madhaura	Taraiya	S034	Yakuchak Pachraur PMGSY to Pokhara tak	0.605	25.623	42.3520661
34	Chapra	Madhaura	Panapur	S036	Ubhawa Bhola Pandey ke ghar to Masitid tak	0.445	29.037	65.2516854
35	Chapra	Madhaura	Panapur	S030	Totha PMGSY to Simari Pakki Sadak.	0.999	62.17	62.2322322
36	Chapra	Sonpur	Maker	S18	Maker-Mahesh Chapra PMGSY to Purshotimpur Bazar	1.595	104.87	65.7492163

Sl. No.	District	Works Division	Block	MMGSY CNCL No.	Name of Road	Length (K.M)	TA Amount (In Lac)	Amount Lac/K.M
1	2	3	4	5	6	7	8	9
37	Chapra	Sonpur	Maker	S001	Bishunpura Piprahi PMGSY Sadak to Gandak Nahar	3.375	194.45	57.6148148
38	Chapra	Sonpur	Dariyapur	S04	Khajauli PMGSY path se Ghanechapra gram in path tak.	1.845	120.12	65.1056911
39	Chapra	Chapra-1	Nagra	S011	Chapra-Masrakh PWD Road (Yogendra Singh ke Ghar) to Afaur Purab Tola.	2.040	110.32	54.0784314
40	Chapra	Chapra-1	Nagra	S015	T05 Sargatti PMGSY to takliya.	1.685	98.30	58.3382789
41	Chapra	Chapra-2	Baniyapur	S039	Dhobwal Sekhpura PMGSY se Gowa Piparpatti Nagdevi Tola hote	1.950	114.43	58.6820513
42	Chapra	Chapra-2	Baniyapur	S054	Harpur Karah PMGSY se Ram Tola tak	1.690	108.43	64.1597633
43	Chapra	Chapra-2	Lahaladpur	S024	Ekna Masrakh PMGSY Sansa Transformer ke pass se Shambhu Chapra Khas tak	1.805	103.22	57.1855956
44	Chapra	Madhaura	Amnaur	S043	Salkhua Marhaura PMGSY Path to Parsa Bhatti PMGSY Road.	2.890	179.18	62.00
45	Chapra	Madhaura	Masrakh	S070	Nirsu dhala Pakki sadak to 40 RD Nahar Pul tak.	3.250	203.10	62.4923077
46	Chapra	Madhaura	Madhaura	S016	Silauri Paharpur PMGSY Path to Mathiya tak	2.550	134.16	52.6117647
47	Chapra	Madhaura	Masrakh	S021	Mashrakh Sahajitpur road to Sankauli PCC.	2.095	140.89	67.2505967
48	Chapra	Madhaura	Taraiya	S02	Bhataura Primary School to Bhataura Devi Asthan.	1.415	91.98	65.0035336
49	Muzaffarpur	Muzaffarpur East-1	Bandra	S031	Patsara dhobi tola samudaiyk bhawan to Baijnathpur.	2.490	170.38	68.4257028
50	Muzaffarpur	Muzaffarpur East-1	Kurhani	S06	PMGSY (Kharauna Dih) to Harijan Dalit Basti	0.850	54.30	63.8788235
51	Muzaffarpur	Muzaffarpur East-1	Bandra	S032	Karmaith Kewatsa path to Marha tola	0.650	46.74	71.9076923
52	Muzaffarpur	Muzaffarpur East-1	Kurhani	S05	MMGSY (Paltan Chaudhary ke Ghar) to Jairam Tola (Kharauna Dih)	0.57	45.70	80.1754386
53	Muzaffarpur	Muzaffarpur East-1	Sakra	S030	PMGSY Rasulpur Maniyari to Muslim Tola.	1.125	80.14	71.2355556
54	Muzaffarpur	Muzaffarpur East-1	Saraiya	S051	Karja Jaitpur road Nawada kedar misra ke ghar to Repura muslim tola tak.	1.782	109.12	61.2345679
55	Muzaffarpur	Muzaffarpur East-1	Saraiya	S098	Nargi Jivnath PMGSY road to Govindpur se Khaira road tak.	2.207	129.410	58.6361577

Sl. No.	District	Works Division	Block	MMGSY CNCPL No.	Name of Road	Length (K.M)	TA Amount (In Lacs)	Amount Lac/K.M
1	2	3	4	5	6	7	8	9
56	Muzaffarpur	Muzaffarpur East-1	Sakra	S033	Middle school Majhauria to Satpura muraul block siman tak.	2.260	154.860	68.5221239
57	Muzaffarpur	Muzaffarpur East-1	Musahari	S046	SH102 Ramesh Thakur ke Dalan to Patahi Jagannath Late Kalyan Thakur ke ghar tak	1.00	76.04	76.04
58	Begusarai	Teghara	Bachhwara	S029	Tara to Maranchi	0.51	35.86	70.3137255
59	Samastipur	Samastipur	Samastipur	S026	L073 Chaknoor to Sahni Tola	0.700	47.63	68.0428571
60	Begusarai	Teghara	Bhagwanpur	S049	S048 Mahadalit tola to Larwapur Bandh via house of Munna Mahto (Telan)	1.340	92.57	69.0820896
61	Begusarai	Teghara	Bhagwanpur	S048	Naula pul to Kharooli via Jokia Bandh, Khakhara Gusha	4.105	249.01	60.6601705
62	Madhubani	Fulparas	Khutauna	S060	Malik Arjun Thakur Ghar to Kolhatta	1.901	133.73	70.3471857
63	Siwan	Siwan-1	Hasanpura	S021	Arjal Bazar to Mandrauli Mauja Bhediari Tola	1.000	65.736	65.736
64	Siwan	Siwan-1	Siswan	S026	Naya Gao PWD Road to Chhotaki Nawada via Badaki Nawada	0.500	33.568	67.136
65	Siwan	Siwan-1	Siwan	S02	Siwan Lakadi Path ke Orma Uttar Tola Kothi to Bindusar Hamid	1.050	69.866	66.5390476
66	Siwan	Siwan-1	Siswan	S05	Siswan Chapra CMDG Road to Tolapur	0.800	54.443	68.05375
67	Siwan	Siwan-1	Hasanpura	S027	Laheji Bazar to Mandrauli	1.000	67.513	67.513
Total						84.766	5330.65967	

2. इस योजना को दो द्वितीय वर्ष 2017-18 एवं 2018-19 में पूरा किये जाने का लक्ष्य है।

3. कार्यपालक अभियंता, ग्रामीण कार्य विभाग, संबंधित कार्य प्रमंडल, योजना की विस्तृत कार्य योजना तैयार करेंगे तथा उसके अनुरूप कार्यों को समयबद्ध ढंग से पूर्ण कराना सुनिश्चित करेंगे।

4. कार्यपालक अभियंता, संबंधित कार्य प्रमंडल सुनिश्चित करेंगे कि स्वीकृत पथ किसी अन्य योजना के अन्तर्गत सम्मिलित नहीं है।

5. कार्यपालक अभियंता, संबंधित कार्य प्रमंडल, योजना के कार्य सम्पादन हेतु निकासी एवं व्ययन पदाधिकारी होंगे।

6. कार्य ई-निविदा के माध्यम से Standard Bidding Document के आधार पर कराया जायेगा।

7. कार्यों की गुणवत्ता सुनिश्चित करने की जिम्मेवारी संबंधित कार्यपालक अभियंता की होगी; किये गये कार्यों का भुगतान गुणवत्ता के जाँचफल के गुण-दोष के आधार पर किया जायेगा।

8. योजना के क्रियान्वयन से पूर्व इस पर सक्षम पदाधिकारी से प्रावधिक स्वीकृति प्राप्त कर ली जायगी। प्रावधिक स्वीकृति के समय सभी सक्षम प्राधिकार IRC SP-72 वर्ष 2015 एवं IRC SP-62 वर्ष 2014 के तकनीकी प्रावधानों का अक्षरशः अनुपालन सुनिश्चित करेंगे।

9. इस योजना का व्यय योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूँजीगत परिव्यय-103-ग्राम विकास-राज्य योजना-0105-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना)-उपशीर्ष निव्यय विभाग कोड P-4515001030105 एवं स्कीम कोड-5369 के अन्तर्गत वित्तीय वर्ष 2017-18 में उपबंधित राशि से विकलनीय होगा।

10. योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूँजीगत परिव्यय-103-ग्राम विकास-राज्य योजना-0105-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना)-उपशीर्ष के अन्तर्गत वित्तीय वर्ष 2017-18 में 454.31 लाख रुपये का बजट उपबंध स्वीकृत है।

11. कार्यपालक अभियंता, ग्रामीण कार्य विभाग, संबंधित कार्य प्रमंडल, द्वारा योजना का भौतिक एवं वित्तीय प्रगति प्रतिवेदन प्रत्येक माह के 10 तारीख तक निश्चित रूप से कमशः संबंधित अधीक्षण अभियंता एवं संबंधित मुख्य अभियंता, पटना के माध्यम से विभाग को उपलब्ध कराया जायेगा।

12. इन योजनाओं का निर्माण नाबार्ड के तहत कराये जाने के प्रस्ताव पर मा० मुख्यमंत्री महोदय, बिहार सरकार का अनुमोदन प्राप्त है।

13. इन पथवार योजनाओं के प्रशासनिक स्वीकृति के प्रस्ताव पर संधिका सं०- मु० अ०-४ (मु०) नाबार्ड-०३-३९/२०१७ के पृ० सं०-१२/टि० पर दिनांक ०७.०४.१७ को अनुमोदन प्राप्त है।

14. बिहार कोषागार संहिता में निहित प्रावधानों के आलोक में बजट प्रावधान के अंतर्गत ही राशि की निकासी की जाय।

15. वित्त विभाग के संकल्प संख्या-४-४५/९४-३०१ वि (२) दिनांक ३१.०१.१९९५ एवं वित्त विभाग के पत्रांक स्कीम (८)-११-२००५-५०९० वि (२) दिनांक १५.०९.०५ एवं २९५ दिनांक २४.०३.१५ के आलोक में तथा वित्त विभाग के संकल्प सं० ९६ दिनांक ०३.०१.२००८ में निहित निदेशों का अक्षरशः पालन किया जाय तथा बिहार वित्त नियमावली के सुसंगत प्रावधानों के आलोक में योजना में उपबंधित राशि की उपलब्धता के आधार पर व्यय की जाय। यह आदेश आंतरिक वित्तीय सलाहकार की सहमति प्राप्त कर निर्गत किया जा रहा है। आंतरिक वित्तीय सलाहकार की सहमति संधिका सं०- मु० अ०-४ (मु०) नाबार्ड-०३-३९/२०१७ के पृष्ठ संख्या-१५/टि० पर दिनांक- २३.५.१७ को प्राप्त है।

16. यह राशि उसी मद में खर्च की जायेगी, जिसके लिए पुनर्विनियोजित की गयी है, अन्य में नहीं।

17. योजना के लिए संबंधित कार्यपालक अभियंता से विस्तृत कार्य योजना मांगी जायेगी एवं प्राक्कलन की विशिष्टताओं के अनुसार निर्धारित समय सीमा के अंदर कार्य पूर्ण कराना सुनिश्चित किया जाय।

18. योजना के कार्यान्वयन के कम में इनका निर्धारित निरीक्षण (नियमित अंतराल पर) अनिवार्य रूप से किया जाय तथा प्रतिवेदन अभिलेखबद्ध किया जाय।

19. वित्त विभाग के पत्रांक-७७०, दिनांक २०.०९.११ के द्वारा सूचित किया गया है कि नाबार्ड से RDPF के अन्तर्गत नई परियोजनाओं की प्रशासनिक अनुमोदन प्राप्त करने के उपरान्त ही स्वीकृति हेतु नाबार्ड को भेजी जाये।

विश्वासभाजन

ह०/-

(संजय कुमार)

अपर सचिव

ज्ञापक- मु० अ०-४ (मु०)-नाबार्ड-०३-३९/२०१७

/पटना, दिनांक-

प्रतिलिपि- सभी संबंधित कोषागार पदाधिकारी, जिला कोषागार/उप कोषागार को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित।

ह०/-

अपर सचिव

ज्ञापक- मु० अ०-४ (मु०)-नाबार्ड-०३-३९/२०१७

5761

/पटना, दिनांक- ०५/०५/१७

प्रतिलिपि- माननीय मंत्री के आप्त सचिव, ग्रामीण कार्य विभाग/प्रधान सचिव, योजना एवं विकास विभाग/वित्त विभाग (आय-व्यय शाखा)/आंतरिक वित्तीय सलाहकार, ग्रामीण कार्य विभाग/मंत्रिमंडल सचिवालय एवं समन्वय विभाग/कार्मिक एवं प्रशासनिक सुधार विभाग, सभी संबंधित प्रमण्डलीय आयुक्त/सभी संबंधित जिला पदाधिकारी/सभी संबंधित उप विकास आयुक्त/अभियंता प्रमुखए ग्रा० का० वि०, बिहार, पटना/सभी संबंधित मुख्य अभियंता, पटना, ग्रामीण कार्य विभाग/मु० अ०-४ (मुख्यालय), ग्रा० का० वि०/सभी संबंधित अधीक्षण अभियंता, ग्रा० का० वि०, कार्य अंचल/सभी संबंधित कार्यपालक अभियंता, ग्रा० का० वि० कार्य प्रमंडल/मुख्य महाप्रबंधक नाबार्ड, बिहार क्षेत्रीय कार्यालय, (मौर्या कम्पलेक्स, पौंचवी मंजिल) डाक बंगला रोड, पटना को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित। अतिरिक्त नोडल, ग्रामीण कार्य विभाग को विभाग के वेबसाइट पर अपलोड करने हेतु प्रेषित।

अपर सचिव

भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये

रु.1000

ONE THOUSAND RUPEES

Rs.1000

INDIA



2800
7/1/18

2800, 942 12/1/18
Amilgopal 427286
127(1) 5 100/18

AGREEMENT FORM

This Agreement made on the between Executive Engineer R.W.D. Works Division, Muzaffarpur East-1 (name and address of Employer) hereinafter called "the employer" and Satish Kumar Mishra, S/o - Hari Narayan Mishra, Vill. : Fatehabad, Post - Paroo, Distt. : Muzaffarpur (name and address of contractor) hereinafter called "the contractor" on the other part.

Whereas the Employer is desirous that the contractor execute Karmaitina Kewatsa Path to Marha Tola UNDER Naward.

(name and identification number of contract) (hereinafter called 'the works') and the Employer has accepted the Bid by the contractor for the execution and completion of such works and the remedying of any defects therein, at a cost of Rs. 41,01,249.00 (Rupees Forty One Lakh One Thousand Two Hundred Forty Nine Only).

NOW THIS AGREEMENT WITNESSETH as follows:-

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the conditions of contract hereinafter referred to and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer, the contractor as hereinafter mentioned, the contractor hereby covenants with the employer to execute and complete the works and remedy any defects therein in conformity in all aspects with the provisions of the contract.

[Signature]

[Signature]
07.12.18

[Signature]
Executive Engineer
R.W.D. Works Division
Muzaffarpur East-1

[Signature]
7/1/18

1. Name of the work : Karmaita Kewatsa Path to Marha Tola UNDER Naward.
2. No. of roads. : One
3. Length of the road. : 0.65 K.M.
4. Name of the Agency & Address : Satish Kumar Mishra,
S/o - Hari Narayan Mishra, Vill. : Fatchabad,
Post - Paroo, Distt. : Muzaffarpur
5. Agreement No. : 92/SBS/2017-18
6. Approval of Rate : S.E., R.W.D. Muzaffarpur, letter No. 1544 enc.
dt. 07.09.2017 on 10.00 % below from
Schedule rate.

7. Agreement value of the work:-

(a) Construction cost ———

Rs. 42,94,298.00

(b) Maintenance cost ———

Rs. 2,62,645.00

Rs. 45,56,943.00 Less 10.00% below from
Schedule rate.

Rs. 41,01,249.00

(Rupees Forty One Lakh One Thousand Two
Hundred Forty Nine Only).

8. Performance security (including
earnest money)

4.75% (Four point Seven five percent) of the
Agreement value. (Rs. 1,95,000.00)

Performance security (including earnest money) deposited by the Agency in the
form of FD & NSC amounting to Rs. 1,95,000.00 The details of FD & NSC is as follow:-

(i) Allahabad Bank	A/c No. 50389659219	Rs. 21,000.00
(ii) Allahabad Bank	A/c No. 50349518446	Rs. 25,000.00
(iii) Allahabad Bank	A/c No. 50326775342	Rs. 92,000.00
(iv) Allahabad Bank	A/c No. 50349154011	Rs. 40,000.00
(v) Allahabad Bank	A/c No. 50431607503	Rs. 3,000.00
(vi) Allahabad Bank	A/c No. 50393399784	Rs. 3,000.00
(vii) NSC5NS90CC454897	1000 x 1	Rs. 1,000.00
(viii) NSC5NS30EF854778	10000 x 1	Rs. 10,000.00
		Rs. 1,95,000.00

(Rs. One Lakh Ninty Five Thousand Only)

9. Date of work Order : 14.09.2017
10. Date of completion : 13.06.2018 (9 Months)
11. Security Deposit : 9% (Nine percent) to be deducted from the
gross amount of each running Bill.
Five years from the actual date of completion
of the work.
12. Defect liability period : After five years from the actual date of
completion of the work.
13. Refund of performance security
and security deposit. : 35 (Thirty five) item in each road.
14. Total item of Agreement : 35 (Thirty five) item in each road.

Note:- S.B.D. Rules, terms and conditions will be applicable.

Ach

Divisional Accounts Officer
R.W.D. (W) Division

Executive Engineer
R.W.D. Works Division
Muzaffarpur

MUKHYA MANTRI GRAM SAMPRAK YOJANA (MMGSY) NABARD FUNDED

BILL OF QUANTITIES (BOQ) - CONSTRUCTION

Name of Road : Karmalith Kewatsa path To Marha tola

Package No. :

Length of Road : 0.650

District : Muzaffarpur

L / TR No. : S0-32

Block : Bandra

Sl. No.	SOR No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
(A) PREPRATORY WORK & SITE CLEARANCE						
1	1.16	Setting Out Setting Out as MORD Specification 100 Item Nos (i), (ii), (iii) & (iv)				
i	i, ii	Construction of Reference & Working Benchmarks	Km	0.650	4063.96	2642
ii	iii	Construction of Reference Pillars/Burjees	Km	0.650	1862.10	1210
2	2.2	Clearing and Grubbing Road Land Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300 mm, removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150 mm in thickness as per Technical Specification Clause 201.				
	(i)	By Manual Means				
	(A)	In area of non-thorny jungle	Hect.	0.26	45966.85	11951
3	3.3	Construction of Embankment with Material Obtained from Roadway Cutting Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5.	Cum	703.55	129.4979	91108
	3.5(ii)	Excavation for roadwork in soil by Mechanical Means including cutting and pushing the earth to site of embankment up to a distance of 100 m, including trimming bottom and side slopes in accordance with requirement of lines, grades and cross sections	Cum	60.75	28.71	1744
4	3.4	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	Cum	731.68	159.31	116562
5	3.5	Box Cutting For Pavement Construction Excavation for roadway in soil Using manual means for currying of cut earth to embankment site with a lift upto 1.5 m and lead upto 100 m as per Technical Specification Clause 302.3	Cum	60.75	113.29	6882
(C) SUB-BASE						
6	4.1	Granular Sub-base with Well Graded Material (Table 400.1) Construction of granular sub-base by providing well graded material (Crushed Stone Aggregates and Local Sand), spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with three wheel 80-100 kN static roller capacity to achieve the desired density, complete as per Technical Specification Clause 401				
	(ii)	For Grading I Material	Cum	303.54	3356.42	1018808
(D) BASES						
7	4.7	Water Bound Macadam with Stone screening				
	3)	WBM Grading 3				

Approved as Corrected

BILL OF QUANTITIES (BOQ) - CONSTRUCTION

Name of Road : **Karmalth Kewatsa path To Marha tola**

Package No. :

Length of Road : **0.650**

District : **Muzaffarpur**

L / TR No. : **S0-32**

Block : **Bandra**

Sl. No.	SOR No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
		Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.				
	(A)	(A) By Manual Means	Cum	209.95	3889.26	816550
8	4.18	Laying brick soling layer on prepared sub-grade with brick on end edging according to lines, graded and cross-section shown on the drawing filling joints with sand and earth, spreading 25 mm thick layer of earth over brick soling, watering and rolling the same with three wheel road roller 80-100 kN as per Technical Specification Clause 412	Sqm	250.00	630.91	157727
(D) WEARING COURSE						
9	5.1	Prime Coat (Low Porosity)				
	(i)	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70±1.0kg/sqm using mechanical means as per Technical Specification Clause 502	Sqm	1740.00	47.51	82668

99

Approved as Corrected

S.E.

BILL OF QUANTITIES (BOQ) - CONSTRUCTION

Name of Road : Karmalth Kewatsa path To Marha tola

Package No. :

Length of Road : 0.650

District : Muzaffarpur

L / TR No. : S0-32

Block : Bandra

Sl. No.	SOR No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
10	5.6	Surface Dressing using Bituminous Case I				
		Providing and laying surface dressing as weaing couesd consisting of a layer of bituminous binder laid on the prepared surface. Followed a cover of crusehd stone chipping s of specified size and rolling with 80-100 kN static roller including cleaning the road surface as per Technical Specification clause 507.	Sqm	1515.00	86.84	131556
11	5.6	Surface Dressing using Bituminous Case II				
		Providing and laying surface dressing as weaing couesd consisting of a layer of bituminous binder laid on the prepared surface. Followed a cover of crusehd stone chipping s of specified size and rolling with 80-100 kN static roller including cleaning the road surface as per Technical Specification clause 507.	Sqm	1515.00	76.94	116561
		(E) C.C. PAVEMENT				
12	6.4 (a)	Cement Concrete Pavement M30 Construction of un-reinforced, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M25 (Grade); coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and water finishing to lines and grade as per drawing and Technical Specification Clause 1501.	Cum	169.50	7391.67	1252889

9/24

Approved as Corrected

✓

SE

26

BILL OF QUANTITIES (BOQ) - CONSTRUCTION

Name of Road : Karmalith Kewatsa path To Marha tola

Package No. :

Length of Road : 0.650

District : Muzaffarpur

L / TR No. : S0-32

Block : Bandra

Sl. No.	SOR No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
TRAFFIC SIGNS, MARKINGS & OTHER ROAD APPURTENANCES						
13	10.10	Kilometre Stone Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703				
ii	ii	Ordinary Kilometer Stone (Precast)	Each	1	2393.25	2393
iii	iii	200 m stone (precast)	Each	3	638.41	1915
14	10.11	Boundary Pillar Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC:25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	Each	13	520.18	6762
15	10.5	Painting Two Coats on New Concrete Surfaces Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701 (For culverts)	Sqm	22.32	100.38	2240
16	10.1	Printing New Letters and Figures of any Shade Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701	Per cm ht. per letter			
	ii	English and Roman (for culverts)		88	0.49	43

Approved as Corrected

BILL OF QUANTITIES (BOQ) - CONSTRUCTION

Name of Road : Karmalith Kewatsa path To Marha tola

Package No. :

Length of Road : 0.650

District : Muzaffarpur

L/ TR No. : S0-32

Block : Bandra

Sl. No.	SOR No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
17	10.16	Providing and Fixing 'PMGSY sign board and Logo' of PMGSY Project				
	(A)	PMGSY Sign Board				
		Providing and fixing of typical PMGSY Informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	Each	2	10901.02	21802
18	10.2	Retro-reflectorised Traffic Signs				
	(A)(i)	Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801				
	(ii)	600 mm equilateral triangle	Each	6	3993.28	23960
	(v)	600 mm x 450 mm rectangular	Each	2	5383.09	10766
	(vii)	900 mm side octagon	Each	2	10071.36	20143
19	8.13 RCD SOR MoRTH	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface	Sqm	80	829.00	66320
20	8.13	Cable Duct Across the Road: Providing and laying of a reinforced cement concrete pipe duct, 300 mm dia, across the road (new construction), extending from drain to drain in cuts and toe of	Rmt	38	1107.18	41519
					Total	4006721

99

Approved as Corrected

[Handwritten signature]
S.E.
[Handwritten signature]

BILL OF QUANTITIES (BOQ) - CONSTRUCTION

Name of Road : Karmalith Kewatsa path To Marha-tola

Length of Road : 0.650

L / TR No. : S0-32

Package No. :

District : Muzaffarpur
Block : Bandra

Sl. No.	SOR No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
Cross Drainage Work						
21	11.1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	Cum	33.54	263.65	8843
22	11.4(I) (I)	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-15	Cum	2.65	5,723.35	15167
23	11.5(II)	Brick masonry work in cement mortar in foundation complete excluding pointing and plastering as per drawing and technical specifications Clauses 600, 1202 & 1203	Cum	16.61	6,776.62	112560
24	12.1 (II)	Brick masonry work in cement mortar in substructure complete excepting pointing and plastering, as per drawing and technical specification Clauses 602, 603, 604, 1202 & 1204	Cum	10.16	7,077.21	71904
25	13.9	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	Cum	2.88	7,013.63	20199
26	12.3	Plastering with cement mortar (1:4), 15 mm thick on brickwork in substructure as per technical specification Clauses 613.4 & 1204	Sqm	20.16	171.41	3456
27	9.3	Providing and laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry				
	B	1000MM Dia Pipe	RM	7.50	4,278.08	32086
28	9.2(ii)	Laying (First Class) bedding on well compacted sand, moorum or approved granular material as per Clause 1105 (ii) Type B (First Class) Bedding	Cum	4.87	450.73	2195
29	11.2	Filling in foundation trenches as per drawing and technical specification Clause 305.3.9 (i) Sand Filling				
		Using Fine Sand	Cum	7.64	450.73	3444
30	14.1	Providing and laying boulder apron for bed protection with stone boulders of minimum size and weight as per Table 1300.1, no fragment weighing less than 25 kg laid dry complete as per drawing and technical specifications Clause 1301	Cum	5.57	3,181.94	17723
Total						4294297.6
Grand Total Cost (in Lacs)						42.94
31		1st Year Maintenance Cost	year	1	25032	25032
32		2nd Year Maintenance Cost	year	1	29614	29614
33		3rd Year Maintenance Cost	year	1	57040	57040
34		4th Year Maintenance Cost	year	1	69073	69073
35		5th Year Maintenance Cost	year	1	81873	81873
Total						262632.0
Grand Total Cost (in Lacs)						45.57

Handwritten signature

Approved as Corrected

Handwritten signature

Handwritten signature

Approved for


4-294297.00

Construction Cost for Rs. ~~4-29429~~ (Rupees Crores. Forty

Two Lac. ~~Ninety four~~ Thousand Two Hundred ~~Ninety seven~~ Only

(ii) Maintenance Cost for Rs. 262632.00 (Rupees Two Lac.

sixty two Thousand Six Hundred Thirty two) Only.


Superintending Engineer
Rural Works. Department
Works Circle, Muzaffarpur


29/05/12
AE