



First Party Name * : Not Applicable
Second Party Name * : ARPIT ENGICON PVT LTD
Purchased By * : ARPIT ENGICON PVT LTD
Certificate Number : BR038161211731137708584
Consideration Price : ₹0.00/-
Stamp Duty Paid : ₹1000.00/-
Registration Fee & Other Fees : ₹0.00/-
LLR & Proc Fee : ₹0.00/-
Miscellaneous Fees : ₹0.00/-
Discore SC : ₹0.00/-
Total Amount : ₹1000.00/- (One Thousand)



----- This stamp paper will only be valid if embossed below with special RED ink impression -----

Phone No:
Sold To/Issued To:
For Whom/ID Proof:
ARPIT ENGICON

भारत INDIA
INDIA NON JUDICIAL
DSR OFFICE
HAJIPUR
844101



NOV-09-2024 13-13-43
₹ 0001000/-
38161211731137708584-00008167
2816121 2848

SUPPLEMENTARY AGREEMENT FORM

Agreement No.- *Supplementary of OF/MBD/2022-27*

This supplementary agreement, made the Day of
between The Executive Engineer, Rural Work Department, Work Division, Patori and Arpit Engicon
Pvt. Ltd., At- NayaTola, Dighi Khurd, Hajipur, Distt – Vaishali - 844101 (Bihar) hereinafter called “
The Contractor” of the other part.

Whereas The Employer is desirous that the Contractor execute the work – MR-N/19-
20 Patori/02 under head MR (3054. Details of roads are as follow-

Sl. No.	Name of Road	Length in K.M.	Construction work Amount	5 Year Maintenance Amount in Rs.	Total	Agreement Value in Rs. At Below quoted rate 10%
02	Patori Madudabad Purani Bazar To Sultanpur	6.50	25102374.9	6530025.90	31632400.8	28469160.70
			25102374.9	6530025.9	31632400.8	28469160.7

(hereinafter called “The works and the Employer has accepted the Bid by the contractor for the execution and completion of such works and the remedying of any defects therein on his quoted rate 10 % (TenPercent) below of the B.O.Q. rate for a cost of Rs. Rs. 45469876.00 (Rs. Four Crore Fifty Four Lakh Sixty Nine Thousand Eight Hundred Seventy Six) only. Which Include (Construction Cost. 34290158.89 and Maint.Cost. Rs. 11179717.00 only. Construction cost of Above road has been revised from Rs. 17967695.30 to Rs. 25102374.90. (Revised amount is Rs. 7134679.60) due to Flood.

ARPIT ENGICON PVT.LTD.
Raman Kumar Ray
Director

26.11.24
Executive Engineer
R.W.D Works Division
Patori (Samastipur)
27/11/24

NOW THIS AGREEMENT WITNESSETH AS FOLLOWS-

1. In this Agreement, words and expressions shall have the same meanings as are respectively assigned to them in the condition of contract hereinafter referred to, and they shall be deemed to form and be constructed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the works and remedy any defects therein in conformity in all aspects with the provisions of the Contract.
3. The Employer hereby covenants to pay the contractor in consideration of the execution and completion of the works and the remedying the defects wherein the contract price or such other sum as may become payable under the provisions of the contract at the times and the manner prescribed by the contract.
4. The following documents shall be deemed to form and be read and constructed as part of this Agreement, Viz.-
 - i) Letter of Acceptance
 - ii) Notice to proceed with the works
 - iii) Contractor's Bid
 - iv) Contract Data
 - v) Special Conditions of contract and general condition of contract
 - vi) Specifications
 - vii) Drawings
 - viii) Bill of Quantity and
 - ix) Any other document listed in the Contract Data as forming part of the contract.

In witness whereof the parties thereto have caused this Agreement to be executed the day and year first before written.

The Common Seal of _____

Was hereunto affixed in the presence of:-


Signed, Sealed and Delivered by the said _____


In the presence of:

Binding Signature of Employer _____

Binding Signature of Contractor _____

ARBIT ENGICON PVT.LTD.


Director


26.11.24
Executive Engineer
R.W.D Works Division
Patna (Bihar)
26/11/24

FDR

Bill Of Quantities

Name of Road :		Patori Mududabad Purani Bazar to Sultanpur			
BLOCK :		Patori			
DIVISION :		Patori			
TOTAL FDR CONSIDERED LENGTH OF ROAD :		2.950			
Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	Cum	1390.63	176.75	245793.85
2	Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	Cum	134.25	1,994.10	267711.46
3	WBM Grading 2 (By Mechanical Means) :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	Cum	106.0041	3,629.86	384780.04
4	WBM Grading 3 (By Mechanical Means):- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	Cum	158.8753	3,264.69	516678.60
5	Prime Coat Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	Sqm	1817.798	40.99	74511.54


 26.11.24
 Executive Engineer