

RURAL WORKS DEPARTMENT GOVT OF BIHAR



NAME OF WORKS :- Kursail to Bardenga

BLOCK :- Jokihat

FDR
Phase-I
4,35,364

YEAR(2024-25)

R.W.D., WORKS CIRCLE, KISHANGANJ

R.W.D., WORKS DIVISION, ARARIA

प्रतिवेदन

Kursail to Bardenga

पथ का नाम :-

कार्य का नाम :-

Kursail to Bardenga


में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

संलग्न प्राक्कलन 2024 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त पथ

..... में बाढ़ क्षतिग्रस्त मरम्मति मद से यातायात चालू करने हेतु तैयार किया गया है जिसकी प्राक्कलित लागत 435364 (Four Lakhs thirty-five thousand three hundred sixty) है। उक्त पथ का निर्माण FDR योनान्तर्गत हुआ है एवं योजना अनुरक्षण अवधि में 4 - four

पथ के कटे (क्षतिग्रस्त) भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट रूप से प्राक्कलन में दर्शाया गया है।


प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।


6/11/24

कनीय अभियंता,

ग्रामीण कार्य विभाग,


कार्य प्रशाखा, जालपाईगढ़



सहायक अभियंता,

ग्रामीण कार्य विभाग,

कार्य अवर प्रमण्डल,।


6/11/24

कार्यपालक अभियंता,

ग्रामीण कार्य विभाग,

कार्य प्रमण्डल,

SUMMARY OF COST ESTIMATE FOR THE PROJECT		
NAME OF ROAD :-	Kursail to Bardenga	
DISTRICT :-	ARARIA	
BLOCK :-	Jokihat	
Length of Road:-	0.00KM	
Length of Cutting in mtr :-	27.250	
Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Filling of local sand	0.00
2	Labour for cutting 62mm to 75mm dia bamboo	47712.40
3	Labour for fitting 62mm to 75mm dia bamboo	6515.94
4	Labour for filling empty cement bags with local sand Nylon crate	0.00
5	Supplying of EC bag, of local sand	223072.96
6	Supply and Carriage of brick bats	143062.41
7	Supply, laying and carriage of 1000 mm HPC	0.00
8	Drone Videography Charj Three times	15000.00
	SUB TOTAL COST =	435363.70
	TOTAL (RS.) =	4,35,364

[Signature]
J.E
6/11/24

[Signature]
A.E
6/11/24

[Signature]
E.E
6/11/24

S.E

Technically ^{approved} ~~Sanctioned~~ for ₹ 4,35,364 = 00
(Four Lakhs Thirty-five thousand Three
hundred Sixty-four) only

[Signature]
Superntending Engineer
RWD Work Circle
Kishanganj

Bill of Quantity

NAME OF ROAD :-		Kursall to Bardenga			
DISTRICT :-		ARARIA			
BLOCK :-		Jokihat			
Sl. No.	DESCRIPTION OF ITEMS	QUANTITY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge	0.00	CUM	1272.78	0.00
2	Construction of embankment with approved materials obtained from excavation for road way in soil using manual means for carrying of cut earth to embankment site 1.5 mt and lead upto 50 m, graded and compacted to meet requirement of table 300.1, 300.2 with lift up to	0.00	CUM	549.74	0.00
3	Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-charge.	689.63	MTR	69.19	47712.40
4	Labour for fitting & fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-charge.	181.25	MTR	35.95	6515.94
5	Labour for fitting empty cement bags with local sand, stitching the bags and placing in Nylon crate of size (1 m X 1 m X 1 m) with lead of 150 M including supply of sutli etc. at site in dry portion all complete as per approved design, specification and direction of E/I	0.00	Each	1151.80	0.00
6	Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.	3992.00	Each	55.88	223072.96
7	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	51.85	CUM	2759.12	143062.41
8	Supplying and carriage of hume pipe 1000 mm dia, all complete job	0.00	RM	5172.30	0.00
A) SUB TOTAL =					420363.70

		TOTAL COST =	420364
--	--	--------------	--------

[Signature]
6/11/24
J.E

[Signature]
6/11/24
A.E

[Signature]
6/11/24
E.E

ESTIMATE FOR REPAIRING / RESTORATION/ MAKING MOTORABLE ROADS DAMAGED DURING FLOOD

NAME OF ROAD :-		Kursail to Bardenga									
DISTRICT :-		ARARIA									
BLOCK :-		Jokihat									
Length of Cutting:-		27.25 mtr									
Sl. No.	DESCRIPTION OF ITEMS	Unit	Nos.	L(m)	B(m)	D(m)	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)		
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge										
	At ch:-1.10 km	cum	0	49.00	3.33	3.20	0.00				
	Deductionfor H.P 1000MM dia (1.23 x 1.23)=1.52	cum	0	0.79	1.52	7.50	0.00				
		cum		total qty :-			0.000	1,272.78	0.00		
2	Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer- in -charge.										
	At ch:-0.100 km		2	36.00	4.50		324.00				
	At ch:-0.100 km		1	20.00	4.50		90.00				
	At ch:-0.100 km		1	11.25	4.50		50.63				
	At ch:-150m		1	50.00	4.50		225.00				
	Mtr.		total qty:-				689.63	69.19	47,712.40		

3	Labour for fitting & fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-charge.										
	At ch:-0.100 km	2	9.00	5.00		90.00					
	At ch:-0.100 km	1	6.00	5.00		30.00					
	At ch:-0.100 km	1	2.25	5.00		11.25					
	At ch:-150m	1	10.00	5.00		50.00					
	Mtr.	total qty :-				181.25	35.95	6515.94			
4	Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.										
	At ch:-0.100 km	cum	2	9.00	(1.5+1.25+1.5)/3	(2.5+3.85+1.25)/3	64.60				
	At ch:-0.100 km	cum	1	6.00	(1.5+1.15)/2	(2.05+3.85+2.5)/3	22.26				
	At ch:-0.100 km	cum	1	2.25	(0.6+0.6)/2	(1.5+0.95+0.95)/3	1.53				
	At ch:-150m	cum	1	10.00	(2.5+1.5)/2	(2.85+2.5+1.75)/3	47.33				
	Total No of E C Bags(0.034cum=100Bags)			135.72			/	0.034	3992.00		
	Each	Say No of Bage :-							3992.00	55.88	223072.960
5	Providing laying & filling Geo bags of size 1m X 0.700m (Type A) 300 GSM nonwoven weight 420 gm volume of filled bag 0.070 cum Weight of filled Geo bag 126 kg with local sand including stitching in four lines by approved Nylon thread with Staching machine and generator, stacking and placing after loading, Unloading and carriage with the help of Trolly within 150 mtr. lead and all complete as per specification and direction of E/I.										
	At ch:-23500 m	cum	0	9.00	4.50	2.73	0.00				
	(0.07m3=1 no. of Geo Bags)										
	Each										
	0.000										

6	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.									
	At ch:-0.100 km	cum	2	9.00	3.33	0.35	21.00			
	At ch:-0.100 km	cum	1	6.00	2.10	0.25	3.15			
	At ch:-0.100 km	cum	1	2.25	2.60	0.22	1.27			
	At ch:-150m	cum	1	10.00	3.25	0.25	8.13			
	At ch:-150m	cum	1	26.00	3.25	0.22	18.31			
		cum					51.85	2,759.12	143062.41	
Supplying and carriage of hume pipe 1000 mm dia , all complete job.										
7	At ch:-50 m	RM	0	3	2.5		0.00			
		RM	0	1	2.5		0.00			
		RM	total qty :-				0.00	7,385.85	0.00	
							TOTAL COST =		420363.70	
							A) SUB TOTAL =		420363.70	
							TOTAL COST =		420363.70	

Junior Engineer
6/11/24

Asstt. Engineer
6/11/24

Executive Engineer
6/11/24

S.E
KISHANGANI

FINAL RATE UNDER WORKS CIRCLE KISHANGANJ

S.No	Discription of Item	Unit	Final Rate (Excluding GST,Seigniorage & L.Cess)	Final Rate (Including GST,Seigniorage & L.Cess)	S.F. Per Cum / Per Bag BAG
1	EARTH WORK	CUM	459.003	549.740	3.530
2	BRICK BAT	CUM	2209.576	2759.115	129.720
3	G.S.B	CUM	4328.501	5172.300	21.380
4	SAND BAG (Cement Bag)	Each	46.550	55.880	0.490
5	BAMBOO PILE	Per Mtr.	58.140	69.186	
6	BAMBOO CHACHRI	Per Mtr.	302.258	359.690	
7	BAMBOO RUNNER	Per Mtr.	30.210	35.950	
8	HUME PIPE (1000 mm Div)	Per Mtr.	6206.598	7385.850	
9	HUME PIPE (600 mm Div)	Per Mtr.	2492.260	2965.790	
10	STEEL DRUM SHEET	Per Sqr.Mtr.	215.352	256.270	
11	GEO BAG WITH SAND	EACH	967.490	1152.320	1.010
12	EACH N.C. BAG WITH SAND (Cement Bag)	Each E.C	967.490	1151.800	0.490
13	LOCAL SAND	CUM	721.110	1272.780	0.490

Shri Nave
6/11/24
Junior Engineer

Prasanna
6/11/24
Assistant Engineer

Prasanna
6/11/24
Executive Engineer

Superintending Engineer
Rural Works Department
Works Circle Kishanganj

BASIC RATES
(A) Labour

Sl. No.	Description of Labour	Unit	Rate (Rs.)
L-01	Bhisti	day	373
L-02	Blumen Sprayer (semi skilled)	day	393
L-03	Blacksmith special	day	503
L-04	Blaster, 2nd class	day	619
L-05	Carpenter 1st Class	day	503
L-06	Chips spreader, semi-skilled	day	449
L-07	Chiseller (Skilled)	day	577
L-08	Dresser (Skilled)	day	472
L-09	Driller, 2nd class	day	449
L-10	Electrician, skilled	day	476
L-11	Finer, skilled	day	511
L-12	Mason (1st class)	day	503
L-13	Mason (2nd Class)	day	449
L-14	Mate, Semi skilled	day	397
L-15	Mazdoor (Unskilled)	day	373
L-16	Mazdoor (Semi skilled)	day	388
L-17	Mazdoor (Skilled)	day	472
L-18	Painter (1st class)	day	476
L-19	Plumber, Special	day	476
L-20	Surveyor	day	454
L-21	White Washer	day	476
L-22	Head blacksmith	day	531
L-23	Welder 1st Class	day	584
	Carpenter Head	day	531
	Night Guard	day	415

*(Basic Rates Taken From SOR, Seventeenth Edition, Road Construction Department, Govt. of Bihar
effective from 01/04/2023)*

**BASIC RATES
(B) Material**

S. No.	Description	Unit	Basic Rate as per SOR	Add Royalty	Final Rate With Royalty
M-001	Bamboo (1st Class) 100 mm - 100 mm dia. 6.0 m - 8.0 m long (per mtr.- 23.52 Rs.)	No.	188.00		188.00
M-002	Bamboo (1st Class) 100 mm - 100 mm dia. 6.0 m - 8.0 m long (per mtr.- 23.52 Rs.)	No.	188.00		188.00
M-003	Bamboo (1st Class) 50 mm - 100 mm dia. 6.0 m - 8.0 m long (per mtr.- 14.71 Rs.)	No.	118.00		118.00
M-004	Bamboo (1st Class) 50 mm - 100 mm dia. 6.0 m - 8.0 m long (per mtr.- 14.71 Rs.)	No.	118.00		118.00
M-005	Bamboo (2nd Class) 75mm dia. 1.8 m - 6.0 m - 8.0 m long (per mtr.- 22.03 Rs.)	No.	176.00		176.00
M-006	Bamboo (2nd Class) 75mm dia. 6.0 m - 8.0 m long (per mtr.- 22.03 Rs.)	No.	176.00		176.00
M-007	Brick Bars	cum	1063.00	18.00	1081.00
M-008	Selected earth (including @ Rs. 33.00 per cum & compensation @ Rs. 2.25 Per Cum	cum	2.25	33.00	35.25
M-009	Empty Cement Bag IS 11632:2000	Nos.	11.11		11.11
M-010	Steel Drum 300 mm dia 1.2 m high / empty bitumen drum	Nos.	170.13		170.13
M-011	Sand bags (Cost of sand and Empty cement bag)	Nos.	7.31	2.59	9.90
M-012	Suti (Brown)	kg	20.59		20.59
M-013	Granular material (Natural occurring, soil gravel mixture / quarry waste, kankar, laterite, dhandla	cum	84.03	83.00	167.03
M-014	Nails	kg	108.00		108.00
M-014	RCC Pipe NP3 (1000 mm dia)	m	5787.23		5787.23
M-015	RCC Pipe NP3 (600 mm dia)	m	2310.00		2310.00
M-015	Sand (Fine) at source	cum	69.75	75.00	144.75
M-016	Empty Steel Drum 300 mm dia 1.2 m height	Nos.	170.13		170.13
M-016	Water	kl	60.30		60.30
M-017	Geo Bags	Each	124.00		124.00
M-018	G.S.B.	cum	69.75	75.00	144.75

(Basic Rates Taken From SOR, Seventeenth Edition, Road Construction Department, Govt. of Bihar effective from 01/04/2023.)

**BASIC RATES
(C) USAGE RATES OF PLANT & MACHINERY**

Sr. No.	sor Code	Description of		Activity	Output of Machine		Usage Rates in Rs.	
		Machine			Unit	Output	Unit	Rate
PM-009	PE&M-012	Crane upto 80 T		Lifting of materials			per hour	5,373.00
PM-010	PE&M-013	Dozer D-80 - A12 Dozer D-50 - A13		Dozing cutting	cum h	260.00	per hour	2,997.00
PM-011					cum h	120.00		4,336.00
PM-014	PE&M-017	Front end-loader 1 cum bucket capacity of 45 cum hour		Loading Aggregates	cum h	45.00	per hour	1,419.00
PM-017	PE&M-026	Hydraulic Excavator of 1cum bucket		Excavation	cum h	100.00	per hour	2,272.00
PM-031	PE&M-044	Three wheel 80-100 KN Static Roller		Compaction Rolling				1,593.00
PM-032				Earth - Embankment or sub-grade	cum h	80/70		1,593.00
PM-033				Sub-base G-I	cum h	10.00		1,593.00
PM-034				Sub-base G-II G-III	cum h	8.00		1,593.00
PM-035				WNM	cum h	16.00		1,593.00
PM-036				BSNG	cum h	10.00		1,593.00
PM-037				BM 50/75 mm	cum h	12.00		1,593.00
PM-038				Pavement 20 mm	sqm h	250.00		1,593.00
PM-039				Seal Coat	sqm h	500.00		1,593.00
PM-040				Surface Dressing 1st Coat	sqm h	400.00		1,593.00
PM-041				Surface Dressing 2nd coat	sqm h	500.00		1,593.00
PM-042	PE&M-048	Tipper 5.5 cum 10 T		Carriage	cum trip	5.50	per hour	1,326.00
PM-043	PE&M-053	Tractor with Disc Harrows		Pulverisation of soil	cum h	80.00	per hour	693.00
PM-044	PE&M-055	Tractor with ripper @ 60 cum per hour		Ripping Pavements, uprooting trees	cum h	60.00	per hour	693.00
PM-045	PE&M-053	Tractor with trolley with Grading equipment		Transportation of materials	1 trip	3 to 5	per hour	676.00
PM-046	PE&M-054	Tractor with Reclaimer		Scarifier	cum h	25.00	per hour	693.00
PM-047	PE&M-057	Truck 10 t capacity		Carriage	cum trip	5.50	per hour	1,054.00
PM-048	PE&M-059	Vibratory roller 80-100 KN		Compaction of soil WNM	cum h	100.00	per hour	2,033.00
PM-049				Compaction of BM	cum h	60.00		2,033.00
PM-050	PE&M-060	Water tanker 6 kl capacity (Truck Mounted)		Carriage of water	litre h	12000.00	per hour	732.00
PM-063	PE&M-060	Generator 3KVA		suckling	per hour		per hour	74.00
PM-064	PE&M-060	suckling machine		suckling	day		day	30.00

(Basic Rates Taken From SOR, Seventeenth Edition, Road Construction Department, Govt. of Bihar effective from 01/04/2023.

SUMMARY OF CARRIGE COST

Sl. No.	Item	Unit	Amount (Rs.)
1	Earth Work	Cum	274.42
2	Brick Bats	Cum	521.97
3	Bamboo	Per Mtr.	3.00
4	G.S.B.	Cum	2960.13
5	Local Sand	Cum	345.14
6	HUME PIPE (1000 mm DIA)	Per Pipe	745.93
7	HUME PIPEP PIR METER	Per Mtr.	298.37
8	HUME PIPE (600 mm DIA)	Per Pipe	310.88
9	HUME PIPE (600 mm DIA)	Per Mtr.	124.35
10	Local Sand	Cum	345.10

Comparison of carriage cost of Material via Road from different sources

Comparison of carriage cost of Material via Road from different sources																		
Sl No	Item	Unit	Source	Carriage Cost & Lead in Km												Loadi ng & Unloa	Carriage by Road	Total
				Pucka / Surface						Katcha								
1	By Tractor																	
A	Earth Work Via Road	Cum	Local	3.60	x 20.04	x 0 Km	= Rs 0.00	3.60	x 31.30	x 1 Km	= Rs 55.24	219.18	274.42	274.420				
				2.04				2.04										
B	Brick Bat Via Road	Cum	Local	3.60	x 20.04	x 7 Km	= Rs 247.55	3.60	x 31.30	x 1 Km	= Rs 55.24	219.18	521.97	521.970				
				2.04				2.04										
B	Bamboo Via Road	pet mtr.	Local	3.60	x 20.04	x 2 Km	= Rs 1.15	3.60	x 31.30	x 1 Km	= Rs 0.89	0.96	3.00	3.000				
				126.00				126.00										
D	Local Sand Via Road	Cum	Local	3.60	x 20.04	x 2 Km	= Rs 70.73	3.60	x 31.30	x 1 Km	= Rs 55.24	219.18	345.14	345.140				
				2.04				2.04										
2	By Tipper																	
A	GSB Via Road	Cum	Siliguri	8.00	x 9.83	x 177 Km	= Rs 2789.43	8.00	x 23.81	x 0 Km	= Rs 0.00	170.70	2960.13	2960.130				
				4.99				4.99										
3	By Truck																	
A	Hume Pipe (1000 mm) Via Rod	Mtr.	purnea	8.00	x 7.27	x 53 Km	= Rs 308.25	8.00	x 17.60	x 0 Km	= Rs 0.00	437.68	745.93	745.930				
				10.00				10.00										
A1	Rate Per Mtr. Pipe	Mtr.	purnea						Rate per mtr				298.37	298.370				
B	Hume Pipe (600 mm) Via Road	Mtr.	purnea	8.00	x 7.27	x 53 Km	= Rs 123.30	8.00	x 17.60	x 0 Km	= Rs 0.00	187.58	310.88	310.880				
				25.00				25.00										
B1	Rate Per Mtr. Pipe	Mtr.	purnea						Rate per mtr				124.35	124.350				

Cost of Haulage Excluding Loading & Unloading as per SO* Subjected to Verification of Lead

Edwan Naser
6/11/24
Junior Engineer
R.W.D. Works Section

Asstt. Engineer
9/11/24
Asstt. Engineer
R.W.D. Works Sub - Division,

Executive Engineer
6/11/24
Executive Engineer
R.W.D. Works

SDB Sl. No.	MORD Ref.No.	DESCRIPTION	Unit	QTY	Rate	Amount In Rs
1		Carriage Of Material (By Tractor)				
4.4		Loading and unloading of stone Boulder /stone aggregates sand/ kankar/ moorum Placing tractor at loading point loading with front end loader dumping ,turning for return trip excluding time for haulage and return trip				
		Unit = cum				
		Taking output = 2.25 cum				
		Time required for				
	i)	positioning of tractor at loading point	min	1 min		
	ii)	Loading by front end loader 1 cum bucket capacity @ 25 cum	min	5 min		
		Total		6 min		
	a)	Labour				
		Mate	day	0.030	397.00	11.91
		Mazdoor (Unskilled)	day	0.720	373.00	268.56
	b)	Machinery				
		Tractor 3.60 Tonnes Capacity	hour	0.100	676.00	67.60
		Front end loader 1 cum bucket capacity @ 25 Cum/hour	hour	0.083	1,419.00	117.78
		Cost for 2.25 cum = a+b+c	cum			465.85
		Rate per cum = (a+b+c)/2.25	cum			207.044
		Total per cum	cum			207.044
1.10		Haulage excluding Loading & Unloading Haulage of materials by truck excluding cost of Loading, Unloading and stocking				
		Unit = 7km				
		Taking output 3.6t load and lead 10km = 36t/km				
		Case- I : Surfaced Road				
		Speed with load : 15km per hour				
		Speed while returning empty : 25km per hour				
	a)	Machinery				
		Tractor 3.6 tonnes Capacity	hour	0.667	676.00	450.89
		Haulage with load	hour	0.400	676.00	270.40
		Empty return trip				721.29
		Cost for 36t/km = a+b+c				20.040
		Cost for 1 t, km = a+b/36				20.040
		Total per t per km				20.040
		Case - II Kutcha Track and Track in River Bed / Nallah Bed and Choe Bed				
		Speed with load : 10km per hour				
		Speed while returning empty : 15km per hour				
	a)	Machinery				
		Tractor 3.6 tonnes Capacity	hour	1.00	676.00	676.00
		Haulage with load	hour	0.667	676.00	450.89
		Empty return trip				1126.89
		Cost for 36t/km = a+b+c				31.300
		Cost for 1 t, km = a+b/36				31.300
		Total per t per km				31.300
2		Carriage Of Material (By Tipper)				
1.1		Loading and Unloading Lime, Aggregate, Stone Boulder, Brick Aggregate, Kankar, Building Rubbish, Crushed Slag, Stone for Masonry Work by Manual Means				
	(1)	Loading of lime, Aggregates, Stone boulder, Brick aggregate, Kankar, Building Rubbish, Crushed Slag Stone for masonry work by manual means including a lead upto 30m				
		Unit = cum				
		Taking output = 5.5 cum				
		Time required for				
	(i)	Position of tipper at loading point		1Min		
	(ii)	loading by front end loader 1 cum bucket capacity @25		13Min		
	(iii)	maneuvering, reversing, dumping and turning for return		2Min		
	(iv)	Waiting time unforeseen contingencies etc.		4Min		
		Total		20Min		
	b)	Machinery				
		Tipper 5.5 Tonnes Capacity	hour	0.330	1,426.00	470.58
		Front end loader 1 cum bucket capacity @ 25 Cum/hour	hour	0.330	1,419.00	468.27
		Cost for 5.5 cum = a+b+c				938.85

		Rate per cum = (a+b+c)/5.5	cum		170.70
		Total per cum	cum		170.700
1.10		Haulage excluding Loading & Unloading			
		Haulage of materials by truck excluding cost of loading, unloading and stacking			
		1 ton 1km			
		Taking output 10n load and lead 10km 100n km			
		Case - I : Surfaced Road			
		Speed with load : 25km per hour			
		Speed while returning empty : 35km per hour			
	a)	Machinery			
		Trapper			
		Haulage with load	hour	0.40	1426.00
		Empty return trip	hour	0.29	1426.00
		Cost for 100n km a b c			983.94
		Cost for 1 c km = a+b+c/100			9.830
		Total per c per km			9.830
		Case - III Katcha Track and Truck in River Bed / Nallah Bed and Choe Bed			
		Speed with load : 10km per hour			
		Speed while returning empty : 15km per hour			
	a)	Machinery			
		Trapper			
		Haulage with load	hour	1.00	1426.00
		Empty return trip	hour	0.67	1426.00
		Cost for 100n km a b			955.42
		Cost for 1 c km = a+b+c/100			2381.42
		Cost for 1 c km = a+b+c/100			23.81
		Total per 1 per km			23.810
3					
		Carriage Of Material (By Truck)			
1.10		Haulage excluding Loading & Unloading			
		Haulage of materials by truck excluding cost of Loading, Unloading and stacking			
		Unit = 1km			
		Taking output 10n load and lead 10km = 100n km			
		Case - I : Surfaced Road			
		Speed with load : 25km per hour			
		Speed while returning empty : 35km per hour			
	a)	Machinery			
		Truck			
		Haulage with load	hour	0.40	1054.00
		Empty return trip	hour	0.29	1054.00
		Cost for 100n km = a+b+c			305.66
		Cost for 1 c km = a+b+c/100			727.26
		Total per c per km			7.270
		Case - III Katcha Track and Truck in River Bed / Nallah Bed and Choe Bed			
		Speed with load : 10km per hour			
		Speed while returning empty : 15km per hour			
	a)	Machinery			
		Truck			
		Haulage with load	hour	1.00	1054.00
		Empty return trip	hour	0.67	1054.00
		Cost for 100n km = a+b			706.18
		Cost for 1 c km = a+b+c/100			1760.18
		Total per c per km			17.60
1.9		Loading and Unloading of Hume Pipes			17.600
	(i)	Loading of RCC Hume pipes by mechanical means including a lead upto 30 m			
	A.	1000 / 1200 mm dia Hume pipe			
		Unit = per pipe			
		Taking output = 9 pipes			
	a)	Labour			
		Male	day	0.02	397.00
		Mazdoor (Unskilled)	day	0.50	373.00
	b)	Machinery			
		Truck	hour	0.33	1054.00
		Crane	hour	0.33	5573.00
		Cost for 9 pipes = a+b+c+d			2381.35

		Rate per pipe = (a+b+c)/9	per p			264.594
		Total per pipe				264.594
	C.	600/450 mm dia Hume pipe				
		Unit = per pipe				
		Taking output = 21 pipe				
	a)	Labour				
		Mate	day	0.02	397.00	7.94
		Mazdoor (Unskilled)	day	0.50	373.00	186.50
	b)	Machinery				
		Tractor 3.60 Tonnes Capacity	hour	0.33	1054.00	347.82
		Crane	hour	0.33	5573.00	1839.09
		Cost for 21 pipes = a+b+c+d				2381.35
		Rate per pipe = (a+b+c)/21	per p			113.398
		Total per pipe				113.398
	(iii)	Unloading of RCC Hume pipe by Mechanical means including a lead upto 30 m				
	A.	1000/1200 mm dia RCC Hume pipes				
		Unit = per pipe				
		Taking output = 9 pipes				
	a)	Labour				
		Mate	day	0.02	397.00	7.94
		Mazdoor (Unskilled)	day	0.50	373.00	186.50
	b)	Machinery				
		Truck	hour	0.20	1054.00	210.80
		Crane	hour	0.20	5573.00	1114.60
		Cost for 9 pipes = a+b+c+d				1519.84
		Rate per pipe = (a+b+c)/9	per p			168.871
		Total per pipe				168.871
	C.	600/450 mm dia Hume pipe				
		Unit = per pipe				
		Taking output = 21 pipes				
	a)	Labour				
		Mate	day	0.020	397.00	7.94
		Mazdoor (Unskilled)	day	0.50	373.00	186.50
	b)	Machinery				
		Truck	hour	0.20	1054.00	210.80
		Crane	hour	0.20	5573.00	1114.60
		Cost for 21 pipes = a+b+c+d				1519.84
		Rate per pipe = (a+b+c)/21	per p			72.373
		Total per pipe				72.373
	1.9	Loading and Unloading of Bamboo				
	(i)	Loading & unloading Bamboo				
		Unit = per metre				
		Taking output = per mtr.				
	a)	Material				
		Bamboo =2016/300	per pipe			6.72
		Bamboo Per Mt.	per mt			0.96
		Total per m				0.960
4	3.3	301.5	Construction of Embankment with material obtained from roadway cutting			
			Construction of Embankment with approved material deposit at site from roadway cutting and excavation from drain and foundation of other structure graded and compacted to meet requirement of Table 300.1 and 300.2 as per Technical Specification Clause 301.5.			
		Unit = cum				
		Taking output = 100 cum				
	a)	Labour				
		Mate	day	0.02	397.00	7.94
		Mazdoor (Unskilled)	day	0.50	373.00	186.50
	b)	Machinery				
		Dozer D -50 for spreading @200 cum per hour	hour	0.50	0.00	0.00
		Motor Grader for grading @200 Cum per hour	hour	2.00	697.00	1,394.00
		Water tanker 6 kl capacity	hour	2.00	752.00	1,504.00
		Three Wheel 80-100 KN Static Roller	hour	1.25	1593.00	1,991.25
	c)	Material				
		Water	kl	12.00	60.30	723.60
		Cost for 100 cum = a+b+c+d				5807.29

		Rate per cum = (a+b+c+d)/100	cum			58.073
		Total per cum	cum			58.073
5	3.5	301.5	Excavation in soil with Dozer with lead upto 100 m			
	(ii)	(ii)	Excavation for roadway in soil by mechanical means including cutting and pushing the earth to site of embankment upto a distance of 100 m, including trimming bottom and side slopes in accordance with requirements of lines, grades and cross-sections.			
		Unit = cum				
		Taking output = 100 cum				
		Labour				
		Mate	day	0.08	397.00	31.60
		Mazdoor (Unskilled)	day	2.00	373.00	822.00
		Machinery				
		Dozer D-50 for spreading @200 cum per hour	hour	3.60	4326.00	15,573.60
		Cost for 100 cum = a+b+c+d+e				16427.20
		Rate per cum = (a+b+c+d)/180	cum			91.262
		Total per cum	cum			91.260
6	3.3	301.5	Construction of Embankment with approved material obtained from borrow pits with a lift upto 1.5 m transporting to site, spreading grading to required slope and compacting to meet requirement of Table 300.1 and 300.2 with a lead of 1000 m as per Technical			
		Unit = cum				
		Rate item no. 3.3 Clause 301.5				58.073
		Rate item no. 3.5(ii) Clause 301.5				91.260
		Royalty Compensation for earth taken from private land				35.250
		Carriage of Earth by Tractor Lead 1 K.M.				274.420
		Total Cost of 1 cum =				459.003
		Labour Cess @ 1%				4.590
		G.S.T. @ 18%				82.621
		Add Seigniorage Fee @ 10 % of Materials	cum	1.00	35.25	3.53
		Total Cost of 1 cum 1% Cess & 18 % GST =				549.743
7	4.5		Placing tractor at loading point loading with front end loader dumping, turning for return trip excluding time for haulage and return trip			
		Unit = cum				
		Taking output = 2.83 cum				
		Labour				
		Mazdoor (Unskilled)	day	2.170	373.00	809.41
		Materials				
		Brick Bats	cum	3.396	1,081.00	3671.08
		Total (a+b)=				4480.49
		Total (a+b+c) =				4480.49
		Carriage				
		Brick Bats	cum	3.396	521.97	1772.61
		TOTAL				6253.10
		Rate per cum = (a+b+c+d)/2.83	cum			2209.576
		Total per cum	cum			2209.576
		Labour Cess @ 1%				22.096
		G.S.T. @ 18%				397.724
		Add Seigniorage Fee @ 10 % of Materials	cum	1.20	1,081.00	129.72
		Total Cost of 1 cum 1% Cess & 18 % GST =				2,759.115
8	4.1	401	PAVEMENT CRUST LAYERS			
			For Grading II Material			
		(ii)	Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.			
		Unit = cum				
		Taking output = 300 cum				
		Labour				
		Mate	day	0.48	397.00	190.56
		Mazdoor (Skilled)	day	2.00	472.00	944.00
		Mazdoor (Unskilled)	day	10.00	373.00	3730.00

	b)	Machinery		hour	12.00	676.00	4864.56
		Tractor mounted grader/arrangement		hour	30.00	1593.00	47790.00
		Three wheel 400-1100 KN static roller @ 10 cum per hour		hour	12.00	693.00	8316.00
		Tractor with Rotavator 2.5 cum per hour		hour	5.00	752.00	3760.00
	c)	Material					67978.00
		Well graded granular sub-base material as per Table 400.1					
		GSR		cum	1.20	167.03	213.80
		Cost of 300 cum without Carriage = (a+b+c+d)					73056.36
		A) Basic Cost per cum = (a+b+c+d)/300		cum			243.521
		CARRIAGE					
		G.S.R.		Cum	414.00	2960.13	1225493.82
		Carriage cost of 300 cum					1225493.82
		B) Carriage cost per cum					4084.98
		Rate per cum = (A+B)		CUM			4328.501
		Total per cum		CUM			4328.501
		Labour Cess @ 1%					43.285
		G.S.T. @ 18%					779.130
		Add Seginiorage Fee @ 10 % of Materials		cum	1.28	167.03	21.38
		Total Cost of 1 cum 1% Cess & 18 % GST =					5,172,296
9	9.3	Providing and laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets Clause 1106.					
	R	1000 MM DIA (Single Row)					
	a)	Material					
		RCC NP3 pipe including collar		m	7.50	5787.23	43404.23
	b)	Labour					
		Mate		day	0.09	397.00	35.73
		Mason (1st class)		day	0.25	503.00	125.75
		Mazdoor (Unskilled)		day	2.00	373.00	746.00
		Cost for 7.5m = (a+b+c)					44311.71
		A) Basic Cost per m = (a+b)/7.5		m			5908.23
		Rate per m of Pipe					5908.23
	(d)	CARRIAGE COST					
		NP3 Pipe		m	7.5	298.37	2237.78
		Carriage cost of 7.5 m					2237.78
		Carriage cost per m		m			298.37
		Rate per m with Carriage		m			6,206,598
		Total per m		m			6,206,598
		Labour Cess @ 1%					62.066
		G.S.T. @ 18%					1,117,188
		Total Cost of 1 mtr. 1% Cess & 18 % GST =					7,385,852
2	C	600 MM DIA (Single Row)					
	a)	Material					
		RCC NP3 pipe including collar		m	7.50	2310.00	17325.00
	b)	Labour					
		Mate		day	0.04	397.00	15.88
		Mason (1st class)		day	0.12	503.00	60.36
		Mazdoor (Unskilled)		day	0.96	373.00	358.08
		Cost of 7.5m = (a+b+c+d)					17759.32
		A) Basic Cost per m = (a+b)/7.5		m			2367.91
		Rate per m of Pipe					2367.91
		CARRIAGE COST					
		NP3 Pipe		m	7.5	124.35	932.63
		Carriage cost of 7.5 m					932.63
		B) Carriage cost per m		m			124.35
		Rate per m with Carriage		m			2,492,260
		Total per m		m			2,492,260
		Labour Cess @ 1%					24.923
		G.S.T. @ 10%					448.607
		Total Cost of 1 mtr. 1% Cess & 18 % GST =					2,965,789
3	5.740.1	Labour for filling empty cement bags with local sand, stitching the bags and placing including supply of sack etc. all complete as per approved design, specification and direction E/I.					

Unit = Per % Nos.						
(A) For Filling & Stacking						
Labour		No.	2.00	472.00		944.00
Skilled Labour for filling sand into bags and sewing		kg	0.50	20.59		10.30
Unskilled						
(B) Labour Rate For Carrying & Placing filled E.C. bags.						
Labour						
Skilled Labour for Carrying filled bags and placing to work site		No.	3.00	472.00		1416.00
TOTAL =						2370.30
	Per % Nos. (B) =			509.		2370.30
	Rate per bag (A+B) = 7100					23.70
	(C) Cost of empty cement bag & cost of sand	each				11.11
(D) Carriage cost						
	Tractor with trolley	cum	0.034	345.14		11.73
	(G) Total = (A+B+C+D) =					46.55
Labour Cess @ 1%						0.465
G.S.T. @ 18%						8.379
Add Seigniorage Fee @ 10 % of Materials						0.49
TOTAL Cost of 1 E.C.Bag 1% Cess & 18 % GST =		cum	0.034	144.75		55.882
Supply Labour for fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every verticle pile with 150 mm long nails or 38 swg G. I. wire including cost of G.I. or nails complete job as per specification and direction						
4	Unit = Per mt.					
	Taking Out Put = 30.50 m					
(i)	Materials					
	Bamboo	m	30.50	20.21		616.41
	Nails	kg	0.50	108.00		54.00
(ii)	Labour					
	Carpenter Gr -II	No.	0.125	531.00		66.38
	Unskilled Labour	No.	0.25	373.00		93.25
	Rate for 30.5 m					830.04
	TOTAL =					830.04
	Rate per mt					27.21
(iii)	Carriage cost					
	bamboo	mt	1	3.00		30.21
	Total Cost with Carriage					0.302
	Labour Cess @ 1%					5.439
	G.S.T. @ 18%					
	TOTAL Cost of 1 mtr. 1% Cess & 18 % GST =					35.955
5	Labour for cutting 62 mm to 75 mm dia bamboo piles in size and making shoes and driving etc. complete job as per specification and direction E/I.					
	Unit = Per mt.					
	Taking Out Put = 30.50 m					
	Assuring					
	20 no pile sunk 1.525 m deeps					
	Total depth sunk 30.50 m					
(i)	Materials					
	Bamboo	m	30.50	20.21		616.41
(ii)	Labour					
	Carpenter Gr -II	No.	0.25	531.00		132.75
	Unskilled Labour for piling	No.	2.50	373.00		932.5
	Rate for 30.5 m					1681.66
	Total					1681.66
	Rate for 1 m					55.14
	Carriage Cost of Bamboo	per mtr.				3.00
	Total Cost with Carriage					58.14
	Labour Cess @ 1%					0.581
	G.S.T. @ 18%					10.465
	TOTAL Cost of 1 mtr. 1% Cess & 18 % GST =					69.102

		Labour for fitting and and fixing Steel Drum 300 mm dia 1.2 m high as per specification and direction			
		(Assuming Per Mtr. = 3.14x3.10 = 0.942 mtr)			
		Area of Assuming in one Drum = 0.942x1.20 = 1.130 sqm			
		One Sgm sheet Cost = 127.00/1.130 = 113.12 Cost			
		Unit = per sqm			
		Taking Out = 100 sqm			
	a	Labour			
		Hammer man	No.	4.00	531.00
		Mazdoor (Unskilled)	No.	4.00	373.00
		Carpenter 1st Class	No.	4.00	501.00
	b	Materials			2012.00
		Nails	kg	5.00	5628.00
		Steel Drum sheet	Mos	00.5	850.65
				170.13	15026.51
		Rate Per m = (a+b+c)/100			21535.160
		Labour Cess @ 1%			215.352
		G.S.T. @ 18%			2154
					38.763
5.28 mtr		Total Cost of 1 mtr 1% Cess & 18 % GST =			256.266
		Labour for fitting and and fixing split bamboo woven charchart In position with 20 swg G.I. wire of 75 mm to 100 mm long nails alternatively including cost of G.I. wire or nails complete job as per specification and direction of E/I.			
		(Assuming strip of 3.05x3.05 = 9.30 sqm			
		Unit = per sqm			
		Taking Out = 9.30 sqm			
	a	Labour			
		Carpenter Gr -II	No.	1.00	531.00
		Mazdoor (Unskilled) for piling	No.	1.00	373.00
	b	Materials			373.00
		Bamboo	Mtr.	10.00	1880.00
		Nails	kg	0.25	108.00
					27.00
		Rate Per m = (a+b+c)/9.30			2811.000
		Labour Cess @ 1%			302.258
		G.S.T. @ 18%			3.023
		Total Cost of 1 mtr. 1% Cess & 18 % GST =			54.406
5.750		Providing laying & filling Geo bags of size 1m X 0.700m (Type A) 300 GSM nonwoven) weight 420 gm volume of filled bag 0.070 cum. Weight of filled Geo bag 126 kg with local sand including stitching in four lines by approved Nylon thread with Stitching machine and generator, stacking and placing after loading. Unloading and carriage with the help of Trolley within 150 mtr. lead and all complete as per specification and direction of E/I.			
		Unit = Each Bag			
		Taking Out = 40 Nso.			
		Labour			
		Unskilled Loading For filling stacking	nos	2	373.00
		Skilled labour for stacking	nos	0.33	472.00
		Unskilled labour for carrying and placing	nos	4.00	373.00
		Male	nos	0.25	397.00
		Stitching Machine	day	0.33	50.00
		Tractor with trolley	day	1.00	676.00
		Generator 3KVA	hrs	20.67	74.00
		Total			4715.09
		Rate per bag (Total/40) (A)			117.88
	(ii)	charge for placing & dumping	nos	16	373.00
		unskilled labour for loading unloading & dumping	nos	1	397.00
		Male	nos	1	419.00
		Tractor with trolley	each	4	2704.00
		Total			9,443,000
		Rate per bag (Total/256) (B)			36.887
		Materials			
		cost of Geo Bag	each	1	124.00
		Total cost (a+b+c)			270.764

Rate per bag					
Labour Cess @ 1%					278.764
G.S.T. @ 18%					2.788
Add Seigniorage Fee @ 10 % of Materials					50.178
Total Cost of 1 Geo Bag 1% Cess & 10 % GST =		cum	0.070	144.75	1.01
Labour for filling empty concrete bags with local sand, stitching the bags and placing the bags and putting in Nylon crate of size (1m x 1m x 1m) with a lead of 150 m including supply of soil etc. and placing the filled crates in water portion within a lead 10 m off complete as per approved design specification and direction of E/1					332.739
Unit = Each N.C.					
(i)	Labour Cost for filling bags in one Nylon crate in dry portion	M ₀	1	472.00	411.00
(ii)	Labour Cost for filling bags in one Nylon crate in dry portion	M ₀	1	472.00	611.60
	Placing of filled N.C with .30 m lead in water portion				
	Labour				
	Mate				
	Labour (Skilled)	M ₀	0.37	397.60	146.89
	Labour (Unskilled)	M ₀	1.00	472.00	472.60
		M ₀	1.00	373.00	373.00
	Hence, Total Labour for 100 C/L				2013.89
	Taking one E.C. Bags to contain 1.20 C/L of sand				2013.89
(iii)	Hence, labour rate for placing one filled N.C.				2013.89
	Hence rate per mu; pin crate on water portion (1+ii)		356.49		356.49
	Labour Cess @ 1%			509.	967.49
	G.S.T. @ 18%				9.675
	Add Seigniorage Fee @ 10 % of Materials				174.148
	Total Cost of 1 E.C. 1% Cess & 18 % GST =	cum	0.034	144.75	0.49
(1)	800				1,151.803
local sand Filling in foundation trenches as per drawing and technical specification					
local sand Filling in foundation trenches as per drawing and technical specification Clause 305.3.9					
I.	Sand filling				
	Unit = cum				
a)	Labour				
	Mate				
	Mazdoor (Unskilled)	day	0.01	397.00	3.97
b)	Material	day	0.30	373.00	111.90
	Sand (assuming 20 per cent voids)				
	Overheads @ 6 % on (a)	cum	1.20	144.75	173.70
					17.37
	CARRIAGE COST				306.94
	sand				
	Rate per cum = a+b+c	Cum	1.2	345.14	414.17
					721.11
	G.S.T. @ 18%				7.21
	Add Seigniorage Fee @ 10 % of Materials				129.80
	Total Cost of 1 E.C. 1% Cess & 18 % GST =				0.49
					1272.78