


RURAL WORKS DEPARTMENT GOVT OF BIHAR



NAME OF WORKS :- PMGSY Denga Chowk to Hat Gaon

BLOCK :- Palasi

FDR
Phase-I
10,44,835

YEAR(2024-25)

R.W.D., WORKS CIRCLE, KISHANGANJ

R.W.D., WORKS DIVISION, ARARIA

प्रतिवेदन

PMGSY Denga Chowk to Hat Gaon

का नाम :-
का नाम :-

PMGSY Denga Chowk to Hat Gaon

में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

मग्न प्राक्कलन 2024 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त 521
में बाढ़ क्षतिग्रस्त मरम्मत मद से यातायात चालू करने हेतु तैयार किया गया है जिसकी
स्कलित लागत 10,44,835 है। उक्त पथ
निर्माण PMGSY योनान्तर्गत हुआ है एवं योजना अनुरक्षण अवधि में 5/1।
के कटे (क्षतिग्रस्त) भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं
Bats देने के बाद यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य
विवरणी स्पष्ट रूप से प्राक्कलन में दर्शाया गया है।
क्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।

अधीनस्थ
6/11/24
ज्तीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा, PMHSI।

सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल, PMHSI।

6/11/24
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, PMHSI।

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :-	PMGSY Denga Chowk to Hat Gaon	
DISTRICT :-	ARARIA	
BLOCK :-	Palasi	
Length of Road:-	0.00KM	
Length of Cutting in mtr :-	42.000	
Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Filling of local sand	538842.02
2	Labour for cutting 62mm to 75mm dia bamboo	20755.80
3	Labour for fitting 62mm to 75mm dia bamboo	2696.25
4	Labour for filling empty cement bags with local sand Nylon crate	0.00
5	Supplying of EC bag, of local sand	304937.16
6	Supply and Carriage of brick bats	162603.84
7	Supply, laying and carriage of 1000 mm HPC	0.00
8	Drone Videography Charj Three times	15000.00
	SUB TOTAL COST =	1044835.07
	TOTAL (RS.) =	10,44,835

J.E

A.E

S.E

Technically ~~approved~~ for ₹ 10,44,835/-
(Rupees Ten Lakh forty four thousand eight
hundred thirty five) only

Superintending Engineer
RWD Work Circle
Kishanganj

Bill of Quantity

NAME OF ROAD :-		PMGSY Denga Chowk to Hat Gaon			
DISTRICT :-		ARARIA			
BLOCK :-		Palasi			
	DESCRIPTION OF ITEMS	QUANTITY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge	423.36	CUM	1272.78	538842.82
3	Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer- in -charge.	300.00	MTR	69.19	20755.80
4	Labour for fitting & fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-charge.	75.00	MTR	35.95	2696.25
5	Labour for fitting empty cement bags with loocal sand, stitching the bags and placing in Nylon crate of size (1 m X 1 m X 1 m)with lead of 150 M including supply of sutli etc. at site in dry portion all complete as per approved design, specification and direction of E/I	0.00	Each	1151.80	0.00
6	Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.	5457.00	Each	55.88	304937.16
7	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job	58.93	CUM	2759.12	162603.84
8	Supplaying and carriage of hume pipe 1000 mm dia , all complete job.	0.00	RM	7385.85	0.00
A) SUB TOTAL =					1029835.07
TOTAL COST =					1029835

JE 08/11/24

AE 08/11/24

EE 08/11/24

Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.

At ch -500M	cum	1	15.00	$(4.75+4.5+3.5)/3$	$(0.45+0.65+0.5)/3$	34.00		
At ch -500M	cum	1	13.00	$(1.75+1.25+1.5)/3$	$(0.75+0.65+0.5)/3$	12.35		
At ch -650M	cum	1	5.00	$(1.5+1.5)/2$	$(0.45+0.65+0.55)/3$	4.13		
At ch -750M	cum	1	7.00	$(2.5+2.5)/2$	$(0.45+0.45+0.65)/3$	8.46		
	cum		total qty :-				58.93	2,759.12 162603.84
							A) SUB TOTAL =	1029835.07
							TOTAL COST =	1029835.07

[Signature]
05/11/24
Junior Engineer

[Signature]
05/11/24
Asstt Engineer

[Signature]
05/11/24
Executive Engineer

S.E
KISHANGANJ

FINAL RATE UNDER WORKS CIRCLE KISHANGANJ

S.No	Discription of Item	Unit	Final Rate (Excluding GST, Seigniorage & L.Cess)	Final Rate (Including GST, Seigniorage & L.Cess)	S.F. Per Cum / Per Bag BAG
1	EARTH WORK	CUM	459.003	549.740	3.530
2	BRICK BAT	CUM	2209.576	2759.115	129.720
3	G.S.B	CUM	4328.501	5172.300	21.380
4	SAND BAG (Cement Bag)	Each	46.550	55.880	0.490
5	BAMBOO PILE	Per Mtr.	58.140	69.186	
6	BAMBOO CHACHRI	Per Mtr.	302.258	359.690	
7	BAMBOO RUNNER	Per Mtr.	30.210	35.950	
8	HUME PIPE (1000 mm Div)	Per Mtr.	6206.598	7385.850	
9	HUME PIPE (600 mm Div)	Per Mtr.	2492.260	2965.790	
10	STEEL DRUM SHEET	Per Sqr.Mtr.	215.352	256.270	
11	GEO BAG WITH SAND	EACH	967.490	1152.320	1.010
12	EACH N.C. BAG WITH SAND (Cement Bag)	Each E.C	967.490	1151.800	0.490
13	LOCAL SAND	CUM	721.110	1272.780	0.490

Junior Engineer

Assistant Engineer

Executive Engineer

Superintending Engineer
Rural Works Department
Works Circle Kishanganj



Latitude: 26.173039
Longitude: 87.627217
Elevation: 54.22±51 m
Accuracy: 11.0 m
Time: 2024-10-23 17:08
Note: Denga choulk To Hatghw

Downloaded by NoteCam



Latitude: 26.172789
Longitude: 87.62697
Elevation: 50.32±24 m
Accuracy: 6.4 m
Time: 2024-10-23 17:07
Note: Denga choulk To Hatghw

Downloaded by NoteCam

Handwritten notes in blue ink:
11/11/24
06/11/24
06
Bhal
Gill
n



3,67,084.36
With Extra Cam



Latitude: 26.173039
Longitude: 87.627217
Elevation: 54.22±51 m
Accuracy: 11.0 m
Time: 2024-10-23 17:08
Note: Denga choul To Hatghw

Powered by InstaCam



Latitude: 26.172714
Longitude: 87.626948
Elevation: 53.22±23 m
Accuracy: 12.6 m
Time: 2024-10-23 17:07
Note: Denga choul To Hato

Powered by InstaCam

Handwritten notes in blue ink, including the word "Handwritten" and a signature.



Khaw
06/11/24
RE

Prasat
Lutay



*Pradip
 Dmoy*

3/04 5/04 7/04 8/04
 State
 or. Col
 In Case