

RURAL WORKS DEPARTMENT

GOVT OF BIHAR



Name Of Work : Thanwar Road No. 17 To Bauharwa

DISTRICT : SAHARSA

DIVISION : SAHARSA

BLOCK : MAHISHI

HEAD : F.D.R.

Total Length of Road	-	1.45KM
Flood affected length of Road	-	132.5m
Total Project Cost	-	Rs. 2333615.00

Year - 2024-25

NAME OF CIRCLE - R.W.D., WORKS CIRCLE, SAHARSA


NAME OF DIVISION - R.W.D., (W) DIVISION, SAHARSA


प्रतिवेदन


पथ का नाम	:— Thanwar Road No. 17 To Bauharwa
पथ की लंबाई	:— 1.450 KM
बाढ़ से क्षतिग्रस्त भाग	:— 132.50 m
प्राक्कलित राशि	:— Rs 2333615
कार्य प्रमंडल	:— सहरसा
कार्य अंचल	:— सहरसा
योजना शीर्ष	:— FDR
योजना वर्ष	:— 2024 - 25

प्रस्तुत प्राक्कलन कार्य प्रमंडल, सहरसा अंतर्गत महिषी प्रखंड में 2024-25 में आई भीषण बाढ़ से क्षतिग्रस्त पथ में मरम्मत मद से यातायात चालू करने हेतु अस्थायी पुनर्स्थापन के अंतर्गत कराये गये कार्य के लिये तैयार किया गया है। पथ में चैनेज -0.160 से 0.400 किमी० में भारी कटाव एवं अत्यधिक जल जमाव हो जाने से यातायात पूर्णरूप से अवरुद्ध हो जाने के कारण तत्काल यातायात बहाल करने हेतु विभागीय निदेशानुसार Drone Time Stamp Videography एवं Geotag Photograph संधारित कर MIS के FDR Module में प्रविष्टि करते हुए पथ के क्षतिग्रस्त भाग में आवश्यकतानुसार Brick Bats,/ Local Sand भरकर यातायात चालू करने हेतु अस्थायी पुनर्स्थापन कार्य कराया गया है। जिसकी प्राक्कलित राशि Rs. 2333615 है।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू सूचित प्रावधानों एवं वर्तमान अनुसूचित दर के अनुसार कार्यहित एवं स्थलीय आवश्यकता के अनुरूप तैयार किया गया है। जिसमें Contractor Profit एवं Overhead Charge शून्य रखा गया है। अतः अस्थायी पुनर्स्थापन कार्य के तहत कराये कार्य के भुगतान हेतु प्राक्कलन अग्रेतर कारवाई हेतु समर्पित ।


कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, सहरसा।


20-11-2024
सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, सहरसा।


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, सहरसा।

DETAILED ESTIMATE FOR F.D.R.

General Abstract of Cost

Name Of Work : Thanwar Road No. 17 To Bauharwa

DISTRICT : SAHARSA


DIVISION : SAHARSA

BLOCK : MAHISHI

Head : FDR

Year : 2024-25

S.No.	Particulars	Total Cost (in Lakh)
1	Total Cost for Motorable Roads	1880750.00
2	Labour cess @1%	18807.50
3	GST @18%	338535
4	Seigniorage Fee @ 10%	95522.16
5	Total Cost of Road Repair	2333614.66
	Say	2333615.00


20/11/24
Junior Engineer
RWD (W) Division, Saharsa


20-11-2024
Assistant Engineer
RWD (W) Division, Saharsa


20/11/24
Executive Engineer
RWD (W) Division, Saharsa

Provisionally
Technically sanction for Rs 23,33,615=00 (Rupees Twenty Three Lakh Thirty Three Thousand Six Hundred Fifteen) only


29/11/24
Superintending Engineer
R W.D. Works Circle
SAHARSA
skm
29.11.24

Schedule of Quantity

####


Thanwar Road No. 17 To Bauharwa

Division
Block


SAHARSA
MAHISHI

S.No	DESCRIPTION OF ITEMS	QTY	UNIT	RATE	AMOUNT
1	Sand Filling in Foundation Trenches as per Drawing & Technical Specification.	0.00	Cum	463.32	0.00
2	Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to acheive required density with all complete as per the direction of engineer in charge.	917.60			0.00
	600 mm HP Dedution	0.00			
		917.60	Cum	2049.64	1880749.66
3	Single bamboo palasiding / walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and struts 1.5 m apart longitudinally and providing brush wood as per drawing and technical specifications Clause 1302.5	0.00	m	198.77	0.00
4	Providing ,laying and placing empty cement bag filled with local sand including stiching with sutali etc. ----- do ----- do-----all complete job as per specification and direction of E/I.(Including Royalty and all Taxes)	0.00	no.	33.95	0.00
5	Providing and Laying 1000 mm Reinforced Cement Concrete Pipe NP3 as per design in Single Row pipe	0.00	m	6798.44	0.00
6	Providing and Laying 600 mm Reinforced Cement Concrete Pipe NP3 as per design in Single Row pipe	0.00	m	3063.83	0.00

Total 1880749.66
Say 1880750.00



20/11/24
Junior Engineer
RWD (W) Division, Saharsa



20-11-2024
Assistant Engineer
RWD (W) Division, Saharsa



20/11/24
Executive Engineer
RWD (W) Division, Saharsa

Details of Measurement

Details of Measurement								
Details of Work	No	Measurement				Height (in mm)		Quantity
		Length (in mm)		Width (in mm)				
NAME OF ROAD :-		Thanwar Road No. 17 To Bauharwa						
Item NO.1	Providing and laying of Brick bat obtained from chimney with mechanical means with all spreading ,grading to required slope and compacted at OMC to achieve required density with all complete as per the direction of engineer in charge .							
CH in 0.160 KM	1	19.00	(2.00+1.50)/2	1.75		1.00	33.25	m ³
	2	19.00	(2.00+1.50)/2	1.75		1.00	33.25	m ³
	3	12.50	(6.00+8.00)/2	7	(2.50+1.90+2.80)/3	2.40	210.00	m ³
	4	8.00	(1.40+1.00)/2	1.2		1.00	9.60	m ³
	5	8.00	(1.40+1.00)/2	1.2		1.00	9.60	m ³
	6	4.00		7.00		0.60	16.80	m ³
CH in 0.250 KM	1	9.50	(5.50+7.50)/2	6.5		2.50	154.38	m ³
	2	11.00	(4.50+6.00)/2	5.25		1.90	109.73	m ³
CH in 0.400 KM	1	3.00		4.50		1.00	13.50	m ³
	2	22.50	(5.00+6.00)/2	5.5		2.00	247.50	m ³
	3	16.00		5.00		1.00	80.00	m ³
		132.50		Total (in Cum)			917.60	m ³
Item NO.2	Providing and laying reinforced Cement Concrete Pipe NP3 as per design in single row (1000mm dia)							
							0	
							0	
		0		Total (in Cum)			0.00	


 20/11/24
Junior Engineer
 RWD (W) Division, Saharsa


 20-11-2024
Assistant Engineer
 RWD (W) Division, Saharsa


 20/11/24
Executive Engineer
 RWD (W) Division, Saharsa