

तकनीकी प्रतिवेदन

योजना का नाम :- 704 ⁸ ~~सि~~ ~~बखर~~ ~~दर~~
क्षतिग्रस्त पथ की लंबाई :- 79.10 मी०
प्राकलित राशि :- 2.80400 लाख
योजना शीर्ष :- 3054 / 2245 F.D.R
आदेश :- सचिव, ग्रामीण कार्य विभाग, बिहार पटना का मु०अ-4 (मु०) विविध
(कार्य)-06-109 / 2024-1956 दिनांक 28.05.2024 / मु०अ-8 (अनु० एवं अन्नयन) F.D.R
-03-01 / 2024-89 पटना दिनांक 18.10.2024

प्रतिवेदन

प्रस्तुत प्राकलन वर्ष-2024 में अतिवृष्टि/बाढ़ के कारण क्षतिग्रस्त पथ के पथांश में क्षतिग्रस्त भाग में आकस्मिक के रूप से मोटरबुल/अस्थायी पुर्नस्थापन कार्य का प्राकलन रू० 280400/- मात्र के लिए ग्रामीण कार्य विभाग, कार्य प्रमंडल बायसी के द्वारा शीर्ष F.D.R 3054 के अंतर्गत तैयार किया गया है।

पथ के आकस्मिक मरम्मत हेतु आवश्यकतानुसार पथांशों में लोकल Brick Bat


इत्यादी से भरकर बचाव कार्य करते हुए यातायात बहाल करते हुए अस्थायी रूप से पुर्नस्थापित किया गया है।

विभागीय निविदा सं०-RWD/FDR/BIHAR/01 (2024-25) के द्वारा प्राप्त निविदा के तुलनात्मक विवरणी में सफल निविदाकारों के द्वारा मदवार उद्धत न्यूनतम दर (सभी कर सहित) जो अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, पूर्णिया द्वारा अनुमोदित है के दर ही प्राकलन तैयार किया गया है।

कार्यहित में प्राकलन पर तकनीकी स्वीकृति अपेक्षित है।


कनीय अभियंता
कार्य प्रशाखा अमरपुर


सहायक अभियंता
कार्य अवर प्रमंडल अमरपुर


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल बायसी।

FDR

Name Of Work :- Temporary restorations Work in Approach Road T04 - Barbatta

CH :-

Year :- 2024-25

Block :- Amour

Division :- Baisi

S.N	Description	Unit	Length (in meter)	Width (in meter)	Depth/Height (in meter)	Quantity	Rate	Amount
1	2	3	4	5	6	7	8	9
1	Local Sand (As Per Specification)	Cum	-	-	-	0	145.87	0.00
2	Empty Cement Bags (Supply of Empty Cement Bag Capacity 1.2 CFT in Good condition And As per Specification)	Each	-	-	-	0	3.50	0.00
3	Bamboos (100 mm Dia 6m to 8m long)	No	-	-	-	0	178.00	0.00
4	Brick Bats (Brick Bat of Well Burnt Bricks)	Cum	-	-	-	157.782	990.00	156204.18
5	Kiln Rubbish (is Should be elen & Free from other impurities)	Cum	-	-	-	0	148.00	0.00
6	Hume Pipe (NP3) 1000mm Dia (NP3 RCC Hume Pipe)	M	-	-	-	0	2400.00	0.00
7	Unskilled Labour (8 Hrs/Day)	Per Day	-	-	-	157	300.00	47100.00
8	Skilled Labour (8 Hrs/Day)	Per Day	-	-	-	31	365.00	11315.00
9	Tractor With Trolley (Transportation of Material) Cum 3 to 5 Ton	Ton/Trip	-	-	-	70	600.00	42000.00
10	8-10 Ton smooth Wheeled (Compaction/Consolidation) Cum/Hour 70/25	Per Hour	-	-	-	0	850.00	0.00
11	Generator Set With Fuel (Gnnaration of Electecal Energy) KVA 5	Per Hour	-	-	-	0	296.00	0.00
12	Front End Loader 1.0 Cum Bucket Capacity (JCB)	Per Hour	-	-	-	17	1400.00	23800.00
Total Amount:-								280419.18

Rate Apporoved by S.E RWD, Work Circle, Purnea

22-11-2024
Junior Engineer

22/11/24
Assistant Engineer

22/11/24
Executive Engineer
Rural Works Department
Work Division Baisi

Technically sanctioned for Rs 2,80,400.00 (Rupees two lac eighty thousand four hundred only).

29/11/24
अधीक्षक अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, पूर्णियाँ