

तकनीकी प्रतिवेदन

Temporary restoration work in Khutiya to Sarniya (Kadwa)

योजना का नाम :-
क्षतिग्रस्त पथ की लंबाई :- 16-00 मी०
प्राक्कलित राशि :- 44900 लाख
योजना शीर्ष :- 3054 / 2245 F.D.R
आदेश :- सचिव, ग्रामीण कार्य विभाग, बिहार पटना का मु०अ-4 (मु०) विविध
(कार्य)-06-109 / 2024-1956 दिनांक 28.05.2024 / मु०अ-8 (अनु० एवं अन्नयन) F.D.R
-03-01 / 2024-89 पटना दिनांक 18.10.2024


प्रतिवेदन


प्रस्तुत प्राक्कलन वर्ष-2024 में अतिवृष्टि/बाढ़ के कारण क्षतिग्रस्त पथ के पथांश में क्षतिग्रस्त भाग में आकस्मिक के रूप से मोटरेबुल/अस्थायी पुर्नस्थापन कार्य का प्राक्कलन रु०..... 44900/-मात्र के लिए ग्रामीण कार्य विभाग, कार्य प्रमंडल बायसी के द्वारा शीर्ष F.D.R 3054 के अंतर्गत तैयार किया गया है।

पथ के आकस्मिक मरम्मत हेतु आवश्यकतानुसार पथांशों में लोकल मिट्टी भरवाई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, बॉस का चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट इत्यादी से भरकर बचाव कार्य करते हुए यातायात बहाल करते हुए अस्थायी रूप से पुर्नस्थापित किया गया है।

विभागीय निविदा सं०-RWD/FDR/BIHAR/01 (2024-25) के द्वारा प्राप्त निविदा के तुलनात्मक विवरणी में सफल निविदाकारों के द्वारा मदवार उद्धत न्यूनतम दर (सभी कर सहित) जो अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, पूर्णिया द्वारा अनुमोदित है के दर ही प्राक्कलन तैयार किया गया है।

कार्यहित में प्राक्कलन पर तकनीकी स्वीकृति अपेक्षित है।


कनीय अभियंता T.S.
कार्य प्रशाखा बायसी।


सहायक अभियंता
कार्य अवर प्रमंडल बायसी।


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल बायसी।

FDR								
Name Of Work :- Temporary restrotration Work in Khutiya To Serniya (Kadwa)								
CH :- 0.100 KM					Year :- 2024-25			
Block :- Baisi								
Division :- Baisi								
S.N	Description	Unit	Length (in meter)	Width (in meter)	Depth/Height (In meter)	Quanityity	Rate	Amount
1	2	3	4	5	6	7	8	9
1	Local Sand (As Per Specification)	Cum	-	-	-	0	145.87	0.00
2	Empty Ciment Bags (Supply of Empty Cement Bag Capicity 1.2 CFT in Good condition And As per Specification)	Each	-	-	-	0	3.5	0.00
3	Bamboos 100mm Dia 6m to 8m long)	No	-	-	-	0	178.00	0.00
4	Brick Bats (Brick Bat of Well Burnt Bricks)	Cum	-	-	-	30.14 25.12	990.00	29838.6 24868.80
5	Kiln Rubbish (is Should be elen & Free from other impurities)	Cum	-	-	-	0	148.00	0.00
6	Hume Pipe (NP3) 1000mm Dia (NP3 RCC Hume Pipe)	M	-	-	-	0	2400.00	0.00
7	Unskilled Labour (8 Hrs/Day)	Per Day	-	-	-	25	300.00	7500.00
8	Skilled Labour (8 Hrs/Day)	Per Day	-	-	-	5	365.00	1825.00
9	Tractor With Trolley (Transportation of Material) Cum 3 to 5 Ton	Ton/T rip	-	-	-	14 11	600.00	7800 6600.00
10	8-10 Ton smooth Wheeled (Compaction/Consolidation) Cum/Hour 70/25	Per Hour	-	-	-	0	850.00	0.00
11	Generator Set With Fuel (Grnaration of Electecal Energy) KVA 5	Per Day	-	-	-	0	296.00	0.00
11	Front End Loader 1.0 Cum Bucket Capacity (JCB)	Per Hour	-	-	-	3	1400.00	4200.00
Total-								44993.80

51163.6

Rate Approved by S.E RWD, Purnia

[Signature]
22.11.24
Junior Engineer / T.S

[Signature]
22/11/24
Assistant Engineer

[Signature]
22/11/2024
Executive Engineer
Rural Works Department
Work Division Baisi

Technically Sanctioned for Rs 44900.00 (Rupees Forty Four thousand Nine Hundred) only.

ATO

Technically Sanction for amount Rs 5,164.00 (Rupees
fifty one ^{thousand} ~~lakh~~ one hundred & sixty four) only.

R
28/11/24

अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, पूर्णियाँ

~~Signature~~
28/11/24