



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

PLAN HEAD- FDR YEAR 2024-25

DISTRICT :- WEST CHAMPARAN
BLOCK :- JOGAPATTI

Scheme Head - FDR (Under Maintenance)

Estimate for Repair of Road breaches
(Damaged by Flood) for Motorability in L056-
Bhawanipur To Ramna

LENGTH OF ROAD (in Km)- 3.800 KM
DAMAGED LENGTH OF ROAD (IN KM) -0.400 KM

ESTIMATED COST - 5.180 Lacs

SUBMITTED BY:
EXECUTIVE ENGINEER,
RWD WORKS DIVISION,
BETTIAH

GENERAL ABSTRACT OF COST

ESTIMATE FOR REPAIR OF ROAD BREACHES (DAMAGED BY FLOOD) FOR MOTORIBILITY IN L056- BHAWANIPUR TO RAMNA

DISTRICT - WEST CHAMPARAN

DIVISION - BETTIAH

BLOCK - JOGAPATTI

LENGTH OF ROAD (in Km)- 3.800 KM

Scheme Head - FDR (Under Maintenance)

SL. No.	Item of Work	Amount
1	EARTH WORK	1.780 Lacs
2	BRICK BATS	2.369 Lacs
3	SAND BAGS	0.000 Lacs
4	BAMBOOS PILING AND RUNNER	0.000 Lacs
5	HUME PIPE	0.000 Lacs
	COST OF RESTORATION	4.149 Lacs
	ADD SEIGNIORAGE FEE @ 10% OF MATERIAL COST	0.242 Lacs
	ADD LABOUR CESS @ 1%	0.041 Lacs
	ADD GST @ 18%	0.747 Lacs
	TOTAL COST OF RESTORATION OF ROAD	5.180 Lacs

Alina
18/11/24
Junior Engineer

Asstt. Engineer
18/11/24
Asstt. Engineer

Executive Engineer
18/11/24
Executive Engineer

Technically Sanctioned for Amount ₹ 5.180 Lacs (Five
lacs eighteen thousand) Only.

अधीक्षक अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, बेतिया

Name of Work:- Estimate for Repair of Road breaches (Damaged by Flood) for Motorbllity In L056- Bhawanipur To Ramna

Head - FDR

SI No.	Item No.	Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
1		filling local sand with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement with a lead as per	cum		As Per Appendix I			490.85	362.80	178007.82
2		Providing and Labour for laying dry graded Brick Bats including light ramming etc. all complete as per approved design, specification and direction of E/I.	cum		As Per Appendix II			105.09	2254.42	236917.00
3		Providing, Filling Sand Bag, Stitching and Placing etc. all complete as per specification and direction of E/I.	Nos.		As Per Appendix III			0	25.14	0.00
4		Providing and Labour for cutting 62 mm to 75 dia Bamboo piles to size and making shoes and driving etc. complete job as per specification and direction of E/I.	RM		As Per Appendix IV			0	66.95	0.00
5		Providing and Labour for fitting & fixing 62 mm to 75 dia Bamboo runners in position at every virtical pile with 150 mm long nails or 38 swg G.I. wire including cost of G.I. wire or nails etc. complete job as per specification and direction of E/I.	RM		As Per Appendix IV			0	31.02	0.00
6		Providing and laying 1000 mm dia reinforced cement concrete pipe NP3 for culvert on first class bedding of granular material in single row excluding excavation, protection works, backfilling, concrete and masonry.	RM		0 Nos*2.5m			0	7076.68	0.00
7		Providing and laying 600 mm dia reinforced cement concrete pipe NP3 for culvert on first class bedding of granular material in single row excluding excavation, protection works, backfilling, concrete and masonry.	RM		0 Nos*2.5m			0	3002.81	0.00
TOTAL (in Rs.)										414924.82

Asin
18/11/24
Junior Engineer,
Rural Works Department,
Works Section, JOGAPATTI

Asin
18/11/24
Assistant Engineer,
Rural Works Department,
Works Sub Division, JOGAPATT

Asin
18/11/24
Executive Engineer,
Rural Works Department,
Works Division, BETTIAH