



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

PLAN HEAD- FDR YEAR 2024-25

DISTRICT :- WEST CHAMPARAN
BLOCK :- JOGAPATTI

Scheme Head - FDR (Under Maintenance)

Estimate for Repair of Road breaches
(Damaged by Flood) for Motorability in L065-
Kablapur To Dhawelwa Madarsa

LENGTH OF ROAD (in Km)- 4.078 KM
DAMAGED LENGTH OF ROAD (IN KM) -0.500 KM

ESTIMATED COST -	5.027	Lacs
------------------	-------	------

SUBMITTED BY:
EXECUTIVE ENGINEER,
RWD WORKS DIVISION,
BETTIAH

GENERAL ABSTRACT OF COST

ESTIMATE FOR REPAIR OF ROAD BREACHES (DAMAGED BY FLOOD) FOR
MOTORIBILITY IN L065-KABLAPUR TO DHAWELWA MADARSA

DISTRICT - WEST CHAMPARAN
BLOCK - JOGAPATTI

DIVISION - BETTIAH
LENGTH OF ROAD (in Km)- 4.078 KM

Scheme Head - FDR (Under Maintenance)

SL. No.	Item of Work	Amount
1	EARTH WORK	0.000 Lacs
2	BRICK BATS	3.866 Lacs
3	SAND BAGS	0.048 Lacs
4	BAMBOOS PILING AND RUNNER	0.000 Lacs
5	HUME PIPE	0.000 Lacs
	COST OF RESTORATION	3.914 Lacs
	ADD SEIGNIORAGE FEE @ 10% OF MATERIAL COST	0.370 Lacs
	ADD LABOUR CESS @ 1%	0.039 Lacs
	ADD GST @ 18%	0.704 Lacs
	TOTAL COST OF RESTORATION OF ROAD	5.027 Lacs

Alina
18/11/24
Junior Engineer

S. S. S.
18/11/24
Asstt. Engineer

Q. S. S.
18/11/24
Executive Engineer

Technically Sanctioned for Amount ₹ 5.027 lacs (Five
lacs two thousand seven hundred) only.

A. S. S.
अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, बेतिया

Name of Work:-

Estimate for Repair of Road breaches (Damaged by Flood) for Motorability in L065-Kablapur To Dhawelwa Madarsa

Head - FDR

SI No.	Item No.	Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
1		filling local sand with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement with a lead as per	cum					0.00	362.80	0
2		Providing and Labour for laying dry graded Brick Bats including light ramming etc. all complete as per approved design, specification and direction of E/I.	cum					171.48	2254.42	386587.94
3		Providing, Filling Sand Bag, Stitching and Placing etc. all complete as per specification and direction of E/I.	Nos.					190	25.14	4776.60
4		Providing and Labour for cutting 62 mm to 75 dia Bamboo piles to size and making shoes and driving etc. complete job as per specification and direction of E/I.	RM					0	66.95	0.00
5		Providing and Labour for fitting & fixing 62 mm to 75 dia Bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wire including cost of G.I. wire or nails etc. complete job as per specification and direction of E/I.	RM					0	31.02	0.00
6		Providing and laying 1000 mm dia reinforced cement concrete pipe NP3 for culvert on first class bedding of granular material in single row excluding excavation, protection works, backfilling, concrete and masonry.	RM		0 Nos*2.5m			0	7076.68	0.00
7		Providing and laying 600 mm dia reinforced cement concrete pipe NP3 for culvert on first class bedding of granular material in single row excluding excavation, protection works, backfilling, concrete and masonry.	RM		0 Nos*2.5m			0	3002.81	0.00
TOTAL (In Rs.)										391364.54

Asita
18/11/24

Junior Engineer,
Rural Works Department,
Works Section, JOGAPATTI

Asita
18/11/24

Assistant Engineer,
Rural Works Department,
Works Sub Division, JOGAPATT

Asita
18/11/24

Executive Engineer,
Rural Works Department,
Works Division, BETTIAH