

तकनीकी प्रतिवेदन

योजना का नाम :- Temporary restoration work in T02-to Sharma
to U more-to Sahibpur
क्षतिग्रस्त पथ की लंबाई :- 9.00 मी0
प्राक्कलित राशि :- 1.389 लाख
योजना शीर्ष :- 3054/2245 F.D.R
आदेश :- सचिव, ग्रामीण कार्य विभाग, विहार पटना का मु0अ-4 (मु0) विविध
(कार्य)-06-109/2024-1956 दिनांक 28.05.2024/ मु0अ-8 (अनु0 एवं अन्नयन) F.D.R
-03-01/2024-89 पटना दिनांक 18.10.2024

प्रतिवेदन

प्रस्तुत प्राक्कलन वर्ष-2024 में अतिवृष्टि/बाढ़ के कारण क्षतिग्रस्त पथ के पथांश में क्षतिग्रस्त भाग में आकस्मिक के रूप से मोटरेबुल/अस्थायी पुर्नस्थापन कार्य का प्राक्कलन रु0...1.389 लाख मात्र के लिए ग्रामीण कार्य विभाग, कार्य प्रमंडल बायसी के द्वारा शीर्ष F.D.R 3054 के अंतर्गत तैयार किया गया है।


पथ के आकस्मिक मरम्मत हेतु आवश्यकतानुसार पथांशों में लोकल मिट्टी भरई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, बॉस का चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट इत्यादी से भरकर बचाव कार्य करते हुए यातायात बहाल करते हुए अस्थायी रूप से पुर्नस्थापित किया गया है।

विभागीय निविदा सं0-RWD/FDR/BIHAR/01 (2024-25) के द्वारा प्राप्त निविदा के तुलनात्मक विवरणी में सफल निविदाकारों के द्वारा मदवार उद्धत न्यूनतम दर (सभी कर सहित) जो अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, पूर्णिया द्वारा अनुमोदित है के दर ही प्राक्कलन तैयार किया गया है।

कार्यहित में प्राक्कलन पर तकनीकी स्वीकृति अपेक्षित है।


कनीय अभियंता/T.S.
कार्य प्रशाखा बायसी


सहायक अभियंता
कार्य अवर प्रमंडल बायसी


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल बायसी।

FDR**Name Of Work :- Temporary restoration Work in T02 Sharma Toli More To Sahidpur****CH :- '1.850 KM****Year :- 2024-25****Block :- Baisi****Division :- Baisi**

S.N	Description	Unit	Length (in meter)	Width (in meter)	Depth/Height (in meter)	Quantity	Rate	Amount
1	2	3	4	5	6	7	8	9
1	Local Sand (As Per Specification)	Cum	-	-	-	0	145.87	0.00
2	Empty Ciment Bags (Supply of Empty Cement Bag Capacity 1.2 CFT in Good condition And As per Specification)	Each	-	-	-	0	3.5	0.00
3	Bamboos 100mm Dia 6m to 8m long)	No	-	-	-	0	178.00	0.00
4	Brick Bats (Brick Bat of Well Burnt Bricks)	Cum	-	-	-	77.51	990.00	76734.90
5	Kiln Rubbish (is Should be elen & Free from other impurities)	Cum	-	-	-	0	148.00	0.00
6	Hume Pipe (NP3) 1000mm Dia (NP3 RCC Hume Pipe)	M	-	-	-	0	2400.00	0.00
7	Unskilled Labour (8 Hrs/Day)	Per Day	-	-	-	78	300.00	23400.00
8	Skilled Labour (8 Hrs/Day)	Per Day	-	-	-	16	365.00	5840.00
9	Tractor With Trolley (Transportation of Material) Cum 3 to 5 Ton	Ton/T rip	-	-	-	34	600.00	20400.00
10	8-10 Ton smooth Wheeled (Compaction/Consolidation) Cum/Hour 70/25	Per Hour	-	-	-	0	850.00	0.00
11	Generator Set With Fuel (Grnaration of Electecal Energy) KVA 5	Per Day	-	-	-	0	296.00	0.00
11	Front End Loader 1.0 Cum Bucket Capacity (JCB)	Per Hour	-	-	-	9	1400.00	12600.00
Total-								138974.90

Say Rs 138900 = 00

Rate Approved by S.E RWD, Purnia

22/11/24
22/11/24
 Junior Engineer / T.S

22/11/24
 Assistant Engineer

22/11/2024
 Executive Engineer
 Rural Works Department
 Work Division Baisi

Technically Sanctioned for Rs 138900 = 00 (Rupees one lac thirty eight thousand Nine Hundred) only.

28/11/24
 अधीक्षण अभियंता
 ग्रामीण कार्य विभाग
 कार्य अंचल, पूर्णिया
28/11/24