

तकनीकी प्रतिवेदन

Temporary Restoration work in length of road from
Manjhok to phulwari

योजना का नाम :-
क्षतिग्रस्त पथ की लंबाई :- 6.50 मी०
प्राक्कलित राशि :- 0.88400 लाख
योजना शीर्ष :- 3054/2245 F.D.R
आदेश :- सचिव, ग्रामीण कार्य विभाग, बिहार पटना का मु०अ-4 (मु०) विविध
(कार्य)-06-109/2024-1956 दिनांक 28.05.2024/ मु०अ-8 (अनु० एवं अन्नयन) F.D.R
-03-01/2024-89 पटना दिनांक 18.10.2024

प्रतिवेदन

प्रस्तुत प्राक्कलन वर्ष-2024 में अतिवृष्टि/बाढ़ के कारण क्षतिग्रस्त पथ के पथांश में क्षतिग्रस्त भाग में आकस्मिक के रूप से मोटरेबुल/अस्थायी पुर्नस्थापन कार्य का प्राक्कलन रु०..... 8.8400/- मात्र के लिए ग्रामीण कार्य विभाग, कार्य प्रमंडल बायसी के द्वारा शीर्ष F.D.R 3054 के अंतर्गत तैयार किया गया है।

पथ के आकस्मिक मरम्मत हेतु आवश्यकतानुसार पथांशों में लोकल मिट्टी भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, बॉस का चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट इत्यादी से भरकर बचाव कार्य करते हुए यातायात बहाल करते हुए अस्थायी रूप से पुर्नस्थापित किया गया है।

विभागीय निविदा सं०-RWD/FDR/BIHAR/01 (2024-25) के द्वारा प्राप्त निविदा के तुलनात्मक विवरणी में सफल निविदाकारों के द्वारा मदवार उद्धृत न्यूनतम दर (सभी कर सहित) जो अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, पूर्णिया द्वारा अनुमोदित है के दर ही प्राक्कलन तैयार किया गया है।

कार्यहित में प्राक्कलन पर तकनीकी स्वीकृति अपेक्षित है।

20/11/24
कनीय अभियंता
कार्य प्रशाखा बैला।

20/11/24
सहायक अभियंता
कार्य अवर प्रमंडल बैला.....।

22/11/2024
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल बायसी।

FDR

Name Of Work :- Temporary restoration Work in Const. Of Road From Manjhok To Phulwari

Change :- 1.975 KM

Year :- 2024-25

Block :- Baisa

Division :- Baisi

Temporary restoration Name Of Work :- CONST. OF ROAD FROM MANJHOK TO PHULWARI

S.N	Description	Unit	Length (in meter)	Width (in meter)	Depth/Height (in meter)	Quantity	Rate	Amount
1	2	3	4	5	6	7	8	9
1	Local Sand (As Per Specification)	Cum	-	-	-	0	145.87	0.00
2	Empty Ciment Bags (Supply of Empty Cement Bag Capacity 1.2 CFT in Good condition And As per Specification)	Each	-	-	-	0.00	3.5	0.00
3	Bamboos (100 mm Dia 6m to 8m long)	No	-	-	-	0	178.00	0.00
4	Brick Bats (Brick Bat of Well Burnt Bricks)	Cum	-	-	-	49.33	990.00	48836.70
5	Kiln Rubbish (is Should be elen & Free from other impurities)	Cum	-	-	-	0	148.00	0.00
6	Hume Pipe (NP3) 1000mm Dia (NP3 RCC Hume Pipe)	M	-	-	-	0	2400.00	0.00
7	Unskilled Labour (8 Hrs/Day)	Per Day	-	-	-	49	300.00	14700.00
8	Skilled Labour (8 Hrs/Day)	Per Day	-	-	-	9	365.00	3285.00
9	Tractor With Trolley (Transportation of Material) Cum 3 to 5 Ton	Ton/T rip	-	-	-	22	600.00	13200.00
10	8-10 Ton smooth Wheeled (Compaction/Consolidation) Cum/Hour 70/25	Per Hour	-	-	-	0	850.00	0.00
11	Generator Set With Fuel (Grnaration of Electecal Energy) KVA 5	Per Hour	-	-	-	0	296.00	0.00
12	Front End Loader 1.0 Cum Bucket Capacity (JCB)	Per Hour	-	-	-	6	1400.00	8400.00
Total Amount-								88421.70

Rate Approved by S.E RWD, Purnia

Junior Engineer

Assistant Engineer

Executive Engineer
Rural Works Department
Work Division Baisi

Technically sanctioned for Rs 88400 = 00 (Rupees Eighty Eight-Thousand and Four Hundred) only

अधीक्षक अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, पूर्णियाँ