SRAL WORKS DEPARAMENTAL SPANNING

GOVERNMENT OF BIHAR

CIRCLE - R.W.D. works Circle, Kishanganj

<u>DIVISION - R.W.D. works Division, Kishanganj-1</u>

Name of Work:-

Restoration work for Repair of Road breaches (Damaged by Flood

for Motoribility in Pmgsy Raod In Paschim Tola to Bastadangi

Block :-

KISHANGANJ

Length of Road:-

0.9 KM

Damage Length:-

27.2 M

Estimated cost :-

Rs 128389.00

Year: 2024-25

INSPECTION REPORT FOR MOTORABLE WORK
Name of Plus: - E.E Work div. Kishanjanj-1 Name of Block Road: - bishanjanj/PMusy Road In Paschin Tola to Bustadangi
Name of Block Road :- Pish ar July Frada In Vasta To Block Road :- Pish adangi
A. For Road
1. Damage Location/Chainage:- ch. 180 M
2. Damage Length: 27.20 M
3. Nature of Damage (Length Wise) (i) Breach :-
(ii) Crust Damage: 27.20 M
(iii) Only Flank Damage :-
whether traffic fully/Partially obstructed: Traffic Partionity obstructed
or restolation :-
i) Material Being Used in Restoration:- Brick bath
ii) Equipment/Tools Being Used in Restoration Works:- Tractor
iii) Restored Length In open Area:- 27.20 M
In habitation Area :-
iv) If Restoration work done in habitation Area give Reason:-
3. For Bridge (Size of Bridge/Culvert)
1) Damage Location/Chainage:-
2) No. of Span Damage :-
3) Length of Span:-
1) Nature of Damage (Pier/Abuttment/
Ving Wall/Approach Road Damage):-
Details of Restoration:-
) Material Being Used in Restoration:-
) Equipment/Tools Being Used in Restoration Works :-
i) Restored Length :-
verall Grade of Restoration work (Satisfactory/Unsatisfactory) :-

(h) In 12.11.20

Signature of Inspector
(Official Seal)

TECHNICAL REPORT

Name of Work:- Restoration work for Repair of Road breaches (Damaged by Flood) for Motoribility in PMGSY Road in Paschim Tola to Bastsdangi

Blcok:- Kishanganj

Estimated Cost:-128389.00

The work done estimate has been framed for the restoration (motorable) of traffic for the above road which was damage/washout during the year 2024-25 flood. This Estimate is prepared for restoration work under FDR as per the instruction of Engineer-in-Chief Rural Works Department Patna Vide Letter No. FDR-03-01/2024-89

- (A) Source of materials
- i) Brick Bats- Local Kiln
- ii) Fine sand-Local
- iii) Cement bags-Local market
- iv) Bamboo-Local
- v) Eart- Private land from 1000m lead
- vi) Hume pipe- Purnea
- (B) Rate Carraige has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carraige of materials has been added to finished rate. Basic rates are evaluated from rate of approved by State schedule rate committee. 18% GST, 1% L.cess and S.fee has been added in the estimate with final rate of the executed items

RWD(W) Sub Division Kishanganj RWD(W) Sub Division Kishanganj Executive Engineer RWD(W) Division Kishanganj-1

ABSTRACT OF COST

Name of Work:-		Restoration work for Repair of Road breaches (Damaged by Flood) for Motoribility in Pmgsy Raod In Paschim Tola to Bastadangi						
Block :-		Kishanganj						
SI. No.		Particulars	Amount (In Rs.) Rs 113389.00 Rs 15000.00 Rs 128389.00					
Α	Cost of Re	estoration work :-						
В	Add Dron	e videography charge three times						
		Total Cost with GST, LC & S.Fee						

RWD

Kishanganj

12.11.24

A.E

R.W.D

Kishanganj

E.E. Mill of

R.W.D Kishanganj - I

Technically affrored for les 128389 (Rupers one land trenty eight thousand three hundred eighty wine) only

> Superintending Engineer Rural Works Department Porks Circle, Kishangani

> > FO

Detailed Estimate

Name of Work:-			Restoration work for Repair of Road breaches (Damaged by Flood) for Motoribility in Pmgsy Raod In Paschim Tola to Bastadangi									
SI. No.	SDB Sl. No.	MORD Ref.No	Description	No.	No.	Length (M)	Width (M)	Height (M)	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
1	WRD	5.7.40	Brick bats	Brick bats							-	
			Providing laying and spreading brick bats in Road ditches all complete as pe approved design, specifications and direction of E/I									
			At ch.180 m	1	1	11.20	(3.40+4.00)/2	(0.3+0.5)/2	16.58			
			At ch.180m	1	1	5.00	(4.0+5.0)/2	(0.9+1.10+0.8)/3	21.00			
			At ch.180m	1	1	7.00	(0.7+0.9)/2	(0.6+0.3)/2	2.52			
			At ch.180m	1	1	4.00	(0.9+1.10)/2	(0.2+0.3)/2	1.00			
								Total:-	41.10	Cum	2759.12	113389.00
	TOTAL									113389.00		

RWD

KISHANGANI

A.E


KISHANGANJ

RWD

KISHANGANJ-1

MGSY Road in Paschim Tola Bastadangi to Malhana Toli Kishanganj





NGSY Road in Paschim Tola Bastadangi to Malhana Toli Kishanganj





121/24 July 211.24

NGSY Road in Paschim Tola Bastadangi to Malhana Toli Kishanganj



(m) france