Abstract of Cost

Name of Work: Estimate for Repairing/Restoration/Making Motorable Roads

Damaged during flood in 2024 in ARARIA District

Name of Road:

HANUMAN NAGAR THAKUR BARI TO MUSLIM TOLA VIA BHAGWAT YADAV MILKI DUMARIYA MAHADALIT BASTI P.S MILKI DUMARIYA

Block: NARPATGANJ District: ARARIA

Divison: RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, KISHANGANJ

SI No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				*
		Cum	59.77	1287.25	76932.50
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
					8
		Mtr.	114.00	72.518	8267.05
	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	33.00	36.179	1193.91

प्रतिवैद्रन

पथ का नाम :- Hanuman Magar Thakurbayi to muslim tula via Bhaguar कार्य का नाम :- for R/2024-25-

में बाढ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

| Maria |

13.11.2024

कनीय अभियंता, ग्रामीण कार्य विभाग, कार्य प्रशाखा, नार्य प्रशाखा, नार्य प्रशाखा, नार्य प्रशाखा, सहायक अभियंता, ग्रामीण कार्य विभाग,

कार्य अवर प्रमण्डल,।

कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमण्डल,