

कार्यपालक अभियंता का कार्यालय,
ग्रामीण कार्य विभाग, कार्य प्रमंडल,
मुजफ्फरपुर पूर्वी-1

पत्रांक 2330/24

दिनांक 30/9/24

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग, कार्य प्रमंडल,
मुजफ्फरपुर पूर्वी-1

सेवा में,

अपर मुख्य कार्यपालक पदाधिकारी-सह-सचिव
बिहार ग्रामीण पथ विकास अभिकरण,
बिहार पटना।

विषय: शीर्ष राज्य योजना (नाबार्ड) अंतर्गत वित्तीय वर्ष 2024-25 में अनुरक्षण मद में व्यय हेतु आवंटन की मांग।

महाशय,

उपर्युक्त विषय प्रासंगिक पत्र के संबंध में शीर्ष राज्य योजना (नाबार्ड) अंतर्गत वित्तीय वर्ष 2024-25 में अनुरक्षण मद में व्यय हेतु संलग्न विवरणी के अनुसार 687773.00 (छह लाख सतासी हजार सात सौ तीहत्तर) रुपये का आवंटन उपलब्ध कराने की कृपा की जाये ताकि किये गये कार्यों का भुगतान किया जा सके।

अनुलग्नक:-यथोक्त

विश्वासभाजन

30/9/24
कार्यपालक अभियंता
ग्रामीण कार्य विभाग, कार्य प्रमंडल,
मुजफ्फरपुर पूर्वी-1
30/9/24
30/9/2024

राज्य योजना (नाबार्ड) अंतर्गत पथों में पंचवर्षीय अनुरक्षण अधियाचना प्रपत्र

राज्य याजना (नाबाड) अतगत पथी न प म न																											
क्र० सं०	कार्य प्रसंडल का नाम	याजना का नाम	एकराशनामा के अनुसार प्राक्धानित राशि वर्षवार					कुल राशि (लाख में)	खय की राशि वर्षवार						कुल राशि (लाख में)	प्रशासनिक स्वीकृति की राशि एवं प्रसंग दिनांक सहित पत्रांक) (लाख में)	पंचवर्षीय अनुरक्षण की राशि सहित अनुमोदित परिमाण विपत्र की राशि (लाख में)	अनुरक्षण हेतु प्रशासनिक स्वीकृति का पत्रांक / दिनांक	मूल निर्माण कार्य करने पूर्ण करने की वास्तविक तिथि	वर्तमान अधियाचित राशि					कुल राशि (लाख में)	कुल अधियाचित राशि (लाख में)	
			प्रथम वर्ष राशि (लाख में)	द्वितीय वर्ष राशि (लाख में)	तृतीय वर्ष राशि (लाख में)	चतुर्थ वर्ष राशि (लाख में)	पंचम वर्ष राशि (लाख में)		प्रथम वर्ष राशि (लाख में)	द्वितीय वर्ष राशि (लाख में)	तृतीय वर्ष राशि (लाख में)	चतुर्थ वर्ष राशि (लाख में)	पंचम वर्ष राशि (लाख में)														
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26		
1	Muzaffarpur East-1	Constriction of bridge of size 3x20.00 m. on Gaurihar man river near brahm sthan Gaurihar mano of Sakra block in Muzaffarpur Dist.	0.52486	1.68838	1.88870	2.31890	4.55883	10.97967	0.00000	0.00000	0.00000	0.00000	0.00000	0.00000	Lt. No.543 dt. 26.03.2015 495.59 Lakh	431.63661	Lt. No.543 dt. 26.03.2015	19.06.2019					2.3189	4.55883	6.87773	6.87773	
																									6.87773		
																									6.87773		

1 कार्य विषयियों के अनुरूप पूर्ण कर लिया गया है।

1 कार्य विषयों के अनुरूप पूर्ण कर लिया गया है।

2 पथ में MQMU/PQM/TE से संबंधित कोई सुधार प्रतिवेदन लंबित नहीं है।

3 अनुमोदित परिमाण विपत्र की कुल राशि प्रासासनिक स्वीकृति की राशि से 20% अधिकतम सीमा के भीतर है साथ ही अनुमोदित परिमाण विपत्र के मदों का विस्तार का विचलन भी 20% से ज्यादा नहीं है।

4 अनुलग्नक - प्रासासनिक स्वीकृति का पत्र, अनुमोदित परिमाण विपत्र एवं एकराशनामा की अभिप्रमाणित प्रतिलिपि।

30/06/2019
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग, कार्य प्रमंडल,
मुजफ्फरपुर पूर्व।
30/06/2019

**बिहार सरकार
ग्रामीण कार्य विभाग**

पत्रांक— मु0 अ0-4 (मु0)-नाबार्ड-03-46/2015

/पटना, दिनांक—

प्रेषक,

गजेन्द्र कुमार मिश्र,
उप सचिव
ग्रामीण कार्य विभाग।

सेवा में,

महालेखाकार, बिहार
वीरचन्द पटेल पथ, पटना।

विषय:— योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परिव्यय-103-ग्राम विकास-राज्य योजना-0105-ग्राम विकास की परियोजनाएं (नाबार्ड संपोषित योजना)-उप शीर्ष के अन्तर्गत बिहार राज्य के विभिन्न जिलों में (परिशिष्ट-1 के रूप में संलग्न सूची के अनुरूप) कुल 230 पुल निर्माण योजनाओं पर प्रशासनिक स्वीकृति प्रदान करने के संबंध में।

महाशय,

निदेशानुसार योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परिव्यय- 103-ग्राम विकास-राज्य योजना-उप शीर्ष-0105-ग्राम विकास की परियोजनाएं (नाबार्ड संपोषित योजना)-उप शीर्ष के अन्तर्गत बिहार राज्य के विभिन्न जिलों में (परिशिष्ट-1 के रूप में संलग्न सूची के अनुरूप) कुल 230 पुल निर्माण योजनाओं जिसकी लम्बाई 12953.90 मी0 एवं राशि 970.32779 करोड़ रु0 (नौ सौ सत्तर करोड़ बत्तीस लाख सत्तहत्तर हजार नौ सौ रुपये) मात्र है, हेतु प्रशासनिक स्वीकृति प्रदान की जाती है।

1. विषयगत 230 पुल योजनाओं का निर्माण संबंधित कार्यपालक अभियंता, ग्रामीण कार्य विभाग द्वारा निविदा के माध्यम से कराने/नामांकन (Nomination) के आधार पर बिहार राज्य पुल निर्माण निगम द्वारा कराने हेतु दिनांक-19.03.15 को मंत्रिपरिषद से स्वीकृति एवं विभागीय संकल्प संख्या-मु0 अ0-4-(मु0) नाबार्ड-03-46/2015-447 अनु0 दिनांक-16.03.15 के आलोक में स्वीकृति दी गई है।
2. इन योजनाओं की स्वीकृति हेतु समीक्षा प्राधिकार, योजना एवं प्राधिकृत समिति द्वारा दिनांक-12.03.2015 को स्वीकृति हेतु अनुशंसा प्राप्त है।
3. इन योजनाओं की स्वीकृति प्राधिकार मंत्रिपरिषद, बिहार सरकार से संचिका संख्या- मु0 अ0-4 (मु0) नाबार्ड-03-46/2015 के पृ0 सं0-17/टि0 पर दिनांक 19.03.15 को स्वीकृति प्राप्त है।
4. इन योजनाओं को तीन वित्तीय वर्षों अर्थात् 2014-15, 2015-16 एवं 2016-17 में पूरा किया जाने का लक्ष्य है।
5. इन योजनाओं के लिए संबंधित कार्यपालक अभियंता ग्रामीण कार्य विभाग/बिहार राज्य पुल निर्माण निगम लिमिटेड द्वारा विस्तृत कार्य योजना उपलब्ध करायेंगे और उसके अनुरूप कार्यों को समयबद्ध ढंग से पूर्ण करने की कार्यवाही करेंगे।
6. इन योजनाओं में उपलब्ध करायी गई राशि के निकासी एवं व्ययन पदाधिकारी संबंधित कार्यपालक अभियंता, ग्रामीण कार्य विभाग होंगे। जो पुल योजना का निर्माण बिहार राज्य पुल निर्माण निगम लिमिटेड द्वारा कराया जायेगा, उन योजनाओं में उपलब्ध करायी गयी राशि की निकासी एवं व्ययन पदाधिकारी अभियंता प्रमुख कार्यालय के पदाधिकारी होंगे, जो इस राशि को बैंक ड्राफ्ट के माध्यम से बिहार राज्य पुल निर्माण निगम लिमिटेड को उपलब्ध करायेंगे।
7. इन योजनाओं के क्रियान्वयन से पूर्व इन योजनाओं पर सक्षम पदाधिकारी से प्रावैधिक स्वीकृति प्राप्त कर ली जायेगी।
8. इन योजनाओं का व्यय योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर: पूंजीगत परिव्यय-103-ग्राम विकास-राज्य योजना-0105-ग्राम विकास की परियोजनाएं (नाबार्ड संपोषित योजना)-उप शीर्ष के अन्तर्गत वित्तीय वर्ष 2014-15 में उपबंधित राशि से विकलनीय होगा।

9. योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूँजीगत परिव्यय-103-ग्राम विकास-राज्य योजना-0105-ग्राम विकास की परियोजनाएं (नाबार्ड संपोषित योजना)-उपशीर्ष के अन्तर्गत वित्तीय वर्ष 2014-15 में 468.57 करोड़ रुपये का बजट उपबंध स्वीकृत है।
10. संबंधित कार्यपालक अभियंता, ग्रामीण कार्य विभाग, संबंधित अधीक्षण अभियंता एवं मुख्य अभियंता के माध्यम से/प्रबंध निदेशक, बिहार राज्य पुल निर्माण निगम लिमिटेड द्वारा इन योजनाओं की भौतिक एवं वित्तीय प्रगति प्रतिवेदन प्रत्येक माह के 10 तारीख तक निश्चित रूप से ग्रामीण कार्य विभाग, मुख्यालय को उपलब्ध करायेगें एवं तदनुसार विभाग द्वारा आवंटन उपलब्ध कराया जाएगा।
11. यह आदेश वित्त विभाग के संकल्प संख्या-4-45/94-301 वि (2) दिनांक 31.01.1995 एवं वित्त विभाग पत्रांक स्कीम (8)-11-2005-5090 वि (2) दिनांक 15.09.05 के आलोक में आंतरिक वित्तीय सलाहकार की सहमति प्राप्त कर निर्गत किया जा रहा है। आन्तरिक वित्तीय सलाहकार की सहमति संचिका सं० मु० अ०-4 (मु०)-4515/नाबार्ड-03-46/2015 के पृ० सं०-20/टि० पर दिनांक-26.03.15 को प्राप्त है।
12. वित्त विभाग के पत्रांक-770, दिनांक 20.09.2011 के द्वारा सूचित करना किया गया है कि नाबार्ड से RIDF के अन्तर्गत नई योजनाओं के प्रशासनिक अनुमोदन प्राप्त करने के उपरांत ही स्वीकृति हेतु नाबार्ड को भेजा जाये।

अनु० - परिशिष्ट-1

विश्वासभाजन

ह०/-

(गजेन्द्र कुमार मिश्र)

उप सचिव

/पटना, दिनांक-

ज्ञापांक- मु० अ०-4 (मु०) नाबार्ड-03-46/2015

प्रतिलिपि- सभी कोषागार पदाधिकारी, बिहार, पटना को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित।

ह०/-

उप सचिव

ज्ञापांक- मु० अ०-4 (मु०) नाबार्ड-03-46/2015

54325/पटना, दिनांक-26/03/15

प्रतिलिपि- माननीय मंत्री के आप्त सचिव, ग्रा० का० वि०/प्रबंध निदेशक, बिहार राज्य पुल निर्माण निगम लिमिटेड, पटना/आयुक्त एवं सचिव, योजना एवं विकास विभाग/वित्त विभाग (आय-व्यय शाखा)/सचिव, पथ निर्माण विभाग पटना/सचिव, ग्रामीण कार्य विभाग पटना/आंतरिक वित्तीय सलाहकार, ग्रामीण कार्य विभाग/मंत्रीमंडल सचिवालय एवं समन्वय विभाग/कार्मिक एवं प्रशासनिक-सुधार विभाग/ सभी प्रमंडलीय आयुक्त/सभी जिला पदाधिकारी/सभी उप विकास आयुक्त/अभियंता प्रमुख-सह-अपर आयुक्त-सह-विशेष सचिव, ग्रा० का० वि०, बिहार, पटना/मुख्य अभियंता-1,2,3 पटना एवं मुख्य अभियंता-4 (मुख्यालय), ग्रा० का० वि०/सभी अधीक्षण अभियंता, ग्रा० का० वि०/सभी कार्यपालक अभियंता, ग्रा० का० वि०/मुख्य महाप्रबंधक नाबार्ड, बिहार क्षेत्रीय कार्यालय, (मौर्या कम्पलेक्स, चौचवी मंजिल) डाक बंगला रोड, पटना को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित तथा आई०टी० नोडल, ग्रामीण कार्य विभाग को विभाग के वेबसाइट पर अपलोड करने हेतु प्रेषित।

26.03.15
उप सचिव

क्र. सं.	संकेत सं.	जिला का नाम	कार्य प्रमोदन का नाम	प्रकल्प का नाम	पुल योजना का नाम	पुल की लंबाई (मीटर में)	सकनीकी अनुमोदन की राशि (लाख में)	सकनीकी अनुमोदन का प्रस्ताव	सकनीकी अनुमोदन प्रस्ताव देने वाले पदाधिकारी का नाम एवं पदनाम
1	2	3	4	5	6	7	8	9	10
166	गु 30-4 (गु) नवार्ड-03-308/2014	गुजरापुर	गुजरापुर पूर्वी-1	कुइनी	गुजरापुर जिलान्तर्गत कुइनी प्रखंड के बुयावन घाट कइने नदी पर 3X25.00 मी० आकार के पुल निर्माण	75 000	605.310	मुख्य अभियंता-3 पटना के पत्रांक 3750 दिनांक 18.11.14	श्री रामजी चौधरी मुख्य अभियंता-3 पटना
167	गु 30-4 (गु) नवार्ड-03-308/2014	गुजरापुर	गुजरापुर पूर्वी-1	सकरा	गुजरापुर जिलान्तर्गत सकरा प्रखंड के ब्रह्म स्थान गरीहारमान के नजदीक गरीहार मान नदी पर 3X20.00 मी० आकार के पुल निर्माण	60.000	495.590	मुख्य अभियंता-3 पटना के पत्रांक 3751 दिनांक 18.11.14	श्री रामजी चौधरी मुख्य अभियंता-3 पटना
168	गु 30-4 (गु) नवार्ड-03-427/2014	गुजरापुर	गुजरापुर पूर्वी-2	औरली	गुजरापुर जिलान्तर्गत औरली प्रखंड के औरली नवा गाँव पथ में 2X15.00 मी० आकार के पुल निर्माण	30.000	331.880	मुख्य अभियंता-3 पटना के पत्रांक 4074 दिनांक 18.12.14	श्री रामजी चौधरी मुख्य अभियंता-3 पटना
169	गु 30-4 (गु) नवार्ड-03-428/2014	गुजरापुर	गुजरापुर पूर्वी-2	नाम घण्ट	गुजरापुर जिलान्तर्गत कटरा प्रखंड के सिसवा और गांव घाट प्रखंड के कडवा के बीच सिसवा नदी पर 3X15.00 मी० आकार के पुल निर्माण	45 000	416.690	मुख्य अभियंता-3 पटना के पत्रांक 4074 दिनांक 18.12.14	श्री रामजी चौधरी मुख्य अभियंता-3 पटना
170	गु 30-4 (गु) नवार्ड-03-428/2014	गुजरापुर	गुजरापुर पूर्वी-2	कोयला	गुजरापुर जिलान्तर्गत कोयला प्रखंड के कोयला इनार घाट के नजदीक कोयली नदी पर 3X15.00 मी० आकार के पुल निर्माण	45 000	408.640	मुख्य अभियंता-3 पटना के पत्रांक 4074 दिनांक 18.12.14	श्री रामजी चौधरी मुख्य अभियंता-3 पटना
171	गु 30-4 (गु) नवार्ड-03-527/2014	देहाती	महुआ	महुआ	देहाती जिलान्तर्गत महुआ प्रखंड के सेरपुर मनी पचावत अन्तर्गत बहुरी घाट से महुआ नदी को जोड़ने वाली पथ में बाज नदी पर 3X21.75 मी० आकार के पुल निर्माण	65.250	523.040	मुख्य अभियंता-3 पटना के पत्रांक 3801 दिनांक 21.11.14	श्री रामजी चौधरी मुख्य अभियंता-3 पटना
172	गु 30-4 (गु) नवार्ड-03-265/2014	देहाती	महना	देहाती	देहाती जिलान्तर्गत देहाती प्रखंड के चौदण्ड से गौजीपुर पथ में डेनी नदी पर 6X3.5 मी० (3 cell) आकार के पुल निर्माण	21.000	114.240	मुख्य अभियंता-3 पटना के पत्रांक 3816 दिनांक 05.11.14	श्री रामजी चौधरी मुख्य अभियंता-3 पटना
173	गु 30-4 (गु) नवार्ड-03-264/2014	देहाती	महना	राधापुर	देहाती जिलान्तर्गत राधापुर प्रखंड के जुआनपुर से चकरीपुर से विनापुर मगलान पथ में जुआनपुर सेना नदी पर 6X3.5 मी० (3 cell) आकार के पुल निर्माण	21 000	102.270	मुख्य अभियंता-3 पटना के पत्रांक 3817 दिनांक 05.11.14	श्री रामजी चौधरी मुख्य अभियंता-3 पटना
174	गु 30-4 (गु) नवार्ड-03-265/2014	देहाती	महना	विदुपुर	देहाती जिलान्तर्गत विदुपुर प्रखंड के विदुपुर मगलान पथ में नगदा नदी पर 6X3.5 मी० (3 cell) आकार के पुल निर्माण	28 000	134.560	मुख्य अभियंता-3 पटना के पत्रांक 3818 दिनांक 05.11.14	श्री रामजी चौधरी मुख्य अभियंता-3 पटना
175	गु 30-4 (गु) नवार्ड-03-88/2015	सीतामढ़ी	पुरी	बाजपट्टी	सीतामढ़ी जिलान्तर्गत बाजपट्टी प्रखंड के रावलपुर से बनटोला जाने वाली सड़क में बनटोला स्कुल के नजदीक संधी घाट पर 3x22.00 मी० उच्च स्तरीय पुल निर्माण	66.000	573.600	मुख्य अभियंता-3 पटना के पत्रांक 155 दिनांक 27.01.15	श्री रामजी चौधरी मुख्य अभियंता-3 पटना
176	गु 30-4 (गु) नवार्ड-03-55/2015	सीतामढ़ी	पुरी	बाजपट्टी	सीतामढ़ी जिलान्तर्गत बाजपट्टी प्रखंड के रावलपुर से बनटोला जाने वाली सड़क में रावलपुर गाँव के नजदीक संधी नदी पर 3x25.00 मी० उच्च स्तरीय पुल निर्माण	75.000	547.790	मुख्य अभियंता-3 पटना के पत्रांक 155 दिनांक 27.01.15	श्री रामजी चौधरी मुख्य अभियंता-3 पटना
177	गु 30-4 (गु) नवार्ड-03-100/2015	सीतामढ़ी	पुरी	बाजपट्टी	सीतामढ़ी जिलान्तर्गत बाजपट्टी प्रखंड के बनटोला बसों के बीच पथ में रावलपुर राव के कलन के नजदीक पुरानी कछारा नदी पर 2X12.00 मी० पुल निर्माण	24 000	457.660	मुख्य अभियंता-3 पटना के पत्रांक 578 दिनांक 11.02.15	श्री रामजी चौधरी मुख्य अभियंता-3 पटना

A.A. ₹ 495.59 Lacs

NABARD (2014-15)

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF BRIDGE : Construction of RCC Bridge over Gorihar Maan River near Braham Asthan Gorihar Maan

DISTRICT : Muzaffarpur

BLOCK : Sakra

LENGTH OF BRIDGE : 64.66 m

LENGTH OF APPROCH : 408.74 m

SPAN ARRANGEMENT : 3 X 20.00 m

TOTAL LENGTH OF IMPROVEMENT 473.40 m

Sl No.	DESCRIPTION	AMOUNT (RS.)
1	COST OF BRIDGE STRUCTURE	36442827.73
2	COST OF APPROACH & Misc.	5640266.01
	TOTAL COST =	42083093.74
	Contingency 1% up to 1.0 Crore & 0.5% of above=	260415.47
	TOTAL COST OF PROJECT =	42343509.00
	TOTAL COST OF PROJECT IN LACS =	423.44
	5 YEARS MAINTENANCE COST (IN LACS)=	11.42

Total Cost = 434.86 Lacs


Junior Engineer
RWD (w) Division, Muzaffarpur East - 1

Assistant Engineer
RWD (w) Division, Muzaffarpur


Executive Engineer
RWD (w) Division, Muzaffarpur

S.E.
RWD (w) Circle, Muzaffarpur


Supervising Engineer
Rural Works Dept. Works Circle
Muzaffarpur
2016

1. Name of the work : Construction of RCC Bridge over Gorihar Maan River near Braham Asthan Gorihar Maan Under NABARD
2. No. of Bridge : 1
3. Size of Bridge. : 3 x 20.00m
4. Name of the Agency & Address : M/s Jai Shankar Kumar
Village + Post : Mahmadda, Via : Pusa
Distt. : Samastipur
5. Agreement No. : 18SRD 2 2016-17
6. Approval of Rate : S.E., R.W.D. Muzaffarpur, letter No. 937 enc. dt. 18.07.2016 on 10.00 % below from Schedule rate.
7. Agreement value of the work:-
 - (a) Construction cost — — — : Rs. 4,20,32,584.00
 - (b) Maintenance cost — — — : Rs. 11,31,077.00

Rs. 4 31,63,661.00 Less 10.00% below from Schedule rate.
Rs. 3,88,47,295.00
(Rupees Three crore eighty eight lakh forty seven thousand two hundred ninety five) only.
8. Performance security (including : 5.75% (Five point seven five percent) of the
earnest money) Agreement value. (Rs. 22,34,000.00)

Performance security (including earnest money) deposited by the Agency in the form of BG amounting to Rs. 22,34,0000.00 The details of BG is as follow:-

- (i) Vijaya Bank, BG No. 8406IBGIS160028 Rs. 22,34,0000.00
Tilak Maidan Road, dated 15.09.2016
Muzaffarpur (Rupees Twenty two lakh thirty four thousand only)

9. Date of work Order : 26.08.2016
10. Date of completion : 25.08.2017 (Twelve Month)
11. Security Deposit : 8% (Eight percent) to be deducted
from the gross amount of each running Bill.
12. Defect liability period : Five years from the actual date of completion
of the work.
13. Refund of performance security : After five years from the actual date of
and security deposit. completion of the work.
14. Total item of Agreement : 47 item in Bridge

Note:-S.B.D. Rules, terms and conditions will be applicable.

Confidential

Executive Engineer

R.W.D. Works Division

Muzaffarpur East-1

Executive Engineer

R.W.D. Works Division

Muzaffarpur East-1



S 869589

शतपरावयक्त लि.

This Agreement made on the14/12/14..... between Executive Engineer R.W.D. Works Division, Muzaffarpur East-1 (name and address of Employer) hereinafter called "the employer" and M/s Jai Shankar Kumar, Village + Post : Mahmadda, Via : Pusa, Distt. : Samastipur (name and address of contractor) hereinafter called "the contractor" on the other part.

Whereas the Employer is desirous that the contractor execute Construction of RCC Bridge over Gorihar Maan River near Braham Asthan Gorihar Maan Under NABARD.

(name and identification number of contract) (hereinafter called 'the works') and the Employer has accepted the Bid by the contractor for the execution and completion of such works and the remedying of any defects therein, at a cost of Rs. 3,88,47,295.00 (Rupees Three crore eighty eight lakh forty seven thousand two hundred ninty five) only.

NOW THIS AGREEMENT WITNESSETH as follows:-

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the conditions of contract hereinafter referred to and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer, the contractor as hereinafter mentioned, the contractor hereby covenants with the employer to execute and complete the works and remedy any defects therein in conformity in all aspects with the provisions of the contract.

१५५५२५०५२

59/-
Executive Engineer,
R.W.L. Works (B.I.),
Muzaffargarh Dist.

3. The Employer hereby covenants to pay the contractor in consideration of the execution and completion of the works and the remedying the defects wherein contract price or such other sum as may become payable under the provisions of the contract at the times and in the manner prescribed by the contract.
4. The following documents shall be deemed to form and be ready and construed as part of this Agreement viz.
- (i) Letter of Acceptance.
 - (ii) Notice to proceed with the works.
 - (iii) Contractor's Bid.
 - (iv) Condition of contract : General and Special.
 - (v) Contract Data.
 - (vi) Additional condition.
 - (vii) Drawings.
 - (viii) Bill of Quantities and
 - (ix) Any other document listed in the contract Data as forming part of the contract.

In witnessed where of the parties there to have caused this Agreement to be executed the day and year first before written.

The common seal of _____
was hereunto affixed in the presence of:

Signed, sealed and Delivered by the said M/S Jai Shree K.V.

VIII. TPD - Mahanagda, via Pusa Dist. Sonosijha
in the presence of:

Binding Signature of the Employer _____

Executive Engineer
R.W. D. Work Division

Binding Signature of the Employer _____

Executive Engineer
R.W. D. Work Division

6/2/2020

अधीक्षण अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य अंचल, मुजफ्फरपुर।

पत्रांक 931/...../अनु0

मुज0/दिनांक-.....18/7...../2018

प्रेषक

ई0 ओम प्रकाश मांझी,
अधीक्षण अभियंता।

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मुजफ्फरपुर पूर्वी-1।

विषय:- शीर्ष 4515 नाबार्ड योजना अन्तर्गत सकरा प्रखंड के ब्रह्म स्थान गौरीहार मान के नजदीक गौरीहार मान नदि पर उच्चस्तरीय पुल निर्माण (Tender Id- 39512) कार्य के निविदा निष्पादन के संबंध में।

महाशय,

शीर्ष 4515 नाबार्ड योजना अन्तर्गत सकरा प्रखंड के ब्रह्म स्थान गौरीहार मान के नजदीक गौरीहार मान नदि पर उच्चस्तरीय पुल निर्माण (Tender Id- 39512) कार्य के वित्तीय बीड में समान दर (परिमाण विपत्र की दर से 10%) होने की स्थिति में लाट्ररी के फलाफल के आधार पर सफल निविदाकार मे0जय शंकर कुमार (BID ID-133369) जिनका उद्धृत दर परिमाण विपत्र की दर से 10% कम है, पर यह कार्य ₹ 3,88,47,295.00/- (तीन करोड़ शठासी लाख सैतालीस हजार दौ सौ पंचानवे रूपय) मात्र की लागत पर प्रासंगिक पत्र के आलोक में आवंटित किया जाता है।

- क्रमांक 1 में अंकित राशि निर्माण कार्य एवं अनुरक्षण कार्य की सम्मिलित राशि है। अनुमोदित परिमाण विपत्र से इसका मिलान कर गणना के पश्चात ही कार्यपलाक अभियंता एकरारनामा की कार्रवाई करेंगे। किसी प्रकार की त्रुटि दृष्टिगोचर होती है तो इसकी सूचना तत्काल अधोहस्ताक्षरी को देंगे।
- कार्य का निष्पादन शीर्ष 4515 नाबार्ड योजना अंतर्गत मार्गदर्शिका एवं मानक निविदा अभिलेख के अनुरूप किया जाएगा।
- इस कार्य का व्यय शीर्ष 4515 नाबार्ड योजना से मिलने वाली राशि के अंतर्गत उपबंधित राशि से विकलित होगा।
- परिमाण विपत्र की दर से कम दर उद्धृत करने वाले संवेदक से विभाग द्वारा पूर्व में निर्गत दिशा-निर्देश के आलोक में अतिरिक्त वांछित परफॉरमेंस सिक्यूरिटी की राशि जमा करना सुनिश्चित करेंगे।
- उक्त निविदादाता से अद्यतन आयकर, बिक्रीकर, वैट निबंधन/वैट स्वच्छता प्रमाण पत्र, खनन स्वच्छता प्रमाण पत्र, लेबर लाईसेंस, पार्टनर-शीप डीड मूल में प्राप्त कर तथा डिबार/कालीकृत का जाँचोपरान्त, नाम नहीं रहने पर ही एकरारनामा की कार्रवाई की जाय।
- इस कार्य के संबंध में ग्रामीण कार्य विभाग, बिहार सरकार द्वारा निर्गत प्रशासनिक स्वीकृति एवं प्रावैधिक स्वीकृति तथा निविदा आमंत्रण सूचना में उल्लेखित शर्त एवं संवेदक से कार्य प्रोग्राम एकरारनामा का भाग होगा।
- कार्यपालक अभियंता को निदेश दिया जाता है कि संवेदक से एकरारित अवधि के अंदर कार्य समाप्त करने हेतु विस्तृत मदवार कार्य प्रोग्राम प्राप्त कर ही एकरारनामा किया जाय।
- कार्य समाप्ति की अवधि निविदा आमंत्रण सूचना के अनुसार होगी।

Executive Engineer
R.W. Works Division
Muzaffarpur District

(2)

10. अग्रधन एवं जमानत के रूप में जमा राशि जो कार्यपालक अभियंता के पदनाम से विधिवत प्रतिज्ञिप्त की गयी है, का सत्यापन संबंधित डाकघर से कराकर एवं स्वयं आश्वस्त होकर ही एकरारनामा करेंगे।
11. अनुमोदित राशि में सभी प्रकार के करों की कटौती की राशि सम्मिलित है।
12. कार्यपालक अभियंता पत्र प्राप्ति के तीन दिनों के अन्दर संवेदक को कार्यारम्भ करने हेतु पत्र निर्गत करेंगे। साथ ही पत्र में स्पष्ट रूप से संवेदक को निदेशित करेंगे कि पत्र निर्गत होने की तिथि से सात दिनों के अंदर अगर संवेदक एकरारनामा नहीं करेंगे तो उनका निविदा रद्द कर उनके इस कार्य में जमा अग्रधन की राशि जब्त करते हुए अन्य निविदादाता को कार्य आवंटन के संबंध में कार्रवाई की जायगी या इस कार्य के लिय पुनः निविदा मांगी जायेगी। निविदा रद्द करने तथा अग्रधन की राशि जब्त करने की सूचना कार्यपालक अभियंता इस कार्यालय को देंगे।
13. अधोहस्ताक्षरी के पूर्वानुमति के बिना कार्य की मात्रा अथवा राशि में किसी प्रकार की बढ़ोतरी नहीं की जायगी।
14. नियमानुसार एकरारनामा की प्रतियाँ स्वीकृत्यादेश हेतु सात दिनों के अंदर इस कार्यालय में समर्पित करेंगे।
15. कार्य में उपयोग होनेवाले सामग्रियों का दर कार्यपालक अभियंता द्वारा दर्शायी गयी लीड पर आधारित है। यदि उससे कम दूरी से सामग्री स्थल पर लाई जाती है तो उसका दर दूरी के अनुपात में कम कर दिया जाएगा।
16. कार्यपालक अभियंता या उनके प्राधिकृत अभियंता स्थल आदेश पुस्तिका पर विस्तृत आदेश देते हुए कार्य करावेंगे जिसकी प्रतिलिपि इस कार्यालय को देंगे।
17. पथ सामग्रियों की आपूर्ति कार्यपालक अभियंता द्वारा निर्धारित उचित स्टैक (थाक) में ली जाएगी जिसका उपयोग कार्यपालक अभियंता के जाँच एवं निर्गत आदेश के उपरांत ही होगी।
18. किसी भी परिस्थिति में निजी जमीन पर निर्माण नहीं कराया जाय।
19. प्रत्येक आवंटन अधियाचना के पूर्व संवेदक को उनके द्वारा निष्पादित कार्यों का अपने अभियंता से मदवार मापी कराकर उनके हस्ताक्षर सहित विपत्र, गुणवत्ता जाँच फल एवं संपादित कार्यों के फोटोग्राफ के साथ प्रमंडलीय कार्यालय में समर्पित करना अनिवार्य होगा।

अनु०:-निविदा कागजात मूल में।

तुलनात्मक विवरणी मूल प्रति।

विश्वासभाजन,
अधीक्षण अभियंता,
ग्रामीण कार्य विभाग, कार्य अंचल,
मुजफ्फरपुर।
18/7/18

Order

Name of Work:- सकरा प्रखंड के ब्रह्म स्थान गौरीहार मान के
नजदीक गौरीहार मान नदी पर उच्चस्तरीय पुल
का निर्माण

Name of Division:- Muzaffarpur East-1

Head:- NABARD

Tender ID:- 39512

1. Amount as per financial Bid ————— Rs. 4,31,63,661=00

Less % rate quoted by

lowest valid tenderer i.e 10%

(Ten Persent) below the

B.O.Q. Rate ————— (-) Rs. 43,16,366 =00

Net Rs. 3,88,47,295=00

2. The Work is allotted to M/S Jai Shankar Kumar

Bid Id- 133369 on 10 % (Ten Persent)

Below the B.O.Q., amounting Rs. . 3,88,47,295=00 (Three Crore Eighty
Eight Lakh Forty Seven Thousand Two Hundred Ninty Five) Only

3. The Time of Completion of work - As per NIT

4. Recovery ————— Nil

Superseding Engineer
Rural Works Deptt. Works Circle
Muzaffarpur

Executive Engineer
R.W.D. Works Division

Construction of RCC Bridge over Gorihar Maan River near Braham Asthan Gorihar Maan UNDER NABARD

Sl. No.	Description of Items	Qty.	Unit	Rate	
				In Figure	In word
	FOUNDATION				
1	Excavation for Structures				
	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.				
	I. Ordinary Soil				
	i) Upto 3m depth	841.800	Cum	215.87	Rupees Two Hundred Fifteen And Eighty Seven Paise Only
	ii) 3m to 6m depth	140.310	Cum	256.35	Rupees Two Hundred Fifty Six And Thirty Five Paise Only
2	Providing and laying of PCC M15 levelling course 100mm thick below the pile cap.				Rupees Six Thousand Two Hundred Eighty Three And Fifty Eight Paise Only
	II. PCC Grade M-15 (Levelling Course for Pile Cap)	35.000	Cum	6,283.58	
3	R.C.C. grade M 30 in Pile Foundation complete as per Dwg & Tech Specification.				Rupees Seven Thousand Five Hundred Twenty One And Sixty Four Paise Only
	Pile Cap in RCC M-30	385.550	Cum	7,521.64	
4	Bored cast-in-situ M35 grade R.C.C. Pile excluding Reinforcement complete as per Drawing and Technical Specifications and removal of excavated earth with all lifts and lead upto 1000 m.				Rupees Seventeen Thousand Four Hundred Thirty Seven And Eighty Seven Paise Only
	II. 1200 mm Dia	560.000	m	17437.87	
5	Supplying, fitting and placing HYSD bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202	91.870	MT	51,851.28	Rupees Fifty One Thousand Eight Hundred Fifty One And Twenty Eight Paise Only
6	Providing steel liner 10 mm thick for curbs and 6mm thick for steining of wells including fabricating and setting out as per detailed drawing	14.200	MT	77,803.62	Rupees Seventy Seven Thousand Eight Hundred Three And Sixty Two Paise Only
7	Providing and Constructing Temporary Earth Island (Assuming depth of water 1.0 m and height of island to be 1.25 m including Royalty for earth @ Rs. 5526.00 for each Island.)	2.000	No.	50,404.79	Rupees Fifty Thousand Four Hundred Four And Seventy Nine Paise Only
8	Carrying out load test on any pile as per standard procedure laid down in the IS:2911 specification including construction of test cap, dismantling the cap after test and cleaning the site and maintaining complete records of load				
	a) Initial Load Test on test pile for 2.5 times the design load specified in Drawings				
	1.2 m Dia Pile (Subject to Approval at the time of work)	2.00	Nos.	150,000.00	Rupees One Fifty Thousand Only
	b) Routine pile load test on pile for 1.5 times the design load specified in Drawings				
	1.2 m Dia Pile (2% of piles in total). (Subject to Approval at the time of work)	2.00	Nos.	125,000.00	Rupees One Twenty Five Thousand Only
	c) Horizontal pile load test on pile for 1.5 times the design load specified in Drawings				
	1.2 m Dia Pile (2% of piles in total) . (Subject to Approval at the time of work)	1.00	Nos.	100,000.00	Rupees One lac only
	SUBSTRUCTURE				
9	R.C.C. grade M-30 in Substructure complete as per Dwg & Tech Specification				
	RCC M-30				
	i) Upto 5m height (Using Concrete Mixer)				
	ii) From 5m upto 10m height (Using Concrete Mixer)	132.690	Cum	7,817.84	Rupees Seven Thousand Eight Hundred Seventeen And Eighty Four Paise Only
10	R.C.C. grade M-35 in Substructure complete as per Dwg & Tech Specification	65.030	Cum	7,959.11	Rupees Seven Thousand Nine Hundred Fifty Nine And Eleven Paise Only
	RCC M-35				
	ii) From 5m upto 10m height (Using Concrete Mixer)	14.060	Cum	8,054.57	Rupees Eight Thousand Fifty Four And Fifty Seven Paise Only

Sl. No.	Description of Items	Qty.	Unit	Rate	
				In Figure	In word
PROTECTION WORK					
27	Providing and laying boulder pitching on slopes laid over prepared filter media as per drawing and technical specifications Clause 1302	824.010	cum	3318.85	Rupees Three Thousand Three Hundred Eighteen And Sixty Five Paise Only
28	Providing and laying filter material underneath pitching in slopes complete as per	199.390	cum	3715.06	Rupees Three Thousand Seven Hundred Fifteen And Six Paise Only
E. APPROCH ROAD					
29	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation , grass ,bushes ,shrubs , saplings and trees of girth upto 300mm , removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification - clause 201.1 and direction of E/I	0.379	Ha	37602.79	Rupees Thirty Seven Thousand Six Hundred Two And Seventy Nine Paise Only
30	Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m , transporting to the site spreading , grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5 .	16,636.750	Cum	161.55	Rupees One Hundred Sixty One And Fifty Five Paise Only
31	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	1,333.514	Cum	162.95	Rupees One Hundred Sixty Two And Ninety Five Paise Only
32	Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	295.488	Cum	2398.28	Rupees Two Thousand Three Hundred Ninety Eight And Twenty Eight Paise Only
33	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.	117.257	Cum	4316.42	Rupees Four Thousand Three Hundred Sixteen And Forty Two Paise Only
34	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	117.257	Cum	3963.05	Rupees Three Thousand Nine Hundred Sixty Three And Five Paise Only
35	Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.90- 1.2 kg/sqm using mechanical means as per Technical Specification Clause 502.	1,563.431	Sqm	34.63	Rupees Thirty Four And Sixty Three Paise Only
36	Providing and applying tack coat with bitumen emulsion (RS) using emulsion distributor @ 0.2 to 0.25 kg per sq m on the prepared bituminous surface cleaned with hydraulic broom as per technical specification clause 503.	1,563.431	Sqm	12.54	Rupees Twelve And Fifty Four Paise Only
37	Providing , laying and rolling of open graded premix carpet of 20 mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumin or emulsion to required line grade , and level to serve as wearing course on a previously prepared base , including mixing in a suitable plant , laying and rolling with a three wheel 80-100 KN static roller capacity , finished to required level and grades to be followed by seal coat of either Type A or Type B or Type as per Technical Specification clause 508	1,563.431	Sqm	174.07	Rupees One Hundred Seventy Four And Seven Paise Only
38	Providing , laying seal coat sealing the voids in a bituminous surface laid to the specified levels ,grades and cross fall using Type B as per the specification in clause 510 (With Bituminous Binder S-90)	1,563.431	Sqm	52.80	Rupees Fifty Two And Eighty Paise Only
39	Providing and Fixing 'Logo' of Project informayory sign board with Logo as per MORD specifications and drawing. Three MS plates of 1.6mm thick, top and middle plate duly welded with MS flat iron 25mm x 5 m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 Nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600 mm,600 mm,600 below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12SWG steel plate tube. All M.S will be stove enameled on both sides. Lettering and printing arrows, border etc, will be painted with ready mixed synthetic enamer paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 abd Annexure 1700.1.	2.000	NO	7825.84	Rupees Seven Thousand Eight Hundred Twenty Five And Eighty Four Paise Only

G129422

59/1-

Sl. No.	Description of Items	Qty.	Unit	Rate	
				In Figure	In word
	E. DIVERSION				
40	Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m , transporting to the site spreading , grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5.	1,530.000	Cum	161.55	Rupees One Hundred Sixty One And Fifty Five Paise Only
41	Granular Sub-base with Well Graded Material (Table 400.1) Grading II - Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	47.813	Cum	2398.28	Rupees Two Thousand Three Hundred Ninety Eight And Twenty Eight Paise Only
42	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row (2 ROW)	60.000	M	3863.37	Rupees Three Thousand Eight Hundred Sixty Three And Thirty Seven Paise Only
43	Total Cost for 1st Year Maintenance Work	1	Year	58318.82	Rupees Fifty Eight Thousand Three Hundred Eighteen And Eighty Two Paise Only
44	Total Cost for 2nd Year Maintenance Works	1	Year	120967.54	Rupees One Twenty Thousand Nine Hundred Sixty Seven And Fifty Four Paise Only
45	Total Cost for 3rd Year Maintenance Works	1	Year	187598.28	Rupees One Eighty Seven Thousand Five Hundred Ninety Eight And Twenty Eight Paise Only
46	Total Cost for 4th Year Maintenance Works	1	Year	257655.65	Rupees Two Lakh Fifty Seven Thousand Six Hundred Fifty Five And Sixty Five Paise Only
47	Total Cost for 5th Year Maintenance Works	1	Year	506537.20	Rupees Five Lakh Six Thousand Five Hundred Thirty Seven And Twenty Paise Only

NOTE:- 10% Below the S/Rate

Signature
Executive Engineer
R.D. ...
...

Signature