

भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये

रु.1000

ONE THOUSAND RUPEES

Rs.1000

सत्यमेव जयते

INDIA

बिहार BIHAR ११/१२/२०१९

AE 154087

सुभाष चन्द्र दुबे
पुद्गल विक्रेता, बेतिया
ला० नं०-5/86-87

Agreement No.: 64 SBD/MMGSY/2019-20

This agreement, made the 24th day of October 2019 between Executive Engineer R.W.D. Works Division, Bettiah of the one part, Madhu Anand Const. Pvt, Ltd., At-Laukariya, Bairiya, West Champaran, Bihar of the other part.

Whereas the Employer is desirous that the Contractor execute of the Construction of Road from S032 Refugee Colony to Churiharwa in Bairia Block (Tendar ID-74982) Under MMGSY and the Employer has accepted the Bid by the Contractor for the execution and completion of such works and the remedying of any defects therein, at a cost of Rs 1,24,93,776.00 (Rs. One Crore Twenty Four Lac Ninety Three Thousand Seven Hundred Seventy Six Only).

NOW THIS AGREEMENT WITNESSETH as follows:

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the conditions of contract hereinafter referred to and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and Complete the Works and remedy any defects therein in conformity in all aspects with the provisions of the contract.
3. The Employer hereby covenants to pay the Contractor in consideration of the Execution and completion of the Works and the remedying the defects wherein Contract Price or such other sum as may become payable under the provisions of the contract at the times and in the manner prescribed by the Contract.

अमानत

24/10/19
R.W.D. Works Div. Bettiah

13 0 AUG 2019



Rate: 0.01% below

Agreement No - 64 SBD/MMGSY/2019-20

Agreement Value: ₹ 12493776 = w

Date of work order: 24.10.19

Time of completion: 23.10.20

Maintenance: 24.10.20 to 23.10.25

PSD/APS: ₹ 250000 = w by FD

Security deduct from bills - Eight percent (8%)

4. The following documents shall be deemed to form and be ready and construed as part of this Agreement viz.

- (i) Letter of Acceptance
- (ii) Notice to proceed with the works;
- (iii) Contractor's Bid
- (iv) Condition of Contract : General and Special
- (v) Contract Data
- (vi) Additional condition
- (vii) Drawings
- (viii) Bill of Quantities and
- (ix) Any other documents listed in the Contract Data as forming part of the Contract.

In witnessed whereof the parties there to have caused this Agreement to be executed the day and year first before written.

The Common Seal of
was hereunto affixed in the presence of :

Signed, Sealed and Delivered by the said
in the presence of :

Binding Signature of Employer
Binding Signature of Contractor
24.11.19 24.11.19

Executive Engineer
R.W.D. Works Div. Bettiah

अमान कोसी

OFFICE OF THE EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION, BETTIAH

Letter no...../Bettiah Date...../

From

Executive Engineer,
Rural Works Department,
Works Division Bettiah.

To

Madhu Anand Const. Pvt. Ltd.,
At-Laukariya, Bairiya, West Champaran, Bihar

Sub:- Issue of Notice to proceed with the work .

Dear Sirs,

Pursuant to your furnishing the requisite security as stipulated in ITB Clause 34.1 and signing of the Contract for the Construction of Road CD Works Form S032 Refugee Colony to Churiharwa in Bairia Block (Tendar ID-74982) Under MMGSY at a Bid Price of Rs 1,24,93,776.00 (Rs. One Crore Twenty Four Lac Ninety Three Thousand Seven Hundred Seventy Six Only).

You are hereby instructed to proceed with the execution of the said works in accordance with the contract documents.

Yours faithfully,

sd/-
Executive Engineer
R.W.D. Works Division Bettiah

Memo No.:.....2297.....Bettiah/Date:....24/10/19...../

Copy Forwarded to Assistant Engineer, R.W.D. Works Sub-division, Bairia for the necessary action.

आमान कोला

24/10/19

sd/-
Executive Engineer
R.W.D. Works Div. Bettiah

24.10.19

OFFICE OF THE EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION, BETTIAH

Letter no.....2297...../Bettiah Date...24/X/19...../

From

Executive Engineer,
Rural Works Department,
Works Division Bettiah.

To

Madhu Anand Const. Pvt. Ltd.,
At-Laukariya, Bairiya, West Champaran, Bihar


Sub:- Issue of Notice to proceed with the work .

Dear Sirs,

Pursuant to your furnishing the requisite security as stipulated in ITB Clause 34.1 and signing of the Contract for the Construction of Road CD Works Form S032 Refugee Colony to Churiharwa in Bairia Block (Tendar ID-74982) Under MMGSY at a Bid Price of Rs 1,24,93,776.00 (Rs. One Crore Twenty Four Lac Ninety Three Thousand Seven Hundred Seventy Six Only).


You are hereby instructed to proceed with the execution of the said works in accordance with the contract documents.


Yours faithfully,



Executive Engineer
R.W.D. Works Division Bettiah


Memo No.:...2297.....Bettiah/Date:-24/X/19...../

Copy Forwarded to Assistant Engineer, R.W.D. Works Sub-division, Bairia for the necessary action.




Executive Engineer
R.W.D. Works Div. Bettiah


24/X/19


24.10.19

OFFICE OF THE EXECUTIVE ENGINEER
R.W.D WORKS DIVISION, BETTIAH

Letter No. 1540 / Bettiah, Date 19/8/19

From,

Executive Engineer,
Rural Works Department
Works division Bettiah.

To,

Madhu Anand Const. Pvt. Ltd.
At-Laukariya, Bairiya
West Champaran, Bihar

Sub:- Letter of Acceptance.


Dear Sir,

This is to notify that your Bid dated _____ for execution of the Road from S032 Refugee Colony to Churiharwa in Baria Block (Tender ID-74982) Under MMGSY for the Contract Rs 1,24,93,776.00 (Rs. One Crore Twenty Four Lac Ninety Three Thousand Seven Hundred Seventy Six Only), as corrected and modified in accordance with the Instructions to Bidders is hereby accepted by our Agency.

You are hereby requested to furnish Performance Security, in the forms detailed in Para 34.1 of the ITB for an amount equivalent to Rs. 2,50,000.00 (P.S. Rs. 1,50,000.00 & Advance Security for unbalanced bid Rs: 4,00.00) within 21 days of the receipt of this L.O.A. valid up to 21 days from the date of Expiry of defect liabilities period i.e. up to _____ and sign the contract, failing which action as stated in Part 34.3 of ITB will be taken.

मान्य कोला


24/8/19


Executive Engineer
R.W.D. Works Div. Bettiah
24.10.19

Your faithfully,



Executive Engineer
Rural Works Department
Works division Bettiah.

14/8/19

Tender Inviting Authority:- Executive Engineer, R.W.D. Works Division, Bettiah					
Name of Work:		S032 Refugee Colony to Churiharwa			
Contract No: Civil Works					
Bidder Name:				Excess (+)	%
SCHEDULE OF WORKS					
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate Figure	AMOUNT Rs. P
1	Construction of Reference & Working Benchmark as per specification and drawing 200.1 & 200.2	1.63	Per Km.	11,439.26	18645.99
2	Construction of Reference Pillars/Burjees as per specification and drawing 200.1 & 200.2	1.63	Per Km.	11,035.07	17987.16
3	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300 mm, removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150 mm in thickness as per Technical Specification Clause 201.	0.49	Hectare	49,809.13	24406.47
4	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	959.65	Cum.	187.92	180336.87
5	Construction of subgrade & earthen shoulders with approved material obtained from borrow pits with all lifts and lead, transporting to site, spreading, grading to required slope and compacted to meet requirement of Tables 300.2 with lead upto 1000m as per Technical Specification Clause 301.4.1	858.60	Cum.	189.80	162962.28
6	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 100m as per Technical Specification Clause 301.5.	2239.18	Cum.	143.08	320381.35
7	Excavation for roadway in soil using manual means for carrying of cut earth to embankment site with a lift upto 1.5 m and lead upto 50 m as per Technical Specification Clause 302.3	109.50	Cum.	82.01	8980.10
8	Laying brick soling layer on prepared sub-grade with brick on , graded and cross-section shown on the drawing filling joints with sand and earth, over brick soling, watering and rolling the same with three Wheeled Road roller 80-100kN as per TS clause 412.	1222.50	Sqm.	499.47	610602.08
9	Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with three wheel 80-100 kN static roller capacity to achieve the desired density, complete as per Technical Specification Clause 401 (For Grading I Material)	208.29	Cum.	2,919.78	608160.98
10	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	463.02	Cum.	3,643.47	1686999.48

अमान अलौ

24/11/15

Executive Engineer
R.W.D. Works Div. Bettiah
24/11/15

Tender Inviting Authority:- Executive Engineer, R.W.D. Works Division, Bettiah					
Name of Work:		S032 Refugee Colony to Churiharwa			
Contract No: Civil Works					
Bidder Name:				Excess (+)	%
SCHEDULE OF WORKS					
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate Figure	AMOUNT Rs. P
11	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0kg/sqm using mechanical means as per Technical Specification	0.00	Sqm.	52.47	0.00
12	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25-0.30kg per sqm on the prepared granular surfaces treated with primer & cleaned with Hydraulic broom as per Technical Specification Clause 503.	0.00	Sqm.	18.99	0.00
13	Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509	0.00	Sqm.	247.86	0.00
14	Construction of un-reinforced, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M 25 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork, spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and water finishing to lines and grade as per drawing and Technical Specification Clause 1501	987.78	Cum	7,634.12	7540831.05
15	(i) 5th Kilometre Stone (precast)- Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703	0	Each	4,367.40	0.00
16	(ii) Ordinary Kilometer Stone (Precast)- Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703	2	Each	2,693.17	5386.34
17	(iii) 200 m stone (precast)- Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703	7	Each	721.19	5048.33
18	Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC:25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	32	Each	561.29	17961.28

अमान्य अवेर

8/24/11

Executive Engineer
R.W.D. Works Div. Bettiah
24.10.11

Tender Inviting Authority:- Executive Engineer, R.W.D. Works Division, Bettiah					
Name of Work:		S032 Refugee Colony to Churiharwa			
Contract No: Civil Works					
Bidder Name:				Excess (+)	%
SCHEDULE OF WORKS					
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate Figure	AMOUNT Rs. P
19	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701 (For culverts)	0.00	Sqm.	108.98	0.00
20	Providing and applying 2 coats of water based cement paint to unplastered concrete surface after cleaning the surface of dirt, dust, oil, grease, efflorescence and applying paint @ of 1 litre for 2 sqm. (at rigid pavement below road marking)	326.00	Sqm.	103.06	33597.56
21	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes.	326	Sqm.	851.80	277686.80
22	Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701	0	/cm ht/lette	0.53	0.00
23	Providing and fixing of typical MMGSY informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	2	Each	11,488.06	22976.12

S
24/11/15

B. R. RAJ
Executive Engineer
R.W.D. Works Div. Bettiah
24/10/15

अलग अलग

Tender Inviting Authority:- Executive Engineer, R.W.D. Works Division, Bettiah

Name of Work:

S032 Refugee Colony to Churiharwa

Contract No: Civil Works

Bidder
Name:

Excess (+)

%

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate Figure	AMOUNT Rs. P
24	Providing and fixing of typical Maintenance Board as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	2	Each	11,488.06	22976.12
25	600 mm equilateral triangle- Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting as per drawings and Technical Specification Clause 801	8	No.	3,996.29	31970.32
26	600 mm Circular- Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting as per drawings and Technical Specification Clause 801	0	No.	5,374.03	0.00
27	600 mm x 450 mm rectangular- Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting as per drawings and Technical Specification Clause 801	2	No.	4,596.11	9192.22
28	900 mm side octagon- Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting as per drawings and Technical Specification Clause 801	2	No.	8,744.79	17489.58
29	Providing and laying 300 mm Dia RCC Hume pipe NP-3 for irrigation purpose	0.00	RM	799.99	0.00
30	Earth work in excavation for foundation of structures upto 3.0 m depth as per drawing and technical specification clause 1104	0.00	cum	285.71	0.00
31	Sand Filling in Foundation Trenches as per drawing and technical specification Clause 1108 - rate as per item No. 11.2 (I) of Chapter 11	0.00	cum	455.62	0.00
32	Brick Flat Soling in foundation:-- Brick Flat Soling in foundation Trenches as per drawing and technical specification Clause 1108	0.00	sqm	292.28	0.00
33	Providing PCC Grade M15 for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	0.00	cum	6,641.02	0.00
34	Brick Masonary work in cement mortar (1:4) in head wall complete as per drawing and technical specification clause 1109 in cement mortar 1:4	0.00	cum	6,412.59	0.00

आमान कोला


24/11/15

Executive Engineer

R.W.D. Works Div. Bettiah

24.11.15

Tender Inviting Authority:- Executive Engineer, R.W.D. Works Division, Bettiah					
Name of Work:			S032 Refugee Colony to Churiharwa		
Contract No: Civil Works					
Bidder Name:				Excess (+)	%
SCHEDULE OF WORKS					
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate Figure	AMOUNT Rs. P
35	Providing and laying 1000 mm Dia RCC pipe NP-3 for culverts on first class bedding of PCC M10 (1:3:6) in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works,backfilling concrete and masonry works in head	0.00	m	4,019.58	0.00
36	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	0.00	sqm	207.63	0.00
37	Providing 1.5 mm cement punning including curing carriage of water with all leads and lifts as per building specification and direction of E/I	0.00	sqm	65.56	0.00
38	Providing Reinforced cement RCC GRADE M-25 concrete in box cell complete as per drawings and technical specification Clauses 802, 804,805, 806, 807, 1202 and 1204.	0.00	cum	8,542.42	0.00
39	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 (Gravular Materials)	0.00	cum	3,049.42	0.00
40	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7	0.00	Each	103.40	0.00
41	Providing and laying boulder apron for bed protection with stone boulders of minimum size and weight as per Table 1300.1, no fragment weighing less than 25 kg laid dry complete as per drawing and technical specifications Clause 1301.	0.00	cum	3,537.85	0.00
42	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructrue complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202	0.00	MT	77,039.10	0.00
Total Construction Cost (A) =					1,16,24,578.48
43	Maintenance for 1st year	1	Year	35983.00	35983.00
44	Maintenance for 2nd year	1	Year	42917.00	42917.00
45	Maintenance for 3rd year	1	Year	360907.00	360907.00
46	Maintenance for 4th year	1	Year	55902.00	55902.00
47	Maintenance for 5th year	1	Year	374737.00	374737.00
Total Maintenance Cost (B) =					8,70,446.00
Total estimated cost (A+B) =					1,24,95,024.48


 24/11/19
 Executive Engineer
 R.W.D. Works Div. Bettiah
 24.10.19

आपका अधिकारी



अधीक्षण अभियन्ता का कार्यालय

ग्रामीण कार्य विभाग, कार्य अंचल, बेतिया

Email ID- se.betia.rwd@gmail.com

पत्रांक-.....1022...../बेतिया दिनांक-02-08-2019/

प्रेषक,

02/08/19

सेवा में

अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, बेतिया

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बेतिया

विषय:-

MMGSY योजना अंतर्गत ग्रामीण कार्य विभाग कार्य प्रमंडल, बेतिया के अधीन स्वीकृत S032 Refugee Colony To Churiharwa तक पथ निर्माण कार्य Tender ID-74982 निर्माण कार्य की निविदा की स्वीकृति के संबंध में ।

प्रसंग:-

मुख्य अभियन्ता-03 ग्रा0 का0 वि0 बिहार, पटना का पत्रांक 5321अनु0 दिनांक 30.7.2019

महाशय,

उपर्युक्त विषयक प्रासंगिक पत्र के संबंध में बिहार लोक निर्माण संहिता के कंडिका -163 के आलोक में इस कार्य को सफल न्यूनतम/लॉटरी द्वारा चयनित निविदाकार Madhu Anand Construction Pvt. Ltd. (BID ID 342987) उनके उद्धृत दर जो कि परिमाण विपत्र की राशि -0.01 प्रतिशत कम है अर्थात् कुल राशि - 1,24,93,776.00 (एक करोड़ चौबीस लाख तिरानबे हजार सात सौ छिहत्तर) रुपया मात्र की लागत पर आपकी अनुशंसा एवं कार्यहित में आवंटित किया जाता है । विभागीय निर्देशानुसार यह सुनिश्चित किया जाय कि इस वित्तीय वर्ष-2019-2020 में कार्य पूर्ण हो जाए, ताकि दायित्वों का सृजन नहीं हो सके

- निविदा की स्वीकृति सिर्फ इसी कार्य के लिए है जो भविष्य में पूर्वाधारण नहीं होगी ।
- संवेदक के द्वारा एकरारनामा के लिए जमा की गई राशि एवं निविदा के साथ जमा किये गये संबंधित NSC/KVP/PASSBOOK आदि का सत्यापन संबंधित डाकघर/बैंक से कराकर प्रमंडलीय कार्यालय में अभिलेखित किया जायेगा । कार्यपालक अभियन्ता अधोहस्ताक्षरी को उपलब्ध कराया जाना सुनिश्चित करेंगे ।
- एकरारनामा के पूर्व निविदा सूचना के अनुसार सभी वांछित कागजातों की अद्यतन स्वच्छ एवं सत्यापित प्रति निश्चित रूप से प्राप्त कर लिया जाएगा एवं मूल कागजात से मिलान कर लेंगे ।
- कार्य में व्यवहृत समाग्रियों का दर प्राक्कलन में स्वीकृत लीड के आधार पर दिया गया है, कार्य करते समय अगर इसमें कमी पाई जाती है तो उसके दर में सापेक्ष कमी कर दी जायेगी ।
- इस कार्य के संबंध में निविदा आमंत्रण सूचना में उल्लिखित शर्त एकरारनामा का भाग होगा, जिसे विशेष शर्त में जोड़कर संवेदक के साथ एकरारनामा किया जायेगा ।

आपका कोलाही

24/8/19

Executive Engineer

R.W.D. Works Div. Bettiah

24/8/19