

5th year Maintenance

85

Sch. XLV-Form No. 134

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
Name of Work: Jagai Khusalpur to Chandapur via Khanpur.					
Agency: Sri Mahendra pr. Sinha					
Agreement No. : 68 SBD/18-19					
Actual Date of Completion : 07.03.2020					
① Restoration of Raincuts/Burns					
	2	8	30.00	0.30	$0.45 = 64.8 m^3$
					Total = $64.8 m^3$
② Making up of Berms/shoulder					
	2	9	30.00	0.5	$= 270.00 m^2$
	2	3	30.00	0.4	$= 72.00 m^2$
					Total = $342.00 m^2$
③ Repair of Potholes with WBM					
	1	8.50	3.75	0.075	$= 2.39 m^3$
	1	18.56	2.50	0.075	$= 3.48 m^3$
					Total = $5.87 m^3$
④ Patch repair over pot with HSS 20mm Premix carpet					
	1	8.50	3.75		$= 31.875 m^2$
	1	18.56	2.50		$= 46.40 m^2$
					Total = $78.28 m^2$
⑤ Patch repair over bituminous Surface :					
	1	8.25	2.10		$= 17.325 m^2$
	1	10.00	2.50		$= 25.00 m^2$
	1	8.50	2.10		$= 17.85 m^2$
	1	3.60	3.10		$= 11.16 m^2$
Continuation					Total = $71.34 m^2$
					$86.835 m^2$

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
		B/P			111257.00
⑤ Patch repair over Bituminous surface. vide item no.					
⑤ VTMP (85)					
		86.835 m ²			
		Qty = 71.34 m ² @ 253.44/m ²			
		Qty limit = 78.28 m ²			19840.00
⑥ Maint. of C/D works (HP culvert) vide item no.					
⑥ VTMP (86)					
		Qty = 6 Nos @ 1109.67/each			6658.00
⑦ Maint. of C/D work Slab culvert vide item no.					
⑦ VTMP (86)					

Qty = 1 No. @ 2291.44/each	2291.00
Total =	140046.00
(-) less 0.04%	-56.00
Total =	139990.00

Sanjay
17/03/25
A.E.

Material Statement :

- ① E/w Qty = 60.87 m³
- ② Stone chips = 4.87 + 4.23 = 9.10 m³
- ③ Bitumen (S-90) = 426.16 kg + 297.46 kg
= 723.62 kg

Sanjay
17/03/25
A.E.

Continuation