

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग कार्य प्रमण्डल, औरंगाबाद

कार्यालय आदेश संख्या 2518 / औरंगाबाद, दिनांक 21/9/24

कार्यालय आदेश

1. T03 Tandwa road se Khjuritika 2. Deo to Kachanpur 3. Dev to Parihaya Via ketaki 4. Jamhaura to Parsaia 5. MR to Road from deo More to Kumhar bigtha पथों की स्थिति क्षतिग्रस्त होने के कारण Emergent work के तहत Temporary Restoration कार्य करने हेतु कनीय अभियंता तथा सहायक अभियंता के देख-रेख में यातायात के मददेनजर सुचारु रूप से आवागमन जारी रखने हेतु श्री निर्भय कुमार सिंह, ग्राम-फुलवरीया, पोस्ट-केताकी, थाना-देव, जिला-औरंगाबाद को आदेशित किया जाता है।

उक्त कार्य का भुगतान अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, औरंगाबाद द्वारा अनुमोदन प्राप्त दर पर किया जायेगा।

21.09.24
कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमण्डल, औरंगाबाद

ज्ञापांक 2518

दिनांक 21/9/24

प्रति: श्री निर्भय कुमार सिंह, ग्राम-फुलवरीया, पोस्ट-केताकी, थाना-देव, जिला-औरंगाबाद को सुचनार्थ एवं अनुपालनार्थ प्रेषित।

21.09.24
कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमण्डल, औरंगाबाद

ज्ञापांक 2518

दिनांक 21/9/24

प्रति: सहायक अभियंता/कनीय अभियंता/वरीय प्रमण्डलीय लेखा पदाधिकारी/रोकडपाल ग्रामीण कार्य विभाग, कार्य प्रमण्डल, औरंगाबाद को सुचनार्थ एवं अनुपालनार्थ प्रेषित।

21.09.24
कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमण्डल औरंगाबाद


GENERAL ABSTRACT OF COST


HEAD:- EMERGENT WORK

Block:--	Deo	District:-	Aurangabad
Total Length Of Road	3.000 KM	BT Length :-	3.000 KM.
Construction Length of Road:--	3.000 KM	PCC Length :-	0.000 KM.
Name of Road:--	Dev To Parihaya Via Ketaki		

SL. No.	Item of Work	Amount
A	TOTAL COST OF CONSTRUCTION :	2.504 Lacs
	LABOUR CESS @1% :	0.025 Lacs
	SEIGNIORAGE FEE :	0.082 Lacs
	TOTAL :	2.611 Lacs
	GST @18% :	0.470 Lacs
	TOTAL (A) :	3.081 Lacs
	TOTAL PROJECT COST :	3.081 Lacs


21.04.25
Junior Engineer
RWD, Deo


21/04/25
Asstt. Engineer
RWD (w) Division, Aurangabad


21/04/25
Executive Engineer
RWD (w) Division, Aurangabad

SE
RWD

Technical by Sanctioned for Rs. 3.081 Lacs
(Rupees Three Lacs Eight thousand
one hundred only.)



24.4.2025
Superintending Engineer
R.W.D. Works Circle
Aurangabad


SUMMARY OF COST ESTIMATE

HEAD:- EMERGENT WORK

NAME OF ROAD :	Dev To Parihaya Via Ketaki
DISTRICT	Aurangabad
BLOCK	Deo
DIVISION	Aurangabad
Total Length Of Road	3.000 km
Construction Length of Road	3.000 km
Length of Flexible Pavement 3.75 M	3.000 km
Length of CC Pavement	0.000 km

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
PART-A		
1	GSB GR-I & GR-II	2.504
2	WBM GRADE II	0.000
3	WBM GRADE III	0.000
4	PRIME COAT	0.000
5	MSS	0.000
6	TACK COAT	0.000
	SUB TOTAL OF PAVEMENT COST IN LACS =	2.504
	AVERAGE COST PER KM (IN LACS) =	0.835
	SUB TOTAL(A) =	2.504
	1% LABOUR CESS	0.025
	10% SEIGNIORAGE FEE (Construction)	0.082
	18 % GST (B)	0.470
	CONTINGENCY FEE @ 1%	0.000
	TOTAL COST OF PROJECT (Including GST & Labour Cess) IN LACS =	3.081


 Junior Engineer
 RWD, Deo



 Asstt. Engineer
 RWD (w) Division, Aurangabad



 Executive Engineer
 RWD (w) Division, Aurangabad

HEAD:- EMERGENT WORK

Detailed Cost Estimate For Road Construction

Name Of Road :-		Dev To Parihaya Via Ketaki		Total Length In Km :-			3.000 Km		BLOCK :-		Deo
Sl.No.	SDB SL.NO	MORD Ref.No	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (In Rs.)
1	4.1	401	Sub Head : PAVEMENT LAYERS - GSB & WBM ITEMS (By Mix in Place Method)- For Graded Material (Table 400.1) Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.								
		(ii)									
			Qty as per Pot Measurement	Cum	5.00%	3,000.00	3.750	0.200	112.500		
			Add for extra widening on curve (1%)						1.125		
			Net GSB Qty						113.625	2,203.822	2,50,409.00
A) SUB TOTAL OF CRUST =											2,50,409.00


 JE 21-04-23
 RWD, Deo


 AE 27/04/25
 RWD (w) Division, Aurangabad


 EE 21/04/25
 RWD (w) Division, Aurangabad

HEAD:- EMERGENT WORK

SEIGNIORAGE FEE

Sl. No.	SDB SI. NO	MORD Ref.No	Description	Unit	Quantity	Rate	Amount (In Rs.)	Total Material Required	Material Amount	Add Seigniorage Fee 10%
EARTHWORK SEIGNIORAGE FEE										
1	4.1	401	Granular Sub-base with Well Graded Material (Table 400.1)							
			(By mix in place method) -Gr 1							
		(i)	Sub Head : PAVEMENT LAYERS - GSB & WBM ITEMS							
			Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.							
			For Grading I Material							
			Material							
		a)	Material							
			Well graded granular sub-base material as per Table 400.1							
			26.5 mm to 9.5 mm @ 35 per cent	0.00	180.00	944.26	1,69,966.80			
			9.5 mm to 2.36 mm @ 25 per cent	0.00	72.00	434.45	31,280.400			
			2.36 mm below @ 40 per cent - Stone Screening	0.00	108.00	145.87	15,753.960			
			Cost for 300 cum = a				2,17,001.16			
			Rate Per Cum = (a)/300=	Cum			723.34			
			Total Cost =	Cum			723.34	113.63	82,189.19	8,218.92

Total Construction Cost (With 10% Seigniorage Fee) :--

8,218.92

Total Construction (With 10% Seigniorage Fee) :--

8,218.92

[Signature]
JE
RWD, Deo

[Signature]
AE
RWD (w) Division, Aurangabad

[Signature]
EE
RWD (w) Division, Aurangabad