

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, औरंगाबाद

कार्यालय आदेश संख्या 2518 / औरंगाबाद, दिनांक 21/9/24

कार्यालय आदेश

1. T03 Tandwa road se Khjuritika 2. Deo to Kachanpur 3. Dev to Parihaya Via ketaki 4. Jamhaura to Parsaia 5. MR to Road from deo More to Kumhar bigtha पथों की स्थिति क्षतिग्रस्त होने के कारण Emergent work के तहत Temporary Restoration कार्य करने हेतु कनीय अभियंता तथा सहायक अभियंता के देख-रेख में यातायात के मददेनजर सुचारु रूप से आवागमन जारी रखने हेतु श्री निर्भय कुमार सिंह, ग्राम-फुलवरीया, पोस्ट-केताकी, थाना-देव, जिला-औरंगाबाद को आदेशित किया जाता है।

उक्त कार्य का भुगतान अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, औरंगाबाद द्वारा अनुमोदन प्राप्त दर पर किया जायेगा।

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमंडल औरंगाबाद

ज्ञापांक 2518

दिनांक 21/9/24

प्रति: श्री निर्भय कुमार सिंह, ग्राम-फुलवरीया, पोस्ट-केताकी, थाना-देव, जिला-औरंगाबाद को सुचनार्थ एवं अनुपालनार्थ प्रेषित।

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमंडल औरंगाबाद

ज्ञापांक 2518

दिनांक 21/9/24

प्रति: सहायक अभियंता/कनीय अभियंता/वरीय प्रमंडलीय लेखा पदाधिकारी/रोकडपाल ग्रामीण कार्य विभाग, कार्य प्रमंडल, औरंगाबाद को सुचनार्थ एवं अनुपालनार्थ प्रेषित।

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमंडल औरंगाबाद

GENERAL ABSTRACT OF COST

HEAD:- EMERGENT WORK

Block:--	Deo	District:-	Aurangabad	
Total Length Of Road		5.900 KM	BT Length :-	5.900 KM.
Construction Length of Road:--		5.900 KM	PCC Length :-	0.000 KM.
Name of Road:--		Deo To Kachanpur		

SL. No.	Item of Work	Amount
A	TOTAL COST OF CONSTRUCTION :	2.968 Lacs
	LABOUR CESS @1% :	0.030 Lacs
	SEIGNIORAGE FEE :	0.097 Lacs
	TOTAL :	3.095 Lacs
	GST @18% :	0.557 Lacs
	TOTAL (A) :	3.652 Lacs
TOTAL PROJECT COST :		3.652 Lacs



Junior Engineer
RWD, Deo


Asstt. Engineer
RWD (w) Division, Aurangabad


Executive Engineer
RWD (w) Division, Aurangabad

SE
RWD

Technical by Sanctioned for Rs. 3,652 Lacs
(Rupees Three Lacs Sixty five thousand
two hundred only)


Superintending Engineer
R.W.D. Works Circle
Aurangabad

HEAD:- EMERGENT WORK

SEIGNIORAGE FEE

Sl. No.	SDB Sl. No	MORD Ref.No	Description	Unit	Quantity	Rate	Amount (In Rs.)	Total Material Required	Material Amount	Add Seigniorage Fee 10%
EARTHWORK SEIGNIORAGE FEE										
1	4.1	401	Granular Sub-base with Well Graded Material (Table 400.1)							
			(By mix in place method) -Gr. I							
		(i)	Sub Head : PAVEMENT LAYERS - GSB & WBM ITEMS							
			Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.							
			For Grading I Material							
			Material							
		a)	Material							
			Well graded granular sub-base material as per Table 400.1							
			26.5 mm to 9.5 mm @ 35 per cent	0.00	180.00	944.26	1,69,966.80			
			9.5 mm to 2.36 mm @ 25 per cent	0.00	72.00	434.45	31,280.400			
			2.36 mm below @ 40 per cent - Stone Screening	0.00	108.00	145.87	15,753.960			
			Cost for 300 cum = a				2,17,001.16			
			Rate Per Cum = (a)/300=	Cum			723.34			
			Total Cost =	Cum			723.34	134.08	96,983.24	9,698.32
Total Construction Cost (With 10% Seigniorage Fee) :-										
Total Construction (With 10% Seigniorage Fee) :-										

[Signature]
16/04/25
RWD, Deo

[Signature]
AE
RWD (w) Division, Aurangabad

[Signature]
EE
RWD (w) Division, Aurangabad

SUMMARY OF COST ESTIMATE
HEAD:- EMERGENT WORK

NAME OF ROAD :	Deo To Kachanpur
DISTRICT	Aurangabad
BLOCK	Deo
DIVISION	Aurangabad
Total Length Of Road	5.900 km
Construction Length of Road	5.900 km
Length of Flexible Pavement 3.75 M	5.900 km
Length of CC Pavement	0.000 km

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
PART-A		
1	GSB GR-I & GR-II	2.968
2	WBM GRADE II	0.000
3	WBM GRADE III	0.000
4	PRIME COAT	0.000
5	MSS	0.000
6	TACK COAT	0.000
	SUB TOTAL OF PAVEMENT COST IN LACS =	2.968
	AVERAGE COST PER KM (IN LACS) =	0.503
	SUB TOTAL(A) =	2.968
	1% LABOUR CESS	0.030
	10% SEIGNIORAGE FEE (Construction)	0.097
	18 % GST (B)	0.557
	CONTINGENCY FEE @ 1%	0.000
	TOTAL COST OF PROJECT (Including GST & Labour Cess) IN LACS =	3.652

15/04/25
Junior Engineer
RWD, Deo

Auman
21/4/25
Asstt. Engineer
RWD (w) Division, Aurangabad

21/04/25
Executive Engineer
RWD (w) Division, Aurangabad