



0.11% Belows/R कम संख्या 337/ 19.9.25/1000 शीट संख्या BA 775348
 बिहार BIHAR केता का नाम एवं पते
 Agreement No. 13 CMBD/MMGSY Awsest SC/2025-26
AGREEMENT FORM
 This Agreement made this 4th day of December 2025 Between The Executive Engineer R.W.D Works Division, Bagha-2 ("The E/I") of the one part, and Chanakya Technos Private Limited, Harihar Pd Purbey Betiahata Gorakhpur Uttar Pradesh, Bihar office Add-Vijay Nagar Gali No.-2 P.O.-B.V. College P.S.-Rupaspur, Dist.-Patna, Pincode-800014 [Name & address of Contractor] ("The Contractor") of the other part.

Where as the E/I is desirous that the Contractor execute Up gradation and performance based Rural Road contract for the maintenance of Package No.- MMGSY (AWSESH-SC)-Bagha-2-606 (hereinafter called "The Works & Routine Maintenance") and the E/I has accepted the Bid by the Contractor for the execution of such The Construction Works & Routine Maintenance and the remedying of any defects therein, at a contract price of Rs. 7,95,91,243.00 (Seven Crore Ninety Five Lakh Ninety One Thousands Two Hundred Forty Three) Only

Sl.No.	Package Number	Road & Bridge Name	Length (Km)
1	MMGSY (AWSESH-SC)-Bagha-2-606	Part-A Jamuniya MMGSY Road to Kachhri Tola Bhitha	1.039
2		Part-B Construction of HL. RCC Bridge Span 4 X 18.75 in Jamuniya MMGSY Road to Kachhri Tola Bhitha, Approach 200m	81.16m

NOW THIS AGREEMENT WITNESSETH and the Parties hereto agree as follows:

- In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the General condition hereafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
- In consideration of the payments to be made by the E/I to the Contractor as here in after mentioned, the Contractor hereby covenants with the E/I to execute and complete the Works and remedy any defects there in conformity in all aspects with the provisions of the contract.

Chanakya Technos Pvt. Ltd.

Director

Executive Engineer
RWD (W) Div., Bagha-2

3. The E/I hereby covenants to pay the Contractor in consideration of the execution and completion of the Works and the remedying the defects wherein the contract price or such other sum as may become payable under the provisions of the contract at the times and in the manner prescribed by the contract.
4. The following documents shall be deemed to form and be read and construed as part of this Agreement, viz:
- i) Letter of Acceptance
 - ii) Contractor's Bid
 - iii) Section VI-General Conditions,
 - iv) Section VII-Particular Conditions
 - v) Section V -Technical Specifications (General and Supplementary Technical Specifications)
 - vi) Appendix A-Drawings
 - vii) Section IV-Works Schedule
 - viii) Quality Plan for Output and Performance Based Road Contract as per Clause A14.1 of the Technical Specifications
 - ix) Appendices to the Contract
 - x) Addenda issued during bid period
 - xi) Any other relevant documents listed in the Particular Conditions together with any post bid correspondence.

In witness where of the parties thereto have caused this Agreement to be executed the day and year first before written.

The Common Seal of.....

was here unto affixed in the presence of :

Signed, sealed and delivered by the said

in the presence of :

Binding Signature of E/I

Chanakya Technos Pvt. Ltd.
Dr. Shashi Pethan
Binding Signature of Contractor
Director

04-12-25
Executive Engineer
BWD (W) Div., Bagha
4/12/25

Name of Agency :- Chanakya Technos Private Limited, Harihar Pd Dubey Betiahata Gorakhpur Uttar Pradesh, Bihar office Add-Vijay Nagar Gali No.-2 P.O.-B.V. College P.S.-Rupaspur, Dist.-Patna, Pincode-800014

Name of Work :-

Sl.No.	Name of Road
1	<u>Part-A</u> Jamuniya MMGSY Road to Kachahri Tola Bhitha
2	<u>Part-B</u> Construction of HL. RCC Bridge Span 4 X 18.75 in Jamuniya MMGSY Road to Kachahri Tola Bhitha, Approach 200m

Package No. :- MMGSY (AWSESH-SC)-Bagha-2-606

Agreement No. :- 13 CMBD/MMGSY (AWSESH-SC)/2025-26

Letter issued by :- Chief Engineer-5, Rural Works Department, Bihar, Patna.

Letter No. :- 3257 अजु, Date- 16.09.2025

Agreement Value :- 7,95,91,243.00

Construction Cost :- 7,79,90,675.00

Maintenance Cost :- 16,00,568.00

Date of Work Order :- 17.09.2025

Time of Completion :- {01 (One Year) + 06 (Six Year)}

Performance Security :- 15,91,825.00 } 16,13,737.00

Additional Performance Guarantee :- 21,912.00 }

Security Deduct From bill :- 8% (Eight Percent)

No of Items :- 125

Rate :- 0.11% (Below)

Chanakya Technos Pvt. Ltd.
Ranishanka Patna
Director

09-12-25
Executive Engineer
RWD (W) Div., Bagha-2
4/12/25

MMGSY (AWSESH-SC)-Bagha-2-606

Name of Contractor-Chanakya Technos Private Limited

Sl. No.	Name of Road	Construction Cost		Maintenance		Agreement Value
		Total Cost	Below Schedule of Rate 0.11%	Total Cost	Below Schedule of Rate 0.11%	
1	Part-A Jamuniya MMGSY Road to Kachahri Tola Bhitha	1,40,40,736.98	1,40,25,292.17	11,85,799.63	11,84,495.25	1,52,09,787.42
2	Part-B Construction of HL. RCC Bridge Span 4 X 18.75 in Jamuniya MMGSY Road to Kachahri Tola Bhitha. Approach Road 200m	6,40,35,823.13	6,39,65,383.72	4,16,530.93	4,16,072.75	6,43,81,456.47
	Total	7,80,76,560.11	7,79,90,675.89	16,02,330.56	16,00,568.00	7,95,91,243.89
	Agreement Value	7,95,91,243.89				

Chanakya Technos Pvt. Ltd.

Devendra Dey

20/12/25

Executive Engineer
BMD (N) Div- Bagha-2

11/11/25

MUKHYAMANTRI GRAMIN SADAK YOJANA MMGSY (Awshesh) SC
BILL OF QUANTITIES (BOQ) - CONSTRUCTION

Name of Road :	Jamuniya Mmgsy Road To Kachahri Tola Bhitaha			
Block :	Bhitaha			
Length :	1.039 km			
Sl. No.	Description of Items	Qty.	Unit	Amount (Rs.)
1	Setting Out Pillars - Providing & fixing of Working benchmark Pillars 01 nos per km & 04 Nos. of reference pillars required for 1 Km. as per drawings given and direction of E/I	1.04	Km	13,677.85
2	Clearing and Grubbing Road Land Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification - clause 201.1 and direction of E/I (By Manual Means) In area of non-thorny jungle	0.24	Hect.	75,360.38
3	Cutting of Trees including Cutting of Trunks, Branches and Removal of Stumps Cutting of trees, including cutting of trunks, branches and removal of stumps & roots, refilling, compaction of backfilling and stacking of serviceable material by manual means with all lifts as per Technical Specification Clause 201.7	12.00	Each	352.90
	Girth above 300 mm to 600 mm	8.00	Each	611.21
4	Girth above 600 mm to 900 mm			
5	Removal of Telephone/Electric Poles and Lines Removal of telephone/electric poles with wires including excavation and dismantling of foundation concrete and lines under the supervision of concerned department, disposal with all lifts and upto a lead of 1000 m and stacking the serviceable and unserviceable material separately as per Technical Specification Clause 202.	10.00	No	246.41
6	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 100 m as per Technical Specification Clause 301.5	1895.60	Cum	147.61
7	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	333.58	Cum	239.97
8	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m & 100 m as per Technical Specification Clause 303.1 (including Royalty & Labour Cess)	2579.79	Cum	243.24

Chanakya Technos Pvt. Ltd.
Ravi Shankar Pathan
Director

04-12-25
Executive Engineer
RWD (W) Div., Bagha-2

Name of Road :	Jamuniya Mmgsy Road To Kachahri Tola Bhitha				
Block :	Bhitaha				
Length :	1.039 km	District : West Champaran			
Sl. No.	Description of Items	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
9	Granular Sub-base with Well Graded Material (Table 400 1) : Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401 (For Grading II Material)	477.68	Cum	3,078.28	1470432.79
10	WBM Grading 2 :-Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per Technical Specification Clause 405.	172.13	Cum	6,549.80	1127417.07
11	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mix plant carriage of mixed material by tipper to site, laying in uniform layers with grader in sub-base/base course on a well surface and compacting with vibratory roller to achieve the desired density.	298.02	Cum	5,399.12	1609046.00
12	Prime Coat (Low Porosity) :- Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0kg/sqm using mechanical means as per Technical Specification Clause 502	2295.00	Sqm	57.36	131641.00
13	Tack Coat:- Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25-0.30kg per sqm on the prepared granular surfaces treated with primer & cleaned with Hydraulic broom as per Technical Specification Clause 503.	2295.00	Sqm	19.74	45303.00
14	Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509	2295.00	Sqm	328.58	754091.10
15	Construction of un-reinforced, plain cement concrete pavement (M35 Grade) over a prepared sub base with 43 grade cement @ 400 kg per cum, coarse and fine aggregate conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form paver, spread, compacted and finished in a continuous operation including provision of 0.5 x 0.5 panel, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures as approved, curing compound, finishing to lines and grades as per drawing	167.86	Cum	8,574.44	1439305.00

Chanakya Technos Pvt. Ltd.
 Gan Shukla Talwar
 Director

04-12-25
 Executive Engineer
 RWD (W) Div., Bagha-2


Name of Road	Jamuniya Mngsy Road To Kachahri Tola Bhittha				
Block	Bhitaha				
Length	1.039 km	District - West Champaran			
Sl. No.	Description of Items	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
16	Laying brick soling layer on prepared sub grade with brick on end edging according to lines, graded and cross section shown on the drawing filling joints with sand and earth, spreading 25 mm thick layer of earth over brick soling, watering and rolling the same with three wheel road roller 80-100 kN as per Technical Specification Clause 412	223.81	Sqm	500.49	112015.00
	TRAFFIC SIGNS, MARKINGS & OTHER ROAD APPURTENANCES				
17	Kilometre Stone				
	Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC 8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703				
	Ordinary Kilometer Stone (Precast)	2.00	Each	3,158.76	6317.52
18	200 m stone (precast)	6.00	Each	834.46	5006.76
19	(1) Providing and fixing "Logo" of PMGSY Project :- Providing and fixing of typical PMGSY informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 16 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All MS will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	4.00	Each	11,208.00	44832.00
20	Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701	132.00	per cm height per letter	0.74	97.68
21	Boundary Pillar/Guard Post :- Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC-25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	52.00	No	639.35	33246.20
22	Rumble Strips : Provision of 15 nos rumble strips covered with premix bituminous carpet, 15-20 mm high at center, 250 mm wide placed at 1 m center to center at approved locations to control speed, marked with white strips of road marking paint.	10.13	Sqm	1,106.98	11213.71


Chanakya Technos Pvt. Ltd.

Dr. Anil Kumar Jethaw
Director

Dr. Anil
04-12-25
Executive Engineer
RWD (W) Div., Bagha-2

Name of Road	Jamuniya Mingsy Road To Kachahri Toa Bhitaha				
Block	Bhitaha				
Length	1.039 km				
		District	West Champaran		
Sl. No.	Description of Items	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
23	Traffic Signs Providing and fixing of Retro reflective cautionary, mandatory and informatory sign board as per IPT 6-7 made of 1.5 mm thick MS steel duly stove white colour on front and gray colour on back with red reflective border of 65 mm width and required letters and figures with reflective tape engineering grade as per clause 1701.39 of MRRD for rural road of required shade and colour supported and welded on 47mmx47mmx12swg sheet tube firmly fixed to the ground by mean of properly designed foundation with M15 grade cement concrete 450x450x600 mm, 600mm below ground level as per approved drawing clause 1701.22				
	400 mm equilateral & triangle, OR	2.00	Each	6,137.07	12274.14
24	600 mm equilateral & triangle, OR	11.00	Each	4,085.74	44943.14
25	600 mm circular, OR	8.00	Each	5,426.01	43408.08
26	600 mm x 450 mm rectangular, OR	4.00	Each	5,288.76	21155.04
27	400 mm side octagon, OR	2.00	Each	9,537.79	19065.58
28	Road Marking with Hot Applied Thermoplastic Compound with Reflectorsing Glass Beads on Concrete Surface : Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorsing glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC.35. The finished surface to be level, uniform and free from streaks and holes.	87.77	Sqm	879.72	77213.02
29	Road Marking with Hot Applied Thermoplastic Compound with Reflectorsing Glass Beads on Bituminous Surface : Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorsing glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC.35. The finished surface to be level, uniform and free from streaks and holes.	120.00	Sqm	778.40	93408.00
30	Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year	24.00	Each	1,248.07	29953.68
	Cross Drainage Works				
31	Irrigation Pipe (300MM Dia) Providing and laying of a reinforced cement concrete pipe duct, 300 mm dia, across the road (new construction), extending from drain to drain in cuts and toe of slope to toe of slope in fills, constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC 981997, bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC 98 - 1997 and approved drawings	40.00	RM	1,006.92	40276.80

Chanakya Technos Pvt. Ltd.

Director


04-12-25
Executive Engineer
RWD (W) Div., Bagha

Name of Road :	Jamuniya Mngsy Road To Kachahri Tola Bhitha				
Block :	Bhitaha		District : West Champaran		
Length :	1.039 km				
Sl. No.	Description of Items	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
	Disment				
32	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 m as per Technical Specification Clause 202				
	Cement Concrete	0.78	Cum	670.71	523.15
33	Reinforced Cement Concrete	6.00	Cum	1,697.74	10186.44
34	Dismantling of existing structures like culverts, bridges, retaining walls and other structures comprising of brick masonry, including disposal of unserviceable material and stacking the serviceable material with all lift and lead of 1000 m as per Technical Specification Clause 202				
	Cement mortar	24.75	Cum	307.62	7613.60
	Box Culverts				
	Foundation				
35	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material.	153.98	Cum	80.87	12452.36
36	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-15 Grade	18.96	Cum	8,084.65	153284.96
37	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-20 Grade	63.44	Cum	8,825.43	559885.28
38	Supplying, fitting and placing HYSD bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202	0.26	MT	65,189.26	16949.21
	Sub Structure				
39	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 PCC M-20 Grade	41.63	Cum	9,105.79	379074.04
40	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7	96.00	Nos	134.35	12897.60
41	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 RCC M-25 Grade	36.08	Cum	9,690.75	349642.26
42	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1707	3.25	MT	65,397.45	212541.71

Chanakya Technos Pvt. Ltd.
Sanjiv Shastri Pathan
Director

Sanjiv
04-12-25
Executive Engineer
RWD (W) Div., Bagha-2

Name of Road :	Jamuniya Mmgsy Road To Kachahri Tola Bhitha				
Block :	Bhitaha	District : West Champaran			
Length :	1 039 km				
Sl. No.	Description of Items	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
43	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204 3 8 (With Sandy Materials)	90 81	Cum	913 96	82996 71
44	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204 3 8	53 58	Cum	4,907 41	262939 03
Superstructure					
45	Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205 4 and 1205 5 RCC M-30 Grade	13 58	Cum	10,389.65	141091 45
46	Supplying, fitting, and placing HYSD bar reinforcement in superstructure complete as per drawing and technical specifications Clauses 1002, 1010 and 1202	1.43	MT	66,914.11	95687 18
47	Parapet Construction Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 (M25)	3 02	Cum	10,142 80	30631.26
48	Painting on Parapet Wall (Black & White Strips) Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	22 08	Sqm	129 57	2860 91
49	Drainage spouts complete as per drawing and technical specifications Clause 1209	8.00	Nos	927 82	7422 56
5TH YEAR PERIODIC RENEWAL					
50	Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydriloc broom as per technical specification clause 503.	2295 00	Sqm	19.74	45303 30
51	Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects	57 38	Cum	15,119.71	867568 96

Chanakya Technos Pvt. Ltd.
Sanjiv Kumar Pathan
 Director

Sanjiv
 04-12-25
 Executive Engineer
 RWD (W) Div., Bagha-2

Name of Road :	Jamuniya Mmgsy Road To Kachahri Tola Dhitha				
Block :	Bhitaha				
Length :	1.039 Km		District :	West Champaran	
Sl. No.	Description of Items	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
52	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes. (Flexible Pavement)	120.00	Sqm	778.40	93408.00
53	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes. (Rigid Pavement)	87.77	Sqm	879.72	77213.02
	Construction Cost (A) :-				11625098.74
54	Add Labour @ 1% on Construction Cost (A) :-				116250.99
55	Add 10% S.F on Basic Materials Cost :-				157579.57
	Sub Total Construction Cost (Including 1% Labour Cess & 10% S.F):-				11898929.30
56	Add GST @ 18% on Sub Total Construction Cost (Including 1% Labour Cess & 10% S.F):-				2141807.27
	Total Construction Cost (A) :-				14040736.57
57	1st Year Maintenance cost	1.00	Year	149752.00	149752.0
58	2nd Year Maintenance cost	1.00	Year	181132.72	181132.7
59	3rd Year Maintenance cost	1.00	Year	184262.00	184262.0
60	4th Year Maintenance cost	1.00	Year	226174.00	226174.0
61	6th Year Maintenance cost	1.00	Year	113528.00	113528.0
62	7th Year Maintenance cost	1.00	Year	128534.00	128534.0
	Maintenance Cost (B) :-				983382.72
63	Add Labour @ 1% on Maintenance Cost (A) :-				9833.83
64	Add 10% S.F on Basic Materials Cost :-				11698.41
	Sub Total Maintenance Cost (Including 1% Labour Cess & 10% S.F):-				1004914.95
65	Add GST @ 18% on Sub Total Maintenance Cost (Including 1% Labour Cess & 10% S.F):-				180884.69
	Total Maintenance Cost (B) :-				1185799.64
	Total Project Cost(A+B)				15226536.22

Chanakya Technos Pvt. Ltd.
Don Shankar Jethan
 Director

Don
 04-12-25
 Executive Engineer
 RWD (W) Div. Bagha-2

RURAL WORKS DEPARTMENT

(Rural Works Department, Govt. of Bihar)

BILL OF QUANTITY

NAME OF ROAD :	Construction of HL RCC Bridge in Jamuniya MMSY Road To Kachahar Tola Bhitha				
BLOCK :	Bhitha				
DISTRICT :	West Champaran				
Sl. No.	Item Description	Unit	Quantity	Rate	Amount (In Rs.)
FOUNDATION					
1	Excavation for Structures Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.				
	I. Ordinary Soil				
	i) Upto 3m depth	Cum	1019.31	117.06	119320.43
2	Providing and laying of PCC M15 levelling course 100mm thick below the pile cap.				
	II. PCC Grade M-15 (Levelling Course for Pile Cap)	Cum	36.52	8197.60	299376.35
3	R.C.C. grade M 30 in Pile Foundation complete as per Dwg & Tech Specification.				
	Pile Cap in RCC M-30 (Using Batching Plant, Transit Mixer and Concrete Pump)	Cum	465.42	8484.62	3948911.84
4	Bored cast-in-situ M35 grade R.C.C. Pile excluding Reinforcement complete as per Drawing and Technical Specifications and removal of excavated earth with all lifts and lead upto 1000 m.				
	II. 1200 mm Dia. (Using Batching Plant, Transit	m	802.00	17310.82	13883277.64
5	Supplying, fitting and placing HYSD bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202	MT	125.16	69502.90	8698982.96
6	Providing steel liner 10 mm thick for curbs and 6mm thick for steining of wells including fabricating and setting out as per detailed drawing	MT	12.07	94016.48	1134778.91
7	Providing and Constructing Temporary Earth Island (Assuming depth of water 1.0 m and height of island to be 1.25 m including Royalty for earth @ Rs. 5526.00 for each Island.)	No.	3.00	47176.14	141528.42
8	Providing and constructing one span service road to reach island location from one pier location to another pier location including Royalty for earth @ Rs. 225.00 per m for service Road.	Rm	81.00	4018.93	325533.33
9	Carrying out load test on any pile as per standard procedure laid down in the IS:2911 specification including construction of test cap, dismantling the cap after test and cleaning the site and maintaining complete records of load a) Initial Load Test on test pile for 2.5 times the design load specified in Drawings				
	1.2 m Dia Pile	Nos.	1.00	200000.00	200000.00
10	b) Routine pile load test on pile for 1.5 times the design load specified in Drawings				
	1.2 m Dia Pile (2% of piles in total).	Nos.	1.00	150000.00	150000.00
11	c) Horizontal pile load test on pile for 1.5 times the design load specified in Drawings				
	1.2 m Dia Pile (2% of piles in total).	Nos.	1.00	100000.00	100000.00

Chanakya Technos Pvt. Ltd.

Dr. Anurag Pathan
Director

Dr. Anurag Pathan
04-12-25

Executive Engineer
RWD (W) Div., Bagha-2

NAME OF ROAD :	Construction of HL RCC Bridge in Jamuniya MMGSY Road To Kachahari Tola Bhitaha				
BLOCK :	Bhitaha				
DISTRICT :	West Champaran				
Sl. No.	Item Description	Unit	Quantity	Rate	Amount (in Rs.)
SUBSTRUCTURE					
12	R.C.C. grade M-30 in Substructure complete as per Dwg & Tech Specification RCC M-30 (Using Batching Plant, Transit Mixer and Concrete Pump) i) Up to 5m height (Using Batching Plant, Transit Mixer and Concrete Pump)	Cum	176.53	9130.99	1611893.66
13	ii) From 5m upto 10m height (Using Batching Plant, Transit Mixer and Concrete Pump)	Cum	162.30	9388.32	1523724.34
14	R.C.C. grade M-35 in Substructure complete as per Dwg & Tech Specification RCC M-35 (Using Batching Plant, Transit Mixer and Concrete Pump) ii) From 5m upto 10m height (Using Batching Plant, Transit Mixer and Concrete Pump)	Cum	15.48	9479.39	146740.96
15	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202	MT	62.65	69724.97	4368269.37
16	Supplying, fitting and fixing in position true to line and level elastomeric bearing conforming to IRC: 83 (Part-II) section IX and clause 2005 of MoRTH specifications complete including all accessories as per drawing and Technical Specifications.	cc	605160.00	0.87	526489.20
17	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7	Nos	180.00	144.07	25932.60
18	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 i) Sandy Material	Cum	196.89	916.47	180443.78
19	Providing and laying filler media with granular crushed aggregates (Jhama Metal) as per specification to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8	Cum	112.68	4881.33	550028.26
SUPERSTRUCTURE					
20	Providing and laying reinforced cement concrete in superstructure complete as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 II. RCC M-30 (Using Batching Plant, Transit Mixer and	Cum	315.70	10722.35	3385045.90
21	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in superstructure complete as per drawings and technical specification Clauses 1002, 1010 & 1202	MT	50.61	71342.74	3610656.07
22	Providing and laying cement concrete wearing course M-30 grade including reinforcement complete as per drawing and technical specifications Clauses 800 and 1206.3	Cum	49.86	16997.33	847486.87
23	Construction of R.C.C. railing of M 30 grade in cast-in-situ with 20 mm nominal size aggregate, true to line and grade, tolerance of vertical railing post not to exceed 1 in 500, centre-to-centre spacing between vertical posts not to exceed 2000 mm as per drawing and technical specifications Clauses 800, 900 and 1208.3	m	177.28	2245.93	398158.47
24	Drainage Spouts complete as per drawing and technical specifications Clause 1209	No	32.00	1311.21	41958.72

Chandraya T. Sharma Dyt. Bhitaha

Director

04-12-25
Executive Engineer
RWD (W) Div., Bagha-2

NAME OF ROAD : Construction of HL RCC Bridge in Jamuniya MMGSY Road To Kachahari Tola Bhitha					
BLOCK : Bhitha					
DISTRICT : West Champaran					
Sl. No.	Item Description	Unit	Quantity	Rate	Amount (In Rs.)
25	P.C.C. M-15 ordinary grade (1:2.5:5) levelling course below approach slab complete as per drawing and technical specifications Clauses 800 & 1211	cum	7.16	8197.60	58694.82
26	Reinforced Cement Concrete M-30 grade approach slab including reinforcement and formwork complete as per drawing and technical specifications Clauses 800 and 1211	cum	16.97	13248.41	224825.52
27	Strip Seal Expansion Joint (Providing and laying of a strip seal expansion joint catering to maximum horizontal movement upto 70 mm, complete as per approved drawings and standard specifications to be installed by the manufacturer/supplier or their authorised representative ensuring compliance to the manufacturer's instructions for installation.)	m	42.25	12605.38	532577.31
PROTECTION WORK					
28	Providing and laying boulder pitching on slopes laid over prepared filter media as per drawing and technical specifications Clause 1302	cum	443.40	3938.29	1746237.79
29	Providing and laying filter material underneath pitching in slopes complete as per drawing and technical specifications Clause 1302	cum	170.60	5002.91	853496.45
E. APPROCH ROAD					
30	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation , grass ,bushes ,shrubs , saplings and trees of girth upto 300mm , removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification - clause 201.1 and direction of E/I	Ha	0.17	75360.38	12811.26
31	Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m , transporting to the site spreading , grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	Cum	3468.00	239.97	832215.96
32	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	Cum	630.00	243.24	153241.20
33	Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	Cum	109.87	3078.28	338210.62
34	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.	Cum	61.68	6549.80	403991.66
35	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mix plant carriage of mixed material by tipper to site, laying in uniform layers with grader in sub-base/course on a well surface and compacting with vibratory roller to achieve the desired density.	Cum	61.68	5399.12	333017.72

Chanakya Technos Pvt. Ltd.
 Director

04-12-25
 Executive Engineer
 RWD (W) Div., Bagha-2

Construction of H. RCC Bridge in Jamuniya MMCSY Road To Kachahari Tola Blitha

Blitha
West Champaran

Sl. No.	Item Description	Unit	Quantity	Rate	Amount (in Rs.)
36	Prime Coat (Low porosity) Providing and applying primer coat with Bitumen emulsion (5% 1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502	Sqm	822.38	57.36	47173.72
37	Tack Coat Providing and applying tack coat with bitumen emulsion (0% 3) using emulsion distributor @ 0.2 to 0.25 kg per sqm on the prepared bituminous surface cleaned with hydraulic broom as per technical specification clause 503	Sqm	822.38	19.74	16233.78
38	Mix Seal Surfacing Type B Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 500 Type B	Sqm	822.38	328.58	270217.62
39	Providing and Fixing 'Logo' of Project Informatory sign board with Logo as per MORID specifications and drawing. Three MS plates of 1.6mm thick, top and middle plate duly welded with MS flat iron 25mm x 5 m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 Nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600 mm, 600 mm, 600 mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12SWG steel plate tube. All M.S. will be stove enamelled on both sides. Lettering and printing arrows, border etc, will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1.	Nos	3.00	11208.00	33624.00
40	Metal Beam Crash Barrier Type - A, "W": Metal Beam Crash Barrier Providing and erecting a "W" metal beam crash barrier comprising of 3 mm thick corrugated sheet metal beam rail, 70 cm above road/ground level, fixed on ISMC series channel vertical post, 150 x 75 x 5 mm spaced 2 m centre to centre, 1.8 m high, 1.1 m below ground/road level, all steel parts and fittings to be galvanised by hot dip process, all fittings to conform to IS:1367 and IS:1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm, 330 mm long complete as per clause 810	RM	80.00	3160.77	252861.60
41	Road Marking with Hot Applied Thermoplastic Compound with Reflectors Glass Beads on Bituminous Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectors glass beads @ 250 gms per sqm area, thickness of 2.5 mm exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes.	Sqm	40.00	778.40	31136.00

Chanakya Technos Pvt. Ltd.

Dr. Shashi Kumar
Director

Dr.
04-12-25
Executive Engineer
RWD (W) Div., Bagha-2

NAME OF ROAD :	Construction of HL RCC Bridge In Jamuniya MMGSY Road To Kachahari Tola Bhitaha				
BLOCK :	Bhitaha				
DISTRICT :	West Champaran				
Sl. No.	Item Description	Unit	Quantity	Rate	Amount (in Rs.)
42	Road Markers/Road Stud with Lens Reflector Providing and fixing of road stud 100 x 100 mm die cast in aluminium, resistant to corrosive effect of salt and grit, fitted with lense reflectors, installed in concrete or asphaltic surface by drilling holes 30 mm upto a depth of 600 mm and bedded in a suitable bituminous grout or epoxy mortar, all as per BS:873 (Part 4) 1973.	Nos	200.00	274.18	54836.00
E. DIVERSION					
43	Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m , transporting to the site spreading , grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	Cum	1080.00	239.97	259167.60
44	Granular Sub-base with Well Graded Material (Table 400.1) Grading II -Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	Cum	67.50	3078.28	207783.90
45	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row	m	22.50	7479.78	168295.05
5th Year Periodic Renewal cost					
46	Providing and applying tack coat with bitumen emulsion (RS) using emulsion distributor @ 0.25 to 0.30 kg per sq m on the prepared Granular Treated with Prime & cleaned with hydraulic broom as per technical specification clause 503.	Sqm	765.00	19.74	15101.10
47	Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects.	cum	19.13	15119.71	289240.05

Chanakya Technos Pvt. Ltd.

Ran. Shankar Pathan
Director

Sanjiv
04-12-25
Executive Engineer
RWD (W) Div., Bagha-2

NAME OF ROAD :		Construction of HL RCC Bridge in Jamuniya MMGSY Road To Kachahari Tola Bhitha			
BLOCK :		Bhitaha			
DISTRICT :		West Champaran			
Sl. No.	Item Description	Unit	Quantity	Rate	Amount (In Rs.)
48	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes.	Sqm	40.00	778.40	31136.00
Construction Cost :-					53384662.82
Add Labour @ 1% on Construction Cost :-					533846.63
49	Add S.F on Basic Materials Cost :-				349137.28
50	Sub Total Construction Cost (Including 1% Labour Cess & S.F):-				54267646.72
Add GST @ 18% on Sub Total Construction Cost (Including 1% Labour Cess & S.F):-					9768176.41
51	Total Construction Cost (A) :-				64035823.13
		Year	1 000	49770 00	49770 00
52 49	1st Year Maintenance cost	Year	1 000	52848 00	52848 00
53 50	2nd Year Maintenance cost	Year	1 000	56510 00	56510 00
54 51	3rd Year Maintenance cost	Year	1 000	59781 00	59781 00
55 52	4th Year Maintenance cost	Year	1 000	63054 00	63054 00
56 53	6th Year Maintenance cost	Year	1 000	66326 00	66326 00
57 54	7th Year Maintenance cost	Year	1 000	66326 00	66326 00
Maintenance Cost :-					348289.00
Add Labour @ 1% on Maintenance Cost :-					3482.89
58	Add S.F on Basic Materials Cost :-				1220.42
59	Sub Total Maintenance Cost (Including 1% Labour Cess & S.F):-				352992.31
Add GST @ 18% on Sub Total Maintenance Cost (Including 1% Labour Cess & S.F):-					63538.62
60	Total Maintenance Cost (B) :-				416530.93
Total Cost(A+B):-					64452354.05
Grand Total Cost(Road+Bridge)					79678890.27

Say 79678890.27

Say Rs 79,67,8890.27

Bill of Quantity Approved as corrected for item No part (A) Road from item ① to ⑥⑤
 and part (B) Bridge ① to ⑥⑤ for Rs 79678890.27 (Rupees Seven crore ninety six lakh seventy
 eight thousand eight hundred ninety only)

including Six Years Maintenance

Certified by
 Clear
 24.7.25

Chanakya Technos Pvt. Ltd.

Ravi Shankar Pathak
 Director

sd
 सहायक अभियंता
 नगर विकास विभाग
 नगर, बेरहमपुर

Doni
 04-12-25
 Executive Engineer
 RWD (W) Div., Bagha

**OFFICE OF THE EXECUTIVE ENGINEER,
RURAL WORKS DEPARTMENT, WORKS DIVISION, BAGHAHA-2**

Letter No. - 778 / Bagaha-2,
From,

Date 17/09/25

Executive Engineer,
Rural Works Department,
Works Division, Bagaha-2

To,

Chanakya Technos Private Limited,
Hamhar Pd Dubey Betiahata Gorakhpur Uttar Pradesh,
Bihar office Add-Vijay Nagar Gali No.-2 P.O.-B.V. College
P.S.-Rupaspur, Dist.-Patna, Pincode-800014

Sub :- Letter of Acceptance.

Ref:-


Chief Engineer-5 Letter No.-3257 अज०, Date 16.09.2025

Dear Sir,

This is to notify that your bid dated 12.04.2024 for execution of the road Package No.- MMGSY (AWSESII-SC)-BAGHAHA-2-606 (Tender ID.-143151) Under MMGSY (Awwesh) for the Contract Price of Rs. 7,95,91,243.00 (Seven Crore Ninety Five Lacs Ninety One thousand Two Hundred Forty Three Only) as Corrected and modified in accordance with the Instruction to Bidders in heredy accepted by Department.

You are hereby requested to furnish Performance Security including an additional security for unbalanced bids in term of ITB Clause 53.3.1 for an amount of Rs. 16,13,737.00 (P.S. Rs. 15,91,825.00 & Add Security for unbalanced bid Rs. 21,912.00) Within 15 days in accordance with the Conditions of Contract and sign the contract, failing which action as stated in Para 58 and 59 of ITB will be taken.


Yours Faithfully


Executive Engineer.


Rural Works Department
Works Division, Bagaha-2

17/09/25

Chanakya Technos Pvt. Ltd.



Director


04-12-25

Executive Engineer
RWD (W) Div., Bagaha-2

मुख्य अभियंता-5, मुजफ्फरपुर का कार्यालय,

ग्रामीण कार्य विभाग, बिहार।

/पटना, दिनांक- 16.09.25

क्रमांक-11 मु030-5 प0पु0-01-515/25 3257

प्रपक,

ई0 जय किशोर ठाकुर,

मुख्य अभियंता-5,

ग्रामीण कार्य विभाग,

बिहार, पटना।

सेवा में,

कार्यपालक अभियंता,

ग्रामीण कार्य विभाग,

कार्य प्रमंडल, बगहा-2

विषय: शीर्ष MMGSY योजना अन्तर्गत कार्य प्रमंडल, बगहा-2 के अधीन MMGSY (Awsesh-SC)-Bagha-2-606 (Tender-ID 143151) निर्माण कार्य के निविदा निष्पादन के संबंध में।

प्रसंग:- अभियंता प्रमुख-सह-आपर आयुक्त-सह-विशेष सचिव, ग्रामीण कार्य विभाग, बिहार, पटना का पत्रांक-BRRDA (HQ) MMGSY-AWSESH-398/25 2427 अनु0 दिनांक-11.09.2025

महाशय,

शीर्ष MMGSY योजना अन्तर्गत कार्य प्रमंडल, बगहा-2 के अधीन MMGSY (Awsesh-SC)-Bagha-2-606 (Tender-ID 143151) निर्माण कार्य के निविदा के वित्तीय बीड में सफल निविदाकार Chanakya Technos Private Limited (Bid ID-626123) द्वारा उद्धृत दर जो कि परिमाण विपत्र की दर से 0.11 प्रतिशत कम है, अर्थात् कुल राशि 7,95,91,243.00 (सात करोड़ पनचानवे लाख एकांवे हजार दो सौ तैतालीस) रु0 मात्र पर कार्यरहित एवं आपकी अनुश्रुति के आलोक में यह कार्य आवंटित किया जाता है। इस निविदा के निष्पादन पर विभागीय निविदा समिति की सहमति प्राप्त है।

2. निविदा की स्वीकृति सिर्फ इसी कार्य के लिए है, जो भविष्य में पूर्वाधार नहीं होगा।

3. कार्यपालक अभियंता, कार्य प्रमंडल, बगहा-2 संवेदक के द्वारा एकरारनामा के लिए जमा की गई राशि एवं निविदा के साथ अग्रधन के रूप में जमा किये गये संबंधित एन0एस0सी0/पासबुक/फिक्सा डिपोजिट/बैंक गारन्टी आदि का सत्यापन कराकर प्रमंडलीय कार्यालय में अभिलेखित करेंगे एवं कार्यादेश निर्गत करने के पूर्व अग्रधन की राशि के सत्यापन से संबंधित कागजात आगे प्रस्तावकर्ता को उपलब्ध कराया जाना सुनिश्चित करेंगे।

4. एकरारनामा के पूर्व Bid Validity की अवधि-विस्तार की जाँच के उपरान्त ही एकरारनामा सुनिश्चित किया जाय।

5. एकरारनामा के पूर्व निविदा सूचना के अनुसार सभी वांछित कागजातों की अद्यतन सत्यता एवं सत्यापित प्रति निश्चित रूप से प्राप्त कर लिया जाय एवं साथ में इसकी भी जाँच कर ली जाय कि संवेदक डीकार सूची से मुक्त है।

6. अधीक्षण अभियंता एवं कार्यपालक अभियंता अग्रतर कार्रवाई से पूर्व भली भाँति आश्चर्य हो लेंगे कि पथ का हस्तक्षेप हेतु विभाग द्वारा अनापत्ति प्रमाण पत्र निर्गत नहीं किया गया है।

7. कार्य में व्यवहृत सामग्रियों का दर प्राक्कलन में स्वीकृत लीड के आधार पर दिया गया है, कार्य करते समय अगर इसमें कमी पाई जाती है तो उसके दर में सापेक्ष कमी कर दी जायेगी।

8. इस कार्य के संबंध में ग्रामीण कार्य विभाग, बिहार सरकार द्वारा निर्गत प्रशासनिक स्वीकृति एवं प्रावधिक स्वीकृति तथा निविदा आमंत्रण सूचना में उल्लिखित शर्त एकरारनामा का भाग होगा, जिसे विशेष शर्त में जोड़ा जायेगा एवं साथ में एकरारनामा किया जायेगा।

9. अनुमोदित किये गये तुलनात्मक विवरणी के प्रत्येक बिन्दु की जाँच अपने स्तर से स्वयं कर लेंगे एवं त्रुटि पाये जाने की स्थिति में वस्तुस्थिति से तत्क्षण अधोहस्ताक्षरी को अवगत करायेंगे। त्रुटि के सुधारोपरान्त एकरारनामा की कार्रवाई की जायेगी।

10. एकरारनामा के समय प्रत्येक मर के भाषा की शुद्धता की जाँच कार्यपालक अभियंता स्वयं कर लेंगे एवं यह सुनिश्चित करेंगे कि इसमें कोई त्रुटि न हो।

11. कार्यारम्भ के पूर्व कार्यपालक अभियंता कार्य स्थल के निरीक्षणोपरान्त स्थल की स्थिति एवं पर्यावरण में किये गये उपबन्ध से पूरी तरह आश्चर्य हो लेंगे एवं प्रशासनिक स्वीकृति तथा प्रावधिक स्वीकृति के अग्रसारण प्राप्त होने के बाद ही कार्यारम्भ का आदेश सुनिश्चित करायेंगे।

12. कार्यादेश निर्गत करने से पहले संबंधित संवेदक से एकरारित अवधि के अन्दर कार्य सम्पन्न करने हेतु विस्तृत मरदार कार्य प्रोग्राम प्राप्त कर ही एकरारनामा किया जाय।

13. अधीक्षण अभियंता एवं कार्यपालक अभियंता विशेष रूप से ध्यान देंगे कि कार्य मानक विशिष्टियों के अनुरूप निर्धारित कार्य अवधि के अंदर पूरा की जाय।

14. कार्य समाप्ति की अवधि परिमाण विपत्र के अनुसार होगी।

15. कार्यपालक अभियंता कार्य आवंटित किये गये संवेदक से 10 दिनों के अन्दर एकरारनामा अंतिम सुनिश्चित करेंगे अनापत्ति पत्र के अग्रधन की राशि जमा कर ली जाय।

16. इस कार्य का व्यय विभाग द्वारा निर्गत प्रशासनिक स्वीकृति में अंकित शीर्ष अन्तर्गत होगा।

17. एकरारनामा के समय प्राक्कलन के अनुसार इस कार्य को पूरा करने हेतु संवेदक से मरदार कार्य योजना एकरारनामा के समय प्राप्त किया जाय तथा उस कार्य योजना की प्रति संबंधित कनिष्ठ अभियंता एवं सहायक अभियंता को भी उपलब्ध कराया जाय, ताकि

Chanakya Technos Pvt. Ltd.

Dr. Shashank Mishra

Director

Executive Engineer
RWD (W) Div., Bagha-2

कनीय अभियंता एवं सहायक अभियंता निर्धारित समय के साथ मदवार प्रगति का आकलन कर कार्यपालक अभियंता एवं संबंधित संवेदक को सूचित प्रत्येक 15 दिनों पर करेंगे। अगर संवेदक द्वारा निर्धारित समय के अन्दर उक्त मद के मात्रा का लक्ष्य प्राप्त नहीं किया गया तो कार्यपालक अभियंता दंडात्मक कार्रवाई संवेदक के विरुद्ध करेंगे। कार्यपालक अभियंता अगर उक्त निदेश का पालन नहीं करते हैं तो वे स्वयं कार्रवाई के पात्र होंगे।

18. सभी निविदा कागजात एवं तुलनात्मक विवरणी की मूल प्रति आवश्यक कार्रवाई हेतु लौटाई जाती है। आप निविदा कागजातों एवं तुलनात्मक विवरणी के जांचोपरांत आप आवश्यक निदेशों को अपने स्तर से निर्गत करेंगे।

19. एकरारनामा से पहले निविदाताओं द्वारा दिये गये कागजात का सत्यापन उनके मूल कागजात से मिलान कर ली जाय। कार्यपालक अभियंता, ग्रामीण कार्य विभाग कार्य प्रमंडल, बगहा-2 तुलनात्मक विवरणी की एक अभिप्रायित प्रति अधीक्षण अभियंता, ग्रामीण कार्य विभाग कार्य अंचल, बेतिया अभिलेख हेतु उपलब्ध करा देंगे। निदेश दिया जाता है कि संवेदक से कार्य प्रोग्राम प्राप्त कर लेंगे तथा उनका कार्य क्षमता, कुशलता एवं पूर्व से आवंटित कार्यों की प्रगति से संतुष्ट हो लें।

20. इस निविदा की राशि में अगर कोई अंतर होता है तो इसकी सूचना तुरन्त इस कार्यालय को दी जाय।

21. कार्यपालक अभियंता, एकरारनामा करने के पूर्व संवेदक का निबंधन संख्या पूर्ण पता एवं मुख्या संख्या कार्यदेश में अंकित करेंगे तथा इस का अनुरोध को सूचित करेंगे।

22. परिमाण विपत्र की दर से कम दर उद्धृत करने वाले संवेदक से विभाग द्वारा पूर्व में निर्गत दिशा निदेश के आलोक में अतिरिक्त वांछित परफॉरमेंस सिक्युरिटी की राशि जमा कराना सुनिश्चित करेंगे।

23. किसी भी परिस्थिति में निजी जमीन पर निर्माण नहीं कराया जाय।

24. प्रत्येक 15 दिनों पर संवेदक से स्वहस्ताक्षरित विपत्र प्राप्त कर रथल से मिलान कर मापी पुरताका में मापी दर्ज कर भुगतान सुनिश्चित करेंगे।

25. एकरारनामा से पूर्व नियमानुसार Character Certificate and GST Clearance Certificate प्राप्त कर लेंगे। इसका प्रतिवेदन अधोहस्ताक्षरी को समर्पित करेंगे।

26. कार्य के कार्यान्वयन में JV के सभी भागीदार की भागीदारी निविदा में दिये गये JV Agreement के अनुरूप होनी चाहिए। यदि इसमें किसी भी प्रकार का भ्रंश है तो सक्षम प्राधिकार के अनुमति प्राप्त करेंगे।

27. निविदा में यंत्र-संयंत्र एवं अभियंताओं के संबंध में दिये गए शपथ के अनुसार एकरारनामा करने से पहले इनके कागजात की जाँच कर लेंगे। कार्य स्थल पर यंत्र-संयंत्र एवं अभियंता की तैनाती सुनिश्चित करायेंगे। अधोहस्ताक्षरी द्वारा किये गए निरीक्षण के क्रम यदि यंत्र-संयंत्र एवं अभियंता की तैनाती में कमी पायी जायेगी तो नियमानुसार संवेदक पर कार्रवाई सुनिश्चित किया जायेगा।

28. संवेदक से बंध वैधता का प्रमाण लेने के पश्चात ही एकरारनामा करना सुनिश्चित करें।

29. कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, बगहा-2 को निदेशित किया जाता है कि विभागीय पत्रांक-मु0अ0-4-(मु0) विविध-23-291/2014-131 पटना दिनांक-13.12.2019 के आलोक में पत्र प्राप्ति के 24 घंटा के भीतर Letter of Acceptance (LOA) संबंधित संवेदक को निर्गत कर इसकी सूचना इस कार्यालय को भी उपलब्ध कराना सुनिश्चित करेंगे।

30. संवेदक के चरित्र प्रमाण पत्र के संबंध में निर्गत विभागीय पत्रांक-499 अंनु0 दिनांक-28.01.2021 को अनुपालन करना सुनिश्चित करेंगे।

31. प्रासंगिक पत्र के साथ संलग्न विभागीय निविदा समिति की बैठक की कार्यवाही में दिए गए निदेशों का अनुपालन सुनिश्चित किया जाय।

कृपया पत्र प्राप्ति की सूचना देंगे।

अनु0-यथावत।

ज्ञापांक - II/मु0अ0- 3257

प्रतिलिपि: अभियंता प्रमुख-सह-अपर आयुक्त-सह विशेष सचिव, ग्रामीण कार्य विभाग, बिहार, पटना को सूचनार्थ समर्पित।

विभागाध्यक्ष

मुख्य अभियंता-5

/पटना, दिनांक- 16.09.25

मुख्य अभियंता-5

/पटना, दिनांक- 16.09.25

ज्ञापांक - II/मु0अ0- 3257

प्रतिलिपि: अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, बेतिया को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित।

मुख्य अभियंता-5

/पटना, दिनांक- 16.09.25

ज्ञापांक II/मु0अ0- 3257

प्रतिलिपि: सहायक आईटी0 नैनजर, मुख्य अभियंता-5 का कार्यालय, ग्रामीण कार्य विभाग, बिहार, पटना को सूचनार्थ एवं ई-मेल पर अपलोड करने हेतु प्रेषित।

मुख्य अभियंता-5

Chanakya Technos Pvt. Ltd.
Dr. Shanka Mishra
Director

Dr. 04-12-25
Executive Engineer
RWD (W) Div., Bagha-2

कार्यपालक अभियन्ता का कार्यालय

ग्रामीण कार्य विभाग, कार्य प्रमंडल, बगहा-2

Mobile No- 8986915944

Email ID- ee.rwd.bagaha2@gmail.com

पत्रांक 982/अनु0

/ बगहा-2, दिनांक 04/11/2025

प्रेषक,

कार्यपालक अभियन्ता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल बगहा-2

सेवा में,

Chanakya Technos Private Limited,
Harihar Pd Dubey Betiahata Gorakhpur Uttar Pradesh,
Bihar office Add-Vijay Nagar Gali No.-2 P.O.-B.V. College
P.S.-Rupaspur, Dist.-Patna, Pincode-800014

विषय :- शीर्ष MMGSY (AWSESH-SC) योजना अन्तर्गत ग्रामीण कार्य विभाग कार्य प्रमंडल बगहा-2 के अधीन MMGSY (AWSESH-SC)-Bagha-2-606 (Tender ID-143151) निर्माण कार्य के कार्यादेश के संबंध में।

प्रसंग :- मुख्य अभियन्ता-5, ग्रामीण कार्य विभाग, बिहार, पटना का पत्रांक 3257 अनु0, दिनांक 16.09.2025

महाशय,

उपरोक्त विषयक प्रसंगिक पत्र द्वारा आपको 0.11% (शुन्य दसमलव एक एक प्रतिशत) कम दर पर अर्थात् 7,95,91,243.00 (सात करोड़ पनचानवे लाख एकानवे हजार दो सौ तैतालीस) रूपया मात्र पर कार्य मुख्य अभियन्ता-5, ग्रामीण कार्य विभाग, बिहार, पटना की स्वीकृति के उपरांत आपको कार्य आवंटित किया गया है।


कार्य आरंभ करने की तिथि 17.09.2025 को आपको कार्यादेश निर्गत किया जाता है तथा कार्य समाप्ति {01 (One Year) + 06 (Six Year)} को होगी।

एकरारनामा की राशि 7,95,91,243.00 (सात करोड़ पनचानवे लाख एकानवे हजार दो सौ तैतालीस) रूपया मात्र होगा। कार्य आरंभ करने से पहले संबंधित सहायक अभियन्ता/कनीय अभियन्ता से मिलकर कार्य स्थल का मासिक कार्य योजना, विडियोग्राफी एवं फोटोग्राफी करा लेना सुनिश्चित करे, कार्य मानक विशिष्टियों के अनुरूप निर्धारित कार्य अवधि में पूर्ण कराएंगे। कार्य स्थल पर गुण नियंत्रण प्रयोगशाला स्थापित करेंगे एवं स्थल आदेश पूस्तिका कार्य स्थल पर रखना सुनिश्चित करेंगे।

एकरारनामा करने के बाद किए गए कार्यों का भुगतान आवंटन उपलब्ध रहने एवं गुणनियंत्रण प्रतिवेदन प्रस्तुत करने के उपरांत ही होगा।

अनु0- मुख्य अभियन्ता-5 की
पत्र की छाया प्रति।

विश्वासभाजन


04-11-25

कार्यपालक अभियन्ता,
ग्रामीण कार्य विभाग,

कार्य प्रमंडल बगहा-2