

Government of Bihar



RURAL WORKS DEPARTMENT AGREEMENT DOCUMENT FOR

RURAL ROAD STRENGTHENING AND MANAGEMENT PROGRAM UNDER MUKHYA MANTRI GRAMIN SADAK UNNAYAN YOJANA (MMGSUY(RRSMP))

Name of Work : Initial Rectification, Minor improvement, Surface renewal, Construction of bridge/drainage/protection and Operation & Management Services (O&M) of Roads Under MMGSUY Scheme , PackageNo.-RRSMP/25-26/Bhagalpur/03 Under Shahkunda /Sultanganj(Sub Section: _____)Block.

Name of Agency: *Pravin Kumar Prasuh,*
Nayatola, Mirzapur, Nathnagar,
Madhusudanpur,
Dist-Bhagalpur-812001
Mob:- 9430613519
Email ID:- pappuyadav2016bgp@gmail.com

Agreement Cost: Rs. 3,44,78,555.00 (Rupees Three Crore Forty Four Lakh Seventy Eight Thousand Five Hundred Fifty Five Only) Vide Engineer-in-Chief, R.W.D, Bihar, Patna, Letter No.3534 Encl.,Dt-16-09-2025, Vide C.E-3, Bhagalpur, R.W.D, Bihar, Letter No. 1301 ,Dt-06-10-2025, Vide E.E (Work Division) Bhagalpur, Lt. No. 1669 (Encl) ,Dt-24-09-2025.

Agreement No: - 15 CMBD of Year 2025-26

Date of Work Start - 06 / 10 / 2025

Date of Work Complete - 05 / 10 / 2026

[Signature]

Praveen
6-10-25

[Signature]
Executive Engineer
Rural Works Department
Works Division Bhagalpur

6/10/25





बिहार BIHAR

प्रमाणित किया गया कि मा. 20/09/2025 को
आरबिंद कुमार सिन्हा

AZ 385829

Arbind Kumar Sinha

Stamp Vendor:-

R.L. No. - 12-81-88

Court Compound Bhagalpur

2025
20 SEP 2025
कोषाचार पदाधिकारी
भागलपुर

1424
25-9-25
1) Agreement Amount :- Construction Cost :- 3,32,06,040.00
Maintenance cost :- 12,72,515.00
Total :- 3,44,78,555.00

Rate: 5.60 % (Five Decimal Six Zero Percent) below the estimate cost

Ref - Engineer-in-chief, RWD, Bihar, Patna Vide Lt. No.- 3534 Encl., Dated:- 16-09-2025

AGREEMENT FORM

Agreement No.-

This Agreement made the _____ day of _____
between The Executive Engineer, Rural Works Department, Works
Division, Bhagalpur. ("The Employer") of the one part, and Pravin Kumar
Prasuh, Nayatola, Mirzapur, Nathnagar, Madhusudanpur, Dist- Bhagalpur-
812001, ("The contractor" of the other part).

Whereas the Employer is desirous that the Contractor execute
Initial Rectification, Minor improvement, Surface renewal, Construction of
bridge/drainage/protection and performance based Rural Road Contractor the
Operation & Management Services of Roads Package No.:-RRSMP/25-
26/Bhagalpur/03 Under MMGSUY(RRSMP) Scheme (Year 2025-2026), Block-
Shahkund/Sultanganj (Sub Section-

प्रमंडलीय लेखा पदाधिकारी
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल भागलपुर

(hereinafter) called "The Works & Services") and the Employer has accepted the bid by the Contractor for the execution of such The Works & Services and remedying of any defects therein, at a contract price of Rs. 3,44,78,555.00 (Rupees Three Crore Forty Four Lakh Seventy Eight Thousand Five Hundred Fifty Five Only)

Package No.:- RRSMP/25-26/Bhagalpur/03 Under MMGSUY(RRSMP) Scheme (Year 2025-2026)						
Sl. No	Block	Road Name	Length (Km)	Construction Cost(In Rs.)	Maintenance Cost (In Rs.)	Total Cost (In Rs.)
1	2	3	4	5	6	7
1	SHAHKUND	Shahkund Sajour REO Road To Jagarnathpur Tinbarba	0.705	30,28,988	2,20,413	32,49,401
2	SHAHKUND	Shahkund Asarganj Road To Bhattachak	0.250	23,53,300	85,256	24,38,556
3	SHAHKUND	REO Road To Jhitkiya Jagarnathpur	1.030	55,28,917	3,28,695	58,57,612
4	SHAHKUND	Samastipur Amkhorla Path (House of Suresh Singh) To House of Ramvaran Singh	1.300	78,38,595	3,65,187	82,03,782
5	SHAHKUND	PMGSY Road To Yadav Tola(Purvi)	0.400	24,40,576	99,959	25,40,535
6	SULTANGANJ	NH-80 Rani Pokhar To Middle School Masdi Via Binoba Nagar	0.650	1,20,15,664	1,73,005	1,21,88,669
Grand Total			4.335	3,32,06,040	12,72,515	3,44,78,555

Constructions & 7-Years Maintenance Cost Rs. 3,44,78,555.00 (Rupees Three Crore Forty Four Lakh Seventy Eight Thousand Five Hundred Fifty Five Only)

NOW THIS AGREEMENT WITNESSTH as follow :

1. In this Agreement, Words and expressions shall have the same meanings as are respectively assigned to them in the general conditions hereafter referred to, any they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payment to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the works and Services remedy any defects therein conformity in all aspects with the provisions of the Contract.
3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the works and the remedying the defects wherein the contract price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract

प्रमंडलीय लेखा पदधिकारी
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर



RURAL WORKS DEPARTMENT

Office of the Engineer-in-Chief-cum-Additional Commissioner-cum-Special Secretary/Engineer-in-Chief,

Rural Works Department, Bihar

5th floor, Visvesvaraya Bhawan, Nehru Path, Patna-800015

DETAILED NOTICE INVITING TENDER (through e-procurement mode only <http://pmgsytendersbih.gov.in>) for Initial Rectification, Minor Improvement, Surface renewal, Construction of bridge/drainage /protection work including Operation & Management for Rural Road Strengthening and Management Program under component of Mukhya Mantri Gramin Sadak Unnayan Yojana (MMGSUY)(Gen).

Notice Inviting Tender No.- RRSMP-10/2025-26

- Designation and Address of the Advertiser : Engineer-in-Chief-cum-Additional Commissioner-cum-Special Secretary, Rural Works Department, Govt. of Bihar
- Date of Notice Inviting Tender : 03.07.2025
- Period for download of Tender Document : From 22.07.2025 (9:00) to 01.08.2025 upto 15:00 hrs
- Date, Time & Place of Pre-Bid meeting : Date 24.07.2025 at 15:00 hrs.
- Last Date & Time for uploading tender documents by bidder : Date 01.08.2025 till 15:00 hrs <http://pmgsytendersbih.gov.in>
- Date and time of opening of Technical Bid : Date 01.08.2025 Time 15:30 hrs.
- Details of Works and Services:

S No	Package	District	Division	Block	No. of Road	Length (in Km)	Cost of Initial Rectification, Minor improvement if required and Surface Renewal (in Lakhs)	Cost of 5 years Operation & Management (O&M) cost (in Lakhs)	Total Estimated Cost Value (ECV) (in Lakhs)	Cost of BOD (in Rs)	Expenditure (in Lakhs)
1	RRSMP/25-26 Arwal/01	Arwal	Arwal	Arwal	3	8.100	484.274	67.504	551.778	10000	11.04
2	RRSMP/25-26 Arwal/02	Arwal	Arwal	Kaler, Kurtha, Sonabhadra Vanshi Surayapur	5	8.170	577.306	73.299	650.605	10000	13.01
3	RRSMP/25-26 Arwal/03	Arwal	Arwal	Karpi	9	18.900	1220.304	158.012	1378.316	10000	23.75
4	RRSMP/25-26 Aurangabad/03	Aurangabad	Aurangabad	Deo, Kutumba, Madanpur	7	6.675	341.753	53.871	395.645	10000	7.71
5	RRSMP/25-26 Aurangabad/04	Aurangabad	Aurangabad	Nab nagar, Aurangabad	4	31.030	2707.024	346.445	3053.469	10000	45.54
6	RRSMP/25-26 Aurangabad/05	Aurangabad	Aurangabad	Nabinagar, Barun	11	26.845	2267.587	260.591	2528.178	10000	35.25
7	RRSMP/25-26 Daudnagar/01	Aurangabad	Daudnagar	Daudnagar, Haspura, Odra	6	6.900	356.673	36.590	393.263	10000	7.87
8	RRSMP/25-26 Daudnagar/02	Aurangabad	Daudnagar	Goh	5	5.030	306.166	95.514	401.680	10000	8.73
9	RRSMP/25-26 Banka 2/01	Banka	Banka-2	Borhat, Bouns	12	24.350	1221.210	217.030	1438.240	10000	24.75
10	RRSMP/25-26 Banka 2/02	Banka	Banka-2	Chancan	7	13.006	551.185	122.300	673.485	10000	13.87
11	RRSMP/25-26 Banka 2/03	Banka	Banka-2	Dhoraiya	9	9.950	408.943	88.871	497.814	10000	9.94
12	RRSMP/25-26 Banka 2/04	Banka	Banka-2	Katoriya	7	26.934	1216.999	253.186	1470.185	10000	24.71
13	RRSMP/25-26 Banka 2/05	Banka	Banka-2	Rajauri	11	20.480	1901.628	162.416	2064.044	10000	30.65
14	RRSMP/25-26 Begusarai/01	Begusarai	Balia	Balia, Dandari	4	3.695	182.702	22.285	204.987	10000	4.12
15	RRSMP/25-26 Begusarai/02	Begusarai	Begusarai	Begusarai, Barauni	4	6.610	359.456	49.189	408.645	10000	8.17
16	RRSMP/25-26 Begusarai/03	Begusarai	Begusarai	Matihani	1	7.650	447.276	59.571	506.847	10000	10.14
17	RRSMP/25-26 Begusarai/04	Begusarai	Manihari	Chena Bariaipur, Chhorahi	2	3.250	158.321	13.134	171.455	5000	1.43
18	RRSMP/25-26 Begusarai/05	Begusarai	Teghra	Rachnawara	7	7.700	378.906	59.590	438.496	10000	8.37
19	RRSMP/25-26 Begusarai/06	Begusarai	Teghra	Bhagwanpur, Mansurachak, Teghra	7	6.550	384.673	47.373	432.046	10000	8.64
20	RRSMP/25-26 Bhagalpur/01	Bhagalpur	Bhagalpur	Gauradhi	5	6.150	380.710	30.469	411.179	10000	8.22
21	RRSMP/25-26 Bhagalpur/02	Bhagalpur	Bhagalpur	Jagdishpur, Nethnagar	7	7.210	420.701	42.347	463.048	10000	9.25
22	RRSMP/25-26 Bhagalpur/03	Bhagalpur	Bhagalpur	Shahkundi, Sultanganj	6	4.335	350.771	13.199	363.970	10000	7.23
23	RRSMP/25-26 Bhagalpur/04	Bhagalpur	Bhagalpur	Sanhaua	2	4.650	189.263	31.159	220.422	10000	4.41
24	RRSMP/25-26 Ara/01	Ara	Ara	Agiaon, Udwartnagar	4	5.200	345.375	46.563	391.938	5000	7.54
25	RRSMP/25-26 Ara/02	Ara	Ara	Mahdumpur, Ratnagar	10	17.230	995.135	150.803	1145.938	10000	21.45
26	RRSMP/25-26 Jehanabad/01	Jehanabad	Jehanabad	Baroli	6	6.550	500.414	24.878	525.292	10000	10.51
27	RRSMP/25-26 Katihar/01	Katihar	Katihar	Falka	11	11.865	716.164	79.491	795.655	10000	15.91
28	RRSMP/25-26 Katihar/02	Katihar	Katihar	Hasanganj	4	8.880	1038.362	72.118	1110.480	10000	21.11
29	RRSMP/25-26 Katihar/03	Katihar	Katihar	Katihar	9	24.050	3112.163	201.697	3313.860	10000	43.14
30	RRSMP/25-26 Katihar/04	Katihar	Katihar	Korha	11	13.744	843.196	76.578	919.774	10000	18.40
31	RRSMP/25-26 Katihar/05	Katihar	Katihar	Kursela, Sameli	8	7.110	451.488	30.291	481.779	10000	9.76
32	RRSMP/25-26 Katihar/06	Katihar	Katihar	Amdabad	3	4.900	312.499	32.339	344.838	10000	6.92
33	RRSMP/25-26 Manihari/01	Manihari	Manihari	Manihari	10	19.463	1434.638	128.742	1563.380	10000	25.64
34	RRSMP/25-26 Manihari/02	Manihari	Manihari	Manihari	24	46.940	3467.451	366.696	3834.146	10000	48.35
35	RRSMP/25-26 Manihari/03	Manihari	Manihari	Azamganj	4	6.065	408.522	32.031	440.553	10000	8.81
36	RRSMP/25-26 Manihari/04	Manihari	Manihari	Pranpur	17	37.421	2775.307	302.543	3077.850	10000	40.78
37	RRSMP/25-26 Manihari/05	Manihari	Manihari	Pranpur	11	11.865	716.164	79.491	795.655	10000	15.91
38	RRSMP/25-26 Kishanganj/01	Kishanganj	Kishanganj	ALAULI, Kishanganj	8	14.515	752.786	127.965	880.751	10000	17.62
39	RRSMP/25-26 Lakhisarai/01	Lakhisarai	Lakhisarai	Lakhisarai, Ramgarh, Chouk, Surajgarh	8	13.960	751.221	114.851	866.072	5000	17.30
40	RRSMP/25-26 Lakhisarai/02	Lakhisarai	Lakhisarai	Lakhisarai	8	13.960	751.221	114.851	866.072	5000	17.30

For details please visit : www.state.bihar.gov.in/prd/bihar

Engineer-in-Chief-cum-Additional Commissioner-cum-Special Secretary, Rural Works Department, Govt. of Bihar

PR No. 007790 (RWD) 25-26

प्रमंडलीय लेखा पदाधिकारी
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल भागलपुर

BILL OF QUANTITY (BOQ)

Tender Inviting Authority: Engg-In Chief RWD Patna

Name of Road: = Shabkund Sajaour R/O Road to Jagannathpur Tinharha
 Name of Block = Shabkund
 Name of District = Bhagalpur
 Length of Road = 0.705 Km

Contract No: Civil Works/

Bidder

Name:

Excess (+)

%

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1.00	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.21	ha	75360.38	Seventy Five Thousand Three Hundred Sixty Rupees and Thirty Eight Paise	15825.68
2.00	Scarifying the existing bituminous road surface to a depth of 150 mm and disposal of scarified material with a lift upto 3 m and lead upto 1000 m as per Technical Specification Clause 301.4.	93.75	Sqm	19.16	Nineteen Rupees and Sixteen Paise	1796.25
3.00	Construction of subgrade and earthen shoulders :-Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	220.31	Cum	244.79	Two Hundred Forty Four Rupees and Seventy Nine Paise	53929.68
4.00	WBM Grading 3 (By Mechanical Means) :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	7.82	Cum	3954.40	Three Thousand Nine Hundred Fifty Four Rupees and Forty Paise	30923.41

प्रमंडलीय लेखा पदाधिकारी
 ग्रामीण कार्य विभाग
 कार्य प्रमंडल, भागलपुर

कार्यपालक अभियंता
 ग्रामीण कार्य विभाग

Scanned with OKEN Scanner



Scanned with OKEN Scanner

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1.00	1st Year O&M cost	1.00	Year	32652.00	Thirty Two Thousand Six Hundred Fifty Two Rupees	32,652.00
2.00	2nd Year O&M cost	1.00	Year	32652.00	Thirty Two Thousand Six Hundred Fifty Two Rupees	32,652.00
3.00	3rd Year O&M cost	1.00	Year	32652.00	Thirty Two Thousand Six Hundred Fifty Two Rupees	32,652.00
4.00	4th Year O&M cost	1.00	Year	32652.00	Thirty Two Thousand Six Hundred Fifty Two Rupees	32,652.00
5.00	6th Year O&M cost	1.00	Year	32652.00	Thirty Two Thousand Six Hundred Fifty Two Rupees	32,652.00
6.00	7th Year O&M cost	1.00	Year	32652.00	Thirty Two Thousand Six Hundred Fifty Two Rupees	32,652.00
	1% Labour					1,959.12
	18% GST on Total Main. cost					35,616.80
	Total Cost Of Maintainance					2,33,487.92
	Total Estimated Cost					34,42,164.00
	Estimated Cost in Words				Thirty Four Lac Forty Two Thousand One Hundred Sixty Four Rupees	

21/10/25
NE

21/10/25
NE

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

BOB Approved for 34,42,164.00 (Thirty four lakh forty-two thousand one hundred sixty four rupees) only.

21/10/25

Superintending Engineer
Rural Work Department
Works Circle, Bhagalpur

प्रमंडलीय लेखा पदाधिकारी
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

Scanned with OKEN Scanner

BILL OF QUANTITY (BOQ)

Tender Inviting Authority: Engg-In Chief RWD Patna

Name of Road: = Shahkunt Assarganj Road to Bhattachak

Name Of Block = Sahkunt

Name Of District = Bhagalpur

Length of Road = 0.250 Km

Contract No: Civil Works/

Bidder Name:

Excess (+)

%

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1.00	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.00	ha	75360.30	Seventy Five Thousand Three Hundred Sixty Rupees and Thirty Eight Paise	6028.83
2.00	Dismantling of existing structures, like culverts, bridge, retaining wall and other structures comprising of brick masonry including unserviceable material and stacking the serviceable material with all lift and lead of 1000m as per technical specification clause 202.	24.75	Cum	307.62	Three Hundred Seven Rupees and Sixty Two Paise	7,613.60
3.00	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 m as per Technical Specification Clause 202.	4.50	Cum	566.16	Five Hundred Sixty Six Rupees and Sixteen Paise	2,547.72
4.00	Dismantling of Cement Concrete Pavements by mechanical means using pneumatic tools breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials upto a lead of 1000 m, stacking serviceable and unserviceable materials separately	65.63	Cum	1751.25	One Thousand Seven Hundred Fifty One Rupees and Twenty Five Paise	1,14,934.54

प्रमडलीय लेखा पदाधिकारी
ग्रामीण कार्य विभाग
कार्य प्रमडली, भागलपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमडली, भागलपुर

Scanned with OKEN Scanner



Scanned with OKEN Scanner

Sl. No.	Description of work	No. or Qty.	Unit	Figure	Estimated Rate Words	AMOUNT Rs. P
28.00	Providing HYSD Bars :- Supplying, fitting and placing HYSD / TMT bar reinforcement in superstructure complete as per drawings and technical specifications Clauses 1002, 1010 and 1202	0.61	mt	68003.68	Sixty Eight Thousand Eighty Three Rupees and Sixty Eight Paise	41190.63
29.00	Providing and filling joint sealing compound as per drawings and technical specifications with coarse sand and 6 per cent bitumen by weight	15.00	rm	54.50	Fifty Four Rupees and Fifty Paise	817.50
30.00	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	2.64	Cum	5726.18	Five Thousand Seven Hundred Twenty Six Rupees and Eighteen Paise	15117.12
31.00	Plastering with cement mortar (1:4), 15 mm Thick on brick work in substructure as per Technical Specifications Clause 613.4 & 1204.	53.93	Sqm	168.92	One Hundred Eighty Eight Rupees and Ninety Two Paise	10188.46
32.00	Providing 1.5 mm cement punning including curing carriage of water with all leads and lifts as per building specification and direction of E/I	18.56	nos	61.88	Sixty One Rupees and Eighty Eight Paise	1148.49
33.00	Providing Weepholes in brick masonry, Plain / Reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing	20.00	Sqm	129.58	One Hundred Twenty Nine Rupees and Fifty Eight Paise	2591.60
Cost Of Construction						19,99,836.18
1% Labour						19,998.36
TOTAL SEIGNIORAGE FEE						92,794.00
18% GST on Total Const.cost						3,80,273.14
Total Cost Of Construction						24,92,901.68
1.00	1st Year O&M cost	1.00	Year	12630.00	Twelve Thousand Six Hundred Thirty Rupees	12,630.00
2.00	2nd Year O&M cost	1.00	Year	12630.00	Twelve Thousand Six Hundred Thirty Rupees	12,630.00
3.00	3rd Year O&M cost	1.00	Year	12630.00	Twelve Thousand Six Hundred Thirty Rupees	12,630.00
4.00	4th Year O&M cost	1.00	Year	12630.00	Twelve Thousand Six Hundred Thirty Rupees	12,630.00
5.00	6th Year O&M cost	1.00	Year	12630.00	Twelve Thousand Six Hundred Thirty Rupees	12,630.00

प्रमंडलीय लेखा पदाधिकारी
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

Scanned with OKEN Scanner

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
6.00	7th Year O&M cost	1.00	Year	12630.00	Twelve Thousand Six Hundred Thirty Rupees	12,630.00
	1% Labour					757.80
	18% GST on Total Main. cost					13,776.80
	Total Cost Of Maintenance					90,314.60
	Total Estimated Cost					25,83,216.00
	Estimated Cost In Words			Twenty Five Lac Eighty Three Thousand Two Hundred Sixteen Rupees		

22/07/25
41

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

BOS Approved for 25,83,216.00 (Twenty five lac eighty three thousand two hundred sixteen rupees) only.

[Signature]

22/07/25
Superintending Engineer
Rural Work Department
Works Circle, Bhagalpur

22/07/25

22/07/25

प्रमंडलीय लेखा पदाधिकारी
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल भागलपुर

22/07/25

Scanned with OKEN Scanner



Scanned with OKEN Scanner

BILL OF QUANTITY (BOQ)

Tender Inviting Authority: Engr.-In-Chief RWD Patna

Name of Road = R/O road to Jhikdiya Jagannathpur
 Name Of Block = Sahkund
 Name Of District = Bhagalpur
 Length of Road = 1.030 Km

Contract No: Civil Works/

Bidder Name: Excess (+) %

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1.00	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.31	ha	75360.38	Seventy Five Thousand Three Hundred Sixty Rupees and Thirty Eight Paise	23361.72
2.00	Scarifying the existing bituminous road surface to a depth of 150 mm and disposal of scarified material with a lift upto 3 m and lead upto 1000 m as per Technical Specification Clause 301.4.	403.13	Sqm	19.16	Nineteen Rupees and Sixteen Paise	7723.97
3.00	Dismantling of Cement Concrete Pavements by mechanical means using pneumatic tools breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials upto a lead of 1000 m, stacking serviceable and unserviceable materials separately	30.00	Cum	1751.25	One Thousand Seven Hundred Fifty One Rupees and Twenty Five Paise	52537.50
4.00	Construction of subgrade and earthen shoulders :- Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	321.88	Cum	244.79	Two Hundred Forty Four Rupees and Seventy Nine Paise	78793.01
5.00	Excavation for roadway in soil using manual means for carrying of cut earth to embankment site with a lift upto 1.5 m and lead upto 50 m as per Technical Specification Clause 302.3	15.00	Cum	96.35	Ninety Six Rupees and Thirty Five Paise	1445.25

प्रमंडलीय लेखा पदाधिकारी
 ग्रामीण कार्य विभाग
 कार्य प्रमंडल, भागलपुर

कार्यपालक अभियंता
 ग्रामीण कार्य विभाग
 कार्य प्रमंडल, भागलपुर



Scanned with OKEN Scanner

Sl. No.	Description of work	No. or Qty.	Unit	Figure	Estimated Rate Words	AMOUNT Rs. P
37.00	providing and laying cement concrete wearing course M 30 grade including reinforcement complete as per drawing and technical specifications Clauses 800 and 1206.3	1.50	Sqm	12280.59	Twelve Thousand Two Hundred Eighty Rupees and Fifty Nine Paise	19,403.33
	Cost Of Construction					47,86,670.26
	1% Labour					47,866.70
	TOTAL SEIGNIORAGE FEE					1,28,941.00
	18% GST on Total Const cost					8,93,426.03
	Total Cost Of Construction					58,56,903.99
1.00	1st Year O&M cost	1.00	Year	48423.00	Forty Eight Thousand Four Hundred Twenty Three Rupees	48,423.00
2.00	2nd Year O&M cost	1.00	Year	48747.00	Forty Eight Thousand Seven Hundred Forty Seven Rupees	48,747.00
3.00	3rd Year O&M cost	1.00	Year	48747.00	Forty Eight Thousand Seven Hundred Forty Seven Rupees	48,747.00
4.00	4th Year O&M cost	1.00	Year	48747.00	Forty Eight Thousand Seven Hundred Forty Seven Rupees	48,747.00
5.00	6th Year O&M cost	1.00	Year	48747.00	Forty Eight Thousand Seven Hundred Forty Seven Rupees	48,747.00
6.00	7th Year O&M cost	1.00	Year	48747.00	Forty Eight Thousand Seven Hundred Forty Seven Rupees	48,747.00
	1% Labour					2,921.58
	18% GST on Total Main. cost					53,114.32
	Total Cost Of Maintenance					3,48,193.90
	Total Estimated Cost					62,05,098.00
	Estimated Cost in Words				Sixty Two Lac Five Thousand Ninety Eight Rupees	

24/3/25
24/3/25

प्रमंडलीय लेखा पदाधिकारी
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

PTO



BILL OF QUANTITY (BOQ)

Tender Inviting Authority: Engr.-in-Chief RWD Patna

Name of Road: = Samastipur Amkhorla Path (House Of Suresh Singh) to House Of Ramvaran Singh

Name Of Block = Sahkund

Name Of District = Bhagalpur

Length of Road = 1.300 Km

Contract No: Civil Works/

Bidder Name:

Excess (+)

%

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1.00	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.39	ha	75360.30	Seventy Five Thousand Three Hundred Sixty Rupees and Thirty Eight Paise	29390.55 ✓
2.00	Scarifying the existing bituminous road surface to a depth of 150 mm and disposal of scarified material with a lift upto 3 m and lead upto 1000 m as per Technical Specification Clause 301.4.	206.25	Sqm	19.16	Nineteen Rupees and Sixteen Paise	3951.75 ✓
3.00	Construction of subgrade and earthen shoulders :-Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	406.25	Cum	244.79	Two Hundred Forty Four Rupees and Seventy Nine Paise	99445.94 ✓
4.00	Granular Sub-base with Well Graded Material (Table 400.1) For Grading II Material :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	5.63	Cum	2472.40	Two Thousand Four Hundred Seventy Two Rupees and Forty Paise	13919.61 ✓

प्रमंडलीय लेखा पदाधिकारी
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

Scanned with OKEN Scanner

Sl. No.	Description of work	No. or Qty.	Unit	Figure	Estimated Rate Words	AMOUNT R. P
37.00	Construction of R.C.C. railing of M 25 grade in cast-in-situ with 20 mm nominal size aggregate, true to line and grade, tolerance of vertical railing post not to exceed 1 in 500, centre-to-centre spacing between vertical posts not to exceed 2000 mm as per drawing and technical specifications Clauses 800, 900 and 1208.3	6.00	m	6790.55	Six Thousand Seven Hundred Ninety Eight Rupees and Fifty Five Paise	40,791.30
38.00	Drainage spouts complete as per drawing and technical specifications Clause 1209	0.00	nos	917.05	Nine Hundred Seventeen Rupees and Eighty Five Paise	7,342.80
39.00	providing and laying cement concrete wearing course M 30 grade including reinforcement complete as per drawing and technical specifications Clauses 800 and 1206.3	1.50	Sqm	12280.59	Twelve Thousand Two Hundred Eighty Rupees and Fifty Nine Paise	19,403.33
Cost Of Construction						68,17,727.08
1% Labour						68,177.27
TOTAL SEIGNIORAGE FEE						1,51,041.00
18% GST on Total Const.cost						12,66,650.16
Total Cost Of Construction						83,03,595.51
1.00	1st Year O&M cost	1.00	Year	54099.00	Fifty Four Thousand Ninety Nine Rupees	54,099.00
2.00	2nd Year O&M cost	1.00	Year	54099.00	Fifty Four Thousand Ninety Nine Rupees	54,099.00
3.00	3rd Year O&M cost	1.00	Year	54099.00	Fifty Four Thousand Ninety Nine Rupees	54,099.00
4.00	4th Year O&M cost	1.00	Year	54099.00	Fifty Four Thousand Ninety Nine Rupees	54,099.00
5.00	6th Year O&M cost	1.00	Year	54099.00	Fifty Four Thousand Ninety Nine Rupees	54,099.00
6.00	7th Year O&M cost	1.00	Year	54099.00	Fifty Four Thousand Ninety Nine Rupees	54,099.00
1% Labour						3,245.94
18% GST on Total Main. cost						59,011.19
Total Cost Of Maintainance						3,86,851.13
Total Estimated Cost						86,90,447.00

प्रमडलीय लेखा पदाधिकारी
ग्रामीण कार्य विभाग
कार्य प्रमंडल भागलपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल भागलपुर



BILL OF QUANTITY (BOQ)

Tender Inviting Authority: Engg-In Chief RWD Patna

Name of Road: PMGSY road to Yadav Tola (Purvi)

Name Of Block: Sahkund

Name Of District: Bhagalpur

Length of Road: 0.400 Km

Contract No: Civil Works/

Bidder Name:

Express (+)

%

SCHEDULE OF WORKS.

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1.00	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.12	ha	75360.38	Seventy Five Thousand Three Hundred Sixty Rupees and Thirty Eight Paise	9043.25
2.00	Construction of subgrade and earthen shoulders :-Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	150.00	Cum	244.79	Two Hundred Forty Four Rupees and Seventy Nine Paise	36718.50
3.00	Cement Concrete Pavement (PQC):- Construction of un-reinforced, plain cement concrete pavement (M35 Grade) over a prepared sub base with 43 grade cement @ 400 kg per cum, coarse and fine aggregate conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form paver, spread, compacted and finished in a continuous operation including provision of 0.5 x 0.5 panel, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures as approved, curing compound, finishing to lines and grades as per drawing	196.88	Cum	6021.15	Six Thousand Twenty One Rupees and Fifteen Paise	1185444.01

प्रमंडलीय लेखा पदाधिकारी
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

Scanned with OKEN Scanner

Sl. No.	Description of work	No. of Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
15.00	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes. (ii) At Edge CC Portion	80.00	Cum	887.99	Eight Hundred Eighty Seven Rupees and Ninety Nine Paise	71039.20
16.00	Earth work in excavation for foundation of structures upto 3.0 m depth as per drawing and technical specification clause 1104	99.00	Cum	397.76	Three Hundred Ninety Seven Rupees and Seventy Six Paise	39378.24
17.00	Sand Filling in Foundation :- Sand Filling in Foundation Trenches as per drawing and technical specification Clause 1108	9.00	Cum	545.79	Five Hundred Forty Five Rupees and Seventy Nine Paise	4912.11
18.00	Providing M15 (PCC 1:2.5:5) as levelling course in foundation :- Providing PCC M 15 (1:2.5:5) concrete for plain concrete in open foundations complete as per drawings and technical	9.00	Cum	6221.75	Six Thousand Two Hundred Twenty One Rupees and Seventy Five Paise	55995.75
19.00	Providing PCC M 20 (1:2:4) concrete for plain concrete in open foundations complete as per drawings and technical specifications Clause 802, 804, 805, 806, 807, 1202 & 1204	25.50	Cum	6601.98	Six Thousand Six Hundred One Rupees and Ninety Eight Paise	168350.49
20.00	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202	2.30	mt	66566.17	Sixty Six Thousand Five Hundred Sixty Six Rupees and Seventeen Paise	153102.19
21.00	Providing R.C.C. M-25 as cover slab:- Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5	14.00	Cum	7149.59	Seven Thousand One Hundred Forty Nine Rupees and Fifty Nine Paise	100094.26
22.00	Providing HYSD Bars :- Supplying, fitting and placing HYSD / TMT bar reinforcement in superstructure complete as per drawings and technical specifications Clauses 1002, 1010 and 1202	1.00	Cum	68083.68	Sixty Eight Thousand Eighty Three Rupees and Sixty Eight Paise	68083.68
Cost Of Construction						20,95,299.01
1% Labour						20,952.99
TOTAL SEIGNIORAGE FEE						74,728.00
18% GST on Total Const.cost						3,94,376.40
Total Cost Of Construction						25,85,356.40
1.00	1st Year O&M cost	1.00	Year	14808.00	Fourteen Thousand Eight Hundred Eight Rupees	14,808.00
2.00	2nd Year O&M cost	1.00	Year	14808.00	Fourteen Thousand Eight Hundred Eight Rupees	14,808.00

प्रमंडलीय लेखा पदाधिकारी
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

Scanned with OKEN Scanner



Scanned with OKEN Scanner

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate			AMOUNT Rs. P
				Figure	Words	Eight	
3.00	3rd Year O&M cost	1.00	Year	14808.00	Fourteen Thousand Hundred Eight Rupees		14,808.00
4.00	4th Year O&M cost	1.00	Year	14808.00	Fourteen Thousand Hundred Eight Rupees		14,808.00
5.00	6th Year O&M cost	1.00	Year	14808.00	Fourteen Thousand Hundred Eight Rupees		14,808.00
6.00	7th Year O&M cost	1.00	Year	14808.00	Fourteen Thousand Hundred Eight Rupees		14,808.00
	1% Labour						888.48
	18% GST on Total Main. cost						16,152.57
	Total Cost Of Maintainance						1,85,889.05
	Total Estimated Cost						26,91,245.00
	Estimated Cost In Words				Twenty Six Lac Ninety One Thousand Two Hundred Forty Five Rupees		

21/7/25
OE

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

BOB Approved for 26,91,245 (Twenty six lac -
Ninety one thousand two hundred forty five
rupees) only

[Signature]

[Signature] 22/07/25
Superintending Engineer
Rural Work Department
Works Circle, Bhagalpur

[Signature]
22/07/25

[Signature]
22/07/25

[Signature]
प्रमंडलीय लेखा पदाधिकारी
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर
Scanned with OKEN Scanner

BILL OF QUANTITY (BOQ)

Tender Inviting Authority: Engg-in Chief RWD Patna

NH-80 Rant Pokhar to Middle School Masdi via Binoba nagar

Name of Road =

Name Of Block =

Sultanganj

Name Of District =

Bhagalpur

Length of Road =

0.650 Km

Contract No: Civil Works/

Bidder

Excess (+)

%

Name:

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1.00	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.20	ha	75360.38	Seventy Five Thousand Three Hundred Sixty Rupees and Thirty Eight Paise	15072.08
2.00	Construction of subgrade and earthen shoulders :-Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	162.50	Cum	244.79	Two Hundred Forty Four Rupees and Seventy Nine Paise	39778.38
3.00	Granular Sub-base with Well Graded Material (Table 400.1) For Grading II Material :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	18.75	Cum	2503.90	Two Thousand Five Hundred Three Rupees and Ninety Paise	46948.13

1/4
22/11/25
JB

22/11/25
AE

[Signature]

[Signature]

प्रमंडलीय लेखा पदाधिकारी
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल भागलपुर

[Signature]

Scanned with OKEN Scanner



Scanned with OKEN Scanner

Sl. No.	Description of work	No. or Qty.	Unit	Figure	Estimated Rate Words	AMOUNT Rs. P
	18% GST on Total Const.cost					19,11,573.97
	Total Cost Of Construction					1,27,28,096.02
1.00	1st Year O&M cost	1.00	Year	25494.00	Twenty Five Thousand Four Hundred Ninety Four Rupees	25,494.00
2.00	2nd Year O&M cost	1.00	Year	25656.00	Twenty Five Thousand Six Hundred Fifty Six Rupees	25,656.00
3.00	3rd Year O&M cost	1.00	Year	25656.00	Twenty Five Thousand Six Hundred Fifty Six Rupees	25,656.00
4.00	4th Year O&M cost	1.00	Year	25656.00	Twenty Five Thousand Six Hundred Fifty Six Rupees	25,656.00
5.00	6th Year O&M cost	1.00	Year	25656.00	Twenty Five Thousand Six Hundred Fifty Six Rupees	25,656.00
6.00	7th Year O&M cost	1.00	Year	25656.00	Twenty Five Thousand Six Hundred Fifty Six Rupees	25,656.00
	1% Labour					1,537.74
	18% GST on Total Main. cost					27,956.11
	Total Cost Of Maintenance					1,83,267.85
	Total Estimated Cost					1,29,11,364.00
	Estimated Cost in Words				One Crore Twenty Nine Lac Eleven Thousand Three Hundred Sixty Four Rupees	

25/7/25
JE

22-07-25
A.E.

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

G.O. Approved for 1,29,11,364 (One crore twenty-nine lakh eleven thousand three hundred sixty four rupees) only.

प्रगडलीय लेखा पदाधिकारी
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

प्रगडलीय लेखा पदाधिकारी
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

Superintending Engineer
Rural Work Department
Works Circle, Bhagalpur

Scanned with OKEN Scanner

Scanned with OKEN Scanner

पत्रांक- 1301
प्रेषक, 06/10/25

मुख्य अभियंता-3 भागलपुर का कार्यालय
ग्रामीण कार्य विभाग।

दिनांक- 06/10/25

ई0 जय किशोर ठाकुर
अभियंता प्रमुख-सह-
मुख्य अभियंता-3, भागलपुर, ग्रामीण कार्य विभाग।

कार्यपालक अभियंता
ग्रामीण कार्य विभाग, कार्य प्रमण्डल, भागलपुर।

विषय : शीर्ष 4515 MINGSUY (RRSMP) योजनान्तर्गत कार्य प्रमण्डल, भागलपुर के अर्धीन पैकेज
संख्या-RRSMP/25-26 Bhagalpur/03 (Tender ID-143258) कार्य की निविदा की स्वीकृति के संबंध में।

महाराज,

- विभागीय पत्रांक-गु0310(31030)-4515-01-791/2025 पार्ट-III-3534 अनु0, दिनांक-16.09.2025 द्वारा संसूचित आदेश के अनुपालन में उपर्युक्त विषय के संबंध में बिहार लोक निर्माण संहिता के कडिका-103 के आलोक में इस कार्य को इसके योग्य एवं सफल निविदाकार Pravin Kumar Prasuh (बीड आईडी-626892) को उनके द्वारा निविदित दर, जो परिमाण विपत्र की दर से 5.60 (पाँच दशमलव छः शून्य प्रतिशत) कम है, को स्वीकृत करते हुए सम्पूर्ण कार्य कुल 3,44,78,555/- (तीन करोड़ चौवालीस लाख अठहत्तर हजार पाँच सौ पचपन) रुपये मात्र की लागत पर आपकी अनुशंसा एवं कार्यहित में आवंटित किया जाता है।
- निविदा की स्वीकृति सिर्फ इसी कार्य के लिए है, जो भविष्य में पूर्वाधारण नहीं होगा।
 - CMBD के सुसंगत कंडिकाओं के अनुरूप संवेदक से एकरारनामा हेतु Performance Security के रूप में E-BG प्राप्त किया जायेगा।
 - एकरारनामा के पूर्व निविदा सूचना के अनुसार सभी वांछित कागजातों की अधतन स्वच्छ एवं सत्यापित प्रति निश्चित रूप से प्राप्त कर लिया जायेगा।
 - एकरारनामा से पूर्व कार्यपालक अभियंता यह सुनिश्चित कर लेंगे कि निविदाकार डिवार सूची/काली सूची या कार्य लंबित सूची में शामिल न हो।
 - कार्य में व्यवहृत सामग्रियों का दर प्राक्कलन में स्वीकृत लीड के आधार पर दिया गया है, कार्य करते समय अगर इसमें कमी पाई जाती है तो उसके दर में सापेक्ष कमी कर दी जायेगी।
 - इस कार्य के संबंध में ग्रामीण कार्य विभाग, बिहार सरकार द्वारा निर्गत प्रशासनिक स्वीकृति एवं प्रावैधिक स्वीकृति तथा निविदा आमंत्रण सूचना में उल्लेखित शर्त एकरारनामा का भाग होगा, जिसे विशेष शर्त में जोड़कर संवेदक के साथ एकरारनामा किया जायेगा।
 - अनुमोदित किये गये तुलनात्मक विवरणी के प्रत्येक बिन्दु की जाँच अपने स्तर से स्वयं कर लेंगे एवं त्रुटि पाये जाने की स्थिति में वस्तुस्थिति से तत्क्षण अधोहस्ताक्षरी को अवगत करायेंगे। त्रुटि के सुधारोपरान्त एकरारनामा की कार्रवाई की जायेगी।
 - एकरारनामा के समय प्रत्येक मद के भाषा की शुद्धता की जाँच कार्यपालक अभियंता स्वयं कर लेंगे एवं यह सुनिश्चित करेंगे कि इसमें कोई त्रुटि न हो।
 - कार्यारम्भ के पूर्व कार्यपालक अभियंता कार्य स्थल के निरीक्षणोपरान्त स्थल की स्थिति एवं प्राक्कलन में किये गये उपबंध से पूरी तरह आश्वस्त हो लेंगे एवं प्रशासनिक स्वीकृति तथा प्रावैधिक स्वीकृति के अग्रसारण प्रारूप में दिये गये निर्देश का अनुपालन सुनिश्चित करायेंगे। पथ का नाम, परिमाण विपत्र की राशि, तकनीकी स्वीकृति की राशि, प्रशासनिक स्वीकृति की राशि, संवेदक द्वारा उद्धृत दर, परक्रमित दर, Bid Capacity आदि का मिलान कर ही कार्य आवंटन आदेश निर्गत करेंगे। कार्यपालक अभियंता कार्य आवंटन/LOA निर्गत करने से पूर्व मिलान कर लेंगे कि परिमाण विपत्र की राशि प्रशासनिक अनुमोदन की राशि के अनुज्ञेय सीमा के अन्दर है। यदि अनुज्ञेय सीमा से अधिक हो तो एकरारनामा के पूर्व पुनरीक्षित प्रशासनिक अनुमोदन प्राप्त कर लिया जाय।
 - कार्यादेश निर्गत करने से पहले संबंधित संवेदक से एकरारित अवधि के अन्दर कार्य समाप्त करने हेतु मासिक कार्य प्रोग्राम हस्ताक्षरित कराकर प्राप्त कर लेंगे जो की एकरारनामा का भाग होगा।

प्रमंडलीय लेखा पदाधिकारी
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल भागलपुर

Scanned with OKEN Scanner

कार्यपालक अभियंता का कार्यालय,
ग्रामीण कार्य विभाग, कार्य प्रमंडल, भागलपुर।

पत्रांक:- 1669
प्रेषक,

भागलपुर/दिनांक:- 24/09/25

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, भागलपुर।

सेवा में,

Pravin Kumar Prasuh,
Nayatola, Mirzapur, Nathnagar,
Madhusudanpur,
Dist-Bhagalpur-812001

विषय:- Performance Security, Additional Performance Guaranty मूल कागजात निविदा से समर्पित शपथ पत्र के अनुसार Machinery एवं Key Personal से संबंधित कागजात जमा करने के संबंध में।

प्रसंग:- अभियंता प्रमुख, ग्रामीण कार्य विभाग, पटना, विहार का पत्रांक:- मु0अ0(अ0उ0)- 4515-01-791 /2025 पार्ट-III 3534 (अनु0), पटना, दिनांक:-16.09.2025

महाराय,

उपर्युक्त विषयक के संबंध में सूचित करना है कि प्रसांगिक पत्र द्वारा निविदा आई0डी0:-143258, प्रखंड:-शाहकुण्ड एवं सुलतानगंज अंतर्गत पंकेज सं0:-RRSMP/25-26/Bhagalpur/03 (MMGSUY) से सड़क का निर्माण कार्य एवं सात साल के लिए रख-रखाव हेतु राशि रू0 3,44,78,555/- (तीन करोड़ चौवालीस लाख अठहत्तर हजार पाँच सौ पचपन) Below 5.60 % पर दिनांक:-15.09.2025 को संपन्न विभागीय निविदा समिति की बैठक की कार्यवाही में आपको चयनित की गयी है। आपको सूचित किया जाता है कि CMBD के Clause 53.3.1 एवं सह-पटित Clause 34.1 के अनुसार Performance Security @5% रू0 17,24,000/- एवं NIT की कंडिका -23 एवं प्रसांगिक पत्र की कंडिका-10 के अनुसार Additional Performance Guaranty @1.75% रू0 6,39,200/- की लागत है। आपके द्वारा Upload की गई निविदा में सभी कागजात की मूल प्रति, चरित्र प्रमाण-पत्र एवं अन्य कागजात के साथ-साथ ITB Clause 4.2 b (ii) के अनुसार निविदा में जमा किये गये Machinery एवं Key Personal से संबंधित आपके द्वारा Upload शपथ पत्र के अनुसार कागजात कार्यालय में तीन दिनों के अंदर समर्पित करना सुनिश्चित करे ताकि सत्यापन कराते हुए कार्यदेश निर्गत होने के पश्चात् ससमय एकरारनामा किया जा सके।




विश्वासभाजन



कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, भागलपुर।

प्रमंडलीय लेखा पदाधिकारी
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, भागलपुर



Scanned with OKEN Scanner



Scanned with OKEN Scanner