



INDIA NON JUDICIAL Government of Bihar

e-Stamp



Certificate No. : IN-BR-2500251844
 Certificate Issue Date : 31-Jan-2025 11:56 AM
 GRN No. : BHR20250101179243E
 Unique Doc Reference : EST-BR-1903-2500001730
 Party Name : RETNESH KUMAR SINGH
 Purchase by : RETNESH KUMAR SINGH
 Purpose : NA Article no (NA)
 Stamp Du. Paid (Rs.) : 1000 (One Thousand Only)
 Reg. Fee (Rs.) : 0 (Zero Only)
 LLR & P (Rs.) : 0 (Zero Only)
 Miscellaneous Fee (Rs.) : 0 (Zero Only)
 Discor S (Rs.) : 0 (Zero Only)
 Total Amount (Rs.) : 1000 (One Thousand Only)

Revised Agreement

Bihar Rural Road maintenance Policy 2018

Agreement - 48 MBP/2024-2025 work completion - 30/01/25

This agreement made on the 31 day of January between Executive Engineer, Rural Works Division, Works Division, Dalsinghsarai, Samastipur and **RATNESH KUMAR SINGH**, At-Khoksha Kalyan, Ps- Deshri, District-Vaishali (Reg No-1210361), whereas the Employer is desirous that the contractor execute the Work construction of improvement of Road from **MUSTAFAPUR SAKRA TO BAYA BARETHA MISROLIYA HIGH SCHOOL** (Name and identification number of Contract) (hereinafter Called "the works") and the employer has accepted the bid by the contractor for the execution and completion of such works and the remedying of any defect therein, at a Construction amount Rs. 2,75,66,480.00, Maintenance amount Rs. 30.00 and the total amount Rs. 34189210.00 (Three Crore forty one lakh eighty nine thousand two hundred ten rupees Only) (0.81% Below the Scheduled Rate.)

Stat: Authenticity of this Stamp certificate should be verified at <https://enibandhan.bihar.gov.in> or using enibandhan Mobile App.
 1. Any discrepancy in the details on this Certificate and as available on the website/Mobile App renders it invalid.
 2. The onus of checking the legitimacy is on the users of the certificate.
 3. In case of any discrepancy please inform the Competent Authority.

2 अनेर अथर

31/01/25

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
दालसिंगसराय

Issue of Notice to Proceed with the work
Executive Engineer

R.W.D. Works Div-Dalsinghsarai (Samastipur)

Letter no/ Date

To,

RATNESH KUMAR SINGH

At- Khoksha Kalyan, Ps- Deshri,
District- Vaishali.

Dear Sir,


Pursuant to your furnishing the requisite security as stipulate in ITB Clause 34.1 and signing of the contract dor, the Contruction of Improvement of **MUSTAFAPUR SAKRATO BAYA BARETHA MISROLIYA HIGH SCHOOL** (Name and identification number of Contract) (hereinafter Called "the works") and the employer has accepted the bid by the contractor for the execution and completion of such works and the remedying of any defects therein, at a Cosntruction amount Rs. 2,75,66,480.00, Maintenance amount Rs. 66,22,730.00 and the total amount Rs. 34189210.00 (Three Crore forty one lakh eighty nine thousand two hundred ten rupess Only) (0.81% Below the Scheduled Rate.)

Enclosers:-

Your's Faithfully,

1. Instruction

२-निर्देशपत्र


31.01.25
Executive Engineer
कार्यपालक अभियंता
R.W.D. Works Division, Dalsinghsarai
23/01/2025
31/01/25

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, दलसिंहसराय, समस्तीपुर

Email ID:- rwddalsinghsaray@gmail.com

पत्रांक 100 दिनांक 27/1/25

प्रेषक, कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, दलसिंहसराय

सेवा में,
अधीक्षक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल- समस्तीपुर

विषय- बिहार अनुरक्षण निती- 2018 योजनान्तर्गत 1 पथ का पुनरीक्षित परिमाण विपत्र (BOQ)
स्वीकृति के संबंध में।


महाशय,

उपर्युक्त विषय के संबंध में कहना है कि बिहार अनुरक्षण निती- 2018 योजनान्तर्गत पूर्व से प्रदत्त प्रशासनिक स्वीकृति के विरुद्ध पुरीक्षित तकनीकी स्वीकृति 1 पथ का परिमाण विपत्र (BOQ) तैयार कर स्वीकृति हेतु समर्पित की जाती है।

S.N o	Name of Road	Block	Length	Total BOQ Cost.
1	2	3	4	5
1	Mustafapur Sakra to Baya Baretha Misroliya High School	Bibhutipur	6.115	10.840


अनु०- यथोक्त।

विश्वासभाजन


27.01.25

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, दलसिंहसराय

B.O.C. Approved Rs 10,840,24=00 (Rupees
ten lakh eight four thousand merely
four) only from item no. (Dtd 6)


25/01/25
अधीक्षक ग्रामीण कार्य
ग्रामीण कार्य विभाग
कार्य अंचल, समस्तीपुर

MR-3054

BILL OF QUANTITIES (BOQ)

Name of Road :	MUSTAFAPUR SAKRA To BAYA BARETHA MISROLIYA HIGH SCHOOL				
Block :	Bibhutipur	District :	Samastipur		
Length :	6.115 km				
Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
SCHEDULE A					
1	<u>Granular Sub-base with Well Graded Material(Grade 2)</u> : Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density,	Cum	33.141	2,715.39	89989.48
2	<u>Water Bound Macadam with Stone Screening Gr-II</u> : Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.	Cum	24.249	5,515.46	133744.39
3	<u>Water Bound Macadam Gr III</u> : Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	Cum	63.874	5,398.98	344853.10
4	Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	Sqm	851.65	60.11	51192.68
5	Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 13.2 mm to 0.09 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509	Sqm	851.65	306.39	260937.04
6	Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydrilloc broom as per technical specification clause 503.	Sqm	851.65	20.67	17603.61
Total					898320.30
18 % GST					161697.65
1% LABOUR CESS					8983.20
Seigniorage Fee					15025.76
Total Construction Cost					1084026.92
Grand Total Cost (A)					1084026.92

21/01/25

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
बलसिंहसराय

31/01/25
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
बलसिंहसराय