

Particulars	Details of actual measurement			Contents of area
	No.	L.	B.	
Nhr-Maint. of Road from Rasulpur				
Nahar (PM Crst) Path to Rasulpur				
Agency - Sri Kant Tiwari				
Ag. No - 46/SB/D/2019-20				
Date of start - 18/10/2019				
Actual date of comp - 16/07/2020				
Details				
① Restoration of Rainads -				
3 X 3.40 X 1.40 X 0.30 =				4.28 m ³
4 X 4.10 X 1.30 X 0.30 =				6.396 m ³
5 X 4.60 X 1.30 X 0.30 =				8.97 m ³
4 X 4.50 X 1.35 X 0.30 =				7.39 m ³
				40.246 m ³
② Making up of Berms/shoulder -				
2 X 2 X 30 X 1.15 =				138 m ²
1 X 2 X 30 X 1.45 =				87 m ²
				225 m ²
③ Repair of puthways 75mm BM -				
1 X 3.75 X 0.5 =				1.875 m ³
2 X 1.60 X 0.5 =				1.60 m ³
				3.475 m ³

Continuation

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
4th Year ABSTRACT OF COST					
① Rectification of Paved					
Qty vide TMB P.No - (42)					
I.No ① 40-246m ² @ 378.32 =					15226.00
② Making up of Road shoulders					
Qty vide TMB P.No - (42)					
I.No ② 225m ² @ 57.35 =					12904.00
③ Repair of pot holes 75mm BM					
Qty vide TMB P.No - (42)					
I.No ③ 3.475m ³ @ 11930.10 =					41457.00
④ Patch repair of pot holes.					
20 mm premix carpet do -					

Qty vide TMB P.No - (43)					
I.No ④ 46.82m ² @ 320.65 =					15013.00
⑤ Patch repair over bituminous					
20 mm premix carpet do -					
Qty vide TMB P.No - (43)					
I.No ⑤ 46.56m ² @ 338.22 =					15748.00
⑥ Maint. of H.P.C.					
Qty vide TMB P.No - (43)					
I.No ⑥ 2. No @ 1109.67 =					2219.00
⑦ Maint. of Slab Curb wall					
Qty vide TMB P.No - (43)					
I.No ⑦ 1. No @ 2291.44 =					2291.00
⑧ Maint. of Road signs					
Qty vide TMB P.No - (43)					

