

कार्यपालक अभियन्ता का कार्यालय
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, गोपालगंज-2

पत्रांक 1804 अनु०

दिनांक 27/12/21

प्रेषक,

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, गोपालगंज-2

सेवा में,

अपर मुख्य कार्यपालक पदाधिकारी -सह-
सचिव,
ब्राडा,
बिहार, पटना।

विषय:-नाबार्ड शीर्ष अन्तर्गत अनुरक्षण मद में आवंटन उपलब्ध कराने के संबंध में।

महाशय,

उपर्युक्त विषयक योजनान्तर्गत कराये गये कार्य के भुगतान हेतु संलग्न मांग पत्र के अनुसार आवंटन उपलब्ध कराने की कृपा की जाए।

अनु०:- यथोक्त।

विश्वासभाजन


23.12.21

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, गोपालगंज-2

राज्य योजना (नाबार्ड) अर्थात् फार्म में पंचवर्षीय अनुसूचना अधिमाना प्रपत्र

क्र० कार्य प्रगति को नाम	योजना का नाम	एकरचना के अनुसार प्राथमिकता राशि वर्षवार					व्यय की राशि वर्षवार					प्रशासनिक स्वीकृति की राशि एवं प्रगत दिनांक सहित (लाख में)	पंचवर्षीय अनुसूचना की राशि सहित अनुमानित परिवर्धन बिना की राशि (लाख में)	अनुसूचना हेतु प्राथमिकता राशि का प्रकार / दिनांक	मूल निर्माण कार्य करने की राशि वर्षवार सहित (लाख में)	वर्तमान अधिमानित राशि					कुल अधिमानित राशि (लाख में)				
		प्रथम वर्ष राशि (लाख में)	द्वितीय वर्ष राशि (लाख में)	तृतीय वर्ष राशि (लाख में)	चतुर्थ वर्ष राशि (लाख में)	पंचम वर्ष राशि (लाख में)	कुल राशि (लाख में)	प्रथम वर्ष राशि (लाख में)	द्वितीय वर्ष राशि (लाख में)	तृतीय वर्ष राशि (लाख में)	चतुर्थ वर्ष राशि (लाख में)					पंचम वर्ष राशि (लाख में)	कुल राशि (लाख में)								
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26
1	Gopalganj-2	Hamidpur Matiyat poharpur road to mahir toa hote hne karmashila	0.64000	0.80000	0.94000	1.16000	1.31000	4.85000	0	0	0	0	0	0	126.28 / 8712/17.10.2017	123.90377	8712/17.10.2017	10.11.2019	0	0	0	0	1.30626	1.30626	1.30626

- कार्य विनिश्चयों के अनुसार पूर्ण कर दिया गया है।
- पत्र में MOMU/POM/IE से संबंधित कोई सुधार प्रतिवेदन लंबित नहीं है।
- अनुमोदित परिमाण विपत्र की कुल राशि प्राथमिकता स्वीकृति की राशि से 20% अधिकतम सीमा के भीतर है अनुमोदित परिमाण के मर्तो की मात्रा का विस्तार किया गया है।
- अनुसूचना - प्राथमिकता स्वीकृति का पत्र अनुमोदित परिमाण विपत्र एवं एकरचना का अधिमानित प्रति।

प्रदेशीय क्षेत्र अधिकारी
ग्रामीण कार्य विभाग, कार्य प्रवर्तन
गोपालगंज-2

कार्यवाहक अधिकारी
ग्रामीण कार्य विभाग
कार्य प्रवर्तन गोपालगंज-2
25.12.24

To Haridpur Matiyari road to Ahir Kola late line
Karanshila Pak path.

and there after undertake routine maintenance for five years; and the employer has accepted the bid by the contractor for the execution and completion of such works and the remedying of any defects and routine maintenance therein at a total cost Rs. 1,23,90,271.54 (One crore Twenty three lac ninety thousand two hundred & seventy one) only.

Construction cost Rs. 1,19,68,067.54 (Rs. one crore nineteen lac three thousand & sixty eight) only. Five year maintenance cost Rs. 4,37,223.54 (Rs. Four lac eighty seven thousand two hundred & three) only.

NOW THIS AGREEMENT WITNESSETH as follows :

1. In this agreement, words and expression shall have the same meanings as are respectively assigned to them in the conditions of contract hereinafter referred to and they shall be deemed to form and be read and construct as part of this agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the works and remedy any defects therein in conformity in all aspects with the provisions of the contract and undertaking routine maintenance for five years.
3. The Employer hereby covenants to pay the Contractor in consideration of the Execution and completion of the work and the remedying the defects wherein and undertaking routine maintenance for five years, the contract Price or such other sum as become payable under the provisions of the contract at the times and in the manner prescribed by the contract.
4. The following documents shall be deemed to form and be read and construct as part of this agreement, viz;
 - (i) Letter of Acceptance
 - (ii) Notice to proceed with the works

M/s. A.D. Construction
Part 808
Partner

Handwritten signature and stamp of the contractor.

Executive Engineer
H.M.D. W.D.
Bhadrachal-2
Handwritten signature and stamp of the Executive Engineer.

21/5/16

- (iii) Contractor's Bid
- (iv) Contract Data,
- (v) Condition of Contract : General and Special
- (vi) Additional Condition
- (vii) Drawings
- (viii) Bill of Quantities and
- (ix) Any other documents listed in the contract Data as forming part of the Contract

In witnessed whereof the parties thereto have caused this Agreement to be executed the day and year first before written.

The Common Seal of _____
was hereunto affixed in the presence of:

Signed, Sealed and Delivered by the said _____

In the presence of :

Binding Signature of Employer _____

Binding Signature of Contractor _____

M/s. A.D. Construction
Anil Das
Partner

Smriti
20.12.07
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल
बलरामपुर (गोपालगंज)

01.06.18
Executive Engineer
R.W.D. W.D
Gopalganj - 2
Sd/-
01.06.18

MUKHYA MANTRI GRAM SADAK YOJANA (MABARD)
(Ministry of Rural Development, Govt. of India)
BILL OF QUANTITIES (BOQ) - CONSTRUCTION

Name of Road :
Length of Road :
L/TH No. :

Hemidpur Matiyari Paharpur Road to Ahir Tola Hata Husekaramshila
2.20 Km
502

Package No. : BR-34H-501
District : Gopalganj
Block : Bakhunthpur

Sl. No.	BOQ Item No.	Description of Items	Unit	Quantity	Rate	Amount
1	1.18	Reference Pillar				
2	2.1	Reference Pillar as per Standard Data Book @ 1 per Km Clearing Grass and Removal of Rubbish Clearing grass and removal of rubbish up to a distance of 30 m outside the periphery of the area as per Technical Specification Clause 201. By Manual Means	Ha	9.00	1,818.86	16370.00
3	2.5 (i)	Dismantling of Structures Dismantling of existing structures like culverts, bridges, retaining walls and other structures comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and load of 1000 m as per Technical Specification Clause 202. By Manual Means	Ha	0.88	11,700.59	10297.00
4	2.6	(B) Cement Concrete Dismantling Brick/Tile Work Dismantling of existing structures like culverts, bridges, retaining walls and other structures comprising of brick masonry, including disposal of unserviceable material and stacking the serviceable material with all lifts and load of 1000 m as per Technical Specification Clause 202.	Cum	3.02	416.41	1259.00
5	2.11	Cement mortar Removing all types of Hume pipe and stacking. Removing all types of Hume pipe and stacking withing a load of 1000 m including Earthwork and Dismantling of Masonry Works as per Technical Specification Clause 202.	Cum	109.40	299.40	32753.00
6	3.3	(A) up to 600 mm dia. Hume Pipe. (B) above 600 mm to 900 mm dia. Hume Pipe. Construction of Embankment with Material Obtained from Roadway Cutting Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 200.1 and 200.2 as per Technical Specification Clause 201.5	RM RM Cum	5.00 15.00 1446.19	151.87 205.37 43.03	759.00 3080.00 62224.00
7	3.4	Construction of Embankment with Material Obtained from Fills Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Table 200.1 and 200.2 with a load upto 1000 m as per Technical specification 201.5	Cum	1373.62	115.89	159183.00
8	3.5	Excavation for roadway in soil using manual means for carrying of cut earth to embankment site with a lift up to 1.5 m and load up to 50 m as per technical specification.	Cum	134.76	66.12	8927.00
9	3.5(i)	Excavation in cutting soil, by manual means with load upto 50 m Excavation for road work in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes in accordance with requirements of lines, grades and cross sections and transporting to the embankment location with a lift upto 1.5 m and load upto 1000 m as per technical specification clause 202.3	Cum	1232.44	109.49	135190.00
10	3.14	Construction of Embankment subgrade & earthen shoulders with Material Obtained from Borrow Fills Construction of subgrade and earthen shoulders with approved material (granular material having CBR more than 7) obtained from borrow pits with all lifts and loads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 200.2 as per Technical Specification Clause 202.1.	Cum	2450.41	131.44	321779.00

M/s. A.D. Construction
Part B & C
Partner

सहायक अभियंता
महामा नगर विभाग
काठमाडौं

Executive Engineer
R.W.D. WD
Gopalganj - 2

Sl. No.	Rev. No.	Description of Item	Unit	Quantity	Rate	Amount
12	11/2	Removal of Old Road Excavating, leveling and compacting original ground supporting embankment to suitable pavement of last layer of embankment marked at a depth of 150 mm below water at GWC and then compacted by rolling at 10 to achieve minimum dry density as given in Table 1001 and 1002 for embankment construction as per Technical Specification Clause 1001.	Cum	205.78	20.15	4145.00
13	11/2	Construction of uniform surface drains of average cross section 0.60 m wide and 0.30 m deep using grading track and dimensions specified in the work as embankment with a bit grade for 10% of 10 m (average haul 10 m) as per Technical Specification Clause 1002 (By Mechanical Means).	Metre			0.00
14	11/2	Gravel Sub Base with Well Graded Material (Table 1002) Construction of gravel/subgrade base by providing well graded material spreading in uniform layer with motor grader on prepared surface using 30 ton roller with three wheel 80 kN roller at GWC and compacting with three wheel 80 kN roller to achieve the desired density, conforming to per Technical Specification Clause 1002 (By Mechanical Means). (After Grading if Material from will be provided by Material obtained from of Dewatering of Rock (Waste) 10% of the total dewatered Quantity (Waste) (including 10% for Labour for Spreading Laying Rocks Adding Sand Quantity 10% of Machine is given for the Quantity to be used as GWC) 10% Compacted base. (After Grading if Material) (Speed Breaker 1 No.)	Cum	1165.12	20.15	23464.00
		(After Grading if Material) (Speed Breaker 1 No.)	Cum			0.00
		(After Grading if Material) (Speed Breaker 1 No.)	Cum			0.00
15	11/2	100% Grading Using Stone Screening Type A 1.5 mm for Chd Providing laying spreading and compacting three aggregate of specified base to water bound material specifications including spreading in uniform thickness 100% grading rolling with three wheel 80 kN roller at GWC and compacting with three wheel 80 kN roller to achieve the desired density, conforming to per Technical Specification Clause 1002 (A) By Machine Means.	Cum	611.11	42.60	25833.00
16	11/2	Prime Coat Providing and applying prime coat with bitumen emulsion (50-10) on prepared surface of granular base including clearing of road surface and spreading prime at the rate of 0.25 kg/m ² using mechanical means as per Technical Specification Clause 1002 (Prime Coat).	Sqm	6215.61	42.10	26164.00
17	11/2	Surface Dressing using Bituminous Binder With Waste Plastic using modified mechanical roller (Second Coat) Nominal aggregate size 1.5 mm Providing and laying (first coat) surface dressing as wearing course consisting of a layer of bituminous binder laid on the prepared surface followed by a cover of crushed stone aggregate of specified size and rolling with three wheel 80 kN roller including clearing the road surface as per technical specification clause 1002 (Second Coat - Nominal chipping size 1.5 mm).	Sqm	6215.61	56.25	34950.00
18	11/2	Surface Dressing using Bituminous Binder With Waste Plastic using modified mechanical roller (Second Coat) Nominal aggregate size 1.5 mm Providing and laying (second coat) surface dressing as wearing course consisting of a layer of bituminous binder laid on the prepared surface followed by a cover of crushed stone aggregate of specified size and rolling with three wheel 80 kN roller including clearing the road surface as per technical specification clause 1002 (Second Coat - Nominal chipping size 1.5 mm).	Sqm	6215.61	74.00	46017.00
19	11/2	CC Pavement Construction of C/C Pavement Compacted Concrete Pavement (RCCP) with coarse and fine aggregate conforming to IS 884 the size of coarse aggregate not exceeding 20 mm with minimum aggregate cement ratio of 1:1 and with minimum cement content of 150 kg per cum aggregate gradation to be as per Table 1002 after bleeding, using in concrete mixer at optimum moisture content incorporating in situ laying with wheel barrows or steel pans or with mechanical pans compacting with 80 kN smooth wheel barrow vibratory roller to achieve the designed flexural strength finishing as per drawings and Technical Specification Clause 1002 under.	Cum	215.61	7651.27	164045.00

M/s. A.D. Construction

And po S.

महापौर अतिथि

Executive Engineer
A.W.R. 100
10/10/10

Sl. No.	SOR Item No	Description of Items	Unit	Quantity	Rate	Amount
19	10.1(i)	Printing New Letters and Figures of any Shade Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701. (Hindi (Matras commas and the like not to be measured and paid for. Half letters shall be counted as half only)	Per cm height per letter	2420.00	0.76	1842.00
20	10.2 (A-3)	Cautionary, mandatory, Informatory, direction and place identification signs Providing and fixing of retro-reflectorised cautionary, mandatory and Informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 1.5 mm thick supported on RCC Post 100 mm x 100 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing Clause 1701 (600 mm circular)	Each	8.00	4156.52	33252.00
21	10.16	Providing and fixing of typical MMSY Informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	Each	4.00	10353.91	41416.00
22	RCD	Road Marking with Hot Applied Thermoplastic Compound with Reflectors/Glass Beads on Bituminous Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectors/glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes.	Sqm	325.00	782.81	254414.00
23	10.1	Kilometer Stone Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703.				
	(i)	Ordinary Kilometer Stone (Precast)	Each	3.00	2415.65	7247.00
	(ii)	200 m stone (precast)	Each	9.00	622.98	5607.00
24	10.11	Boundary Pillars Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC:25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	Each	22.00	470.12	10343.00
25	11.1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Up to 3.0 m Below GL.	Cum	278.02	234.01	65060.00
26	11.4 (i)	Plain Cement Concrete M10 (1:3:6 nominal mix) in levelling course below open foundation of Head walls as per drawings & Technical Specification Clause 1109	Cum	27.07	6126.10	165808.00
27	11.4 (ii)	Plain Cement Concrete M15 (1:3:6 nominal mix) in levelling course below open foundation of Head walls as per drawings & Technical Specification Clause 1109	Cum	80.25	5846.60	469181.00
28	12.5(i)	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 801, 805, 806, 807, 1202 and 1204.P.C.C grade M 15, Nominal mix (1:2.5:5)	Cum	99.50	6220.46	618950.00
29	12.5(ii)	M/S. A.D. Construction concrete in substructure complete as per drawings				

Amudha
Partner

सहायक अभियंता
सामान्य जनक विभाग
पटना-22

Executive Engineer
R.W.D. W.D
Sahibganj - 2
21.02.18

No.	Rev. No.	Description of Items	Unit	Quantity	Rate	Amount
31	2.5 (7)	Providing and laying reinforced cement concrete pipe NPS for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets Clause 1100, 1000 mm Dia	Rm	7.80	3740.87	28054.00
32	2.5 (8)	Providing and laying reinforced cement concrete pipe NPS of 1000mm dia for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets Clause 1100	Rm	18.00	7917.74	112766.00
33	13.1	Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 803, 1203.4 and 1203.5				
33	13.1	R.C.C.M 25	Cum	9.36	7,711.81	72183.00
34	13.2	Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 803, 1203.4 and 1203.5 R.C.C grade M 20 For nominal mix 1:2:4	Cum	0.94	4,983.34	634.00
34	13.2	Supplying, fitting and placing HYSD bar reinforcement in superstructure complete as per drawing and technical specifications Clauses 1001, 1010 and 1202	Tonne	2.28	5147.12	117416.00
35	4.1	Construction of granular sub-base by providing well graded material using stone aggregates, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification clause 401 -				
35	4.1	(ii) For Grading III Material	Cum			0.00
36	4.1	Construction of un-reinforced, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1201.2.2 M20 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, dowel bars 25mm dia and 500mm long @25cm c/c or as per design, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batches using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovel, taken, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14 days, using curing compound (where specified) and water finishing to lines and grade as per drawing and Technical Specification Clause 1501	Cum			0.00
37	12.9	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7	Rm	28.01	99.61	2790.00
38	12.10	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 (ii) Sandy Material	Cum	49.44	567.65	28067.00
39	12.11	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and providing over the existing media behind abutment, return	Cum	30.25	2947.87	89161.00
40	13.16(ii)	Providing and fixing in position 20 mm thick precast joint filler in expansion joint for fixed ends of simply supported spans, covered with sealant complete as per drawing and technical specifications	Cum	19.50	289.46	5643.00
41	14.1	Providing and laying counter apron for cast precast concrete structure of minimum size and weight as per Table 1300.1, no fragment weighing less than 30 kg, laid on concrete base and technical specifications	Cum	12.91	3169.56	40911.00
42	14.3	Providing and laying pitching on slopes laid over prepared filter media as per drawing and technical specifications Clause 1302	Cum	13.49	3169.56	42755.00

W/s. A.D. Construction
 Anil D. S.
 Partner

राज्यक अधिकारी
 राजपूत अड्डा
 10/01/2019

Executive Engineer
 R.W.D. W.D
 Sub Division - 2
 10.02.19

S. No.	Description of Items	Unit	Quantity	Rate	Amount
1	1st Year Maintenance Cost			80952.60	80952.60
2	2nd Year Maintenance Cost			94456.17	94456.17
3	3rd Year Maintenance Cost			116261.46	116261.46
4	4th Year Maintenance Cost			131681.57	131681.57
Total Cost					12390177.50
				Total Cost (in Lacs)	123.9

B.O. & Approved for Rs 12590378.20 (One crore Twenty Three Lacs
Ninety Thousand Three Hundred & Seventy Eight / Rupees only
for Serial no 1 to 48

[Signature]
19.12.17

M/s. A.D. Construction

[Signature]
Partner

[Signature]
28.12.17

सहायक अभियंता
सामान्य कार्य विभाग
राज्य नगर निगम
(मुंबई महानगर)

[Signature]
Executive Engineer
R.W.D. W.D.
Dopalganj - 2
61.06.18

बिहार सरकार
ग्रामीण कार्य विभाग

पत्रांक - मु० अ०-४ (मु०)-नाबार्ड-०३-३९/२०१७

8712

1 पटना, दिनांक-12/10/17

प्रेषक,

राजय कुमार, 110020000

अपर सचिव।

आचार्यक विभाग सहायकार द्वारा
अनुमोदित रूप से परामर्शित

सेवा में,

महासेवाकार (लेखा एवं हकदारी)

बिहार, पटना।

विषय - योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परियोजना-103-ग्राम विकास-राज्य योजना-0105-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना)-उपशीर्ष के अन्तर्गत बिहार राज्य के विभिन्न जिलों में (परिशिष्ट-1 के रूप में संलग्न सूची के अनुरूप) कुल 50 पथ निर्माण योजनाओं पर पथवार प्रशासनिक स्वीकृति प्रदान करने के संबंध में।

महाराज,

निदेशानुसार योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परियोजना-103-ग्राम विकास-राज्य योजना - उप शीर्ष-0105 - ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना) - उप शीर्ष के अन्तर्गत बिहार राज्य के विभिन्न जिलों में (परिशिष्ट - 1 के रूप में संलग्न सूची के अनुरूप) कुल 50 पथ निर्माण योजनाओं जिसकी लम्बाई 75.680 कि०मी० एवं राशि रु० 46.7233 करोड़ (छियासिस करोड़ बहत्तर लाख तैंतीस हजार रु० मात्र) है-हेतु पथवार प्रशासनिक स्वीकृति प्रदान की जाती है।

परिशिष्ट-1

नाबार्ड संपोषित योजना अन्तर्गत वित्तीय वर्ष 2017-18 के लिए प्रशासनिक अनुमोदित योजनाओं की सूची :-										
योजनाओं की सूची										
Chief Engineer -3										
Sl. No.	District	Works Division	Block	MNGSY CNCPL No.	Name of Road	Length (K.M)	Constructio n Cost	Maintenan ce Cost	TA Amount (In Lacs)	Amount Lac/K.M
1	2	3	4	5	6	7	8	9	10	11
1	Muzaffarpur	Muzaffarpur East2	Gaighat	S065	Bunni Chowk PMGSY Road To Dhala Bhandh NH-57	3.290	191.13	11.66	202.79	58.09
2	Muzaffarpur	Muzaffarpur East-2	Minspur	S-012	Tengrari Murgiya Chowk To Jagdar Nath Pakri PMGSY Path	1.405	83.55	4.29	87.84	59.47
3	Vaishali	Mahnar	Sahdai Bujurg	S056	PMGSY Sone Lal Thakur Ke Ghar To Braham Asthan Hote Huye Ram Babu Rai Ke Ghar Tak (Din Dyalpur)	0.821	58.213	1.920	60.133	70.90
4	Vaishali	Mahnar	Desri	S028	In Taiyabpur Village Near House of Raghunath Mahto To Khadagpur Dev Ali Rai House	0.555	40.788	1.301	42.089	73.49
5	Vaishali	Mahnar	Jandaha	S097	Swasth Upkendra Loma To Baiju Usar Ke Ghar Tak	1.125	62.280	4.183	66.463	55.36
6	Vaishali	Mahnar	Desri	S06	House of Binda Rai in Drampur Ram Rai Village To House of Visendra Rai	0.510	37.835	1.197	39.032	74.19
7	Vaishali	Mahnar	Bidupur	S019	Chechar Mandir to Gopalpur Siman Mahadalit Tola	1.000	80.63	2.47	83.10	80.63

8	Vaishali	Mahar	Bidpur	8020	Hajipur Mahnar Road ke Pakshi Bajar to Bhainpur Ghat	1.300	90.00	2.80	93.80	75.00
9	Vaishali	Hajipur	Lalganj	8019	Lalganj Hajipur Road ke Namdh Pipal tree to Kartaha gram sinha tak	1.410	109.58	3.365	112.94	77.71
10	Vaishali	Hajipur	Patedhi Belsar	8020	Nagwan Mishrauliya Bibiapur (RWD) Road to Mishrauliya Afaal Khas	1.100	68.00	4.740	72.74	61.82
11	Vaishali	Hajipur	Lalganj	8020	Lalganj Hajipur Road to Dhamahi gram Usay Singh House to Dhamahi Vishun Kunar ke Borina tak	2.100	137.694	8.076	135.77	60.81
12	Vaishali	Hajipur	Vaishali	8048	Sain Vaishali Road to Bhagwanpur Pandit Tola	1.775	102.141	5.699	107.84	57.54
13	Vaishali	Hajipur	Patedhi Belsar	808	Majhiya Kameji Road to Kameji North Tola	1.010	74.715	2.365	77.08	73.98
14	Vaishali	Hajipur	Bhagwanpur	807	PMGSY Road Ashoi hat to Asai Sahni Tola	2.500	149.156	10.054	159.21	50.66
15	Vaishali	Hajipur	Bhagwanpur	8026	NH-77 Ghaghra Nadi ke North Akhaurpur to Vishunpur Indhi Chintaman tak	1.796	94.769	8.591	103.36	53.06
16	Vaishali	Hajipur	Vaishali	8046	Mansurpur Harpur Bazar Road to Chakramdas East Tola	2.024	107.143	8.498	115.64	52.94
17	Vaishali	Hajipur	Hajipur	8040	Dharanpur Phulhara Road to Kauri Buzurg	1.000	73.834	2.336	76.17	73.83
18	Gopalganj	Gopalganj-2	Barauli	807	Rupn Chhap Paika Godam To Gathiya Toli Musahar Toli Tak Path	1.150	49.300	3.44	53.64	43.78
19	Gopalganj	Gopalganj-2	Balkusapur	8072	Usari Bazar PMGSY To Maulana Tola Hote Hua Saran Bandh	0.900	33.97	1.56	35.53	37.74
20	Gopalganj	Gopalganj-2	Sidhuwalla	8019	Reo Pitch Sarak Se To Mudiy Tola Hote Hua Yadav Tola Tak	1.500	66.86	2.87	69.73	44.57
21	Gopalganj	Gopalganj-2	Manjha	8012	Koini Bhasahi Pitch Path Se Shyama Nagar	0.750	40.32	1.32	41.64	53.76
22	East Champaran	Chakia	Chakia	801	PMGSY Road Panchayat Bhawan Bangari to Madhya Vidyalaya Bangari Tola Via Pathak Tola	2.045	112.74	5.82	118.56	55.13
23	East Champaran	Chakia	Kalyanpur	8031	Kandhya Chowk to Sulahiya via Lariya	1.804	93.73	6.93	100.66	51.96
24	East Champaran	Chakia	Mehai	8036	Bhainpur Bazar to Bahia	1.405	85.32	0.90	86.22	60.73

25	East Champaran	Chakia	Kalyanpur	S023	Bahura World Bank to Kathariya Purdev Pandey ke Ghar Via Bhusaulwa	3.004	158.86	10.21	169.07	52.88
26	East Champaran	Chakia	Kesariya	S010	Rampur Kolar to Bairiya	2.579	140.91	5.19	146.10	54.64
27	Siwan	Maharajganj	Bhagwanpur Hat	S023	Banpura to Baghi Tola via Bishnu Dham	1.850	117.00	5.48	122.48	63.25
28	Siwan	Maharajganj	Basantpur	S02	L029 to Barhoga Biri Ahir tola	1.100	69.42	3.48	72.90	63.11
29	Siwan	Maharajganj	Bhagwanpur Hat	S01	Nathua More To Lahuri Kauria	2.500	122.81	8.37	131.18	49.12
30	Siwan	Maharajganj	Maharajganj	S012	Gularbagga To Sonbarsa Mauje	2.400	150.32	8.69	159.00	62.63
31	Siwan	Maharajganj	Goriakothi	S012	Sadipur To Jarno Mirzapur Path Tak	1.250	76.06	4.56	80.62	60.85
32	Siwan	Maharajganj	Daraundha	S013	Rama Chapra Bindu Singh ka Ghar To Bhusi Ki Ore	1.700	106.484	5.971	112.46	62.64
33	Siwan	Maharajganj	Lakrinabiganj	S09	S016 To Imadpur	2.050	126.474	7.645	134.12	61.69
34	East Champaran	Chakia	Kesariya	S012	Bairiya To Tajpur Rampur Koral	0.832	43.88	2.15	46.027	52.74
35	Gopalganj	Gopalganj-1	Gopalganj	S024	Pee Bhitbherwa Near Ramjee Manjhi House to Pachim Tola	1.200	53.31	2.80	56.11	44.43
36	Gopalganj	Gopalganj-1	Gopalganj	S043	Red Road to Derwa Tola	1.200	55.50	3.24	58.74	46.25
37	Darbhanga	Benipatti	Benipatti	S031	Mohammad pur Chowk to Mohammad Pur Paschim	1.924	130.26	8.59	138.85	67.70
38	Darbhanga	Benipatti	Bisfi	S040	Chandrawana to Bhopondaul Paschim Tola	1.955	135.51	8.59	144.10	69.31
39	Darbhanga	Benipatti	Hartakhi	S035	Narhania (Harney) to East Tol	1.031	70.84	2.96	73.80	68.71
40	Darbhanga	Benipatti	Madhwapur	S06	Nawntola to Parsalla Dalit Tola	1.647	114.23	8.60	122.83	69.36
41	Darbhanga	Benipatti	Madhwapur	S025	Patar Tola to Taraiya Paschim	2.175	143.79	8.37	152.16	66.11
42	Gopalganj	Gopalganj-2	Sidhawnia	S041	Jhahawa Salehput PMGSY Sarak Ramkrishna Sharma Ke Ghar ke Pass se to Rampurwa Kalwar Tola Bandh Tola	2.500	109.66	5.28	114.94	43.86
43	Gopalganj	Gopalganj-2	Barauli	S025	Madhopur PMGSY Ambika Chaudhari to Giri Tola Harizan Tola Tak Path	2.200	97.01	3.57	100.58	44.10
44	Gopalganj	Gopalganj-2	Baikunthpur	S09	Hamidpur Matiyari Paharpur Road to Ahir Tola Hote Hue Karamshila	2.200	121.19	5.09	126.28	55.09
45	Madhubani	Benipatti	Benipatti	S018	Reo Path Shahpur To Rampur Tola	0.570	40.105	2.249	42.354	70.36

46	Madhubani	Benipatti	Bisti	S072	Bisti To Ghat Bhatra	0.884	62.16	3.93	66.09	70.31
47	Madhubani	Benipatti	Harlakhi	S06	Gangaur To Pansalwa	0.564	39.02	1.61	40.63	69.18
48	Madhubani	Jainagar	Basopatti	S080	Khauna PMGSY Road To Khauna Pachhiyari Patwan Tol Khauna	0.600	38.08	0.007	38.087	63.47
49	Siwan	Maharjganj	Maharjganj	S013	Ratan Baba to Sarngpur	0.600	32.00	2.010	34.009	53.33
50	Gopalganj	Gopalganj-1	Gopalganj	S07	Hem Bardaha Khairwa MMGSY Road to Dumaria Maule Tola	1.000	46.12	2.70	48.82	46.12
Total						75.648	443.459	237.74	4672.33	

2. इस योजना को दो वित्तीय वर्ष 2017-18 एवं 2018-19 में पूरा किये जाने का लक्ष्य है।
3. कार्यपालक अभियंता, प्राणीय कार्य विभाग, संबंधित कार्य प्रबंधन, योजना की विस्तृत कार्य योजना तैयार करने तथा उसके अनुरूप कार्यों को समयबद्ध ढंग से पूर्ण करना सुनिश्चित करने।
4. कार्यपालक अभियंता, संबंधित कार्य प्रबंधन सुनिश्चित करने कि स्वीकृत पथ किसी अन्य योजना के अन्तर्गत सम्मिलित नहीं है।
5. कार्यपालक अभियंता, संबंधित कार्य प्रबंधन, योजना के कार्य सम्पादन हेतु निकासी एवं व्ययन पदाधिकारी होने।
6. कार्य ई-निविदा के माध्यम से Standard Bidding Document के आधार पर कराया जायेगा।
7. कार्यों की गुणवत्ता सुनिश्चित करने की जिम्मेवारी संबंधित कार्यपालक अभियंता की होगी। किये गये कार्यों का गुणवत्ता गुणवत्ता के जीवफल के गुण-दोष के आधार पर किया जायेगा।
8. योजना के क्रियान्वयन से पूर्व इस पर सहाय पदाधिकारी से प्राथमिक स्वीकृति प्राप्त कर ली जायेगी। प्राथमिक स्वीकृति के समय सभी स्थान प्राधिकार IRC SP-72 वर्ष 2015 एवं IRC SP-43 वर्ष 2014 के तकनीकी प्रावधानों का अक्षरशः अनुपालन सुनिश्चित करेंगे।
9. इस योजना का व्यय योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर वृत्तीय परियोजना-103-ग्राम विकास-राज्य योजना-0106-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संचालित योजना)-उपशीर्ष जिसका विषय कोड 37-4515001030105 एवं स्कीम कोड-6369 के अन्तर्गत वित्तीय वर्ष 2017-18 में उपबंधित राशि से विकसनीय होगा।
10. योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर वृत्तीय परियोजना-103-ग्राम विकास-राज्य योजना-0106-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संचालित योजना)-उपशीर्ष के अन्तर्गत वित्तीय वर्ष 2017-18 में 454.31 लाख रुपये का बजट उपबंध स्वीकृत है।
11. कार्यपालक अभियंता, प्राणीय कार्य विभाग, संबंधित कार्य प्रबंधन, द्वारा योजना का भौतिक एवं वित्तीय प्रगति प्रतिवेदन प्रत्येक माह के 10 तारीख तक निश्चित रूप से कमरा संबंधित अधीक्षण अभियंता एवं संबंधित मुख्य अभियंता, पटना के माध्यम से विभाग को उपलब्ध कराया जायेगा।
12. इन योजनाओं का निर्माण नाबार्ड के तहत कराये जाने के प्रस्ताव पर मा0 मुख्यमंत्री महोदय, बिहार सरकार का अनुमोदन प्राप्त है। ये 50 पन्ना Brics New development Bank (NDB) के वित्त पोषण के लिए पूर्व में निहित मुख्यमंत्री ग्राम संपर्क योजना के 856 पन्नों की सूची में शामिल है।
13. इन पथवार योजनाओं के प्रशासनिक स्वीकृति के प्रस्ताव पर संयिका सं0- मु0 अ0-4 (गु0) नाबार्ड-03-39/2017 को पृ0 सं0-37/टि0 पर दिनांक 23.09.17 को अनुमोदन प्राप्त है।
14. बिहार कोषागार संहिता में निहित प्रावधानों के आलोक में बजट प्रावधान के अंतर्गत ही राशि की निकासी की जाय।
15. वित्त विभाग के संकल्प संख्या-4-45/04-301 जि (2) दिनांक 31.01.1995 एवं वित्त विभाग के पत्रांक स्वीम (0)-11-2005-6090 वि (2) दिनांक 15.09.05 एवं 295 दिनांक 24.03.15 के आलोक में तथा वित्त विभाग के संकल्प सं0 90 दिनांक 03.01.2008 में निहित विवेचों का अक्षरशः पालन किया जाय तथा बिहार वित्त निगमावली को सुसंगत प्रावधानों के आलोक में योजना में उपबंधित राशि की उपलब्धता के आधार पर व्यय की जाय। यह आदेश आंतरिक वित्तीय सहायकार की सहमति प्राप्त कर निर्गत किया जा रहा है। आंतरिक वित्तीय सहायकार की सहमति संयिका सं0- मु0 अ0-4 (गु0) नाबार्ड-03-39/2017 के पृष्ठ संख्या- /टि0 पर दिनांक- को प्राप्त है।
16. यह राशि उसी मद में खर्च की जायेगी, जिसके लिए पुनर्विधियोजित की गयी है, अन्य में नहीं।
17. योजना के लिए संबंधित कार्यपालक अभियंता से विस्तृत कार्य योजना मांगी जायेगी एवं प्रावधानों की विशिष्टताओं के अनुसार निर्धारित समय सीमा के अंदर कार्य पूर्ण करना सुनिश्चित किया जाय।

18. योजना के कार्यान्वयन के कम में इनका निर्धारित निरीक्षण (नियमित अंतराल पर) अनिवार्य रूप से किया जाय तथा प्रतिवेदन अभिलेखबद्ध किया जाय।

19. वित्त विभाग के पत्रांक-770, दिनांक 20.09.11 के द्वारा सूचित किया गया है कि नाबार्ड से RADF के अन्तर्गत नई परियोजनाओं की प्रशासनिक अनुमोदन प्राप्त करने के उपरान्त ही स्वीकृति हेतु नाबार्ड को भेजी जाये।

विरवासाधन

(संजय कुमार)

अपर सचिव

ज्ञापक- मु0 अ0-4 (मु0)-नाबार्ड-03-39/2017 8712 /पटना, दिनांक-17/10/17
प्रतिलिपि- सभी संबंधित कोषागार पदाधिकारी, जिल्ला कोषागार/उप कोषागार को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित।

अपर सचिव

ज्ञापक- मु0 अ0-4 (मु0)-नाबार्ड-03-39/2017 8712 /पटना, दिनांक-17/10/17
प्रतिलिपि- माननीय मंत्री के आप्त सचिव, ग्रामीण कार्य विभाग/प्रधान सचिव, योजना एवं विकास विभाग/वित्त विभाग (आय-व्यय शाखा)/आंतरिक वित्तीय सलाहकार, ग्रामीण कार्य विभाग/मंत्रिमंडल सचिवालय एवं समन्वय विभाग/कार्मिक एवं प्रशासनिक सुधार विभाग, सभी संबंधित प्रमण्डलीय आयुक्त/सभी संबंधित जिला पदाधिकारी/सभी संबंधित उप विकास आयुक्त/अभियंता प्रमुख ग्रा0 का0 वि0, बिहार, पटना/सभी संबंधित मुख्य अभियंता, पटना, ग्रामीण कार्य विभाग/मु0 अ0-4 (मुख्यालय), ग्रा0 का0 वि0/सभी संबंधित अपीकरण अभियंता, ग्रा0 का0 वि0, कार्य अंचल/सभी संबंधित कार्यपालक अभियंता, ग्रा0 का0 वि0 कार्य प्रमंडल/मुख्य महाप्रबंधक नाबार्ड, बिहार क्षेत्रीय कार्यालय, (भीर्या कम्पलेक्स, पौंचवीं मंजिल) डाक बंगला रोड, पटना को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित। आई0टी0 नोटल, ग्रामीण कार्य विभाग को विभाग के वेबसाईट पर अपलोड करने हेतु प्रेषित।

अपर सचिव