



बिहार BIHAR

6238 1000 सुमान सौरभ वसु. रीमडगन 61कु/रु  
16.10.24 मंडकुईया बरौली भागा बरौली म.र.रु. 51194  
हजारी

### AGREEMENT

Work has been allotted by S. E. , R.W.D. Works Circle, Siwan vide letter no. 824, dt. 24.10.2024

Below 24.57% on BOQ Rate

PAN- GNMPS5332C1Z6  
Reg.-2230571 Valid upto  
20.10.2028  
GST No- 10GNMPS5332C1Z6

1. Agreement No.-10/S.B.D/2024-25
2. Estimated Cost Rs. 59,24,752.00 (Fifty Nine lakh Twenty Four thousand Seven hundred Fifty Two only.)
3. Agreement value:- 44,69,040.00 (Forty Four lakh Sixty Nine thousand Forty only)
4. Performance security Rs. 1.12 Lac PSD+ Rs. 12.09 Lac Extra PSD in shape of FDR
5. Date of commencement of work: 04/11/2024
6. Date of completion of work: 03/05/2025

This agreement, made the...<sup>th</sup> day of ... 2024 Between Executive Engineer, R.W.D. Works Division. Gopalganj-2. of, the one part, and Suman Saurabh, Vill- Bharkuiya, PO+PS- Barauli, Distt- Gopalganj Where as the Employer is desirous that Contractor execute construction of Road from MMGSY(Awsesh), Package No- MMGSY(Awsesh)-NDB-BRRP2-730-Gopalganj-2, Under MMGSY(Awsesh) (Length- 0.550 km.) and the employer has accepted the bid by the contractor for the execution and completion of such works and the remedying of any defects there in at total cost of Rupees.

Road	Length (In K.M)	Construction Cost.	Maintenance Cost.	Total Cost.
Baikunthpur to Gopalganj Barahariya road Pratappur Balua Tola	0.550	4212117.00	256923.00	4469040.00

SUMAN SAURABH

Suman Saurabh  
Proprietor

04.11.24  
Divisional Accounts Officer  
RWD (W) Division  
Gopalganj-2

04.11.24  
Executive Engineer  
RWD (W) Division  
Gopalganj-2





# SYNOPSIS OF AGREEMENT


(Agreement Below on – 24.57%)

Name of Works :- MMGSY(Awsesh), Package No- MMGSY(Awsesh)-NDB-BRRP2-730-Gopalganj-2, Under- MMGSY(Awsesh) (Length- 0.550 km.)

1. Estimated Cost. : 59,24,752.00
- Ref. of NIT : RWD/MMGSY(AWSESH)/HQ/ET/2023-24/37
2. AA Amount : Mentioned in Cost Sheet
3. TS Amount : Mentioned in Cost Sheet
4. Agreement Value : 44,69,040.00
5. Date of Tender : 12.04.2024
6. Details of Earnest Money : 13.21 Lac. PSD in shape of FD
7. Date of Works Order : 04/11/2024
8. Date of Completion : 03/05/2025
9. Actual Date of Completion :
- 10.No. of Items Tender for : 30 Nos in One Road

  
D.A.O.  
R.W.D. Works Division  
Gopalganj-2

  
Executive Engineer  
R.W.D. Works Division  
Gopalganj-2

SUMAN SAURABH  
  
Proprietor



Issue of Notice to proceed with the work

Dated:-...../...../.....

Memo No.

To.

Suman Saurabh,  
Vill- Bharkuiya, PO+PS- Barauli, Distt- Gopalganj

Dear Sir,

Pursuant to your furnishing the requisite performance security as stipulated in ITB Clause 32.1 and signing of the contract for the construction from MMGSY(Awsesh), Package No- MMGSY(Awsesh)-NDB-BRRP2-730-Gopalganj-2, Under- MMGSY(Awsesh) (Length-0.550 km.) you are hereby instructed to proceed with the execution of the said works in accordance with the contract documents.

Yours Faithfully,

Executive Engineer.  
R.W.D. Works Division.  
Gopalganj-2

ज्ञापांक—

दिनांक—

प्रतिलिपि— संबंधित सहायक अभियंता, ग्रामीण कार्य विभाग कार्य अवर प्रमंडल, मांझा / कनीय अभियंता मांझा, को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित/ निर्देश दिया जाता है कि संवेदक द्वारा कार्य आरंभ करने के पूर्व कार्य स्थल का फोटों एवं कार्य पूर्ण होने पर कार्य स्थल का फोटों प्रमंडलीय कार्यालय में ससमय समर्पित करना सुनिश्चित करें साथ ही निर्माण से संबंधित यंत्र-संयंत्र तथा प्रयोगशाला कार्य स्थल पर स्थापित कराना सुनिश्चित करेंगे एवं उसका फोटोग्राफ प्रमंडलीय कार्यालय में समर्पित करेंगे। कार्य में प्रयुक्त होने वाले सभी सामग्रियों का गुण-नियंत्रण जॉच प्रतिवेदन एवं अन्य वांछित जॉच प्रतिवेदन प्रत्येक चालु विपत्र के साथ संलग्न कर समर्पित करना सुनिश्चित करें। कार्य में पी0सी0सी0 पथांश का Mix Design AICTE approved Engineering College से लेना सुनिश्चित करेंगे।

कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमंडल गोपालगंज-2

ज्ञापांक—

दिनांक—

प्रतिलिपि— कार्यपालक अभियंता, ग्रामीण कार्य, विभाग, गुण नियंत्रण प्रमंडल ग्रामीण कार्य विभाग छपरा को सूचनार्थ एवं आवश्यक कार्रवाई हेतु समर्पित/ अनुरोध है कि संबंधित कार्य के गुण नियंत्रण प्रणाली का टेस्ट रिपोर्ट भुगतान के पूर्व इस प्रमंडलीय कार्यालय को ससमय उपलब्ध कराना सुनिश्चित करेंगे।

कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमंडल गोपालगंज-2

ज्ञापांक—

दिनांक—

प्रतिलिपि— मुख्य अभियंता-5 ग्रामीण कार्य विभाग, बिहार पटना/ अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, सिवान को आवश्यक कार्रवाई हेतु सूचनार्थ समर्पित।

कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमंडल गोपालगंज-2

SUMAN SAURABH

Suman Saurabh  
Proprietor



Validate

Print

Help

## Percentage BOQ

Tender Inviting Authority: Engg-in Chief RWD Patna

Name of Work: BAIKUNTHPUR TO GOPALGANJ BARHARIYA ROAD TO PARTAPUR BALUA TOLA

Contract No: Civil Works/

Name of the  
Bidder/  
Bidding Firm /  
Company :

## PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender.  
Bidders are allowed to enter the Bidder Name and Values only.)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
SL No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT With Taxes	TOTAL AMOUNT In Words
1	Setting Out Pillars Providing & Fixing of Working benchmark Pillars 2 nos. per km & 6 Nos. of reference pillars required for 1 Km as per drawings given and direction of E/I	4	5	6	54	55
1	Setting Out Pillars Providing & Fixing of Working benchmark Pillars 2 nos. per km & 6 Nos. of reference pillars required for 1 Km as per drawings given and direction of E/I	4.000	No	3058.24	12232.96	INR Twelve Thousand Two Hundred & Thirty Two and Paise Ninety Six Only
2	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.193	Ha	76926.08	14846.73	INR Fourteen Thousand Eight Hundred & Forty Six and Paise Seventy Three Only

SUMAN SAURABH

Suman Saurabh

Proprietor

18.11.21

18/11/21



3	Box Cutting Excavation for roadway in soil by manual means for carrying of cut earth to embankment site with a lift upto 1.5 m and lead upto 50 m as per technical specifications clause 302.3	41.250	Cum	190.23	7846.99	INR Seven Thousand Eight Hundred & Forty Six and Paise Ninety Nine Only
4	Construction of embankment with approved material deposited from road way cutting and excavation from drain and foundation of other structures and excavated with an average lead of 50 m graded and compacted to meet requirement of tables 300.1 and 300.2 as per technical specification clause 301.5 (including Royalty & Labour Cess).	41.250	Cum	62.83	2591.74	INR Two Thousand Five Hundred & Ninety One and Paise Seventy Four Only
5	Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m, transporting to the site spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 100 m as per Technical Specification Clause 301.5. (including Royalty & Labour Cess). For 1000 m lead @ 20 %	85.772	Cum	260.98	22384.78	INR Twenty Two Thousand Three Hundred & Eighty Four and Paise Seventy Eight Only
6	Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m, transporting to the site spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 100 m as per Technical Specification Clause 301.5. (including Royalty & Labour Cess). For 100 m lead @ 80 %	343.088	Cum	188.29	64600.04	INR Sixty Four Thousand Six Hundred and Paise Four Only

18.11.24

25/11/24

SUMAN SAURABH

Suman Saurabh

Proprietor



7	Construction of Subgrade and Earthen Shoulders Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m & 100 m as per Technical Specification Clause 303.1. (Including Royalty & Labour Cess).	230.310	Cum	264.51	60919.33	INR Sixty Thousand Nine Hundred & Nineteen and Paise Thirty Only
8	Granular Sub-base with Well Graded Material (Table 400.1) (By mix in place method) For Grading I Material Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, roller to achieve the desired density, complete as per Technical Specification Clause 401.	58.160	Cum	3702.55	215340.31	INR Two Lakh Fifteen Thousand Three Hundred & Forty and Paise Thirty One Only
9	WBM Grading 3 (By Mechanical Means) Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	156.230	Cum	5437.31	849470.94	INR Eight Lakh Forty Nine Thousand Four Hundred & Seventy and Paise Ninety Four Only

SUMAN SAURABH

Suman Saurabh  
Proprietor

Executive Engineer  
RWD (W) Division  
Gopalgarh-2



10	Cement Concrete Pavement Construction of un-reinforced, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and	333.300	Cum	9406.38	3135146.45	INR Thirty One Lakh Thirty Five Thousand One Hundred & Forty Six and Paise Forty Five Only
11	Cable Duct Across the Road Providing and laying of a reinforced cement concrete pipe duct, 300 mm dia, across the road (new construction), extending from drain to drain in cuts and toe of slope to toe of slope in fills, constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC:981997, bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC: 98 - 1997 and approved drawings.	7.500	M	1192.17	8941.28	INR Eight Thousand Nine Hundred & Forty One and Paise Twenty Eight Only

18.11.23

VI

Executive Engineer  
RWD (W) Division  
Gopalgarh-2

SUMAN SAURABH  
Suman Saurabh  
Proprietor



12	Kilometre stone Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703.	2.000	No	3218.06	6436.12	INR Six Thousand Four Hundred & Thirty Six and Paise Twelve Only
13	Kilometre stone Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703. iii) 200 m stone	2.000	No	877.26	1754.52	INR One Thousand Seven Hundred & Fifty Four and Paise Fifty Two Only
14	Retro-reflectorised Traffic Signs Providing and fixing of retro- reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 600 mm equilateral & triangle,	3.000	Nos	5216.14	15648.42	INR Fifteen Thousand Six Hundred & Forty Eight and Paise Forty Two Only

SUMAN SAURABH  
Suman Saurabh  
Proprietor

MS-24  
04.11.24

CALCULATIVE ENGINEER  
RWVD (W) DIVISION  
Gopalgarh-2  
11/11/24



15	Retro-reflectorised Traffic Signs Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 900 mm side octagon, OR Stop	1.000	Nos	13063.96	13063.96	INR Thirteen Thousand & Sixty Three and Paise Ninety Six Only
16	Retro-reflectorised Traffic Signs Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 600 mm x 450 mm rectangular,	2.000	Nos	6949.96	13899.92	INR Thirteen Thousand Eight Hundred & Ninety Nine and Paise Ninety Two Only

MR  
04.11.24

SUMAN SAURABH  
Suman Saurabh  
Proprietor

RVL (04) Division  
Gopalgarh-2

11/11/24



17	Road Marking with Hot Applied Thermoplastic Compound with Reflecting Glass Beads on Concrete Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes. Sealing primer may be applied in advance which is incidentally included to the work.	110.000	Sqm	886.50	97515.00	INR Ninety Seven Thousand Five Hundred & Fifteen Only
18	Provision of 15 nos. rumble strips covered with premix bituminous carpet, 15-20 mm high at centre, 250 mm wide placed at 1 m centre-to-centre at approved locations to control speed, marked with white strips of road marking paint.	1.000	No	15599.53	15599.53	INR Fifteen Thousand Five Hundred & Ninety Nine and Paise Fifty Three Only
19	(i) Providing and Fixing 'Logo' of MMGSY BRICS (NDB) Project Providing and fixing of typical MMGSY WB informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enamered on both sides. Lettering and	5.000	Nos	15674.16	78370.80	INR Seventy Eight Thousand Three Hundred & Seventy and Paise Eighty Only
20	Add Labour @ 1% SAURABH	0.01	PERCENT	4636609.79	46366 10	INR Forty Six Thousand Three Hundred & Sixty Six and Paise Ten Only

Suman Saurabh  
Proprietor

18.11.24



21	Add Seigniorage Fee @ 10%	0.10	PERCENT	493460.00	49346.00	INR Forty Nine Thousand Three Hundred & Forty Six Only
22	Add GST @ 18%	0.18	PERCENT	4732321.89	851817.94	INR Eight Lakh Fifty One Thousand Eight Hundred & Seventeen and Paise Ninety Four Only
23	1st Year Maintenance cost	0.550	KM	46860.00	25773.00	INR Twenty Five Thousand Seven Hundred & Seventy Three Only
24	2nd Year Maintenance cost	0.550	KM	55836.36	30710.00	INR Thirty Thousand Seven Hundred & Ten Only
25	3rd Year Maintenance cost	0.550	KM	238101.82	130956.00	INR One Lakh Thirty Thousand Nine Hundred & Fifty Six Only
26	4th Year Maintenance cost	0.550	KM	73741.82	40558.00	INR Forty Thousand Five Hundred & Fifty Eight Only
27	5th Year Maintenance cost	0.550	KM	82718.18	45495.00	INR Forty Five Thousand Four Hundred & Ninety Five Only
28	Add Labour Cess @ 1%	0.01	PERCENT	273192.00	2734.92	INR Two Thousand Seven Hundred & Thirty Four and Paise Ninety Two Only
29	Add Seigniorage Fee @ 10%	0.10	PERCENT	124270.00	12427.00	INR Twelve Thousand Four Hundred & Twenty Seven Only
30	Add GST @ 18%	0.18	PERCENT	288653.92	51957.71	INR Fifty One Thousand Nine Hundred & Fifty Seven and Paise Seventy One Only
Total in Figures					5924751.46	Fifty Nine Lakh Twenty Four Thousand Seven Hundred & Fifty One and Paise Forty Six Only
Quoted Rate in Figures		INR Zero Only		Select	0.00	INR Zero Only
Quoted Rate in Words						

1.3.2 approved for Rs 5924752.00 (Rupees fifty nine thousand four hundred and seven hundred and fifty two) only from 01.10.21.

SUMAN SAURABH

Suran Saurabh  
Proprietor

Superintending Engineer  
RWD Works Circle, Sivadi

09.11.21

Executive Engineer  
RWD (W) Division

Gopalgarh-2

02/11/21