

5th year maintenance Bill

88

Sch. XLV—Form No. 134


Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
Name of Work:- Dhanhar mmhsy					
road to injori Bigha dharai					
school under mmhsy (sc)					
Agency:- Shri mukesh Kumar					
Ass No.:- 38 SBD / 18-19					
Actual Date of completion:- 7.12.19					
① Restoration of Rain cuts-					
$2 \times 11 \times 30 \times 0.90 \times 0.300 =$					178.2 m^3
$2 \times 18 \times 1.0 \times 0.300 =$					10.8 m^3
					<u>189.0 m^3</u>
② Maintenance of Berms/					
Shoulders Stripping/2g excess					
$2 \times 4 \times 29.50 \text{ m} \times 0.950 \text{ m} =$					224.2 m^2
$2 \times 6 \times 28 \text{ m} \times 0.800 \text{ m} =$					268.8 m^2
$2 \times 4 \times 27 \text{ m} \times 0.900 \text{ m} =$					194.4 m^2
$2 \times 4 \times 25 \text{ m} \times 0.900 \text{ m} =$					180.0 m^2
$2 \times 2 \times 26 \text{ m} \times 0.850 \text{ m} =$					88.4 m^2
$2 \times 27 \text{ m} \times 0.800 \text{ m} =$					43.2 m^2
total =					<u>999 m^2</u>
③ Repair of Potholes with					
75 mm WBM:-					
$6 \times 6.00 \times 3.75 =$					135 m^2
$3 \times 8.50 \times 3.75 =$					95.62 m^2
total =					<u>230.62 m^2</u>
④ Periodical Renewable					
to existing BT surface					
$6 \times 6.00 \times 3.75 =$					135 m^2
$3 \times 8.50 \times 3.75 =$					95.62 m^2
total =					<u>230.62 m^2</u>

Continuation

5th yr. maintenance Bill
(ABSTRACT)

90

Sch. XLV—Form No. 134

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
① Restoration of Rain Cuts					
vide item no. ① VTMP ⑧⑧					
Qty = 189.00m ³ @ 365.25/m ³ = 69032—					
② maintenance of beams/shoulders					
vide item no. ② VTMP ⑧⑧					
Qty = 999.00m ² @ 54.16/m ² = 54106—					
③ Repair of Potholes 75mm WBM					
vide item no. ③ VTMP ⑧⑧					
Qty = 230.62m ³ @ 264.43/m ³ = 60983—					
④ Periodical Renewable to Existing B+ surface single coat					
vide item no. ④ VTMP ⑧⑧					
Qty = 230.62m ² @ 75.58/m ² = 17430—					
⑤ Periodical Renewable to Existing B+ surface double coat					
vide item no. ⑤ VTMP ⑧⑨					
Qty = 231m ² @ 66.38/m ² = 15334—					
⑥ maintenance of CD work					
(H.P) vide item no. ④ VTMP ⑧⑨					
Qty = 4 NOS. @ 1131.64/each = 4527—					
⑦ maintenance of CD work					
(slab culvert) vide item no. ⑧ VTMP ⑧⑨					
Qty = 2 NOS. @ 2336.91/each = 4674—					
Total =					226,086—
 11/12/24 A.E.					

Continuation