

18) years maintenance

43

Sch. XLV—Form No. 134

Sch. XLV—Form No. 134					Contents of area
Particulars	Details of actual measurement				
	No.	L.	B.	D.	
Name of work: Construction					
of Road from H/H-104					
Nagar Panchayat Sonar					
to High school					
Jaynagar Naya Mulalla					
Tak Under Ministry (H.B.D.)					
Agency: M/s Ananya Corporation					
Agreement No- 23 S.B.D 2018-19					
Date of start: 10-10-2018					
Date of Completion: 09/07/2019					
Actual Completion date:					
Below 10%					

Measurement					
(4) <u>Restoration of Rain</u>					
<u>Cuts - do - do - 611</u>					
	3 Nos	2.00	1.10	0.30	2.475 m ³
	5 Nos	2.40	1.15	0.30	4.140 m ³
	7 Nos	2.10	1.00	0.30	4.410 m ³
	6 Nos	1.80	1.10	0.30	3.564 m ³
	4 Nos	1.90	0.95	0.30	2.166 m ³
	5 Nos	1.75	0.85	0.30	2.231 m ³
	3 Nos	2.20	1.10	0.30	2.178 m ³
	8 Nos	1.50	1.15	0.30	4.140 m ³
	10 Nos	1.65	1.10	0.30	5.445 m ³
	7 Nos	1.25	1.00	0.30	2.625 m ³
	12 Nos	1.75	1.10	0.30	6.93 m ³

Continuation

40.304 m³



Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
	5 Nos	2.30	1.10	0.30	3.795 m^3
	11 Nos	1.75	1.10	0.30	6.352 m^3
	Total Qty =				50.451 m^3
(2) Making up of Bore shafts ... etc - 6/1					
	5 Nos	2.10	1.25		13.125 m^2
	7 Nos	1.50	1.25		13.125 m^2
	10 Nos	1.75	1.25		21.875 m^2
	6 Nos	1.65	1.25		12.375 m^2
	11 Nos	1.85	1.25		25.437 m^2
	9 Nos	1.65	1.25		18.562 m^2
	12 Nos	1.95	1.25		29.25 m^2
	7 Nos	2.10	1.25		18.375 m^2
	8 Nos	2.20	1.25		22.00 m^2
	10 Nos	2.00	1.25		25.00 m^2
	6 Nos	2.10	1.25		15.75 m^2
	9 Nos	1.75	1.25		19.687 m^2
	12 Nos	1.85	1.25		27.75 m^2
	2 Nos	1.50	1.25		3.75 m^2
	10 Nos	1.65	1.25		20.625 m^2
	Total Qty =				286.686 m^2
(3)					

Continuation

Continuation

Continuation

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
	<u>Abstract of Cost</u>				
(1)	Restoration of Rain culps -- do -- do -- 610				
	(TMB Page No - 44)				
	Qty - 50.451 m ³				
	@ Rs	327.36 / m ³		Rp -	16516 = 100
(2)	Making up of shoulders -- do -- do -- 610				
	(TMB Page No - 44)				
	Qty - 286.686 m ²				
	@ Rs	49.71 / m ²		Rp -	14251 = 100
(3)	Patch Repairs over Irregular Surface with 20 mm -- do -- do -- 610				
	(TMB Page No - 45)				
	Qty - 23.06 m ²				
	@ Rs	296.68 / m ²		Rp -	6841 = 100
(4)	Maintenance of H.P culverts -- do -- do -- 610				
	(TMB Page No - 45)				
	Qty - 2 Nos				
	@ Rs	949.83 / No		Rp -	1899 = 100

Continuation

Rp - 39507 = 100

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
(5) Maintenance of Road					
Gravel - do - do - etc					
(TMB Page No - 45)					
Qty - 0.12 K.m					
@ Rs 935.04/K.m Rs - 112=00					
(6) Maintenance of 200m					
and 10m stone - do -					
- do - do - etc					
Qty 0.15					
(TMB Page No - 45)					
Qty - 0.15 K.m					
@ Rs 565.49/K.m Rs - 85=00					
(7) Trimming of grass					
and weeds - do -					
- do - etc					
(TMB Page No - 46)					
Qty - 4.615 m ²					
@ Rs 1.75/m ² Rs - 8=00					
(8) White washing of Pasa-					
ret walls of do -					
- do - do - etc					
(TMB Page No - 46)					
Qty - 41.28 m ²					
@ Rs 14.01/m ² Rs - 578=00					

Continuation

40,290=00

[illegible]

2nd year Maintenance

Sc

51

P

Sch. XLV—Form No. 134

Sch. XLV—Form No. 134					Contents of area
Particulars	Details of actual measurement				
	No.	L.	B.	D.	
Name of work - Construction of Road from NH-104 Nagar Panchayat corner to High school Jaynagar Nagar Mahalla bus stand Munisi (Nabad)					
Agency: M/S Pradyo Corporation					
Agreement No - 28 SBD 2018-19					
Date of start, 10-10-2018					
Date of Completion - 09-07-2019					
Actual Completion Date -					
Below - 10 %					

Restoration of Raincuts d. eff.

(4)	4 Nos	1.70	0.75	0.30	= 1.53 m ³
	2 Nos	1.35	0.85	0.30	= 0.69 m ³
	5 Nos	1.55	0.65	0.30	= 1.51 m ³
	11 Nos	1.75	1.10	0.30	= 6.352 m ³
	5 Nos	2.30	1.10	0.30	= 3.795 m ³
	12 Nos	1.75	1.10	0.30	= 6.93 m ³
	7 Nos	1.25	1.00	0.30	= 2.625 m ³
	10 Nos	1.65	1.10	0.30	= 5.445 m ³
	8 Nos	1.50	1.15	0.30	= 4.14 m ³
	3 Nos	2.20	1.10	0.30	= 2.178 m ³
	5 Nos	1.75	0.85	0.30	= 2.231 m ³
	4 Nos	1.90	0.95	0.30	= 2.166 m ³
	6 Nos	1.80	1.10	0.30	= 3.564 m ³

Continuation



Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
	7 Nos	2.10	1.00	0.30	4.410 m^3
	5 Nos	1.15	2.40	0.30	4.140 m^3
	3 Nos	2.0	1.10	0.30	2.475 m^3
	8 Nos	2.10	1.0	0.30	5.040 m^3
	2 Nos	1.80	1.10	0.30	1.188 m^3
	Total Qty =				60.409 m^3

② Making up of shoulder
stripping do do
do do do

10 Nos	1.75	1.25		21.875 m^2
7 Nos	1.50	1.25		13.125 m^2
6 Nos	1.65	1.25		12.375 m^2
11 Nos	1.85	1.25		25.437 m^2
12 Nos	1.95	1.25		29.25 m^2
9 Nos	1.65	1.25		18.562 m^2
7 Nos	2.10	1.25		18.375 m^2
8 Nos	2.20	1.25		22.00 m^2
10 Nos	2.10	1.25		25.0 m^2
6 Nos	2.10	1.25		15.75 m^2
9 Nos	1.75	1.25		19.687 m^2
12 Nos	1.85	1.25		27.75 m^2
2 Nos	1.50	1.25		3.75 m^2
10 Nos	1.65	1.25		20.625 m^2
5 Nos	1.95	1.25		12.187 m^2
7 Nos	2.10	1.25		18.375 m^2

Continuation

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
	1 Nos	1.85	1.25		9.25 m^2
	6 Nos	1.75	1.25		13.125 m^2
	2 Nos	1.65	1.25		4.125 m^2
	Total Qty =				343.739 m^2
(3) Patch Repairs over Bituminous Surface with 20 m.w. --- do --- do ---					
	8 Nos	1.30	0.70		7.28 m^2
	10 Nos	1.15	0.65		7.475 m^2
	2 Nos	1.40	0.85		9.520 m^2
	3 Nos	1.10	0.50		1.65 m^2
	5 Nos	1.35	0.60		4.05 m^2
	9 Nos	1.50	0.80		10.80 m^2
	7 Nos	1.25	0.75		6.562 m^2
	Total Qty =				47.337 m^2
(4) Maintenance of H.P culverts --- do --- do ---					
	2 Nos				2 Nos -
(5) Maintenance of Road signs --- do --- do ---					
	0.15 K.m				0.15 K.m

Continuation

Continuation

Sch. XLV—Form No. 134

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
<u>Abstract of Cost</u>					
(1) Restoration of Rain					
culverts -- do -- do -- 6/11					
(T.M.B Page No- 52)					
Qty- 60.409 m ³					
@ Rs- 327.36/m ³				Rs- 19,775.00	
(2) Making up of Shoulder					
-- do -- do -- 6/11					
(T.M.B Page No- 53)					
Qty- 343.739 m ²					
@ Rs- 49.71/m ²				Rs- 17087.00	
(3) Patch Repairs over Pot					
holes with Round --					
-- do -- do -- 6/11					
(T.M.B Page No- 53)					
Qty- 47.337 m ²					
@ Rs- 296.68/m ²				Rs- 14044.00	
(4) Maintenance of U.P					
culverts -- do -- do -- 6/11					
(T.M.B Page No- 53)					
Qty- 02 Nos					
@ Rs- 939.33/No				Rs- 1879.00	
<u>Total Rs</u>					<u>52785.00</u>

Continuation

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
(5) Maintenance of Road					
Sign - dec - dec - 6/11					
(TMB Page No - 53)					
Qty - 0.15 km					
@ Rs 935.00/km Rs - 140 = 00					
(6) Maintenance of 200m and 100m stone - dec - dec - dec - 6/11					
(TMB Page No - 54)					
Qty - 0.18 km					
@ Rs 565.49/km Rs - 102 = 00					

(7) Trimming of grass and weeds - dec - dec - 6/11					
(TMB Page No - 54)					
Qty - 5.39 sqm					
@ Rs 1.75/sqm Rs - 9 = 00					
(8) White washing of parapet wall of c/d - dec - dec - 6/11					
(TMB Page No - 54)					
Qty - 41.88 sqm					
@ Rs 14.01/sqm Rs - 578 = 00					

Continuation

Total Rs - 53614 = 00

[illegible]

Continuation

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
3rd year maintenance					
Name of work: maintenance of road and					
from HH-104 Nagar Panch					
along Karna to High School					
Subnagar Haba Malalla					
under MMBS (NABARD)					
Agency - M/S Ananda Corporation					
Agreement No 28SBI/2018/19					
Date of 3rd year maintenance start - 13/7/21					
Date of 3rd year maintenance complete - 17/7/22					
Date of measurement -					
(1) Restoration of earthen beamed					
with soil conversion as					
per E/I					
	2+2	2.75	1.125	0.300	10.46 M ³
	2+2	2.75	1.125	0.300	11.14 "
	2+2	5.85	1.125	0.300	7.89 "
Sandy	5	5.90	1.125	0.300	9.96 "
10/02/23	2+2	4.25	1.125	0.300	6.42 "
	4	6.50	1.125	0.300	8.72 "
	2+2	3.90	1.125	0.300	5.26 "
	3	5.15	1.125	0.300	5.25 "
	2+2	4.28	1.125	0.300	5.78 "
	2	2.93	1.125	0.300	1.98 "
					22.86 M ³
(2) making up beamed shoulder					
stop by the left side from					
shoulder as per E/I					
	2+4	8.25	1.125		78.35 M ²

Continuation

Sch. XLV—Form No. 134

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
				0.12	78.75 m ²
	2+2+	7.90+	1.125		35.55 "
	2+4+	4.85+	1.125		43.65 "
	6+	6.25+	1.125		42.19 "
	2+2+	5.85+	1.125		26.32 "
	2+2+	9.45+	1.125		42.52 "
	5+	5.85+	1.125		32.91 "
	2+	8.15+	1.125		18.34 "
	2+2+	4.25+	1.125		19.22 "
	1+	6.75+	1.125		7.59 "
					346.94 m ²
(3) Repair of pot hole with dowel					
					75 mm BM as per E/A
	2+2+	5.85+	0.875+	0.075	1.53 m ³
	2+2+	6.50+	0.920+	0.075	1.79 "
	2+	4.90+	1.05+	0.075	0.77 "
	2+	4.25+	0.850+	0.075	0.54 "
	2+2+	4.22+	0.625+	0.075	0.79 "
					5.42 m ³
(4) Patch repairs over pot hole					
					with 70 mm PMC as per E/A
					Cont. Type B as per E/A
	2+2+	4.25+	0.920		15.64 m ²
	2+2+	3.90+	0.880		13.73 "
	3+	6.25+	0.850		15.94 "
	2+2+	2.90+	0.90		10.44 "
	4+	4.25+	0.920		12.85 "
					73.60 m ²
				4 m ²	72.28 m ²

Continuation

Particulars	Details of actual measurement				Contents of area
	No. of	Length	Breadth	Depth	
(5) Planting of trees over boundary wall surface with 150 mm pipe	2+	6.50	1.50		19.50 m ²
	4+	4.15	1.15		19.09 "
	1+	8.75	1.35		11.81 "
	2+	2.90	1.9		11.02
	3+	3.25	1.25		9.37 14.06 "
	1+	3.31	0.450		1.49 "
					72.28 m ²
(6) Maintenance of H.P. culvert					
as per E/H					
	1+	2 No.			02 No.
(7) Maintenance of road drain					
as per E/H					
	1+	0.18 km			0.18 km
(8) Maintenance of 20m and					
E.M. Stone as per E/H					
	1+	0.22 km			0.22 km
(9) Cutting of branches of trees					
and shrubs as per E/H					
	1+	3 No.			03 No.
(ii) Cutting of shrubs from road					
ways as per E/H					
	1+	11 No.			11 No.
(iii) Trimming of grass and weeds					
as per E/H					
	2+	9.75	0.300		5.85 m ²
(10) Whitewashing of parapet wall					
of C.P. work as per E/H					
	2+2+	6.15	0.40		9.84 m ²
	2+2+	6.15	0.600		29.52 "
					39.36 m ²

Continuation

Sch. XLV—Form No. 134

Particulars	Details of actual measurement				Contents of area
	No	L	B	D	
				B.P	39.36 M ²
	272721	0.400	0.600		1.92 "
					41.28 M ²
ABSTRACT OF COST.					
380 year maintenance					
(1/1)	Restoration of rainwater bearing				
	with 50 mm BM as per E/I				
Sandy	10/02/23 per E/I				
	Qty vide T.M.B.P-53(1)				
	72.86 M ³ @ 327.36/M ³ = 23851.00				

(2/2)	making up bearing steel				
	as per E/I				
	Qty vide T.M.B.P-59(2)				
	346.96 M ² @ 49.71/M ² = 17247.00				
(3/3)	Repair of pot hole with				
	with 75 mm BM as per E/I				
	Qty vide T.M.B.P-60(3)				
	5.42 M ³ @ 10573.43/M ³ = 57308.00				
(4/4)	Patch repair over pot hole				
	with 20 mm P.M.C with				
	seal coat type B as per E/I				
	Qty vide T.M.B.P-60(4)				
	72.28 M ² @ 279.29/M ² = 20187.00				
(5/5)	Patch repair over bituminous				
	surface as per E/I				

Continuation

C100-118593.00

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
				BFA	118593=10
				ats vide T.MBP-61(5)	
		72.28 m ²	@ 296.68/m ²		21444=10
(6/7)		maintenance 4 H.P.			
		current as per E/I			
				ats vide T.MBP-61(6)	
		02 Mo.	@ 949=32/Mo.		1899=10
(7/8)		maintenance 4 road sign			
		as per E/I			
				ats vide T.MBP-61(7)	
		0.28 km	@ 935=04/km		168=10
(8/9)		maintenance 4 20 m and			
		K-M Stone as per E/I			
				ats vide T.MBP-61(8)	
		0.22 km	@ 565=49/km		124=10
(9/10)		cuttings 4 60 m and 4 trees			
		and shrubs as per E/I			
				ats vide T.MBP-61(9-i)	
(ii)		03 Mo.	@ 85=63/Mo.		257=10
		cutting 4 shrubs 150 m			
		roadways as per E/I			
				ats vide T.MBP-61(9-ii)	
		01 Mo.	@ 5=25/Mo.		58=10
(ii)		Trimming 4 grass and weeds			
		as per E/I			
				ats vide T.MBP-61(9-iii)	
		5.85 m ²	@ 1=75/m ²		10=10
(10/11)		white washing 4 parapet			
		wall 4 C.D. work as per E/I			
				ats vide T.MBP-61(10)	

Continuation

C100-142553=10

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
	4th year maintenance bill				
Name of work - maintenance of road and					
	C.D. work from NH 104 near				
	Panchayat Samita to bridge				
	School Jabnagar Nagla				
Sansu 07/05/24	Mahalla under MM 655				
	(CHABARD)				
Agency - M/S Ananya Corporation					
Agreement No. 295BJ/2018 - 19					
Date of 4th year maintenance start - 13/7/22					
Date of 4th year maintenance complete - 12/07/23					
Date of measurement -					
(1) Restoration of rain cut beams					
with steel reinforcement as per E/I					
	2+2+	11.45+	1.125+	0.30	15.46 m ³
	2+2+	9.85+	1.125+	0.30	13.29 "
	2+4+	4.75+	1.125+	0.30	12.82 "
	2+3+	6.85+	1.125+	0.30	13.87 "
	2+	5.50+	1.125+	0.30	3.71 "
	2+	6.15+	1.125+	0.30	4.15 "
	4+	4.90+	1.125+	0.30	6.61 "
	2+2+	5.85+	1.125+	0.30	7.89 "
	2+2+	4.05+	1.125+	0.30	5.47 "
					83.27 m ³
(2) Making up beams shoulder					
stripping the old base					
from shoulder as per E/I					
	2+4+	8.85+	1.125		79.65 m ²

Continuation

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
					BP 79.65 M ²
	2+2+	6.75+	1.125		30.37 "
	2+2+	7.50+	1.125		33.75 "
	5+	5.85+	1.125		32.91 "
	4+	6.25+	1.125		28.12 "
	3+	3.90+	1.125		13.16 "
	2+3+	7.50+	1.125		50.62 "
	2+2+	9.75+	1.125		43.87 "
	6+	6.90+	1.125		46.57 "
	2+	5.85+	1.125		13.16 "
	2+3+	6.15+	1.125		41.51 "
	2+2+	8.65+	1.125		38.92 "
	4+	4.25+	1.125		21.82 "
	1+	15.60+	1.125		13.55 "
					480.16 M ²
					limit 462.60 M ²
(3) repair of pot hole to H/W					
with 25 mm BM as per E/H					
	2+4+	6.85+	0.980+	0.075	4.03 M ³
	2+3+	5.50+	0.875+	0.075	2.16 "
	2+	6.15+	0.825+	0.075	0.76 "
	2+	4.15+	0.450+	0.075	0.28 "
					7.23 M ³
(4) patch repair over pot hole					
with 20 mm P.M.C. with seal					
cont type B as per E/H					
	2+2+	4.85+	0.980		19.01 M ²
	2+3+	3.90+	1.05		24.57 "
	5+	5.15+	0.880		22.86 "
					66.24 M ²

Continuation

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
				BP	66.24M ²
	2+	6.85+	0.915		12.53'
	1+	5.10+	1.05		7.45 "
	2+2+	5.65+	0.450		10.17'
					96.39M ²
				km ²	96.38M ²
(5) patch repair curb bitumen					
and surface width 20mm					
PM curbs seal coat type					
B as per E/H					
	2+	6.65+	1.60		21.28M ²
	3+	3.90+	1.85		21.64 "
	1+	9.90+	1.90		18.81 "
	1+	5.50+	1.50		8.25 "
	3+	4.15+	1.25		15.56 "
	1+	2.90+	2.15		6.23 "
	1+	7.38+	0.625		24.94 "
					4.61 "
					96.38M ²
(6) maintenance of H.P. culvert					
as per E/H					
1+ 2M					
					= 02 No.
(7) maintenance of road kerb					
as per E/H					
1+ 0.18km					0.18km
(8) maintenance of 20cm and					
10cm stone as per E/H					
1+ 0.22km					0.22km
(9) cutting of branches of trees					
and sharps as per E/H					

Continuation

	14340	03 No
(15)	Cutting of slabs from road	
	Waste as per E/H	
	14340	11 No
(16)	Trimming of grass and weeds	
	as per E/H	
	2 x 9.75 x 0.30	5.85 m ²
(17)	White washing of parapet	
	Wall of C.D. Waste as per E/H	
	2 x 2 x 6.15 x 0.40	9.84 m ²
	2 x 2 x 6.15 x 0.60	29.52 "
	2 x 2 x 0.40 x 0.60	1.92 "
		41.28 m ²

Sandya

67/03/29

ABSTRACT OF COST.

4th year maintenance

(1/1) Restoration of concrete

bearings with sand mosaic
as per E/H

Qty vide T.M.B.P-67(1)

83.27 m² @ 327.36/m³ = 27259 = ₹

(2/2) Making up bearings slabs

as per E/H

Qty vide T.M.B.P-67(2)

462.60 m² @ 49.71/m² = 22996 = ₹

Continuation

400-50255 = ₹

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
				356	50255=0
(3/3) Repair of pot hole with bit					
36 mm BM as per E/I					
qty vide T.M.B.P-68(3)					
7.23 M ³ @ 10573 = 43/M ³					76446=0
(4/4) patch repair grey pot hole					
with 20 mm PMC with seal					
cont type B as per E/I					
qty vide T.M.B.P-68(4)					
96.38 M ² @ 279.29/M ²					26918=0
(5/5) patch repair over bitumen					
old surface with 20 mm					
PMC with seal coat type					
B as per E/I					
qty vide T.M.B.P-69(5)					
96.38 M ² @ 296.68/M ²					28594=00
(6/7) maintenance of H.P. culvert					
as per E/I					
qty vide T.M.B.P-69(6)					
62 No. @ 345.33/Mo.					1899=00
(7/8) maintenance of road sign					
as per E/I					
qty vide T.M.B.P-69(7)					
0.18 km @ 935.04/km					168=00
(8/9) maintenance of 200 m and					
100 m stone as per E/I					
qty vide T.M.B.P-69(8)					
0.22 km @ 565.49/km					124=00
(9/10) cutting & branches of trees					
					400-184404=00

Continuation

Continuation

Continuation

Sch. XLV—Form No. 134

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
	2+3+	8.85+	1.02+	0.30	17.92 m ³
	2+2+	9.40+	1.125+	0.30	12.69 "
	2+2+	7.75+	1.02+	0.30	10.46 "
	2+2+	6.75+	1.125+	0.30	9.11 "
	5+	5.90+	1.125+	0.30	9.96 "
	4+	4.85+	1.125+	0.30	6.55 "
	3+	3.90+	1.125+	0.30	3.95 "
	2+2+	6.85+	1.125+	0.30	9.25 "
	2+3+	4.75+	1.125+	0.30	9.62 "
	2+	6.12+	1.125+	0.30	4.16 "
					93.67 m ³

(2) Making up borrow bank

at village The reference
toom bank above E/t

	2+6+	8.85+	1.125		125.42 m ²
	2+4+	9.40+	1.125		85.05 "
	2+3+	7.75+	1.125		52.31 "
	2+2+	8.50+	1.125		38.25 "
	2+2+	7.75+	1.125		34.87 "
	5+	5.95+	1.125		32.91 "
	4+	4.50+	1.125		20.25 "
	6+	6.90+	1.125		46.57 "
	2+2+	8.65+	1.125		38.92 "
	2+2+	7.75+	1.125		34.87 "
	2+2+	5.75+	1.125		25.87 "
	3+	9.60+	1.125		32.40 "
	2+2+	5.65+	1.125		25.42 "
	2+2+	4.85+	1.125		21.82 "
	6+	6.85+	1.125		46.24 "

Continuation

528.89 m²

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
				BF	528.89 m ²
				h _{max}	520.43 m ²
(2) Repair of pot hole + wheel					
with 25mm BM 2 per					
E/I					
2+	5.85	1.05	0.075		0.92 m ³
2+2+	4.75	1.25	0.075		1.60 "
2+2+	0.25	0.925	0.075		1.73 "
2+	9.40	0.85	0.075		1.20 "
4+	6.50	1.05	0.075		2.05 "
2+	5.50	0.975	0.075		0.80 "
2+2+	4.42	0.55	0.075		0.74 "
					9.04 m ³
(4) patch repair over pot hole					
with 25mm BM 2 per					
Seal coat type B 2 per E/I					
2+2+	5.85	0.975			22.81 m ²
2+2+	4.50	0.925			16.45 "
5+	5.15	0.775			19.96 "
2+	9.45	1.05			19.84 "
3+	3.90	1.15			13.45 "
1+	12.50	0.920			12.50 "
2+	4.85	0.880			8.54 "
2+2+	4.40	0.450			7.92 "
					120.47 m ²
(5) patch repair over bitumen					
surface with 20mm P.M.C					
with Seal coat type B 2					
per E/I					

Continuation

Sch. XLV—Form No. 134

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
	4+	4.85+	1.5		29.10 M ²
	2+	2.90+	1.90		11.02 "
	3+	2.90+	1.85		21.64 "
	2+	2.80+	2.80		15.68 "
	1+	9.50+	1.50		14.25 "
	1+	6.85+	1.65		11.30 "
	2+	2.33+	3.75		17.47 "
					120.46 M ²
(6) maintenance of H.P. Culvert					
as per E/I					
1+	2 Mo.				02 Mo.
(7) maintenance of road					
as per E/I					
1+	2 Mo.				02 Mo.
(8) maintenance of 200 M road					
K.M. Stone as per E/I					
1+	0.29 KM				0.29 KM
(9) (i) cutting & boarding of trees					
and shrubs as per E/I					
1+	3 Mo.				03 Mo.
(ii) cutting of shrubs for road					
work as per E/I					
1+	11 Mo.				11 Mo.
(iii) Trimming of grass and					
Weeds as per E/I					
2+	16.25+	0.30			9.75 M ²
(10) White washing of parapet					
Wall of H.P. Culvert as per E/I					

Continuation

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
	2121	6.15	0.400		9.84 M ²
	2122	6.15	0.600		29.52 1
	2123	0.40	0.600		1.92 1
					41.28 M ²
ABSTRACT OF COST					
5th year maintenance					
(1/1)	Restoration of sunken beams				
	with sand on 100mm aspc				
Sand	EH				
05/14/22	at vide T.M.B.P-75(1)				
	93.67 M ³ @ 327.36/M ³ 30664.20				
	as per EH				
	at vide T.M.B.P-76(2)				
	520.43 M ² @ 49.71/M ² 25870.20				
(3/3)	Repair of pot hole with				
	25mm BM as per EH				
	at vide T.M.B.P-77(3)				
	9.04 M ³ @ 10573.43/M ³ 95533.20				
(4/4)	Patch repair over pot hole				
	with 25mm P.M.C. with				
	Seal coat Type B as per E/1				
	at vide T.M.B.P-77(4)				
	120.47 M ² @ 278.29/M ² 33646.20				
(5/5)	Patch repair over bitumen				
	Surface with 20mm P.M.C.				

Continuation

4109-195713-60

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
					0.54 185713.2
with seal cont type B as					
per E/T					
at side T.M.B.D. - 20(5)					
120.46 m ² @ 296.68/m ²					35738.2
(6/6) maintenance of H.P. channel					
as per E/T					
at side T.M.B.D. - 28(6)					
02 Mo. @ 949.33/Mo.					1899.2
(7/7) maintenance of road sign					
as per E/T					
at side T.M.B.D. - 28(7)					
0.18 km @ 335.04/km					168.2
(8/8) maintenance of road					
K.M. Stone as per E/T					
at side T.M.B.D. - 28(8)					
0.29 km @ 565.49/km					164.2
(9/10) cutting of ground of trees					
as per E/T					
at side T.M.B.D. - 28(9-i)					
03 Mo. @ 85.63/Mo.					257.2
(ii) cutting of shrubs from road					
as per E/T					
at side T.M.B.D. - 28(9-ii)					
11 Mo. @ 5.25/Mo.					58.2
(iii) Trimming of grass/weeds					
as per E/T					

Continuation

C100 - 223957-2

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
					BFA 223997=0
at node FMBP-78(9-ii)					
9.75M ² @ 1.75/M ²					17=0
(10/11) with washing of pavement					
with g.c.p. work as per E-1					
at node FMBP-78(1)					
41.28M ² @ 14=01/M ²					578=0
					224592=0
below					22459=0
					202133=0

Sandy

05/12/21

Continuation