

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	

4th years maintenance bill:-

Name of roads:- Giliya PMGSY Road +
Giliya Mathe Bazar MK.

Agency:- Krishnita infra project Pvt L.

Agreement:- 22/SBD/2019-20.

Actual date of completion:- 7/03/2020

(1) Restoration of Rain Water

4x3.5x0.90x0.30 — 3.78 m³

10x4.0x0.75x0.40 — 12.0 m³

6x2.5x0.80x0.30 — 3.60 m³

8x6.5x0.75x0.30 — 11.70 m³

9x7.5x0.80x0.40 — 21.60 m³

2x2.5x0.75x0.30 — 1.125 m³

Total = 53.16 m³ — 53.80 m³

(2) Maintenance of earthen shoulder:-

12x9.5x0.90 — 102.6 m²

6x6.0x0.75 — 27.0 m²

4x3.5x1.0 — 14.0 m²

3x5.5x0.80 — 13.20 m²

10x4.0x0.95 — 38.0 m²

15x2.5x0.90 — 33.75 m²

8x6.5x1.0 — 52.0 m²

6x2.5x0.97 — 14.55 m²

Total — 295.10 m²

(3) Repair for pot-holes mix road surface:-

6x4.0x0.75 — 18.0 m²

4x2.0x0.90 — 7.20 m²

9x2.5x0.80 — 18.0 m²

Continuation

A.T.O

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
Abstract of cost					
① Restoration of Rain cuts:-					
TMBP-53, 53.16 m ³					
@ Rs 380.58/m ³ —20232=00					
② Maintenance of earthen shoulder:-					
TMBP-53, 295.10 m ²					
@ Rs 58.60/m ² —17293=00					
③ Repair to pot holes Mix (Leak) surface:-					
TMBP-53, 52.73 m ²					
@ Rs 251.35/m ² —13254=00					
④ providing and laying of hot applied thermoplastic:-					
TMBP-54, 222.0 m ²					
@ Rs 755.53/m ² —167728=00					
⑤ Maintenance patch repair on already filled pot holes:-					
TMBP-54, 52.73 m ²					
@ Rs 385.70/m ² —16120=00					
⑥ Maintenance of Hume pipe/inverts:-					
TMBP-54, 2 NO					
@ Rs 1117.0/each—2234=00					
⑦ Maintenance of 200mm and 1.11km cane post:-					
TMBP-54, 1.11 km					
@ Rs 735.27/km—816=00					
Total—=237677=00					
less 10% belph					=(-)23768=00
Unit - Rs per Area					213909=00
Continuation					72676=00