

बिहार सरकार
कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, लखीसराय

पत्रांक:- लखीसराय / दिनांक:-
सेवा में,
Pankaj Kumar Pawan c/o- Spishyam Dev Prasad
Munger Road Near Darinapurhanch P.O- Jamalpur
Dist- Munger
विषय:- शीर्ष MGSY योजनान्तर्गत MGSY/SETU/24-25/Lakhisarai/02
..... तक निर्माण कार्य का कार्यादेश।
प्रसंग:- मुख्य अभियंता-3, ग्रामीण कार्य विभाग, भागलपुर का पत्रांक 693 दिनांक 10.6.2025
महाशय,

उपर्युक्त विषयक प्रासांगिक पत्र के आलोक में योजना का निर्माण कार्य हेतु आपके द्वारा
एकरारनामा संख्या- 09/CMRD/MGSY/25-26 सम्पन्न किया जा चुका है। तदनुसार कार्य प्रारंभ करने की
तिथि 07.7.2025 एवं समाप्ति तिथि- 12.6.2025 है।

अतः आप संबंधित सहायक अभियंता एवं कनीय अभियंता, ग्रामीण कार्य विभाग, कार्य अवर
प्रमंडल/प्रशाखा, से निरंतर सम्पर्क कर निर्धारित तिथि दिनांक- 12.6.2025 तक
प्राक्कलन के अनुरूप गुणवत्ता एवं विशिष्टियों के अनुरूप कार्य सम्पन्न करावें तथा कार्य प्रारंभ के पूर्व मध्य
एवं अन्त का फोटोग्राफी कार्य तालिका (Work Program) कनीय अभियंता एवं सहायक अभियंता के माध्यम
से अधोहस्ताक्षरी के कार्यालय को उपलब्ध कराना सुनिश्चित करेंगे।

विश्वासभाजन


कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल लखीसराय

पत्रांक :-लखीसराय / दिनांक:-.....


प्रतिलिपि:- सहायक अभियंता एवं कनीय अभियंता, ग्रामीण कार्य विभाग, कार्य अवर प्रमंडल/प्रशाखा,
को एकरारनामा के अभिप्रमाणित प्रति के साथ सूचनार्थ एवं एकरारनामा के अनुरूप कार्य प्रारंभ करवाना
सूनिश्चित करने हेतु प्रेषित। कार्य प्रारम्भ द्वारा के पूर्व मध्य एवं अंत कर निर्माण स्थल का फोटोग्राफी एवं
कार्य तालिका (Work Program) लेना सुनिश्चित करेंगे।



कार्यपालक अभियंता
ग्रामीण कार्य विभाग,

पत्रांक :-लखीसराय / दिनांक:-.....

प्रतिलिपि:- कार्यपालक अभियंता, क्षेत्रीय प्रयोगशाला, ग्रामीण कार्य विभाग, मुंगेर को एकरारनामा की प्रति के
साथ सूचनार्थ एवं आवश्यक कार्रवाई हेतु समर्पित।


कार्यपालक अभियंता
ग्रामीण कार्य विभाग,

कार्य प्रमंडल लखीसराय



07/07/25



०५/०७-०५/०५/२५ एक हजार रुपये का पुराना नोट न्यायिक न्यायिक
बिहार BIHAR

AY 595172

Agreement (SETU)

This agreement, made the **07 day of July 2025**, ("The between The Executive Engineer, R.W.D, (W) Division, Lakhisarai cum PIU, E/I") of the one part, and **Pankaj Kumar Pawan, C/o- Sri Shyam Dev Prasad, Munger Road near Dariyapur Charch, PO.- Jamalpur, Dist.- Munger** of the other part. Whereas the E/I is desirous that the Contractor execute Construction of road/bridge and performance based Rural Road contract for the Routine Maintenance of Roads/Construction of Bridge with maintenance for Tender Group No.- **SETU/MGSY/24-25-Lakhisarai/02** Tender ID-140527. (hereinafter called "The Construction Works & Routine Maintenance") and the E/I has accepted the Bid by the Contractor for the execution of such The Construction Works & Routine Maintenance and the remedying of any defects therein, at a contract price of **Rs.4,75,29,448/- (Construction Cost Rs.,4,72,66,948/- and Maintenance Cost Rs.2,62,500/-) (Rs. Four Crore Seventy Five Lacs Twenty Nine Thousand Four Hundred Forty Eight.)** respectively.

Sl. No.	Package/Project Number	Bridge/Road Name	Length (In m)
1.	MGSY/24-25-Lakhisarai/02	Construction of RCC HL Bridge on Road Rambal Bigha Naya tola Bhalui	67.08

Pankaj Kumar Pawan

Executive Engineer
RWD Works Division
Lakhisarai

07/07/25

AGREEMENT No-09/CMBD/ (MGSY)/2025-2026.

1. Name of Work :- Construction of Bridge with maintenance for Tender Group No.- SETU/MGSY/24-25-Lakhisarai/0`2.
2. Name of Agency :- Pankaj Kumar Pawan, C/o- Sri Shyam Dev Prasad, Munger Road near Dariyapur Charch, PO.- Jamalpur, Dist.- Munger.
3. Authority :- CE-3, R.W.D., Bhagalpur, Vide Letter No.-693 dated-10.06.2025
4. Agreement Value :- Construction cost - Rs. 4,72,66,948/-
Maintenance cost -Rs. 2,62,500/-
Total cost - Rs.4,75,29,448/-
5. Performance Security :-
6. Date of work Start :- 13.06.2025
7. Date of Commencement :- 07.07.2025
8. Date of completion :- 12.06.2027
9. No. of items of Work :- 57 (Fifty Seven) Only.
10. Rate Quoted :- (-) 0.55% (Zero Point Five Five Percent) Below.

Rdwr
7/7/25

As
Executive Engineer
RWD Works Division
Lakhisarai
Rakesh Kumar
7/6/25

Details of Agreement Under Tender Group No.-SETU/MGSY/24-25-Lakhisarai/02

Notation

Block :-Chanan, District :- Lakhisarai

Sl. No.	Name of Road	Length (In Km.)	Construction Cost (In Rs.)	Maintenance Cost (In Rs.)	Total Cost (In Rs.)	Notation
1	2	3	4	5	6	7
1	Construction of RCC HL Bridge on Road Rambal Bigha Naya tola Bhalui	67.08	4,72,66,948	2,62,500	4,72,29,448	A
Total=		67.08	4,72,66,948	2,62,500	4,75,29,448	

A) **TOTAL COST OF CONSTRUCTION IN**

Rs.- 4,72,66,948/-

B) **TOTAL COST OF MAINTENANCE FOR 5 YEARS IN**

Rs.- 2,62,500/-

Handwritten signature
7/7/15

Handwritten signature
Executive Engineer
RWD Works Division
Lakhisarai
Rakesh
7/7/15

Sl. No.	Item Description	Unit	Quantity	Rate	
36	Providing and Fixing 'Logo' of Project Informayory sign board with Logo as per MORD specifications and drawing. Three MS plates of 1.6mm thick, top and middle plate duly welded with MS flat iron 25mm x 5 m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 Nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600 mm, 600 mm, 600 below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12SWG steel plate tube. All M.S will be stove enameled on both sides. Lettering and printing arrows, border etc, will be painted with ready mixed synthetic enamer paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 abd Annexure 1700.1.	NO	3.000	10733.00	32199.00
37	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes.	Sqm	32.000	723.00	23136.00
38	Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC:25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	No	215.000	702.00	150930.00
E. DIVERSION					
39	Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m , transporting to the site spreading , grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5 .	Cum	1,200.000	241.07	289283.40
40	Granular Sub-base with Well Graded Material (Table 400.1) Grading II -Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	Cum	75.000	2009.02	150676.50
41	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row (2 ROW)	M	37.500	7046.66	264249.78
Total Construction Cost "A" =					39812906.37
42		Rs	1	7166323.15	7166323.15
43	Add GST 18%	Rs	1	398129.06	398129.06
44	Add labour Cess 1%	Rs	1	149700.00	149700.000
45	Add Seignorage Fee	Rs			47527058.578
46	Total Costruction Cost "A" Including GST =	Rs	1	39,715.00	39715.00
47	Total Cost for 1st Year Maintenance Work	Rs	1	41,859.00	41859.00
48	Total Cost for 2nd Year Maintenance Works	Rs	1	44,273.00	44273.00
49	Total Cost for 3rd Year Maintenance Works	Rs	1	46,508.00	46508.00
50	Total Cost for 4th Year Maintenance Works	Rs	1	48,742.00	48742.00
51	Total Cost for 5th Year Maintenance Works	Rs	1		

आयकर विभाग
INCOME TAX DEPARTMENT

भारत सरकार
GOVT. OF INDIA

PANKAJ KUMAR PAWAN

SHYAMDEO PRASAD

15/02/1984
Permanent Account Number
BIFPP6289Q

Pankaj Kumar Pawan
Signature

