

भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये

रु.1000

ONE THOUSAND RUPEES

Rs.1000

बिहार BIHAR

ANNEX- B

AGREEMENT No.: 20/Awsesh / 25-26.

This Agreement made the 27th day of Sept. 2025 Between

The ("The E/I") Executive Engineer R.W.D. Works Division, Bettiah of the one part and Sri Rahul Kumar, At- Khushi Tola, Khiriya Ghat, Ward No. 05, Po- Bettiah, Ps.-Bairiya, West Champaran [Name & address of Contractor] ("The Contractor") of the other part.

Whereas the E/I is desirous that the Contractor execute Construction of road/bridge and performance based Rural Road contract for the Routine Maintenance (output and performance based) of Roads/Construction of Bridge MMGSY(AWSESH-ST)-BETTIAH-36 (Tendar ID-141519) Under MMGSY AWSESH-ST (hereinafter called "The Construction Works & Routine Maintenance") and the E/I has accepted the Bid by the Contractor for the execution of such The Construction Works & Routine Maintenance and the remedying of any defects therein, at a contract price of Rs. 1,55,16,721.00 (Rs. One Crore Fifty Five Lac Sixteen Thousand Seven Hundred Twenty One Only).

S.N.	Package/Project Number	Road Name	Length (KM)
1	MMGSY(AWSESH ST)-BETTIAH-36	Purendrapur Chakla to Kunjlahi	1.240

Rahul Kumar

EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION
BETTIAH, W. CHAMPARAN

NOW THIS AGREEMENT WITNESSETH and the Parties hereto agree as follows:

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the General condition hereafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the E/I to the Contractor as herein after mentioned, the Contractor hereby covenants with the E/I to execute and complete the **Construction Works & Routine Maintenance** and remedy any defects therein in conformity in all aspects with the provisions of the contract.
3. The E/I hereby covenants to pay the Contractor in consideration of the execution and completion of the Works and the remedying the defects wherein the contract price or such other sum as may become payable under the provisions of the contract at the times and in the manner prescribed by the contract.
4. The following documents shall be deemed to form and be read and construed as part of this Agreement, viz:
 - i) Letter of Acceptance
 - ii) Contractor's Bid
 - iii) Section VI – General Conditions,
 - iv) Section VII – Particular Conditions
 - v) Section V – Technical Specifications (General and Supplementary Technical Specifications)
 - vi) Appendix A –Drawings
 - vii) Section IV – Works Schedule/BOQ
 - viii) Quality Plan for Output and Performance Based Road Contract as per Clause A14.1 of the Technical Specifications
 - ix) Appendices to the Contract
 - x) Addenda issued during bid period
 - xi) Any other relevant documents listed in the Particular Conditions together with any post bid correspondence.

In witness whereof the parties thereto have caused this Agreement to be executed the day and year first before written.

The Common Seal of

was here unto affixed in the presence of :

Signed, sealed and delivered by the said

in the presence of:

Binding Signature of E/I

Binding Signature of Contractor

Rahul Kumar

EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION
BETTIAH, W. CHAMPARAN
27/9/25


Name of Agency :- **Sri Rahul Kumar,**
At- Khushi Tola, Khiriyah Ghat,
Ward No. 05, Po- Bettiah,
Ps.- Bairiya, West Champaran
Email- rahulrao129@gmail.com
Mob- +91 +91 97095 68171

Name of Work: - **MMGSY (AWSESH-ST)-BETTIAH-36 (Tendar ID-141519) Under MMGSY
AWSESH-ST**

S.N.	Package/Project Number	Road Name	Length (KM)
I	MMGSY(AWSESH ST)-BETTIAH-36	Purendrapur Chakla to Kunjlahi	1.240

Agreement no. :- 20 / Awseesh / 25-26.
W/O Letter issued by :- 1. Office of the Engineer-in-chief
vide Lt No (Enc), Date-.....
2. C.E-05, BIHAR, PATNA
Letter No.-3141Enc, Date-04.09.2025
LOA Letter No. and Date :- Lt No-1284, Date-09.09.2025
Agreement value :- **Rs. 1,55,16,721.00**
Construction Cost :-
Maintenance Cost :-
Date of work order :-
Time of Completion :-
Performance Security :- **Rs 8,14,628.00**
Additional Performance Guarantee :- **Rs. 38,792.00**
Security Deduct from bill :- %
Rate :- **(-) 0.05% Below**

Rahul Kumar


EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION
BETTIAH, W. CHAMPARAN
27/9/25

**OFFICE OF THE EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION BETTIAH**

Email:- ee.bettiah@gmail.com

Phone:- +91 89869 15267

Letter No 1284

Bettiah, Date 09.09.2025

From,

Executive Engineer,
Rural Works Department
Works division Bettiah.

To,

Sri Rahul Kumar,
At- Khushi Tola, Khiriya Ghat,
Ward No. 05, Po- Bettiah,
Ps.- Bairiya, West Champaran
Email- rahulrao129@gmail.com
Mob- +91 +91 97095 68171

Sub:- Letter of Acceptance.

Dear Sir,

This is to notify that your Bid dated _____ for execution of the Road from MMGSY(AWSESH-ST)-BETTIAH-36 (Tendar ID-141519) Under MMGSY AWSESH-ST for the Contract Rs. 1,55,16,721.00 (Rs. One Crore Fifty Five Lac Sixteen Thousand Seven Hundred Twenty One Only) as corrected and modified in accordance with the Instructions to Bidders is hereby accepted by our Agency.

You are hereby requested to furnish Performance Security, in the forms detailed in Para 34.1 of the ITB for an amount equivalent to Rs. 8,14,628.00 (P.S. Rs. 7,75,836.00 & Add. Security for unbalanced bid Rs. 38,792.00) within 15 days of the receipt of this L.O.A. valid up to 28 days from the date of Expiry of defect liabilities period i.e. up to _____ and sign the contract. If the Performance Security is in the form of a Bank Guarantee, the period of validity of Bank Guarantee could be one year initially, however, the Contractor would get this Bank Guarantee extended in such a way that an amount equal to the requisite Performance Security is always available with the Employer until 45 days after the lapse of Defects Liability Period failing which action as stated in Cl. 30.3 of ITB will be taken.

2. You are also requested to indicate your nominee as required under Clause 53.2 of the GCC.

Your faithfully

[Signature]

Executive Engineer,
Rural Works Department,
Works division Bettiah.

**EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION
BETTIAH, W. CHAMPARAN**
29/9/25

Rahul Kumar

मुख्य अभियंता-5 का कार्यालय,
ग्रामीण कार्य विभाग, बिहार, पटना।

पत्रांक- II/गुओ-5 पओपु-1-315/25
प्रेषक,

314।

/पटना, दिनांक-04-09-25

ई0 जय किशोर ठाकुर,
मुख्य अभियंता-5,
ग्रामीण कार्य विभाग, बिहार, पटना।

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बैतिया।

विषय: शीर्ष MMGSY(AWSESH-ST) अन्तर्गत कार्य प्रमंडल, बैतिया के अधीन MMGSY(AWSESH-ST)-
Bettiah-36 (Tender ID-141519) पथ निर्माण कार्य के निविदा निष्पादन के संबंध में।
महाराय,

- शीर्ष MMGSY(AWSESH-ST) अन्तर्गत कार्य प्रमंडल, बैतिया के अधीन MMGSY(AWSESH-ST)-
Bettiah-36 (Tender ID-141519) पथ निर्माण कार्य के निविदा के वित्तीय बीड में सफल न्यूनतम
निविदाकार **Rahul Kumar (817233)** को उनके द्वारा उद्धृत दर जो कि परिमाण विपत्र की दर से 0.05 प्रतिशत
कम है, अर्थात् कुल राशि 1,55,16,721.00 (एक करोड़ पचपन लाख सोलह हजार सात सौ इक्कीस) रु0 मात्र पर
कार्यहित एवं आपकी अनुशंसा के आलोक में यह कार्य आवंटित किया जाता है।
- निविदा की स्वीकृति सिर्फ इसी कार्य के लिए है, जो भविष्य में पूर्वाधारण नहीं होगा।
 - कार्यपालक अभियंता, कार्य प्रमंडल, बैतिया संवेदक के द्वारा एकरारनामा के लिए जमा की गई राशि एवं निविदा
के साथ अग्रघन के रूप जमा किये गये संबंधित एन0एस0सी0/पासबुक/बैंक फिक्स डिपोजिट/बैंक गरांटी की
सत्यता एवं वैधता आदि का सत्यापन कराकर प्रमंडलीय कार्यालय में अभिलेखित करेंगे एवं कार्यदेश निर्गत करने के
पूर्व अग्रघन की राशि के सत्यापन से संबंधित कागजात अधोहस्ताक्षरी को उपलब्ध कराया जाना सुनिश्चित करेंगे।
 - एकरारनामा के पूर्व निविदा सूचना के अनुसार सभी वांछित कागजातों की अद्यतन स्वच्छ एवं सत्यापित प्रति
निश्चित रूप से प्राप्त कर लिया जाय एवं साथ में इसकी भी जाँच कर ली जाय कि संवेदक डीबार सूची एवं काली
सूची से मुक्त है।
 - कार्य में व्यवहृत सामग्रियों का दर प्राक्कलन में स्वीकृत लीड के आधार पर दिया गया है, कार्य कराते समय
अगर इसमें कमी पाई जाती है तो उसके दर में सापेक्ष कमी कर दी जायेगी।
 - अधीक्षण अभियंता एवं कार्यपालक अभियंता अग्रतर कार्रवाई से पूर्व भली भौति आश्वस्त हो लेंगे कि पथ का
हस्तांतरण हेतु विभाग द्वारा अनापत्ति प्रमाण पत्र निर्गत नहीं किया गया है।
 - इस कार्य के संबंध में ग्रामीण कार्य विभाग, बिहार सरकार द्वारा निर्गत प्रशासनिक स्वीकृति एवं प्रावैधिक स्वीकृति
तथा निविदा आमंत्रण सूचना में उल्लिखित शर्त एकरारनामा का भाग होगा, जिसे विशेष शर्त में जोड़कर संवेदक
के साथ एकरारनामा किया जायेगा।
 - अनुमोदित किये गये तुलनात्मक विवरणी के प्रत्येक बिन्दु की जाँच अपने स्तर से स्वयं कर लेंगे एवं त्रुटि पाये
जाने की स्थिति में वस्तुस्थिति से तत्क्षण अधोहस्ताक्षरी को अवगत करायेगे। त्रुटि के सुधारोपरान्त एकरारनामा की
कार्रवाई की जायेगी।
 - एकरारनामा के समय प्रत्येक मद के भाषा की शुद्धता की जांच कार्यपालक अभियंता स्वयं कर लेंगे एवं यह
सुनिश्चित करेंगे कि इसमें कोई त्रुटि न हो।
 - कार्यारम्भ के पूर्व कार्यपालक अभियंता कार्य स्थल के निरीक्षणोपरान्त स्थल की स्थिति एवं प्राक्कलन में किये
गये उपबंध से पूरी तरह आश्वस्त हो लेंगे एवं प्रशासनिक स्वीकृति तथा प्रावैधिक स्वीकृति के अग्रसारण प्रारूप में
दिये गये निदेश का अनुपालन सुनिश्चित करायेंगे।
 - कार्यदेश निर्गत करने से पहले संबंधित संवेदक से एकारारित अवधि के अन्दर कार्य समाप्त करने हेतु विस्तृत
मदवार कार्य प्रोग्राम प्राप्त कर ही एकरारनामा किया जाय।
 - अधीक्षण अभियंता एवं कार्यपालक अभियंता विशेष रूप से ध्यान देंगे कि कार्य मानक विशिष्टियों के अनुरूप
निर्धारित कार्य अवधि के अंदर पूरा की जाय।
 - कार्य समाप्ति की अवधि परिमाण विपत्र के अनुसार होगी।
 - कार्यपालक अभियंता कार्य आवंटित किये गये संवेदक से 10 दिनों के अन्दर एकरारनामा कराना सुनिश्चित
करेंगे अन्यथा उनके अग्रघन की राशि जब्त कर ली जाय।
 - इस कार्य का व्यय विभाग द्वारा निर्गत प्रशासनिक स्वीकृति में अंकित शीर्ष अन्तर्गत होगा।

Rahul Kumar

EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION
BETTIAH, W. CHAMPARAN
22/9/25

16. एकरारनामा के समय प्राक्कलन के अनुसार इस कार्य को पूरा करने हेतु संवेदक से मदवार कार्य योजना एकरारनामा के समय प्राप्त किया जाय तथा उस कार्य योजना की प्रति संबंधित कनीय अभियंता एवं सहायक अभियंता को भी उपलब्ध कराया जाय, ताकि कनीय अभियंता एवं सहायक अभियंता निर्धारित समय के साथ मदवार प्रगति का आकलन कर कार्यपालक अभियंता एवं संबंधित संवेदक को सूचित प्रत्येक 15 दिनों पर करेंगे। अगर संवेदक द्वारा निर्धारित समय के अन्दर उक्त मद के मात्रा का लक्ष्य प्राप्त नहीं किया गया तो कार्यपालक अभियंता दंडात्मक कार्रवाई संवेदक के विरुद्ध करेंगे। कार्यपालक अभियंता अगर उक्त निदेश का पालन नहीं करते हैं तो वे स्वयं कार्रवाई के पात्र होंगे।

17. सभी निविदा कागजात एवं तुलनात्मक विवरणी की मूल प्रति आवश्यक कार्रवाई हेतु लौटाई जाती है। आप निविदा कागजातों एवं तुलनात्मक विवरणी के जांचोपरान्त आप आवश्यक निदेशों को अपने स्तर से निर्गत करेंगे।

18. एकरारनामा से पहले निविदाताओं द्वारा दिये गये कागजात का सत्यापन उनके मूल कागजात से मिलान कर ली जाय।

19. इस निविदा की राशि में अगर कोई अंतर होता है तो इसकी सूचना तुरन्त इस कार्यालय को दी जाय।

20. कार्यपालक अभियंता, एकरारनामा करने के पूर्व संवेदक का निबंधन संख्या पूर्ण पता एवं दूरभाष संख्या कार्यादेश में अंकित करेंगे तथा इस कार्यालय को सूचित करेंगे।

21. परिमाण विपत्र की दर से कम दर उद्धृत करने वाले संवेदक से विभाग द्वारा पूर्व में निर्गत दिशा निदेश के आलोक में अतिरिक्त वांछित परफॉर्मेंस सिक्युरिटी की राशि जमा कराना सुनिश्चित करेंगे।

22. किसी भी परिस्थिति में निजी जमीन पर निर्माण नहीं कराया जाय।

23. प्रत्येक 15 दिनों पर संवेदक से स्वहस्ताक्षरित विपत्र प्राप्त कर स्थल से मिलान कर मापी पुस्तिका में मापी दर्ज कर भुगतान सुनिश्चित करेंगे।


24. संवेदक से बीड वैधता का प्रमाण लेने के पश्चात ही एकरारनामा करना सुनिश्चित करें।

25. कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, बेतिया को निदेशित किया जाता है कि विभागीय पत्रांक-मु0अ0-4-(मु0) विविध-23-291/2014-131 पटना दिनांक-13.12.2019 के आलोक में पत्र प्राप्ति के 24 घंटा के भीतर Letter of Acceptance (LOA) संबंधित संवेदक को निर्गत कर इसकी सूचना इस कार्यालय को भी उपलब्ध कराना सुनिश्चित करेंगे।

26. संवेदक के चरित्र प्रमाण पत्र के संबंध में निर्गत विभागीय पत्रांक-489 अनु0 दिनांक-28.01.2021 को अनुपालन करना सुनिश्चित करेंगे। कृपया पत्र प्राप्ति की सूचना देंगे।

अनु0-यथा उपर्युक्त।


विश्वासभाजन


मुख्य अभियंता-5, पटना

/पटना, दिनांक-04.09.25

ज्ञापांक- 3141


प्रतिलिपि: अभियंता प्रमुख-सह-अपर आयुक्त-सह-विशेष सचिव, ग्रामीण कार्य विभाग, बिहार, पटना को सूचनार्थ समर्पित।


मुख्य अभियंता-5, पटना

/पटना, दिनांक- 04.09.25

ज्ञापांक- 3141


प्रतिलिपि : अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, बेतिया को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित।


मुख्य अभियंता-5, पटना

/पटना, दिनांक-04.09.25

ज्ञापांक- 3141

प्रतिलिपि : सहायक आई0टी0 मैनेजर, मुख्य अभियंता-5 का कार्यालय, ग्रामीण कार्य विभाग, बिहार पटना को सूचनार्थ एवं ई-मेल पर अपलोड करने हेतु प्रेषित।


मुख्य अभियंता-5, पटना

Rahul Kumar

EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION
BETTIAH, W. CHAMPARAN
23/9/25

मुख्य अभियंता-5, मुजफ्फरपुर का कार्यालय,

ग्रामीण कार्य विभाग, बिहार, पटना।

पत्रांक-11/मु0अ0-5,त0स्वी0-07-48/24

1912 (अ15)

/पटना,दिनांक- 15/5/25

प्रेषक,

मुख्य अभियंता-5,

ग्रामीण कार्य विभाग,

बिहार, पटना।

सेवा में,

अधीक्षण अभियंता,

ग्रामीण कार्य विभाग,

कार्य अंचल, बेतिया

विषय:- शीर्ष **MMGSY (अवशेष) योजना** अन्तर्गत कार्य प्रमंडल, बेतिया के अधीन स्वीकृत 26 अदद पथों के प्राक्कलन पर प्रावैधिक स्वीकृति प्रदान करने के संबंध में।

प्रसंग:- आपका पत्रांक-451 अनु0 दिनांक-13.05.2025

महाशय,

उपर्युक्त विषयक प्रासंगिक पत्र द्वारा प्राप्त कार्य प्रमंडल, बेतिया के अधीन स्वीकृत पथों के प्राक्कलन पर प्रावैधिक स्वीकृति प्रदान कर लौटाया जा रहा है। प्रावैधिक स्वीकृति की राशि पत्र के साथ संलग्न परिशिष्ट 'क' के स्तम्भ 07 में अंकित है।

2. बिहार सरकार के ग्रामीण कार्य विभाग के पत्रांक-804, 805 दिनांक-28.04.2025 के द्वारा प्रशासनिक अनुमोदन प्राप्त है, जो कि पत्र के साथ संलग्न परिशिष्ट 'क' के स्तम्भ 05 एवं 06 में अंकित है।
3. निर्माण कार्य योजना की मार्गदर्शिका के अनुरूप किया जाएगा।
4. स्वीकृत प्राक्कलन की जाँच अधीक्षण अभियंता अपने स्तर से भी कर लेंगे। यदि किसी प्रकार के संशोधन की आवश्यकता हो तो मुख्यालय को सूचित करेंगे।
5. स्थल निरीक्षण के आधार पर यह सुनिश्चित किया जाये कि प्राक्कलनित पुल/पुलियों स्थल के आवश्यकता के अनुरूप है। स्थल के अनुरूप नहीं होने पर मुख्यालय को सूचित किया जाये।
6. अधीक्षण अभियंता पथों का निरीक्षण प्रतिवेदन एवं कार्यों के संबंध में समीक्षात्मक टिप्पणी मुख्यालय को प्रत्येक माह की 5वीं तिथि को उपलब्ध कराना सुनिश्चित करेंगे।
7. प्राक्कलन की स्वीकृति को दसों की स्वीकृति न समझी जाए।
8. अधीक्षण अभियंता, ग्रा0का0वि0, कार्य अंचल, बेतिया ऐसे मदों के दर, जो अनुसूचित दर में नहीं हैं, का दर विशलेषण केन्द्रीय अनुसूचित दर निर्धारण समिति के संयोजक एवं उनके सभी सदस्य को भेजेंगे और समिति की अगली बैठक में उनका अनुमोदन प्राप्त कर लेंगे।
9. प्राक्कलन में क्षेत्रीय पदाधिकारी द्वारा प्रतिवेदित लम्ब काट एवं आड़ी काट के आधार पर मिट्टी की मात्रा की गणना की गयी है।

अनु0-स्वीकृत प्राक्कलन की मूल प्रति।

ज्ञापांक-

1912

/पटना, दिनांक- 15/5/25

प्रतिलिपि : कार्यपालक अभियंता, ग्रा0का0वि0, कार्य प्रमंडल, बेतिया को सूचनार्थ एवं आवश्यक कार्रवाई हेतु अग्रसारित।

विश्वासभाजन

(Signature)
14-05-25

मुख्य अभियंता-5

मुख्य अभियंता-5

EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION
BETTIAH, W. CHAMPARAN

Rahul Kumar

प्रावैधिक टिप्पणी

परियोजना का नाम :-

परिशिष्ट 'क' के स्तम्भ 3 के अनुसार

प्रशासनिक स्वीकृति की राशि एवं प्रसंग:- परिशिष्ट 'क' के स्तम्भ 5 से 6 के अनुसार


विवरण

1. प्रावैधिक स्वीकृति की राशि परिशिष्ट 'क' के स्तम्भ 7 में अंकित राशि पर सीमित की गई है। योजना के कार्यान्वयन के क्रम में व्यय की राशि स्वीकृत प्रावैधिक की राशि से अधिक नहीं होगा।
2. प्राक्कलन की स्वीकृति से दरों की स्वीकृति कदापि नहीं समझा जाये।
3. निर्माण कार्य एम0एम0जी0एस0वाई0 योजना की मार्गदर्शिका के अनुरूप किया जाएगा।
4. प्राक्कलन की भाषा संक्षिप्त और प्रतीकारात्मक मात्र है, यह अपने आप में पूर्ण नहीं है। अतः परिमाण विपत्र तैयार करते समय पूर्ण विशिष्टि लिखी जाये ताकि संवेदक किसी प्रकार का अनुचित लाभ न उठा सके।
5. कार्यारम्भ करने से पहले अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, बेतिया की व्यक्तिगत जिम्मेवारी होगी कि वे स्वयं कार्य स्थल का निरीक्षण कर संतुष्ट हो लें, कि स्वीकृत प्राक्कलन में प्रस्तावित पुल/पुलिया कार्य स्थल की आवश्यकता के अनुरूप है, क्योंकि प्राप्त प्रस्ताव को अपर्याप्त जलीय आंकड़ा की अनुपलब्धता की स्थिति में अनुमोदित किया गया है। यदि इनके निरूपण/विस्तृत आरेखन की आवश्यकता समझते हों तो सक्षम प्राधिकार से इसकी स्वीकृति प्राप्त कर ली जाए तथा उनके प्रस्ताव में कोई परिवर्तन नहीं किया गया है, इसके स्थल चयन आकार प्रकार की जिम्मेवारी पूरी तरह से अधीक्षण अभियंता की होगी।
6. प्रावैधिक स्वीकृति की राशि के अन्तर्गत योजना के कार्यान्वयन में प्राथमिकता निम्न प्रकार से दी जायेगी:-
प्रस्तावित स्थलों पर पुल/पुलियों का निर्माण
अंतिम लेयर छोड़कर पथ बांध की मिट्टी कार्य
7. कार्य प्रारंभ करने के पूर्व पथ के सतह की प्रोसेक्सन निगरानी विभाग के परिपत्र के अनुसार कर लेंगे।
8. पथ निर्माण के लिए एन0एन0आर0डी0ए0/एस0टी0ए0 द्वारा निर्धारित मापदंडों के अनुरूप कराया जाय।
9. मिट्टी की गणना की मात्रा एवं लागत संलग्न आडीकाट एवं लम्ब काट के आधार पर है, यह मानते हुए गणना की गयी है कि आडीकाट में जमीन उपलब्ध है।
10. मिट्टी कार्य, पुलिया कार्य में पथ बांध का स्लोप स्वीकृत प्राक्कलन के अनुरूप रखा जाय तथा मिट्टी की चपाई विशिष्टि के अनुरूप किया जाये।
11. निर्माण में व्यवहृत सामग्री एवं स्वीकृत मदों के कार्यान्वयन में Rural Roads Specification तथा Rural Roads Manual की विशिष्टि का अनुसरण किया जाये।
12. मिट्टी कार्य पुलिया कार्य स्वीकृत प्राक्कलन के अनुसार पूर्ण होने के पश्चात अधीक्षण अभियंता स्वयं निरीक्षण कर संतुष्ट हो लेंगे, तत्पश्चात ही आगे कार्य कराने की स्वीकृति देंगे।
13. विभिन्न मदों की स्वीकृत परिमाण में कोई वृद्धि अनुमान्य सीमा से अधिक पूर्वानुमति के नहीं किया जाये।
14. पथों के निर्माण में कैम्बर, ग्रैडियंट आदि पर पूर्ण ध्यान दिया जाये।
15. अधीक्षण अभियंता सामग्रियों की दुलाई के संदर्भ में वास्तविक दूरी, परिमाण से आश्वस्त हो लेंगे, तदोपरान्त ही निविदा संबंधी कार्रवाई की जाये।
16. निविदा आमंत्रण/निष्पादन में एम0एम0जी0एस0वाई0 योजना की मार्गदर्शिका एवं विभाग से निर्गत आदेशों का कठोरता से पालन किया जाये।
17. अधीक्षण अभियंता/कार्यपालक अभियंता कार्य प्रारम्भ करने से पूर्व सुनिश्चित करेंगे कि इस कार्य से किसी भी तरह से एम0एम0जी0एस0वाई0 योजना की मार्गदर्शिका के निर्देशों का उल्लंघन न हों।
18. स्वीकृत कार्य के विरुद्ध अगर किसी तरह का कार्य अन्य एजेंसी के द्वारा कराया गया हो तो इसकी लागत कार्य की लागत से नियमानुकूल घटा ली जाये।
19. प्राक्कलन की विशिष्टि में परिवर्तन मुख्यालय की स्वीकृति के बिना नहीं किया जाये।
20. स्वीकृत प्राक्कलन में वर्णित कार्य स्वीकृत राशि के अन्तर्गत समय-सीमा के अनुरूप हो।
21. मिट्टी कार्य कराने के पूर्व आश्वस्त हो ले कि एफ0एल0 बाढ़ स्तर के अनुरूप हो।

Ravi Kumar

EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION
BETTAH, W. CHAMPARAN
21/12/25

22. गुणवत्ता की जांच विभाग के द्वारा गुण-नियंत्रण आई0आर0सी0 के विशेष प्रकाशन-11 के प्रावधान के अनुरूप किया जाये।
23. जिन कार्यों का दर अनुसूचित दर पुस्तिका में नहीं है उस स्थिति में क्षेत्रीय पदाधिकारियों द्वारा अंकित दर वगे मान लिया गया है, परन्तु ऐसे मदों के दर का दर विश्लेषण क्षेत्रीय अनुसूचित दर निर्धारण समिति के संयोजक एवं उनके सभी सदस्यों को भेजेंगे और समिति की अगली बैठक में उनका अनुमोदन प्राप्त कर लेंगे, यदि आवश्यक हुआ तो।
24. पूर्व में कराए गए कार्यों से प्राप्त सामग्रियों का लेखा में प्रविष्ट करते हुए सक्षम पदाधिकारी से अनुमोदनोपरान्त निर्माण में प्रयुक्त किया जाये।
25. मिट्टी एवं अन्य कार्य का भुगतान सम्पादित कार्य के अनुसार किया जाये।
26. विलेष्टि के अनुरूप कार्य करने हेतु आवश्यक यंत्र-संयंत्र एवं उपकरणों की उपलब्धता की जांच कार्यपालक अभियंता स्वयं कर प्रमाण-पत्र देंगे।
27. प्राक्कलन में प्रयुक्त तकनीकी आँकड़ों को स्थल निरीक्षण के आधार पर सम्पुष्ट करने के उपरान्त ही कार्य प्रारम्भ किया जाय, यदि इनमें भिन्नता पायी जाती है तो प्राक्कलन संशोधन हेतु प्रस्ताव तत्काल अधोहस्ताक्षरी को समर्पित किया जाए।
28. सामग्रियों की ढुलाई निर्धारित रेल हेड के लोडिंग/अनलोडिंग स्थल तक रेलमार्ग से एवं तत्पश्चात् वहां से कार्य स्थल तक ट्रक द्वारा तथा क्वैरी से सीधे कार्य स्थल तक सड़क मार्ग द्वारा दर विश्लेषण कर न्यूनतम दर का प्रावधान अधीक्षण अभियंता, सुनिश्चित करेंगे।
29. अधीक्षण अभियंता अपने स्तर से दर विश्लेषण की जांच कर लेंगे। यदि त्रुटि हो, तो अपने स्तर से सुधार कर इस कार्यालय को सूचित करेंगे।


 मुख्य अभियंता-5,

Rahul Kumar

EXECUTIVE ENGINEER
 R.W.D. WORKS DIVISION
 BETTIAH, W. CHAMPARAN
 21/7/23

ग्रामीण कार्य विभाग, कार्य प्रमण्डल, बेतिया के अधीन सीव MMGSY
(अवधीय) प्राथमिक स्वीकृति प्रदत्त योजनाओं की सूची।

S. No.	Name of Division	Name of Block	Road Name	Administrative Approval			T.S. Cost (Rs.in lakhs)
				Length (in Kms)	Department Ref Lett. No. & Date	A.A Cost (Rs.in lakhs)	
1	2	3	4	5	6	7	8
1	बेतिया	मंडौलिया	Naval Kishor singh ke Bagicha se Tatwa Tola	0.980	805/28.04.25	108.640	106.11
2	बेतिया	मंडौलिया	Nautan Khurd PMGSY Road To Nautan Khurd	2.150	804/28.04.25	261.970	256.63
3	बेतिया	मंडौलिया	Nanosati Jagdishpur Road to Kohar Toli	1.300	804/28.04.25	166.440	163.37
4	बेतिया	मंडौलिया	Jagiraha se Jagdishpur	1.500	804/28.04.25	210.560	206.77
5	बेतिया	बेतिया	Bara Barwat Tola to To Barwat Lachhu Tola	0.800	804/28.04.25	78.120	76.66
6	बेतिया	मंडौलिया	Jagarnath Das Tola To L036 Buchun Sah ke Tola	1.200	804/28.04.25	162.290	159.59
7	बेतिया	मंडौलिया	Babu Tola Madhopur To Shivrinar	1.060	804/28.04.25	165.060	162.11
8	बेतिया	बेतिया	RCD Road To Devi Sthan Hajma Tola	0.870	804/28.04.25	94.390	92.80
9	बेतिया	मंडौलिया	Gora Semara To L029	1.200	804/28.04.25	131.220	127.98
10	बेतिया	मंडौलिया	Karamwa Bazar To Bharaliya Tal	74.320	804/28.04.25	74.320	71.62
11	बेतिया	मंडौलिया	T03 Dhangar Toli Main Road To Chimni Shivpujan Sah Tak	1.500	804/28.04.25	203.050	200.76
12	बेतिया	बेतिया	Pmgsy Road To Baria Paswan Tola	1.550	804/28.04.25	137.550	135.80
13	बेतिया	मंडौलिया	Bahurwa Kachahri Tola Ward No 07 To Pokhra Sagauli Main Road	2.300	804/28.04.25	229.340	221.66
14	बेतिया	नीतन	Purendra pur Chkla To Kujalahi	1.240	805/28.04.25	158.380	156.19
15	बेतिया	बेतिया	House of Jogendra PD To Mahavir Das ke Tola	1.040	804/28.04.25	133.550	131.23
16	बेतिया	मंडौलिया	L036 Gobri Sahni ke Tola to Manu Kushwaha Tola	1.950	804/28.04.25	225.370	220.38
17	बेतिया	मंडौलिया	Majhauilya Jagdishpur PWD Road (Pokhara Chowk) To Kohar Toli Anirudh Ram ke Ghar TK	2.700	804/28.04.25	302.630	295.75
18	बेतिया	बेतिया	MR Road To Pokharbhinda Musahar Tola	2.210	804/28.04.25	241.170	237.06
19	बेतिया	मंडौलिया	Majhauilya To Harijan Tola	1.400	804/28.04.25	160.100	160.08
20	बेतिया	बेतिया	Raktu Chaudhary ka Tola To Dokari Pul	1.800	804/28.04.25	183.150	180.96
21	बेतिया	मंडौलिया	Nanosati Jagadishpur RCD Road to Sukhlahi Pul Thakur Ji mandir tak	1.840	805/28.04.25	165.030	159.09
22	बेतिया	बेतिया	Lalan Rao ka tola se Sohan Ram ke Tola Tak	0.800	804/28.04.25	77.440	76.39
23	बेतिया	बेतिया	Rajan patel ke Gawas To Muslim tola ward No6	0.700	804/28.04.25	71.960	70.31
24	बेतिया	मंडौलिया	T02 To Toli Tola	1.850	804/28.04.25	249.610	246.27
25	बेतिया	मंडौलिया	saifuddin Ansari ke Ghar To ahwar Shek Moujhe Tola Tk	2.370	804/28.04.25	273.500	270.86
26	बेतिया	मंडौलिया	Rulhi Hanuman Mandir To Bishambhara Ward no.8	1.200	804/28.04.25	141.220	141.63

मुख्य अभियंता-5
ग्रामीण कार्य विभाग,
बिहार पटना

RURAL WORKS DEPARTMENT
Office of the Engineer-in-Chief,
Rural Works Department, Bihar
5th floor, Visvesvaraya Bhawan, Nehru Path, Patna-800015

DETAILED NOTICE INVITING TENDER
(through e-procurement mode only <http://pmgsytendersbih.gov.in>)

Construction and 06 year Routine Maintenance work (output and performance based) for Rural Road/Bridge under component of Mukhya Mantri Gram Sampark Yojana (AWSESH-ST).

Notice Inviting Tender (No.-RWD/MMGSY(AWSESH-ST)/HQ/ET/2025-26/01)

Designation and Address of the Advertiser : Engineer-in-chief, Rural Works Department, Govt. of Bihar
Date of Notice Inviting Tender : 02.05.2025
Period for download of Tender Document : From 19.05.2025 to 28.05.2025 up to 1500 hrs
Date, Time & Place of Pre-Bid meeting : Date 20.05.2025 at Concerned office of SE from 1100 hrs
Date & Time for uploading tender documents by bidder : Date 28.05.2025 till 1500 hrs. <http://pmgsytendersbih.gov.in>
Date and time of opening of Technical Bid : Date 28.05.2025 Time 1530 hrs.

Details of Works and Services:

Package	Description of the Works [CONSTRUCTION AND MAINTENANCE OF ROADS/BRIDGE]		Length (km/m)	Construction cost (in lakh)	Cost of Routine Maintenance for 72 Months Period (in lakh)	Total Amount (in lakh)	Earnest Money / Bid Security (in lakh)
2	3	4	5	6	7	8	9
MMGSY(AWSESH-ST)-FORBISGANI-01	Srinagar Badi Nahar	Mirchar badi Adiwasi Tola	1.500	426.792	47.196	473.988	9.48
Total	1		1.500	426.792	47.196	473.988	9.48
MMGSY(AWSESH-ST)-BANKA-1-02	Gadal More	Baliya Santhal Tola	1.200	151.730	15.060	166.790	3.34
	Khaira More	Parasbani Santhal Tola	1.500	224.430	23.620	248.050	4.96
Total	2		2.700	376.160	38.680	414.840	8.30
MMGSY(AWSESH-ST)-BANKA-1-03	DUDHARI CHHATARPAL PMGSY ROAD, MANADDA MORE	HERIMOTI PANCHAYAT BHAWAN KALI SHTHAN	1.050	102.310	16.300	118.610	2.37
Total	1		1.050	102.31	16.3	118.610	2.37
MMGSY(AWSESH-ST)-BANKA-04	Kurpatari	Malhatari	0.600	132.630	4.820	137.450	2.75
Total	1		0.600	132.63	4.82	137.450	2.75
MMGSY(AWSESH-ST)-BANKA-05	Mohanpur Ghari iti College	Pokari Harijan Tola	1.500	218.390	23.430	241.820	4.84
Total	1		1.500	218.39	23.43	241.820	4.84
MMGSY(AWSESH-ST)-BANKA-2-06	Shyamabajar to Ratansara road Near primary School Sahupokhar	Diwan Soren	0.550	43.598	2.536	46.134	0.92
	Kuraro Gate	Marsa	0.630	57.060	4.326	61.386	1.23
Total	2		1.180	100.658	6.862	107.520	2.15
MMGSY(AWSESH-ST)-KAHALGAON-07	Manikpur Savaiya Road	Santhali Tola (Etwal)	2.080	169.240	13.510	182.750	3.66
Total	1		2.080	169.24	13.51	182.750	3.66
MMGSY(AWSESH-ST)-JAMUI-08	Khaira Soro Rcd Main Road	Rcd Road Nijuwara pull	3.620	322.956	30.439	353.395	7.07
Total	1		3.620	322.956	30.439	353.395	7.07
MMGSY(AWSESH-ST)-JAMUI-09	Kusutari Reo Road	Kusutari Adiwasi Tola	1.291	127.576	10.587	138.163	2.76
Total	1		1.291	127.576	10.587	138.163	2.76
MMGSY(AWSESH-ST)-JHAJHA-10	Saroun Bakshila Road	Karmatani Santhal Tola	5.500	552.06	67.97	620.030	12.40
Total	1		5.500	552.06	67.97	620.030	12.40
MMGSY(AWSESH-ST)-JHAJHA-11	Karngaris Bisodah Road	Karmatani Pani Tanki	2.000	197.17	20.81	217.980	4.36
	Jhajha Chakri SH Road	Silhu Tola	3.300	281.83	40.33	322.160	6.44
Total	2		5.300	479.000	61.140	540.140	10.80
MMGSY(AWSESH-ST)-JHAJHA-12	Bakshila Saron Pwd Road	Sanjhara	3.500	349.27	42.22	391.490	7.83
	Nakta Sagra Mr Road	Bhajusher More	2.800	286.03	36.02	322.050	6.44
	MAHESWARI NAW NIRMIT PRIMARY SCHOOL	JALKHARIA AJAY RIVER	2.600	224.69	31.63	256.320	5.13
Total	3		8.900	859.990	109.870	969.860	19.40
MMGSY(AWSESH-ST)-JHAJHA-13	Madhopur To Lahawan Road	Ghatiyani Adiwasi Tola	2.500	220.93	26.21	247.140	4.94
	Gopalamaran Tilouna Road End Point	Bagwa	2.410	291.59	31.88	323.470	6.47
Total	2		4.910	512.520	58.090	570.610	11.41
MMGSY(AWSESH-ST)-JHAJHA-14	Jaharthan More	Rajadumar Jore St Tola	2.200	202.96	24.51	227.470	4.55
	CHAKAI KIYAJORI RCD ROAD	CHANDRI ST TOLA	2.500	220.86	32.28	253.140	5.06
Total	2		4.700	423.820	56.790	480.610	9.61
MMGSY(AWSESH-ST)-JHAJHA-15	Tola Goswara	Jor	3.500	357.56	39.86	397.420	7.95
	Petarpanan Chandri Road	Koldiha	2.500	220.93	26.21	247.140	4.94
Total	2		6.000	588.830	71.820	660.650	13.21
MMGSY(AWSESH-ST)-JHAJHA-16	CHAKAI KIYAJORI RCD ROAD NEAR AGRA NADI PUL	DAMGI TOLA LEDWARA	2.650	365.59	34.57	400.160	8.00
	Near Panna School	Ghoswara	3.000	392.84	36.34	429.180	8.58
Total	2		5.650	758.430	70.910	829.340	16.59

17	MMGSY(AWSESH-ST)-JHAJHA-17	Churhat Bandemara Road Near Amethiyadih	Dewpahan	2.000	277.81	23.36	301.170	6.02
		Bernar Dam Pucca Road Irrigation Road Near Katahatand Chowk	Ukhariya Village	3.900	397.11	44.65	441.760	8.84
Total	2			5.900	674.920	68.010	742.930	14.86
18	MMGSY(AWSESH-ST)-JHAJHA-18	Sono Chakri Main Road Near Lauwaghat Badi Pedr	Asnatani Santhal Tola 1	2.200	212.490	26.240	238.730	4.77
		Khotwa Panari Road At 1 Skm	Purab Adiwasi Tola Panari	1.000	83.200	9.470	92.670	1.85
		Charkapathar Sarebad Road Near Transformer	Chargharwa	1.200	144.220	14.40	158.620	3.17
Total	3			4.400	439.910	50.110	490.020	9.80
19	MMGSY(AWSESH-ST)-BHABUA-19	Sarodag	Bandha	4.860	415.170	47.193	462.363	9.25
		Kolhua	Sikarwar (UP Boarder)	1.450	99.200	13.328	112.528	2.25
Total	2			6.310	514.370	60.521	574.891	11.50
20	MMGSY(AWSESH-ST)-BHABUA-20	Tamtam Mana	Turia Parwana	5.325	490.820	50.326	541.146	10.82
Total	1			5.325	490.82	50.326	541.146	10.82
21	MMGSY(AWSESH-ST)-BHABUA-21	Forest Blairrier Sikarwar	Kolhua Adiwasi Tola	5.700	517.490	56.784	574.274	11.49
		T01 Adhaura Yadav More	Adhaura Yadav Tola	0.870	70.340	7.217	77.557	1.55
Total	2			6.570	587.830	64.001	651.831	13.04
22	MMGSY(AWSESH-ST)-KATIHAR-22	NH31	Gondwara	1.963	201.457	28.828	230.285	4.61
Total	1			1.963	201.457	28.828	230.285	4.61
23	MMGSY(AWSESH-ST)-KATIHAR-23	Mid Babu Ke Ghar Se Sirajul Miya Ke Ghar Pokhar Hote Hue	Fucho Sharma Ke Ghar NH 31 Tak	1.965	272.41	26.711	299.121	5.98
Total	1			1.965	272.41	26.711	299.121	5.98
24	MMGSY(AWSESH-ST)-MUNGER-24	ITWA Bangalwa Pmgsy To Sharadhi Road	Aadiwasi Sharadhi Naya Tola	0.352	47.721	1.598	49.319	0.99
Total	1			0.352	47.721	1.598	49.319	0.99
25	MMGSY(AWSESH-ST)-DHAMDAHA-25	Baghwa naya tola	gangell pmgsy road	1.906	198.089	24.046	222.135	4.44
Total	1			1.906	198.089	24.046	222.135	4.44
26	MMGSY(AWSESH-ST)-DHAMDAHA-26	Goriyer to bhawanipur turki pmgsy road	Baghwari Rehmat Nagar	1.710	156.934	19.766	176.700	3.53
Total	1			1.710	156.934	19.766	176.700	3.53
27	MMGSY(AWSESH-ST)-DHAMDAHA-27	Sarsi Belagovind Road	Rajputahi Tola	1.032	160.19	15.526	175.716	3.51
Total	1			1.032	160.19	15.526	175.716	3.51
28	MMGSY(AWSESH-ST)-PURNEA-28	Shanti Path MMGSY Naasa Ghat	Aadiwasi Bans Tola	1.558	279.995	23.812	303.807	6.08
Total	1			1.558	279.995	23.812	303.807	6.08
29	MMGSY(AWSESH-ST)-SUPAUL-29	Nauabakher Ward No - 14, Mintu Mukhiya House	Shalendra Yadav House Tak	2.000	354.628	15.279	369.907	7.40
Total	1			2.000	354.628	15.279	369.907	7.40
30	MMGSY(AWSESH-ST)-SUPAUL-30	Ganga Petrol Pump Balba Panchayet Tanuk Paswan Ke Ghar	Ward No 5 Vijay Yadav Ghar Tak Fakirna Via Balba Ward 8, Ward 9	1.200	136.724	12.959	149.683	2.99
				2.275	303.781	13.816	317.597	6.35
Total	2			3.475	440.505	26.775	467.280	9.35
31	MMGSY(AWSESH-ST)-TRIVENIGANGA-31	50 Rd Rannipatti Nahar	Anganbari Kendra Ward No 11	2.350	305.881	24.44	330.321	6.61
		L053 Se Narhiya	Ram Tola	1.450	234.519	17.656	252.175	5.04
		Abdul Gafar Ke Ghar	Mahadalit Toal	1.050	115.744	8.307	124.051	2.48
Total	3			4.850	656.144	50.403	706.547	14.13
32	MMGSY(AWSESH-ST)-BAGHA-1-32	Rwd Road	Jharharwa Bhirsingwa Tola	5.050	545.930	56.930	602.860	12.06
Total	1			5.050	545.93	56.93	602.860	12.06
33	MMGSY(AWSESH-ST)-BAGHA-1-33	Madaharani Mmgsy Road To Bada Sukhwan	Madarani Tola	0.975	87.110	8.270	95.380	1.91
			Gond Tola	1.790	192.140	18.150	210.290	4.21
Total	2			2.765	279.250	26.420	305.670	6.11
34	MMGSY(AWSESH-ST)-BETTIAH-34	Annu Devi Ke Ghar	Ashok Pandey Ke Ghar Tak	0.830	64.740	3.040	67.780	1.36
Total	1			0.830	64.74	3.04	67.780	1.36
35	MMGSY(AWSESH-ST)-BETTIAH-35	Nanosati jagadishpur RCD Road	Sukhlahi Pul Thakur Ji Mandir tak	1.840	153.500	6.810	160.310	3.21
		Nawal Kishore Singh Ke Bagicha Se	Tatwa Tola	0.980	97.380	8.100	105.480	2.11
Total	2			2.820	250.880	14.910	265.790	5.32
36	MMGSY(AWSESH-ST)-BETTIAH-36	Purendra Pur Chakra	Kujalahi	1.240	140.470	14.000	154.470	3.09
Total	1			1.240	140.47	14	154.470	3.09
37	MMGSY(AWSESH-ST)-NARKATIAGANI-37	Hirapakar Shiv Mandir	Ansari Tola	2.070	217.900	24.180	242.080	4.84
Total	1			2.070	217.9	24.18	242.080	4.84
38	MMGSY(AWSESH-ST)-NARKATIAGANI-38	Rajpur	Balbal Village Tak	1.920	254.510	22.240	276.750	5.54
		Jamunia Pul	Ramunia Chhat Ghat	0.950	172.600	9.900	182.500	3.65
		Triveni Canal	Dumra	1.720	264.280	19.310	283.590	5.67
		Parsauni Road	Bhattula School	1.120	140.900	11.700	152.600	3.05
Total	4			5.710	832.290	63.150	895.440	17.91
39	MMGSY(AWSESH-ST)-NARKATIAGANI-39	Pmgsy Mathura Belwana	Srinagar Hajma Tola	1.550	166.630	16.040	182.670	3.65
		Bhabhta Main Road	Lakhaura Ghat	2.150	219.210	23.660	242.870	4.86
		Gamuania	Jamangapur	1.500	218.440	19.560	238.000	4.76
Total	3			5.200	604.280	59.260	663.540	13.27

For further details please visit website state.bihar.gov.in/prdbihar

PR-02652 (RWD) 2025-26

नरो की मार, दबाई करे सुखी परिवार

Engineer-in-chief

Rural Works Department, Govt. of Bihar

बिहार सरकार
ग्रामीण कार्य विभाग

पत्रांक-BRRDA(HQ)-MMGSY-152/25 - 804

/पटना, दिनांक- 28/2/25

प्रेषक,

संजय कुमार, भा0प्र0से0
संयुक्त सचिव,
ग्रामीण कार्य विभाग।

सेवा में,

महालेखाकार (लेखा एवं हकदारी),
बिहार, पटना।

विषय : योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परिव्यय उप मुख्य शीर्ष-00-लघु शीर्ष-789-अनुसूचित जातियों के लिए विशेष घटक योजना-उप शीर्ष-0108 मुख्यमंत्री ग्राम संपर्क योजना (अवशेष), विपत्र कोड संख्या-37-4515-00-789-0108 के अन्तर्गत वित्तीय वर्ष 2025-26 के लिए बिहार राज्य के विभिन्न जिलों में संलग्न सूची के अनुसार कुल 620 अदद योजनाओं का निर्माण कार्य सन्निहित है। प्रत्येक योजना के लिए निर्माण (नये सतहीकरण कार्य सहित) एवं छः वर्षीय सतत् अनुरक्षण कार्य हेतु संलग्न सूची के स्तम्भ-15 में अंकित राशि के अनुरूप कुल राशि ₹107700.977 लाख (एक हजार सतहत्तर करोड सत्तानबे हजार सात सौ) मात्र की राशि के प्रशासनिक स्वीकृति प्रदान किये जाने के संबंध में।

महाशय,

मुख्यमंत्री ग्राम संपर्क योजना (अवशेष-अनुसूचित जाति) अन्तर्गत विभिन्न कार्य प्रमंडलों के अधीन वित्तीय वर्ष 2025-26 के लिए बिहार राज्य के विभिन्न जिलों में संलग्न सूची के अनुसार 620 (छः सौ बीस) अदद योजनाओं के निर्माण कार्य सन्निहित है। प्रत्येक योजना के लिए संलग्न सूची के स्तम्भ-10 में अंकित लम्बाई के निर्माण कार्य (नये सतहीकरण कार्य सहित) एवं छः वर्षीय सतत् अनुरक्षण कार्य हेतु अलग-अलग योजनाओं के लिए संलग्न सूची के स्तम्भ-15 में अंकित राशि के अनुरूप प्रशासनिक अनुमोदन प्रदान किया जाता है। प्रशासनिक स्वीकृति की कुल राशि ₹107700.977 लाख (एक हजार सतहत्तर करोड सत्तानबे हजार सात सौ) मात्र होता है।

2. विभागीय अपर मुख्य सचिव द्वारा दिनांक:- 28.04.25 को निम्न शर्तों के साथ इन योजनाओं की स्वीकृति प्रदान की गई है :-

- I. ब्राडा के लिए निर्धारित प्रावधान/प्रक्रिया के आलोक में बजट प्रावधान के अंतर्गत राशि की निकासी की जायेगी।
- II. कार्यपालक अभियंता (PIU) का दायित्व होगा कि कार्यों को विशिष्टताओं/विशिष्टि के अनुरूप कार्यान्वित कराकर एकरारनामा एवं सुसंगत वित्तीय प्रावधानों के पालन उपरान्त पूर्णतः संतुष्ट होकर ही राशि की निकासी एवं व्ययन करेंगे।
- III. इन योजनाओं के निर्माण एवं नये सतहीकरण कार्य (Road Edge Marking सहित) का भुगतान योजना शीर्ष-4515 एवं सतत् अनुरक्षण कार्य की राशि गैर योजना मद शीर्ष-3054 से भारित किया जायेगा।
- IV. प्राक्कलन की विशिष्टताओं के अनुसार निर्धारित समयावधि के अन्दर कार्य पूर्ण कराना सुनिश्चित किया जायेगा।
- V. योजना के कार्यान्वयन के क्रम में इनका निर्धारित निरीक्षण सरकार से निर्गत आदेशों में प्रावधानित सक्षम नियंत्री पदाधिकारियों द्वारा नियमित अंतराल पर अनिवार्य रूप से किया जायेगा तथा प्रतिवेदन अभिलेखबद्ध किया जायेगा।

(17)

Rahul Kumar

EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION
BETTIAH, W. CHAMPARAN

28/2/25

ANNEXURE - "B"
GOVERNMENT OF BIHAR
RURAL WORKS DEPARTMENT
CERTIFICATE OF REGISTRATION

Old Registration	New Registration
Registration No :- NA	Registration No : 1250085
Class :- NA	Class : Class 1



Rahul Kumar

Rahul Kumar

S/O- Shesh Nath Rao, Khushi Tola Khiriya Ghat, Ward No 05, Po- Bettiah, West Champaran, Bihar Pincode: 845438

Is hereby registered in Class 1 for the period from date 04-Mar-2025 to 03-Mar-2030 As Contractor of Rural Works Department.

04-03-2025 12:03:00

Signature Of Applicant

Rahul Kumar

This Document is Digitally Signed,Need no Signature



Government of India
Form GST REG-06
[See Rule 10(1)]

Registration Certificate

Registration Number : 10EZRPK9459K1ZM

1.	Legal Name	rahul kumar			
2.	Trade Name, if any	rahul kumar			
3.	Constitution of Business	Proprietorship			
4.	Address of Principal Place of Business	40, khushi tola khiriya ghat, bettiah, West Champaran, Bihar, 845438			
5.	Date of Liability				
6.	Period of Validity	From	22/06/2020	To	Not Applicable
7.	Type of Registration	Regular			
8.	Particulars of Approving Authority	Bihar			
Signature					
Name		Akhilesh Kumar Mishra			
Designation		Deputy Commissioner of State Tax			
Jurisdictional Office		Bettiah			
9. Date of issue of Certificate		22/06/2020			
Note: The registration certificate is required to be prominently displayed at all places of business in the State.					

Tender Inviting Authority: Authority: Engineer -in-chief-Additional Commissioner-cum-Special Secretary, RWD, Bihar, Patna

Name of Work:MMGSY(AWSESH-ST)-BETTIAH-36

Contract No:

Name of the

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant

Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT With Taxes in
1	Purendra Pur Chakla To Kujalahi				
2	Setting Out Pillars :- Providing & Fixing of Working benchmark Pillars 01 nos. per km & 04 Nos. of reference pillars required for 1 Km. as per drawings given and direction of E/I	1.24	Km	13091.03	16232.88
3	Clearing and Grubbing Road Land Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation , grass ,bushes ,shrubs , saplings and trees of girth upto 300mm , removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification - clause 201.1 and direction of E/I (By Manual Means) In area of non-thorny jungle	0.36	Hect.	75360.38	27129.74
4	Cutting of Trees including Cutting of Trunks, Branches and Removal of Stumps Cutting of trees, including cutting of trunks, branches and removal of stumps & roots, refilling, compaction of backfilling and stacking of serviceable material by manual means with all lifts as per Technical Specification Clause 201.7				
5	Girth above 300 mm to 600 mm	12.00	Each	352.90	4234.80
6	Girth above 600 mm to 900 mm	8.00	Each	611.21	4889.68
7	Removal of Telephone/Electric Poles and Lines Removal of telephone/electric poles with wires including excavation and dismantling of foundation concrete and lines under the supervision of concerned department, disposal with all lifts and upto a lead of 1000 m and stacking the serviceable and unserviceable material separately as per Technical Specification Clause 202.	10.00	No	246.41	2464.10
8	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 100 m as per Technical Specification Clause 301.5	1276.40	Cum	147.61	188409.40
9	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	614.61	Cum	239.97	147487.96
10	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m & 100 m as per Technical Specification Clause 303.1. (Including Royalty & Labour Cess).	3330.38	Cum	243.24	810081.63
11	Granular Sub-base with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. (For Grading II Material)	651.04	Cum	2574.08	1675829.04

12	WBM Grading 2 :-Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per Technical Specification Clause 405.	291.94	Cum	5395.28	1575098.04
13	WMM :- Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mix plant carriage of mixed material by tipper to site, laying in uniform layers with grader in sub-base/base course on a well surface and compacting with vibratory roller to achieve the desired density.	389.48	Cum	4411.54	1718206.60
14	Prime Coat (Low Porosity) :- Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0kg/sqm using mechanical means as per Technical Specification Clause 502	3892.50	Sqm	55.52	216111.60
15	Tack Coat:- Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25-0.30kg per sqm on the prepared granular surfaces treated with primer & cleaned with Hydraulic broom as per Technical Specification Clause 503.	3892.50	Sqm	19.10	74346.75
16	Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509	3892.50	Sqm	307.26	1196009.55
17	Construction of un-reinforced, plain cement concrete pavement (M35 Grade) over a prepared sub base with 43 grade cement @ 400 kg per cum, coarse and fine aggregate conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form paver, spread, compacted and finished in a continuous operation including provision of 0.5 x 0.5 panel, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures as approved, curing compound, finishing to lines and grades as per drawing	130.05	Cum	7665.92	996952.90
18	Laying brick soling layer on prepared sub-grade with brick on end edging according to lines, graded and cross-section shown on the drawing filling joints with sand and earth, spreading 25 mm thick layer of earth over brick soling, watering and rolling the same with three wheel road roller 80-100 kN as per Technical Specification Clause 412	173.40	Sqm	500.49	86784.97
19	TRAFFIC SIGNS, MARKINGS & OTHER ROAD APPURTENANCES				
20	Kilometre Stone				
21	Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703				
22	Ordinary Kilometer Stone (Precast)	2.00	Each	2943.66	5887.32
23	200 m stone (precast)	5.00	Each	798.22	3991.10

24	(I) Providing and Fixing 'Logo' of PMGSY Project :- Providing and fixing of typical PMGSY informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	4.00	Each	11004.60	44018.40
25	Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701	88.00	per cm height per letter	0.74	65.12
26	Boundary Pillar/Gaurd Post :- Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC:25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	44.00	No	702.33	30902.52
27	Rumble Strips : Provision of 15 nos rumble strips covered with premix bituminous carpet, 15-20 mm high at center, 250 mm wide placed at 1 m center to center at approved locations to control speed, marked with white strips of road marking paint.	6.75	Sqm	1085.66	7328.21
28	Traffic Signs :- Providing and fixing of Retro reflective cautionary , mandatory and informatory sign board as per IRC :67 made of 1.5 mm thick MS steel duly stove white colour in front and gray colour on back with red reflective border of 65 mm width and required letters and figures with reflective tape engineering grade as per clause 1701.3.9 of MORD for rural road of required shade and colour supported and welded on 47mmx47mmx12swg sheet tube firmly fixed to the ground by mean of properly designed foundation with M15 grade cement concrete 450x450x600 mm ,600mm below ground level as per approved drawing clause 1701.2.2.				
29	900 mm equilateral & triangle , OR	2.00	Each	6035.37	12070.74
30	600 mm equilateral & triangle, OR	14.00	Each	3983.53	55769.42
31	600 mm circular , OR	12.00	Each	5324.31	63891.72
32	600 mm x 450 mm rectangular, OR	6.00	Each	5187.06	31122.36
33	900 mm side octagon, OR	4.00	Each	9431.08	37724.32
34	Hazard Board (900 mm x 300 mm)	8.00	Each	5187.06	41496.48
35	Chevron Sign Boards, (Size: 600mm x 500mm)	30.00	Each	5503.78	165113.40
36	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Concrete Surface :- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes.	68.00	Sqm	879.72	59820.96
37	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface :- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes.	180.00	Sqm	778.40	140112.00
38	Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year	36.00	Each	1248.07	44930.52
39	Cross Drainage Works				
40	Irrigation Pipe (300MM Dia)				

41	Providing and laying of a reinforced cement concrete pipe duct, 300 mm dia, across the road (new construction), extending from drain to drain in cuts and toe of slope to toe of slope in fills, constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC:981997, bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt all as per IRC: 98 - 1997	40.00	RM	947.66	37906.40
42	Hume Pipe Culverts				
43	Earth work in excavation for foundation of structures upto 3.0 m depth as per drawing and technical specification clause 1104	99.27	Cum	80.87	8027.96
44	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-15 Grade	13.06	Cum	7277.49	95044.02
45	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 (M20 (PCC 1:2.5:5))	55.36	Cum	8211.38	454582.00
46	Providing and laying RCC pipe NP-4 for culverts on first class bedding of PCC M10 material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling concrete and masonry works in head walls and parapets as per clause 1106 - 1000 mm Dia Pipe	15.00	RM	7124.20	106863.00
47	Painting on Parapet Wall (Black & White Strips) Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	41.28	Sqm	129.57	5348.65
48	5TH YEAR PERIODIC RENEWAL				
49	Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydriloc broom as per technical specification clause 503.	3442.50	Sqm	19.10	65751.75
50	Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects.	86.06	Cum	13970.17	1202272.83
51	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes. (Flexible Pavement)	180.00	Sqm	778.40	140112.00
52	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes. (Rigid Pavement)	68.00	Sqm	879.72	59820.96
53	Add Labour @ 1% on Construction Cost (A) :-	1.00	RS	116602.45	116602.45
54	Add 10% S.F on Basic Materials Cost :-	1.00	RS	173702.77	173702.77
55	Add GST @ 18% on Sub Total Construction Cost (Including 1% Labour Cess & 10% S.F):-	1.00	RS	2151099.03	2151099.03
56	1st Year Maintenance cost	1.00	Year	175413.00	175413.00
57	2nd Year Maintenance cost	1.00	Year	221006.08	221006.08
58	3rd Year Maintenance cost	1.00	Year	224221.00	224221.00
59	4th Year Maintenance cost	1.00	Year	280043.00	280043.00
60	6th Year Maintenance cost	1.00	Year	128605.00	128605.00
61	7th Year Maintenance cost	1.00	Year	150415.00	150415.00
62	Add Labour @ 1% on Maintenance Cost (A) :-	1.00	RS	11797.03	11797.03
63	Add 10% S.F on Basic Materials Cost :-	1.00	RS	14292.54	14292.54
64	Add GST @ 18% on Sub Total Maintenance Cost (Including 1% Labour Cess & 10% S.F):-	1.00	RS	217042.68	217042.68
Total in Figures					15524483.38
Quoted Rate in Figures					Select 0.00
Quoted Rate in Words					INR Zero Only