

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग कार्य प्रमंडल झंझारपुर।

पत्रांक...18.00 अन्तः

दिनांक 26/09/2025

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झंझारपुर।

सेवा में,

नोडल पदाधिकारी,
राज्य योजना (नाबार्ड),
ग्रामीण कार्य विभाग,
बिहार, पटना।

विषय:- शीर्ष राज्य योजना (नाबार्ड) के अनुरक्षण मद में आवंटन उपलब्ध कराने के संबंध में।


महाशय,

उपरोक्त विषय के संबंध में कहना है शीर्ष राज्य योजना (नाबार्ड) के अनुरक्षण मद में संलग्न विवरणी के अनुसार आवंटन उपलब्ध कराने की कृपा की जाय, ताकि संवेदक को किये गये कार्यों का भुगतान किया जा सकें।

अनु० -

1. अधियाचना प्रमाण पत्र 1 पृष्ठ में।
2. उपयोगिता प्रमाण पत्र एक प्रति।
3. मापी पुस्त की छायाप्रति।
4. प्रशासनिक स्वीकृति का पत्र,
अनुमोदित परिमाण विपत्र एवं
एकरारनामा की अभिप्रमाणित प्रति।

विश्वासभाजन



कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, झंझारपुर।

FORM GFR 19-A

(See Government of India's Decision (I) below Rule-150)
Form of Utilisation Certificate Upto the month of September. 2025

Rajya Yojana (NABARD) Maintenance Fund

PIU – Executive Engineer, R.W.D (W) Division, Jhanjhapur.

SL. No	Name of Scheme	Sanction No. & Date with Amount (In Rs. lacs)	Amount Received (In Rs. lacs)	Particulars
1	Construction of Rural roads under Rajya Yojana (Nabard) MAINTENANCE Fund.	Authorisation letter No-5748 Date- 03.06.2025	1.98857	Certified that out of 1.98857 lac received during the years up to 2025-26 in favour of Ex. Engineer, RWD (W) Division Jhanjharpur, Madhubani, Bihar, a sum of Rs. 1.98857 lac has been utilized for the purpose of Rajya Yojana (Nabard) Scheme as given in the margin for which the balance of Rs. 0.0000 remaining unutilized at the end of the period under.


- 2 . Certified that I have satisfied myself that the conditions on which the grants-in-aid was sanctioned have been duly fulfilled/are being fulfilled and that I have exercised the following checks to see that the money was actually utilized for the purpose for which it was sanctioned.

Kind of Checks exercised :-

- Works have been supervised by Executive Engineer/Superintending Engineer.
- Periodical inspection has been conducted by Executive Engineer/Superintending Engineer.
- Construction materials have been tested.
- Measurements have been recorded in the MBs and test check conducted by the Assistant Engineer/Executive Engineer.
- All other codal formalities have been observed.


3. Physical Progress achieved :-

- Construction of Road Works.
- Construction of CD Works.


Executive Engineer
R.W.D (W) Division
Jhanjhapur

राज्य योजना (नाबार्ड) अंतर्गत पथों में पंचवर्षीय अनुरक्षण अधियाचना प्रपत्र																										
क्र०	कार्य प्रमंडल का नाम	योजना का नाम	एकराशिया के अनुसार प्राक्कानित राशि वर्षवार					व्यय की राशि वर्षवार							कुल (लाख में)	प्रशासनिक स्वीकृति की राशि एवं प्रचलन दिनांक (लाख में)	पंचवर्षीय अनुरक्षण की राशि सहित अनुमोदित परिमाण विपत्र की राशि (लाख में)	अनुरक्षण हेतु प्रशासनिक स्वीकृति का पत्रांक / दिनांक	मूल निर्माण कार्य करने की वास्तविक तिथि	वर्तमान अधियाचित राशि वर्षवार						कुल अधियाचित राशि (लाख में)
			प्रथम वर्ष राशि (लाख में)	द्वितीय वर्ष राशि (लाख में)	तृतीय वर्ष राशि (लाख में)	चतुर्थ वर्ष राशि (लाख में)	पंचम वर्ष राशि (लाख में)	प्रथम वर्ष राशि (लाख में)	द्वितीय वर्ष राशि (लाख में)	तृतीय वर्ष राशि (लाख में)	चतुर्थ वर्ष राशि (लाख में)	पंचम वर्ष राशि (लाख में)	प्रथम वर्ष राशि (लाख में)	द्वितीय वर्ष राशि (लाख में)						तृतीय वर्ष राशि (लाख में)	चतुर्थ वर्ष राशि (लाख में)	पंचम वर्ष राशि (लाख में)				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	
1	RWD (Works) Division, Jhankharpur	Kosi Bandh to Dakaha tol	0.74466	0.90061	2.08629	2.69255	3.17744	9.56855	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	162.27 Lakh & Letter No- 8281 Dated- 13.09.2017	146.49399	Letter No- 8281 Dated- 13.09.2017	01.02.2021	0.74197	0.89928	2.08626	0.00000	0.00000	3.72751	3.72751	

- 1 कार्य वृत्तियों के अनुरूप पूर्ण कर लिया गया है।
- 2 पथ में MQMU/PQM/E से संबंधित कार्य सुधार प्रतिवेदन लंबित नहीं है।
- 3 अनुमोदित परिमाण विपत्र की कुल राशि प्रशासनिक स्वीकृति की राशि से 20% अधिकतम सीमा के भीतर है साथ ही अनुमोदित परिमाण के मदों की मात्रा का विस्तार का वि
- 4 अनुसन्धक-प्रशासनिक स्वीकृति का पत्र, अनुमोदित परिमाण विपत्र एवं एकराशिया की अभिप्रायित प्रति।


 कार्यपालक अभियंता,
 ग्रामीण कार्य विभाग,
 कार्य प्रमंडल, झारखपुर।

Koshi Bridge to Dakshineta (JABARD)

Schedule XLV-Form No. 134

Jhanjharpur DIVISION

Malkepur SUB-DIVISION.

Measurement Book

Ran Teet Kandas Raut

1685

Date Date

$$43.30 \text{ m}^3$$

Continuation

Continuation

Executive Engineer
Rural Works Department,
Works Division, Jhunjharpur

Continuation


53-42, pm3

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
(8i) Cutting of boardwalk of forest and clearing of forest E/H					
14 Lino					04 Mo.
(ii) Cutting of shrub forest and clearing of forest E/H					
14 20 Mo					20 Mo.
(iii) Clearing of grass and weeds as per E/H					
24 18.32 x 0.30					11.03 M ²
(9) White washing of parapet wall of H.D. culvert as per E/H					
24 51 6.15 x 0.40					24.60 M ²
24 51 6.15 x 0.60					23.80 M ²
24 51 6.15 x 0.80					9.80 M ²
					103.20 M ²
ABSTRACT OF COST.					
m/y for maintenance					
(11) Restoration of forest beam with soil and grass as per E/H					
Qty. 1/2 T.M.B.P. - 65 (1)					
133.20 M ³ @ 341.72/M ³					45544.00
(12) Making up beam and slender as per E/H					
Qty. 1/2 T.M.B.P. - 66 (1)					
740.48 M ² @ 50.00/M ²					37464.00
					409.83005.00

Continuation

Sch. XLV-Form No. 134

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
	201/0	6-12/10		BP 11	98295=0 1230
(iii) Trimming 9.8 wall and 1/2 wall					
asp. 1/2					
atb vide T.M.B.D. 68 (2-ii)					
11.03 M ² @ 2=06/14 ²					23=0
(9/12) Whistle blowing apparatus					
Wall of H.P. culvert 1/2					
EIT					
atb vide T.M.B.D. 68 (9)					
103.20 M ² @ 15=52 M ²					1602=0
					2 99920=0
103.20 M ² @ 15=52 M ²					9992=0
					2 99528=0


 Executive Engineer
 Rural Works Department
 Works Division, Jhanjharpur

Continuation

73
Sch. XLV-Form No. 134

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
3rd year maintenance work					
Name of work - maintenance of road and					
C.D. Work from Kabi Jankh					
to Dakala Tal under					
M.M.G.S.B.					
Agency - Ram Jee Kumar Row					
Agreement No - 07/SB/D/2019-20					
Agreement value - 1444314.00					
Date of 3rd year maintenance start - 26/04/2023					
Date of 3rd year maintenance complete - 25/04/2024					
Date of entry -					
(1) Restoration of rain cut					
Location and description of work					
as per E/I					
2+44 8.85+ 1.125+ 0.300					23.89 m ²
2+34 9.45+ 1.125+ 0.300					19.24 "
2+24 7.75+ 1.125+ 0.300					10.46 "
2+21 6.90+ 1.125+ 0.300					9.32 "
2+24 8.85+ 1.125+ 0.300					11.95 "
2+31 5.90+ 1.125+ 0.300					11.95 "
6+ 6.85+ 1.125+ 0.300					13.87 "
5+ 5.75+ 1.125+ 0.300					9.70 "
4+ 9.65+ 1.125+ 0.300					13.02 "
2+24 8.85+ 1.125+ 0.300					11.95 "
2+ 3.90+ 1.125+ 0.300					3.95 "
2+ 4.25+ 1.125+ 0.300					2.87 "
2+24 9.95+ 1.125+ 0.300					13.43 "
Continuation					155.50 m ²

77
Sch. XLV-Form No. 134

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
ABSTRACT OF COST.					
300 year maintenance					
(1/1) Restoring & repair of concrete					
with 100 mm concrete					
at 100 m ² M.B.P. - 73 (1)					
155.50 m ² @ 34.72/m ² =					53137.00
(2/2) Making up concrete & slab					
as per E/I					
at 100 m ² M.B.P. - 74 (2)					
240.48 m ² @ 50.59/m ² =					37461.00
(3/3) Repair & patching of concrete					
with 100 mm concrete					
at 100 m ² M.B.P. - 74 (3)					
10.28 m ² @ 106.00/m ² =					10902.00
(4/4) Patch repair of concrete					
with surfacing & curing					
as per E/I					
at 100 m ² M.B.P. - 75 (4)					
137.08 m ² @ 84.23/m ² =					11546.00
(5/5) Patch repair of concrete					
with surface & surface					
finishing as per E/I					
at 100 m ² M.B.P. - 74 (5)					
137.14 m ² @ 74.40/m ² =					10201.00
(6/7) Maintenance of H.P. Culvert					
as per E/I					
at 100 m ² M.B.P. - 75 (6)					
554.00 @ 107.67/m ² =					5384.00

Continuation

C.P. - 226822.4

[illegible]

Continuation

Executive Engineer
Rural Works Department
Works Division, Jhanjharpur

Rs.1000

2266/2096/31000/10000/109000/924/20/2/2/2

कुमार राउत पं० स्व० रामगुलाम राउत AH 298158

શાળા મેજા જિલ્લા મહાવનિ લખાઈ - ૧૦૧ - ૧૦૧ - ૧

Agreement no - 07SBD/2020-21

Agreement Start Date.. 13/05/2020

Agreement Shd Date - 12/05/2021

Below - 10%.

Agreement Form

राजेन्द्र प्रसाद महतो

मुद्रांक विक्रेता

अवर निबंधन का पालन इंदारपुर

ला० नं०- 1 / 2007 ड०

Agreement

This Agreement Made on The 13th Day of May 2020 Between
Executive Engineer R.W.D (W) Division, Jhanjharpur (Here in after Called" The
Employer" of the One Part, and Sri Amar Nath Jha, Vill.- Kishanpur Nawada, P.O.
Nawada, Dist.- Darbhanga. Construction of road and CD works from Kosi bandh to
Dakaha Tol under NABARD (STATE SCHEME). (here in after called "The Contractor
of the Other part)

Where The Employer is desirous that the contractor execute, Construction of Road and C.D work From Construction of road and CD works Kosi bandh to Dakaha Tol under NABARD (STATE SCHEME).. (here in after called "The Contractor of the Other part) and the Employer has Accepted the Bid by The Contractor For The Execution And Completion of Such Works And The Remedying of Any defects there in at a Cost of Rs. 1,41,41,314.00 (Rupees One Crore forty One Lakhs Fourty One thousand Three hundred Fourteen only.)

1. In this Agreement, words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract herein after referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy any

Executive Engineer

Rural Works Department

Works Division-Jharkhand

21
12/25/00


Executive Engineer
Rural Works Department
Works Division, Jhunjharpur


Scanned with OKEN Scanner

defects therein in conformity in all aspects with the provisions of the Contract.

3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the Works and the remedying the defects wherein the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be read and construed as part of this Agreement, viz :
- i) Letter of Acceptance ;
 - ii) Notice to proceed with the works ;
 - iii) Contractor's Bid ;
 - iv) Contract Data ;
 - v) Special Conditions of contract and General Conditions of Contract ;
 - vi) Specifications ;
 - vii) Drawings ;
 - viii) Bill of Quantities ; and
 - ix) Any other document listed in the Contract Data as forming part of the contract. In witness whereof the parties thereto have caused this Agreement to be executed the day and year first before written.

The Common Seal of.....
was hereunto affixed in the presence of
Signed, Sealed and Delivered by the said


Executive Engineer


 Rural Works Department
Works Division-Jhanjharpur
13/05/20

In the presence of :

Binding Signature of Employer.....

Binding Signature of Contractor




Executive Engineer
Rural Works Department
Works Division, Jhanjharpur

Name of Work: Construction of Road & CD Works under NABARD Scheme
KOSI BANDH TO DAKAHA TOL,
 Is a link road with Link No
 S035

DIVISION : JHANJHARPUR

BLOCK :

MADHEPUR

LENGTH: 2.194 KM

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs.
				Figure	Words	
1	Setting Out Pillars Providing & Fixing of Working benchmark Pillars 2 nos. per km & 6 Nos. of reference pillars required for 1 Km. as per drawings given and direction of E/I	18.00000	Per Km	3915.44	Rupees Three Thousand Nine Hundred Fifteen And Forty Four Paise Only	70478.00
2	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.76800	Hec	47809.31	Rupees Forty Seven Thousand Eight Hundred Nine And Thirty One Paise Only	36718.00
3	Dismantling Brick/Tile Work Dismantling of existing structures, like culverts, bridge, retaining wall and other structures comprising of brick masonry including unserviceable material and stacking the serviceable material with all lift and lead of 1000m as per technical specification clause 202.	24.75000	Cum	217.05	Rupees Two Hundred Seventeen And Five Paise Only	5372.00
4	Dismantling of Structures Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 m as per Technical Specification Clause 202. a) Reinforced Cement Concrete	4.50000	Cum	384.95	Rupees Three Hundred Eighty Four And Ninety Five Paise Only	1732.00
5	Removing all types of Hume pipe and stacking within a lead of 1000m including earthwork and dismantling of masonry works as per technical specification clause 202.1					
6	A) Upto 600 mm dia	0.00000	Mtr	163.34	Rupees One Hundred Sixty Three And Thirty Four Paise Only	0.00
7	B) Above 600 mm to 900 mm dia Hume Pipe	0.00000	Mtr	220.88	Rupees Two Hundred Twenty And Eighty Eight Paise Only	0.00
8	C) Above 900 mm dia Hume Pipe	0.00000	Mtr	378.19	Rupees Three Hundred Seventy Eight And Nineteen Paise Only	0.00
9	Box Cutting Excavation for roadway in soil using manual means for carrying of cut earth to embankment site with a lift upto 1.5 m and lead upto 50 m as per Technical Specification Clause 302.3	0.00000	Cum	72.53	Rupees Seventy Two And Fifty Three Paise Only	0.00
10	Construction of embankment with approved material deposited from road way cutting and excavation from drain and foundation of other structures and excavated with an average lead of 50 m graded and compacted to meet requirement of tables 300.1 and 300.2 as per technical specification clause 301.5 (Including Royalty & Labour Cess).	7.45000	Cum	48.07	Rupees Forty Eight And Seven Paise Only	358.00
11	Excavation in Soil using Hydraulic Excavator and Tippers with disposal upto 1000 m Excavation for roadwork in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross-sections, and transporting to the embankment location with a lift upto 1.5 m and lead upto 1000 m as per Technical Specification Clause 302.3 (Including Royalty & Labour Cess).	12.41000	Cum	72.53	Rupees Seventy Two And Fifty Three Paise Only	900.00

Executive Engineer

Rural Works Department

Works Division-Jhanjharpur

Superintending Engineer

Works Circle Darbhanga

Rural Works Department

Executive Engineer
Rural Works Department
Works Division, Jhanjharpur



Scanned with OKEN Scanner

Name of Work: Construction of Road & CD Works under NABARD Scheme
KOSI BANDH TO DAKAHA TOL.
 Is a link road with Link No
5035

LENGTH: 2.194 KM

DIVISION: JHANJIHARPUR

BLOCK: MADHEPUR

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs.
				Figure	Words	
12	Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m, transporting to the site spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m & 100 m as per Technical Specification Clause 301.5. (Including Royalty & Labour Cess).					
	For 1000 m lead @ 20 %	1505.35000	Cum	146.48	Rupees One Hundred Forty Six And Forty Eight Paise Only	220504.00
	For 100 m lead @ 80%	6021.40000	Cum	102.06	Rupees One Hundred Two And Six Paise Only	614544.00
13	Construction of Subgrade and Earthen Shoulders Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m & 100 m as per Technical Specification Clause 303.1. (Including Royalty & Labour Cess).	1937.88000	Cum	148.13	Rupees One Hundred Forty Eight And Thirteen Paise Only	287058.00
14	Granular Sub-base with Well Graded Material (Table 400.1) (By mix in place method) For Grading 1 Material Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	1460.31000	Cum	3556.59	Rupees Three Thousand Five Hundred Fifty Six And Fifty Nine Paise Only	5193724.00
15	WBM Grading 3 (By Mechanical Means) Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	507.05000	Cum	4303.81	Rupees Four Thousand Three Hundred Three And Eighty One Paise Only	2182247.00
16	Prime Coat (Low porosity) Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.7- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	6760.69000	Sqm	46.20	Rupees Forty Six And Twenty Paise Only	312344.00
17	Surface Dressing using Bituminous Binder (First Coat) Providing and laying surface dressing as wearing course consisting of a layer of bituminous binder laid on the prepared surface. Followed by a cover of crushed stone aggregates of specified size and rolling with 80-100 kN static roller including cleaning the road surface as per Technical Specification clause 507.	6760.69000	Sqm	84.23	Rupees Eighty Four And Twenty Three Paise Only	569453.00
18	Surface Dressing using Bituminous Binder (Second Coat) Providing and laying surface dressing as wearing course consisting of a layer of bituminous binder laid on the prepared surface. Followed by a cover of crushed stone aggregates of specified size and rolling with 80-100 kN static roller including cleaning the road surface as per Technical Specification clause 507.	6760.69000	Sqm	74.40	Rupees Seventy Four And Forty Paise Only	502995.00

Executive Engineer

Rural Works Department

Works Division-Jhanjharpur

Superintending Engineer

Works Circle Darbhanga
Rural Works Department

Name of Work: Construction of Road & CD Works under NABARD Scheme
KOSI BANDH TO DAKAHA TOL,
Is a link road with Link No
S035

DIVISION : JHANJIHARPUR

BLOCK :

MADHEPUR

LENGTH: 2.194 KM

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs.
				Figure	Words	
19	Granular Sub-base with Well Graded Material (Table 400.1) (By mix in place method) For Grading I Material Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	92.42000	Cum	3556.59	Rupees Three Thousand Five Hundred Fifty Six And Fifty Nine Paise Only	328700.00
20	WBM Grading 3 (By Manual Means) Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	69.31000	Cum	4303.81	Rupees Four Thousand Three Hundred Three And Eighty One Paise Only	298297.00
21	Cement Concrete Pavement Construction of un-reinforced, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and water finishing to lines and grade as per drawing and Technical Specification Clause 1501	147.86000	Cum	8257.01	Rupees Eight Thousand Two Hundred Fifty Seven And One Paise Only	1220881.00
22	Supply and providing NP2 300 mm dia hume pipe across carriageway in open areas	45.00000	M	620.70	Rupees Six Hundred Twenty And Seventy Paise Only	27932.00
23	Kilometre stone Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703.					
	i) 5th km stone	0.00000	No.	4999.54	Rupees Four Thousand Nine Hundred Ninety Nine And Fifty Four Paise Only	0.00
	ii) Km stone	3.00000	No.	2620.44	Rupees Two Thousand Six Hundred Twenty And Forty Four Paise Only	7861.00
	iii) 200 m stone	9.00000	No.	692.77	Rupees Six Hundred Ninety Two And Seventy Seven Paise Only	6235.00

[Signature] Executive Engineer

Rural Works Department

Works Division-Jhanjharpur

[Signature]
16/11/17
Superintending Engineer
Works Circle Darbhanga
Rural Works Department

Name of Work: Construction of Road & CD Works under NABARD Scheme
KOSI BANDHI TO DAKAHA TOL,
 Is a link road with Link No
 5035

DIVISION : JHANJHARPUR

BLOCK :

MADHEPUR

LENGTH: 2.194 KM

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs.
				Figure	Words	
24	Traffic sign Providing and fixing of semi reflective cautionary , mandatory and informatory sign board as per IRC :67 made of 1.5 mm thick MS steel duly stove white colour in front and gray colour on back with red reflective border of 65 mm width and required letters and figures with reflective tape engineering grade as per clause 1701.3.9 of MORD for rural road of required shade and colour supported and welded on 47mmx47mmx12swg sheet tube firmly fixed to the ground by mean of properly designed foundation with M15 grade cement concrete 450x450x600 mm ,600mm below ground level as per approved drawing clause 1701.2.2.					
	600 mm equilateral & triangle,	9.00000	No.	1754.29	Rupees One Thousand Seven Hundred Fifty Four And Twenty Nine Paise Only	15789.00
	600 mm circular ,	5.00000	No.	1818.18	Rupees One Thousand Eight Hundred Eighteen And Eighteen Paise Only	9091.00
	800 mm x 600 mm rectangular,	9.00000	No.	1917.30	Rupees One Thousand Nine Hundred Seventeen And Thirty Paise Only	17256.00
	600 mm x 450 mm rectangular,	5.00000	No.	1811.64	Rupees One Thousand Eight Hundred Eleven And Sixty Four Paise Only	9058.00
25	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes.	357.00000	Sqm	841.97	Rupees Eight Hundred Forty One And Ninety Seven Paise Only	300583.00
26	Direction and place identification signs up to 0.9 sqm size board Providing and erecting direction and place identifications of semi reflective sign boards as per IRC:67 made of 2 mm thick M.S. Sheet duly stove enameled paint in white colour in front and grey colour on back with red reflective border of 70 mm width and required message, letters, figures with reflective engineering grade tape as per MORD specifications of required shade and colour. Supported and welded on 47 mm x 47mm of 12 SWG Square tube of 3050 mm height duly strengthened by 25 mm x 5 mm M/s flat iron on edges on back firmly fixed to the ground by means of properly designed foundations with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701	9.00000	No.	3040.83	Rupees Three Thousand Forty And Eighty Three Paise Only	27367.00

[Signature]

Executive Engineer

Rural Works Department

Works Division-Jhanjharpur

[Signature]
13/5/20

[Signature]
16/11/17
Superintending Engineer
Works Circle Darbhanga
Rural Works Department

[Signature]
Executive Engineer
Works Division, Jhanjharpur
 Scanned with OKEN Scanner

Name of Work: Construction of Road & CD Works under NABARD Scheme
KOSI BANDH TO DAKAHA TOL,
Is a link road with Link No
5035

DIVISION : JHANJIHARPUR

BLOCK : MADHEPUR
SCHEDULE OF WORKS

LENGTH: 2.194 KM

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs.
				Figure	Words	
27	Providing and fixing of typical PMGSY Informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	2.00000	No.	9744.82	Rupees Nine Thousand Seven Hundred Forty Four And Eighty Two Paise Only	19490.00
28	HPC 1X1000 MM Earth work in excavation for foundation of structures upto 3.0 m depth as per drawing and technical specification clause 1104	178.78800	Cum	274.58	Rupees Two Hundred Seventy Four And Fifty Eight Paise Only	49092.00
29	Providing M15 (PCC 1:2.5:5) as levelling course in foundation :- Providing PCC M 15 (1:2.5:5) concrete for plain concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	17.77200	Cum	6635.49	Rupees Six Thousand Six Hundred Thirty Five And Forty Nine Paise Only	117926.00
30	Brick Masonary work in cm 1:4 in head wall complete as per drawing and technical specification clause 1109 in cement mortar 1:4	183.64200	Cum	6552.07	Rupees Six Thousand Five Hundred Fifty Two And Seven Paise Only	1203235.00
31	Providing and laying RCC pipe NP-3 for culverts on first class bedding of PCC M10 material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling concrete and masonry works in head walls and parapets as per clause 1106	45.00000	M	3856.22	Rupees Three Thousand Eight Hundred Fifty Six And Twenty Two Paise Only	173530.00
32	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	445.38600	Sqm	199.54	Rupees One Hundred Ninety Nine And Fifty Four Paise Only	88872.00
33	Providing 15 mm cement punning including curing carriage of water with all leads and lifts as per building specification and direction of E/I	129.60000	Sqm	47.71	Rupees Forty Seven And Seventy One Paise Only	6183.00
34	Slab 1X2.0X1.5 Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	93.17990	Cum	274.58	Rupees Two Hundred Seventy Four And Fifty Eight Paise Only	25585.00
35	Sand Filling in Foundation Trenches as per drawing and technical specification Clause 1108.	1.25400	Cum	385.35	Rupees Three Hundred Eighty Five And Thirty Five Paise Only	483.00
36	Providing PCC M 15 (1:2.5:5) concrete for plain concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	12.49700	Cum	6635.49	Rupees Six Thousand Six Hundred Thirty Five And Forty Nine Paise Only	82924.00
37	Brick masonry work in cement mortar (CM 1:4) in foundation complete excluding pointing and plastering as per drawing and technical specifications Clauses 602, 603, 604, 1202 & 1203	52.10100	Cum	6282.98	Rupees Six Thousand Two Hundred Eighty Two And Ninety Eight Paise Only	327350.00

अभिषेक कुमार
13.5.20

Executive Engineer
Rural Works Department
Works Division-Jhanchiharpur

16/11/20
Superintending Engineer
Works Circle Darbhanga
Rural Works Department

Name of Work: Construction of Road & CD Works under NABARD Scheme
KOSI BANDH TO DAKAHA TOL,
Is a link road with Link No
5035

DIVISION : JHANJHARPUR

BLOCK :

MADHEPUR

SCHEDULE OF WORKS

LENGTH: 2.194 KM

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs.
				Figure	Words	
38	Brick masonry work in cement mortar (CM 1:4) in substructure and Kerb complete excluding pointing and plastering as per drawing and technical specifications Clauses 602, 603, 604, 1202 & 1203	26.26100	Cum	6552.07	Rupees Six Thousand Five Hundred Fifty Two And Seven Paise Only	172064.00
39	Plain/Reinforced cement concrete (M-20) in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204	4.06800	Cum	7633.00	Rupees Seven Thousand Six Hundred Thirty Three Only	31051.00
40	Providing Bitumen painting over top surface of Abutment cap & inner vertical surface of Dirt Wall including Heating the bitumen & cost of painting brush etc. all complete.	14.10000	Sqm	15.05	Rupees Fifteen And Five Paise Only	212.00
41	RCC M25 in Deck Slab :- Providing and laying reinforced cement concrete in superstructure (Deck slab M25) as per drawing and technical specifications Clauses 800, 1205.4, 1205.5	4.60800	Cum	8412.05	Rupees Eight Thousand Four Hundred Twelve And Five Paise Only	38763.00
42	Supplying, fitting and placing HYSD bar reinforcement in super-structure complete as per drawing and technical specifications	0.76400	MT	64086.48	Rupees Sixty Four Thousand Eighty Six And Forty Eight Paise Only	48962.00
43	Providing and filling joint sealing compound as per drawings and technical specifications with coarse sand and 6 per cent bitumen by weight	15.00000	RM	37.39	Rupees Thirty Seven And Thirty Nine Paise Only	561.00
44	Brick masonry work in cement mortar 1:3 in parrapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	3.84000	Cum	5869.69	Rupees Five Thousand Eight Hundred Sixty Nine And Sixty Nine Paise Only	22540.00
45	Plastering with cement mortar (1:4), 15 mm Thick on brick work in sub-structure as per Technical Specifications Clause 613.4 & 1204.	68.55740	Sqm	199.54	Rupees One Hundred Ninety Nine And Fifty Four Paise Only	13680.00
46	Providing 15 mm cement punning including curing carriage of water with all leads and lifts as per building specification and direction of E/I	26.56000	Sqm	47.71	Rupees Forty Seven And Seventy One Paise Only	1267.00
47	Providing Weepholes in brick masonry, Plain / Reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing	28.00000	Nos	126.82	Rupees One Hundred Twenty Six And Eighty Two Paise Only	3551.00
48	1st Year Maintenance Restoration of Raincuts/Berms with soil, moorum etc (Qty=L*Br*0.3% taken) X 1.25	111.07125	Cum	341.72	Rupees Three Hundred Forty One And Seventy Two Paise Only	37955.27
49	Making up of Berms/shoulder, stripping excess soil from the shoulder surfaces to achieve level etc. (Qty=L*Br*% taken) X 1.25	617.06250	Sqm	50.59	Rupees Fifty And Fifty Nine Paise Only	31217.19
50	Repair of Pot holes filled with 75 mm BM X 1.25	0.00000	Cum	10608.90	Rupees Ten Thousand Six Hundred Eight And Ninety Paise Only	0.00
51	Patch repair over Pot hole with 13.2 mm Surface Dressing (Qty=L*Br*% taken) X 1.25	0.00000	Sqm	84.23	Rupees Eighty Four And Twenty Three Paise Only	0.00
52	Patch repair over bituminous surface with 9.5 mm Surface Dressing (Qty=L*Br*% taken) X 1.25	41.83594	Sqm	74.40	Rupees Seventy Four And Forty Paise Only	3112.59
53	Maintenance of Earthen Drains	0.00000	M	0.00	Rupees Only	0.00
54	Maintenance of C/D Works (Hume Pipe Culvert)	5.00000	No.	1076.79	Rupees One Thousand Seventy Six And Seventy Nine Paise Only	5383.95
55	Maintenance of C/D Works (Slab Culvert)	1.00000	No.	2218.36	Rupees Two Thousand Two Hundred Eighteen And Thirty Six Paise Only	2218.36
56	Maintenance of Road signs	0.21940	Km	1034.49	Rupees One Thousand Thirty Four And Forty Nine Paise Only	226.97
57	Maintenance of 200 m and km stones	0.26328	Km	630.53	Rupees Six Hundred Thirty And Fifty Three Paise Only	166.01

Executive Engineer

Rural Works Department

Works Division-Jhanjharpur

Superintending Engineer
Works Circle Darbhanga
Rural Works Department

Executive Engineer
Rural Works Department
Works Division, Jhanjharpur

Scanned with OKEN Scanner

Name of Work: Construction of Road & CD Works under NABARD Scheme
KOSI BANDH TO DAKAHA TOL,
Is a link road with Link No
5035

DIVISION: JHANJHARPUR

BLOCK: MADHEPUR

LENGTH: 2.194 KM

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs.
				Figure	Words	
59	(i) Cutting of branches of trees and shrubs	4.00000	No.	100.50	Rupees One Hundred And Fifty Paise Only	402.00
60	(ii) Cutting of shrubs from roadway	18.00000	No.	6.17	Rupees Six And Seventeen Paise Only	111.06
61	(iii) Trimming of grass and weeds	8.10000	Sqm	2.06	Rupees Two And Six Paise Only	16.69
62	White washing of parapet walls of CD work and tree trunks	105.00000	Sqm	15.52	Rupees Fifteen And Fifty Two Paise Only	1629.60
63	2nd Year Maintenance Restoration of Raincuts/Berms with soil, moorum etc (Qty=L*Bs*0.3*%taken) X 1.25	133.28550	Cum	341.72	Rupees Three Hundred Forty One And Seventy Two Paise Only	45546.32
64	Making up of Berms/shoulder, stripping excess soil from the shoulder surfaces to achieve level etc. (Qty=L*Br*%taken) X 1.25	740.47500	Sqm	50.59	Rupees Fifty And Fifty Nine Paise Only	37460.63
65	Repair of Pot holes filled with 75 mm BM X 1.25	0.00000	Cum	10608.90	Rupees Ten Thousand Six Hundred Eight And Ninety Paise Only	0.00
66	Patch repair over Pot hole with 13.2 mm Surface Dressing (Qty=L*Br*%taken) X 1.25	0.00000	Sqm	84.23	Rupees Eighty Four And Twenty Three Paise Only	0.00
67	Patch repair over bituminous surface with 9.5 mm Surface Dressing (Qty=L*Br*%taken) X 1.25	83.67188	Sqm	74.40	Rupees Seventy Four And Forty Paise Only	6225.19
68	Maintenance of Earthen Drains	0.00000	M	2.47	Rupees Two And Forty Seven Paise Only	0.00
69	Maintenance of C/D Works (Hume Pipe Culvert)	5.00000	No.	1076.79	Rupees One Thousand Seventy Six And Seventy Nine Paise Only	5383.95
70	Maintenance of C/D Works (Slab Culvert)	1.00000	No.	2218.36	Rupees Two Thousand Two Hundred Eighteen And Thirty Six Paise Only	2218.36
71	Maintenance of Road signs	0.26328	Km	1034.49	Rupees One Thousand Thirty Four And Forty Nine Paise Only	272.36
72	Maintenance of 200 m and km stones	0.32910	Km	630.53	Rupees Six Hundred Thirty And Fifty Three Paise Only	207.51
73	(i) Cutting of branches of trees and shrubs	4.00000	No.	100.50	Rupees One Hundred And Fifty Paise Only	402.00
74	(ii) Cutting of shrubs from roadway	18.00000	No.	6.17	Rupees Six And Seventeen Paise Only	111.06
75	(iii) Trimming of grass and weeds	10.12500	Sqm	2.06	Rupees Two And Six Paise Only	20.86
76	White washing of parapet walls of CD work and tree trunks	105.00000	Sqm	15.52	Rupees Fifteen And Fifty Two Paise Only	1629.60
77	3rd Year Maintenance Restoration of Raincuts/Berms with soil, moorum etc (Qty=L*Bs*0.3*%taken) X 1.25	155.49975	Cum	341.72	Rupees Three Hundred Forty One And Seventy Two Paise Only	53137.37
78	Making up of Berms/shoulder, stripping excess soil from the shoulder surfaces to achieve level etc. (Qty=L*Br*%taken) X 1.25	740.47500	Sqm	50.59	Rupees Fifty And Fifty Nine Paise Only	37460.63
79	Repair of Pot holes filled with 75 mm BM X 1.25	9.41309	Cum	10608.90	Rupees Ten Thousand Six Hundred Eight And Ninety Paise Only	99862.53
80	Patch repair over Pot hole with 13.2 mm Surface Dressing (Qty=L*Br*%taken) X 1.25	125.50781	Sqm	84.23	Rupees Eighty Four And Twenty Three Paise Only	10571.52
81	Patch repair over bituminous surface with 9.5 mm Surface Dressing (Qty=L*Br*%taken) X 1.25	125.50781	Sqm	74.40	Rupees Seventy Four And Forty Paise Only	9337.78
82	Maintenance of Earthen Drains	0.00000	M	2.47	Rupees Two And Forty Seven Paise Only	0.00
83	Maintenance of C/D Works (Hume Pipe Culvert)	5.00000	No.	1076.79	Rupees One Thousand Seventy Six And Seventy Nine Paise Only	5383.95

Executive Engineer
Rural Works Department
Works Division-Jhanjharpur

Superintending Engineer
Works Circle Darbhanga
Rural Works Department

Executive Engineer
Rural Works Department
Works Division, Jhanjharpur

Scanned with OKEN Scanner

Name of Work Construction of Road & CD Works under NABARD Scheme
KOSI BANDH TO DAKAHA TOL,
Is a link road with Link No
5035

DIVISION: JHANJIHARPUR

BLOCK: MADHEPUR
SCHEDULE OF WORKS

LENGTH: 2.194 KM

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs.
				Figure	Words	
82	Maintenance of C/D Works (Slab Culvert)	1.00000	No.	2218.36	Rupees Two Thousand Two Hundred Eighteen And Thirty Six Paise Only	2218.36
84	Maintenance of Road signs	0.32910	Km	1034.49	Rupees One Thousand Thirty Four And Forty Nine Paise Only	340.45
85	Maintenance of 200 m and km stones	0.39492	Km	630.53	Rupees Six Hundred Thirty And Fifty Three Paise Only	249.01
86	(i) Cutting of branches of trees and shrubs	4.00000	No.	100.50	Rupees One Hundred And Fifty Paise Only	402.00
87	(ii) Cutting of shrubs from roadway	18.00000	No.	6.17	Rupees Six And Seventeen Paise Only	111.06
88	(iii) Trimming of grass and weeds	10.12500	Sqm	2.06	Rupees Two And Six Paise Only	20.86
89	White washing of parapet walls of CD work and tree trunks	105.00000	Sqm	15.52	Rupees Fifteen And Fifty Two Paise Only	1629.60
90	4th Year Maintenance Restoration of Raincuts/Berms with soil.moorum etc.(Qty=L*Br*0.3*%taken) X 1.25	177.71400	Cum	341.72	Rupees Three Hundred Forty One And Seventy Two Paise Only	60728.43
91	Making up of Berms/shoulder, stripping excess soil from the shoulder surfaces to achieve level etc. (Qty=L*Br*%taken) X 1.25	987.30000	Cum	50.59	Rupees Fifty And Fifty Nine Paise Only	49947.51
92	Repair of Pot holes filled with 75 mm BM X 1.25	12.55078	Sqm	10608.90	Rupees Ten Thousand Six Hundred Eight And Ninety Paise Only	133149.97
93	Patch repair over Pot hole with 13.2 mm Surface Dressing (Qty=L*Br*%taken) X 1.25	167.34375	Cum	84.23	Rupees Eighty Four And Twenty Three Paise Only	14095.36
94	Patch repair over bituminous surface with 9.5 mm Surface Dressing (Qty=L*Br*%taken) X 1.25	167.34375	Sqm	74.40	Rupees Seventy Four And Forty Paise Only	12450.38
95	Maintenance of Earthen Drains	0.00000	Sqm	2.47	Rupees Two And Forty Seven Paise Only	0.00
96	Maintenance of C/D Works (Hume Pipe Culvert)	5.00000	M	1076.79	Rupees One Thousand Seventy Six And Seventy Nine Paise Only	5383.95
97	Maintenance of C/D Works (Slab Culvert)	1.00000	No.	2218.36	Rupees Two Thousand Two Hundred Eighteen And Thirty Six Paise Only	2218.36
98	Maintenance of Road signs	0.32910	No.	1034.49	Rupees One Thousand Thirty Four And Forty Nine Paise Only	340.45
99	Maintenance of 200 m and km stones	0.39492	Km	630.53	Rupees Six Hundred Thirty And Fifty Three Paise Only	249.01
100	(i) Cutting of branches of trees and shrubs	4.00000	Km	100.50	Rupees One Hundred And Fifty Paise Only	402.00
101	(ii) Cutting of shrubs from roadway	18.00000	No.	6.17	Rupees Six And Seventeen Paise Only	111.06
102	(iii) Trimming of grass and weeds	10.12500	No.	2.06	Rupees Two And Six Paise Only	20.86
103	White washing of parapet walls of CD work and tree trunks	105.00000	Sqm	15.52	Rupees Fifteen And Fifty Two Paise Only	1629.60
104	5th Year Maintenance Restoration of Raincuts/Berms with soil.moorum etc.(Qty=L*Br*0.3*%taken) X 1.25	199.92825	Cum	341.72	Rupees Three Hundred Forty One And Seventy Two Paise Only	68319.48
105	Making up of Berms/shoulder, stripping excess soil from the shoulder surfaces to achieve level etc. (Qty=L*Br*%taken) X 1.25	1110.71250	Sqm	50.59	Rupees Fifty And Fifty Nine Paise Only	56190.95
106	Repair of Pot holes filled with 75 mm BM X 1.25	15.68848	Cum	10608.90	Rupees Ten Thousand Six Hundred Eight And Ninety Paise Only	166437.52
107	Patch repair over Pot hole with 13.2 mm Surface Dressing (Qty=L*Br*%taken) X 1.25	209.17969	Sqm	84.23	Rupees Eighty Four And Twenty Three Paise Only	17619.21

Executive Engineer

Rural Works Department

Works Division-Jhanchiharpur

Superintending Engineer

Works Circle Darbhanga

Rural Works Department

Executive Engineer
Rural Works Department
Works Division, Jhanchiharpur

Scanned with OKEN Scanner

**Name of Work: Construction of Road & CD Works under NABARD Scheme
KOSI BANDH TO DAKAHA TOL,
Is a link road with Link No
S035**

DIVISION: JHANJHARPUR

BLOCK:

MADHEPUR

LENGTH: 2.194 KM

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs.
				Figure	Words	
108	Patch repair over bituminous surface with 9.5 mm Surface Dressing (Qty=L*B*%taken) X 1.25	209.17969	Sqm	74.40	Rupees Seventy Four And Forty Paise Only	15562.97
109	Maintenance of Earthen Drains	0.00000	M	2.47	Rupees Two And Forty Seven Paise Only	0.00
110	Maintenance of C/D Works (Hume Pipe Culvert)	5.00000	No.	1076.79	Rupees One Thousand Seventy Six And Seventy Nine Paise Only	5383.95
111	Maintenance of C/D Works (Slab Culvert)	1.00000	No.	2218.36	Rupees Two Thousand Two Hundred Eighteen And Thirty Six Paise Only	2218.36
112	Maintenance of Road signs	0.32910	Km	1034.49	Rupees One Thousand Thirty Four And Forty Nine Paise Only	340.45
113	Maintenance of 200 m and km stones	0.52656	Km	630.53	Rupees Six Hundred Thirty And Fifty Three Paise Only	332.01
114	(i) Cutting of branches of trees and shrubs	4.00000	No.	100.50	Rupees One Hundred And Fifty Paise Only	402.00
115	(ii) Cutting of shrubs from roadway	18.00000	No.	6.17	Rupees Six And Seventeen Paise Only	111.06
116	(iii) Trimming of grass and weeds	16.87500	Sqm	2.06	Rupees Two And Six Paise Only	34.76
117	White washing of parapet walls of CD work and tree trunks	105.00000	Sqm	15.52	Rupees Fifteen And Fifty Two Paise Only	1629.60
Total estimated cost in Figures						15712749.91
Quoted Amount					15712750.00	15712750.00
Quoted rate in Words					Rupees One Crore Fifty Seven Lakh Twelve Thousand Seven Hundred Fifty Only	

B.O. & Approved for Rs 15712750.00 (Rupees one crore fifty seven lakh twelve thousand seven hundred fifty) only

[Signature]
Superintendent Engineer
Works Circle Darbhanga
Rural Works Department

[Signature]

[Signature]
Executive Engineer

Rural Works Department

Works Division-Jhanjharpur

13/5/20

[Signature]
26/5/14-
Executive Engineer
Rural Works Department
Works Division, Jhanjharpur

बिहार सरकार
ग्रामीण कार्य विभाग

पत्रांक - मु ३०-४ (३०)-नाबार्ड-०३-३९/२०१७

8281

/पटना, दिनांक- 13/9/17

प्रेषक,
संजय कुमार भाठराओ
अपर सचिव।

सेवा में
महासंचालक (लेखा एवं हकदारी)
बिहार, पटना।

विषय- योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परियोजना-103-ग्राम विकास-राज्य योजना-0105-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना)-उपशीर्ष के अन्तर्गत बिहार राज्य के विभिन्न जिलों में (परिशिष्ट-1 के रूप में संलग्न सूची के अनुरूप) कुल 62 पथ निर्माण योजनाओं पर पथवार प्रशासनिक स्वीकृति प्रदान करने के संबंध में।

महोदय,

निदेशानुसार योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परियोजना-103-ग्राम विकास-राज्य योजना - उप शीर्ष-0105 - ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना) - उप शीर्ष के अन्तर्गत बिहार राज्य के विभिन्न जिलों में (परिशिष्ट - 1 के रूप में संलग्न सूची के अनुरूप) कुल 62 पथ निर्माण योजनाओं जिसकी लम्बाई 108.812 कि०मी० एवं राशि रु० 72.8974 करोड़ (बहतर करोड़ नवासी लाख चौहतर हजार रु० मात्र) है-हेतु पथवार प्रशासनिक स्वीकृति प्रदान की जाती है।

परिशिष्ट-1

नाबार्ड संपोषित योजना अन्तर्गत वित्तीय वर्ष 2017-18 के लिए प्रशासनिक अनुमोदित योजनाओं की सूची :-


Sl. No.	District	Works Division	Block	MIMGSY CNCPL No.	Name of Road	Length	Construction Cost	Maintenance Cost	TA Amount	Amount
						(KM)			(In Lacs)	Lac/KM
1	2	3	4	5	6	7	8	9	10	11
1	East Champaran	Motihari	Kotwa	S02	N.H. 28 Taktapur	0.902	56.552	1.678	58.23	62.70
2	East Champaran	Areraj	Areraj	S07	Ramshirya Chowk to Barharwa Kalwar Tola	0.845	56.642	1.748	58.39	67.03
3	East Champaran	Areraj	Areraj	S04	SH Mungra to Harijan Toli	0.819	56.021	1.293	57.314	68.40
4	East Champaran	Chakia	Chakia	S062	Chakia Sahebganj Sadak Kuwan Araa Machine se Kuwan Bichala Tola Noor Alam ke ehar tak via Kanu	0.654	43.330	0.05	43.38	66.25
5	East Champaran	Chakia	Mehsi	S07	Mahammadpur Bajar to Salempur Balakothi PMGSY Road tak	0.629	49.590	1.21	50.80	78.84
6	Madhubani	Jhanjharpur	Andharathar i	S011	Phulwariya to Phulwariya Mushari	1.295	81.339	7.631	88.97	62.81
7	Madhubani	Jhanjharpur	Andharathar i	S030	RWD Road H School to Kwarpatij Navtoli	2.100	134.750	9.680	144.43	64.17
8	Madhubani	Jhanjharpur	Jhanjharpur	S029	NH-57 to Chanauraganj Yadav Tol	1.297	82.290	6.29	88.58	63.45
9	Madhubani	Jhanjharpur	Madhepur	S035	Kosi Bandh to Dakaha Tol	2.194	148.470	13.80	162.27	67.67

Executive Engineer
Rural Works Department
Works Division, Jhanjharpur

Scanned with OKEN Scanner

SL No.	District	Works Division	Block	MSGSY CNCPL No.	Name of Road	Length (K.M.)	Construction Cost	Maintenance Cost	T.A. Amount (In Lacs)
1	2	3	4	5	6	7	8	9	10
47	East Champaran	Arcra	Harsidhi	S044	Bhada Bazar to Jhharwa Miya Tola	1.528	99.365	2.887	102.252
48	Madhubani	Jainagar	Babubarhi	S070	PWD path se to Jatahi (Mahito Tola)	0.760	51.645	3.547	55.192
49	Madhubani	Jainagar	Jainagar	S037	Parsa Durga Mandir to Pithwa Tola tak	3.132	226.45	16.53	242.98
50	Madhubani	Jainagar	Jainagar	S08	N.H.104 Naar Panchayat Seema to High School Jainagar Naya Muhalla	1.428	85.47	8.41	93.88
51	Madhubani	Jainagar	Ladaniya	S0189	Mahua me Kujay Ram Ghar to Chiknowa3a Laxmi Narayan Mandir	0.585	40.64	2.774	43.411
52	Madhubani	Jainagar	Babubarhi	S082	Khair se to Islampur Paswan Tol	1.167	72.76	6.45	79.21
53	East Champaran	Motihari	Kotwa	S05	PMGSY 162 To Chituriya	3.823	242.81	11.25	254.06
54	East Champaran	Motihari	Motihari	S014	L025 to Ramgrwa Barharwa	1.471	92.07	3.45	95.52
55	East Champaran	Motihari	Sugauli	S014	Sripur Bazar to Sripur Miya Tola Chintamanpur Sima	1.126	75.17	3.340	78.510
56	East Champaran	Motihari	Turkauliya	S026	T05 to Muhabat Chhapra Part-3	2.002	112.54	5.720	118.260
57	East Champaran	Motihari	Piprakothi	S01	REO Road Dhekha Bardaha to Chainpur	1.305	81.25	1.75	83.000
58	East Champaran	Motihari	Banjariya	S026	PMGSY Nuniya Tola to Kalwar Tola	1.382	105.49	4.83	110.32
59	East Champaran	Motihari	Piprakothi	S05	Madhu Chhapra Sankar Sarziya to Ahir Tola	2.101	136.20	4.90	141.10
60	East Champaran	Motihari	Banjariya	S020	NH-28 A to Jhakiya Naika Tola	3.078	187.66	8.75	196.41
61	East Champaran	Motihari	Sugauli	S05	Sugaw Dih to Baudha Paschim	2.851	181.94	8.98	190.92
62	East Champaran	Motihari	Motihari	S029	NH-28 to Dusadh Toli	1.677	100.95	3.41	104.36
Total						108.612	6890.637	399.103	7289.74

2. इस योजना को दो वित्तीय वर्ष 2017-18 एवं 2018-19 में पूरा किये जाने का लक्ष्य है।
3. कार्यपालक अभियंता, ग्रामीण कार्य विभाग, संबंधित कार्य प्रमंडल, योजना की विस्तृत कार्य योजना तैयार करेंगे तथा उसके अनुरूप कार्य को समयबद्ध ढंग से पूर्ण कराना सुनिश्चित करेंगे।
4. कार्यपालक अभियंता, संबंधित कार्य प्रमंडल सुनिश्चित करेंगे कि स्वीकृत पथ किसी अन्य योजना के अंतर्गत सम्मिलित नहीं है।
5. कार्यपालक अभियंता, संबंधित कार्य प्रमंडल, योजना के कार्य सम्पादन हेतु निकासी एवं व्ययन पदाधिकारी होंगे।
6. कार्य ई-निविदा के माध्यम से Standard Bidding Document के आधार पर कराया जायेगा।
7. कार्य की गुणवत्ता सुनिश्चित करने की जिम्मेवारी संबंधित कार्यपालक अभियंता की होगी। किये गये कार्य का भुगतान गुणवत्ता के जोषफल के गुण-दोष के आधार पर किया जायेगा।
8. योजना के क्रियान्वयन से पूर्व इस पर स्वाम पदाधिकारी से प्राथमिक स्वीकृति प्राप्त कर ली जायगी। प्राथमिक स्वीकृति के समय सभी सदन प्राधिकार IRC SP-72 वर्ष 2015 एवं IRC SP-62 वर्ष 2014 के तकनीकी प्रावधानों का अक्षरशः अनुपालन सुनिश्चित करेंगे।


Executive Engineer
 Rural Works Department,
 Works Division, Jhanjharpur

9. इस योजना का स्वयं योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूँजीगत परिषद-103-ग्राम विकास-राज्य योजना-0105-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संचोपित योजना)-उपशीर्ष जिसका विपन्न कोड P-4515001030105 एवं स्कीम कोड-5369 के अन्तर्गत वित्तीय वर्ष 2017-18 में उपबंधित राशि से विकसनीय होगा।

10. योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूँजीगत परिषद-103-ग्राम विकास-राज्य योजना-0105-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संचोपित योजना)-उपशीर्ष के अन्तर्गत वित्तीय वर्ष 2017-18 में 454.31 लाख रुपये का बजट उपबंध स्वीकृत है।

11. कार्यपालक अभियंता, ग्रामीण कार्य विभाग, संबंधित कार्य प्रमंडल, द्वारा योजना का भौतिक एवं वित्तीय प्रगति प्रतिवेदन प्रत्येक माह के 10 तारीख तक निश्चित रूप से कमरा संबंधित अधीक्षण अभियंता एवं संबंधित मुख्य अभियंता, पटना के माध्यम से विभाग को उपलब्ध कराया जायेगा।

12. इन योजनाओं का निर्माण नाबार्ड के सहित कराये जाने के प्रस्ताव पर मा० मुख्यमंत्री महोदय, बिहार सरकार का अनुमोदन प्राप्त है। ये 62 एच Brics New development Bank (NDB) के वित्त पोषण के लिए पूर्व में चिन्हित मुख्यमंत्री ग्राम संपर्क योजना के 656 पर्यों की सूची में शामिल है।

13. इन पथवार योजनाओं के प्रशासनिक स्वीकृति के प्रस्ताव पर संचिका सं०- मु० अ०-4 (मु०) नाबार्ड-03-39/2017 के मु० सं०-30/टि० पर दिनांक 05.08.17 को अनुमोदन प्राप्त है।

14. बिहार कोषागार संहिता में निहित प्रावधानों के आलोक में बजट प्रावधान के अंतर्गत ही राशि की निकाली की जाय।

15. वित्त विभाग के संकल्प संख्या-4-45/94-301 वि (2) दिनांक 31.01.1995 एवं वित्त विभाग के पत्रांक स्कीम (8)-11-2005-5090 दि (2) दिनांक 15.09.05 एवं 295 दिनांक 24.03.15 के आलोक में तथा वित्त विभाग के संकल्प सं० 96 दिनांक 03.01.2008 में निहित निर्देशों का अधरशः पालन किया जाय तथा बिहार वित्त नियमावली के सुसंगत प्रावधानों के आलोक में योजना में उपबंधित राशि की उपलब्धता के आधार पर व्यय की जाय। यह आदेश आंतरिक वित्तीय सलाहकार की सहमति प्राप्त कर निर्गत किया जा रहा है। आंतरिक वित्तीय सलाहकार की सहमति संचिका सं०- मु० अ०-4 (मु०) नाबार्ड-03-39/2017 के पृष्ठ संख्या-33/टि० पर दिनांक-08.09.17 को प्राप्त है।

16. यह राशि उसी मद में खर्च की जायेगी, जिसके लिए पुनर्विनियोजित की गयी है, अन्य में नहीं।

17. योजना के लिए संबंधित कार्यपालक अभियंता से विस्तृत कार्य योजना मांगी जायेगी एवं प्राक्कलन की विशिष्टताओं के अनुसार निर्धारित समय सीमा के अंदर कार्य पूर्ण कराना सुनिश्चित किया जाय।

18. योजना के कार्यान्वयन के कम में इनका निर्धारित निरीक्षण (नियमित अंतराल पर) अनिवार्य रूप से किया जाय तथा प्रतिवेदन अभिलेखबद्ध किया जाय।

19. वित्त विभाग के पत्रांक-770, दिनांक 20.09.11 के द्वारा सूचित किया गया है कि नाबार्ड से RUDF के अन्तर्गत नई परियोजनाओं की प्रशासनिक अनुमोदन प्राप्त करने के उपरान्त ही स्वीकृति हेतु नाबार्ड को भेजी जाय।

विभागाध्यक्ष
11.09.17
(संजय कुमार)
अपर सचिव

आपांक- मु० अ०-4 (मु०) नाबार्ड-03-39/2017 8281 /पटना, दिनांक- 13/9/17
प्रतिलिपि- सभी संबंधित कोषागार पदाधिकारी, जिला कोषागार/उप कोषागार को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित।

अपर सचिव

आपांक- मु० अ०-4 (मु०) नाबार्ड-03-39/2017 8281 /पटना, दिनांक- 13/9/17
प्रतिलिपि- माननीय मंत्री के आप्त सचिव, ग्रामीण कार्य विभाग/प्रधान सचिव, योजना एवं विकास विभाग/वित्त विभाग (आय-व्यय शाखा)/आंतरिक वित्तीय सलाहकार, ग्रामीण कार्य विभाग/मंत्रिमंडल सचिवालय एवं समन्वय विभाग/कार्मिक एवं प्रशासनिक सुधार विभाग, सभी संबंधित प्रमण्डलीय आयुक्त/सभी संबंधित जिला पदाधिकारी/सभी संबंधित उप विकास आयुक्त/अभियंता प्रमुखए ग्राम का० वि०, बिहार, पटना/सभी संबंधित मुख्य अभियंता, पटना, ग्रामीण कार्य विभाग/मु० अ०-4 (मुख्यालय), ग्राम का० वि०/सभी संबंधित अधीक्षण अभियंता, ग्राम का० वि०, कार्य अंचल/सभी संबंधित कार्यपालक अभियंता, ग्राम का० वि० कार्य प्रमंडल/मुख्य महाप्रबंधक नाबार्ड, बिहार क्षेत्रीय कार्यालय, (मीर्या कम्प्लेक्स, पॉपुलरी मंजिल) डाक बंगला रोड, पटना को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित। आई०टी० नोटल, ग्रामीण कार्य विभाग को विभाग के वेबसाईट पर अपलोड करने हेतु प्रेषित।

अपर सचिव

Executive Engineer
Rural Works Department
Works Division, Jhanyharpur