



8998 64444 2020 25/10/20

मधुबनी
(स्टाम्प भेन्डर) मधुबनी
नं. 10-995/20-22

Below: 5.31% MMGSUY Time of Completion: 12 Months. Date of Completion: 19.09.20

Notes on Standard form of Agreement

The Agreement should incorporate any corrections or modifications to the Bid resulting from correction of errors (Instructions to Bidders, Clause 26)

Agreement No. 28 CMBD/2025-26 MMGSUY (RRSMP)

This agreement, made the 28th Day of October 2025

Between...Executive Engineer RWD (Works) Division, Jaynagar (Name & Address of Employer) (hereinafter called "the Employer") of the one part, and M/S Maa Rajeshwari Construction Pvt Ltd, Rajeshwari Sadan, At-Po-Fulvariya, PS- Moker, Dist- Saran, Bihar-841416. (Name and Address of Contractor) hereinafter called "the Contractor" of the other part). Whereas the Employer is desirous that the Contractor execute Construction of Road Package No.- MMGSUY-RRSMP/25-26 Jaynagar/06 under MMGSUY (RRSMP). [Name and Identification number of Contract] (hereinafter called "The Works") and the employer has accepted the Bid by the Contractor for the execution and completion of such works and the remedying of any defects therein at a cost of Rupees 15,47,34,681.00 (Rupees Fifteen Core Forty Seven Lakh Thirty four thousand Six hundred Eighty one only.)

Maa Rajeshwari Construction Pvt. Ltd.

28/10/25
Director

Executive Engineer
Rural Works Department
Works Division, Jaynagar

28/10/25

HOW THIS AGREEMENT WITNESSETH as follows:

1. In this Agreement, words and expressions shall have the same meanings as are respectively assigns to them in conditions of Contract hereinafter referred to and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the contractor hereby covenants with the Employer to execute and complete the works and remedy any defects therein in conformity in all aspects with the provisions of the contract.
3. The Employer hereby covenants to pay the Contractors in consideration of the execution and completion of the works and the remedying the defects wherein the Contracts Price or such other sum as may become payable under the provisions of the contract at the times and in the manner prescribed by the Contracts.
4. The following documents shall be deemed to form and be read and construed as part of this Agreement, via:
 - i) Letter of acceptance
 - ii) Notice to proceed with the works
 - iii) Contractors Bid
 - iv) Contract Data
 - v) Special conditions of contract and general conditions of contract
 - vi) Specification
 - vii) Drawings
 - viii) Bill of Quantities, and
 - ix) Any other document listed in the contract Data as forming part of the contract.

In witness whereof the parties there to have caused this Agreement to be executed the day and year first before written.

The Common Seal of.....

was here unto affixed in the presence of :

Signed, Sealed and Delivered by said.....

In the presence of:

Binding Signature of Employer.....

Binding Signature of Contractor.....

Maa Poojeshwari Construction Pvt. Ltd.

[Signature]
Director

[Signature]
31/08/15
Executive Engineer
Rural Works Department
Works Division, Jaynagar

[Signature]
31/08/15

[Signature]
29.09.15

Yojana Under MMGSUY

Agreement

Construction & Six Year maintenance of Road PKG No.-
MMGSUY-RRSMP/25-26 Jaynagar/06 Under MMGSUY (RRSMP)

Agreement No.:- MBD 28/LMBD/25-26

Accepted Rate:- 5.31% Below

Agreement Amount:- 154734681

Construction:- ~~1547~~

Maintenance:-

Start Date:- 20.05.25

Date of Completion:- 19.09.26

Maa Rajeshwari Construction Pvt. Ltd.

[Signature]
Director

[Signature]
31/07/25
Executive Engineer
Rural Works Department
Works Division, Jaynagar

[Signature]
3/10/25

[Signature]
29.09.25

OFFICE OF THE EXECUTIVE ENGINEER

R.W.D WORKS DIVISION, JAYNAGAR

Letter No...../

Date-.....

From,

Executive Engineer,
R.W.D Works Division, Jaynagar

To,

M/S Maa Rajeshwari Construction Pvt Ltd,
Rajeshwari Sadan, At+Po- Fulvariya,
PS- Maker, Dist- Saran, Bihar-841416

Subject :- Issue of Notice to proceed with the work.

Dear sir,

Pursuant to your furnishing the requisite security as stipulated in ITB clause 31 and signing of the contract for the construction and routine maintenance of the works for five years of from Package No.- MMGSUY-RRSMP/25-26Jaynagar/06 Under MMGSUY (RRSMP), you are hereby instructed to proceed with the execution of said works in accordance with contract documents. This site is handed over to you.

Yours Faithfully

Executive Engineer,
R.W.D Works Division, Jaynagar

Memo No..... Date.....

Copy forwarded to Ex. Engineer Soil Investigation Div. Madhubani/A.E./J.E RWD (W) Sub-Division, Basopatti/ Jaynagar with a copy of Agreement for information and necessary action.

Enc.:- Agreement

Maa Rajeshwari Construction Pvt. Ltd.

[Signature]
Director

[Signature]

R.W.D

[Signature]
31/07/25
Executive Engineer,
R.W.D Works Division, Jaynagar
Rural Works Department
Works Division, Jaynagar

[Signature]
20.09.25

Work Programme

Name of PKG. No. :- MMGSUY-RITSMP/25-20Jaynagar/06

Head :- MMGSUY

Name of Division :- Jaynagar

Block :- Basopatti/Jaynagar

Name of Agency :- M/S Maa Rajeshwari Construction Pvt Ltd, Rajeshwari Nudun, At Po- Fulwarlyan, P.N. Maker, Dist. Saran, Bihar-841416

Item	1 Month	2 Months	3 Months	4 Months	5 Months	6 Months	7 Months	8 Months	9 Months	10 Months	11 Months	12 Months
Clearing & Grubbing												
Earth Work												
G.S.B												
WIM GR-III												
C.D												
PCC												
BM												
SDBC												
Road Furniture												
Road Furnishing												

Maa Rajeshwari Construction Pvt. Ltd.

Director

Executive Engineer

Rural Works Department
Jaynagar Division

मुख्य अभियंता-6 दरभंगा का कार्यालय
ग्रामीण कार्य विभाग।

पत्रांक- 1685

/दिनांक- 19/9/25

प्रेषक

ई0 चन्द्रहारा कुमार

मुख्य अभियंता-6

सेवा में

कार्यपालक अभियंता,

ग्रामीण कार्य विभाग, कार्य प्रमण्डल जयनगर।

विषय शीर्ष MIMGSUY योजनान्तर्गत कार्य प्रमण्डल जयनगर का अधीन RRSMP/25-26 Jaynagar/06 (Tender ID-143341) कार्य की निविदा की स्वीकृति के संबंध में।

महोदय,

विभागीय पत्रांक-गु030(अ030)-4515-01-792/2025 पार्ट-II-3571 अगु0, दिनांक 18.09.2025 द्वारा सार्वजनित आदेश के अनुपालन में संपर्कित विषयक कार्य विहार लोक निर्माण संहिता के कडिका-163 के आलोक में सफल निविदाकार MS MAA RAJESHWARI CONSTRUCTIONS PRIVATE LIMITED. (BID ID-626076) को उनके द्वारा निविदित दर, जो परिमाण विपत्र की दर से 5.31% (पाँच दशमलव तीन एक प्रतिशत) कम है, को स्वीकृत करते हुए सम्पूर्ण कार्य कुल 15,47,34,681/- (पन्द्रह करोड़ सैंतालीस लाख चौतीस हजार छः सौ इक्कासी) रुपये मात्र की लागत पर आपकी अनुशंसा एवं कार्यदित में आवंटित किया जाता है।

- निविदा की स्वीकृति सिर्फ इसी कार्य के लिए है, जो भविष्य में पूर्वाधारण नहीं होगा।
- CMBD के संसंगत कडिकाओं के अनुरूप सवेदक से एकरारनामा हेतु Performance Security के रूप में E-BG प्राप्त किया जाय या विभागीय पत्रांक-गु030(नि0 एवं गु0नि0) विविध कार्य-06-153/2024-1725, दिनांक 08.05.2025 में दिये गये निदेश के आलोक में विहार राज्य अवस्थित Scheduled Commercial Banks से e-BG (Electronic Bank Guarantee) के स्थान पर System Generated BG with SFMS (Structured Financial Massaging Services) Number को मान्य करते हुए BG निर्गत करते समय BG के सत्यापन हेतु विभाग के Beneficiary Bank (भारतीय स्टेट बैंक, चेली राउ शाखा, पटना) का IFSC Code-SBIN0006379 एवं संबंधित कार्य प्रमण्डल के Email Id का अनिवार्य रूप से उपयोग किया जाय।
- एकरारनामा के पूर्व निविदा सूचना के अनुसार सभी वांछित कागजातों की अपेक्षित स्पष्ट एवं सत्यापित प्रति निश्चित रूप से प्राप्त कर लिया जायेगा।
- एकरारनामा से पूर्व कार्यपालक अभियंता यह सुनिश्चित कर लेंगे कि निविदाकार डिवार सूची/काली सूची या कार्य लंबित सूची में शामिल न हो।
- कार्य में व्यवहृत सामग्रियों का दर प्राक्कलन में स्वीकृत लीड के आधार पर दिया गया है, कार्य करते समय अगर इसमें कमी पाई जाती है तो उसका दर में सापेक्ष कमी कर दी जायेगी।
- इस कार्य के संबंध में ग्रामीण कार्य विभाग, विहार सरकार द्वारा निर्गत प्रशासनिक स्वीकृति एवं प्रावधिक स्वीकृति तथा निविदा आमंत्रण सूचना में उल्लेखित शर्त एकरारनामा का भाग होगा, जिसे विशेष शर्त में जोड़कर सवेदक के साथ एकरारनामा किया जायेगा।
- अनुमादित किये गये तुलनात्मक विवरणी के प्रत्येक बिन्दु की जाँच अपने स्तर से स्वयं कर लेंगे एवं त्रुटि पाये जाने की स्थिति में वस्तुस्थिति से तत्क्षण अधोहस्ताक्षरी को अवगत कराएंगे। त्रुटि के सुधारोपरान्त एकरारनामा की कार्रवाई की जायेगी।
- एकरारनामा के समय प्रत्येक गद के भाषा की शुद्धता की जाँच कार्यपालक अभियंता स्वयं कर लेंगे एवं यह सुनिश्चित करेंगे कि इसमें कोई त्रुटि न हो।
- कार्यारम्भ के पूर्व कार्यपालक अभियंता कार्य स्थल के निरीक्षणोपरान्त स्थल की स्थिति एवं प्राक्कलन में किये गये उपग्रह से पूरी तरह आवस्त हो लेंगे एवं प्रशासनिक स्वीकृति तथा प्रावधिक स्वीकृति के अग्रसारण प्रारूप में दिये गये निदेश का अनुपालन सुनिश्चित कराएंगे। पथ का नाम, परिमाण विपत्र की राशि, तकनीकी स्वीकृति की राशि, प्रशासनिक स्वीकृति की राशि, सवेदक द्वारा उद्धृत दर, परकर्मित दर, Bid Capacity आदि का मिलान कर ही कार्य आवंटन आदेश निर्गत करेंगे। अधीक्षण अभियंता/कार्यपालक अभियंता कार्य आवंटन/LOA निर्गत करने से पूर्व मिलान कर लेंगे कि परिमाण विपत्र की राशि प्रशासनिक अनुमोदन की राशि के अनुज्ञेय सीमा के अन्दर है। यदि अनुज्ञेय सीमा से अधिक हो तो एकरारनामा के पूर्व पुनरीक्षित प्रशासनिक अनुमोदन प्राप्त कर लिया जाय।
- कार्यारंभ निर्गत करने से पहले संबंधित सवेदक से एकरारित अवधि के अन्दर कार्य समाप्त करने हेतु मासिक कार्य प्रोग्राम हस्ताक्षरित कराकर प्राप्त कर लेंगे जो की एकरारनामा का भाग होगा।
- अधीक्षण अभियंता एवं कार्यपालक अभियंता विशेष रूप से ध्यान देंगे कि कार्य मानक विविधियों के अनुरूप निर्धारित कार्य अवधि के अंदर पूरा की जायेगी।

Maa Rajeshwari C 'uction Pvt. Ltd.

Director

Executive Engineer
Rural Works Department
Works Division, Jaynagar

29.09.25

13. कार्य समाप्ति की अवधि निविदा आमंत्रण सूचना के अनुसार होगी।
14. इस कार्य का व्यय शीर्ष MMSUY योजनान्तर्गत से मिलने वाले राशि अन्तर्गत उपयुक्त राशि से विकलित होगा।
15. कार्य का प्रगति प्रतिवेदन प्रत्येक महीने की सातवीं तारीख तक निश्चित रूप से इस कार्यालय को समर्पित की जाय।
16. आप निविदा कामजातों एवं तुलनात्मक विवरणी के जाचोपरान्त आप आवश्यक निर्देशों को अपने स्तर से निर्गत करेंगे।
17. एकरारनामा से पहले निविदाताओं द्वारा दिये गये कामजात के सत्यापन उनके मूल कामजात से मिलान कर लेंगे। कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, जयनगर तुलनात्मक विवरणी की एक अभिप्रमाणित प्रति अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, मधुबनी को अभिलेख हेतु उपलब्ध करा देंगे। निर्देश दिया जाता है कि संवेदक से कार्य प्रोयाग प्राप्त कर लेंगे तथा उनका कार्यक्षमता कुशलता एवं पूर्व से आवंटित कार्यों की प्रगति से संतुष्ट हो लें।
18. इस निविदा की राशि में अगर कोई अंतर होता है तो इसकी सूचना तुरन्त इस कार्यालय को दी जाय।
19. कार्यपालक अभियंता, एकरारनामा करने के पूर्व संवेदक का निवेदन संख्या, पूर्ण पता एवं दूरभाष संख्या कार्यादेश में अंकित करेंगे तथा इस कार्यालय को सूचित करेंगे।
20. परिमाण विपत्र की दर से कम दर उद्धृत करने वाले संवेदक से विभाग द्वारा पूर्व में निर्गत दिशा निर्देश के आलोक में अतिरिक्त वांछित परफॉरमेंस सिब्युरिटी की राशि जमा कराना सुनिश्चित करेंगे।
21. किसी भी परिस्थिति में निजी जमीन पर नियमानुसार कार्रवाई किये बिना निर्माण कार्य नहीं कराया जाय।
22. प्रत्येक 15 दिनों पर संवेदक से स्वहस्ताक्षरित विपत्र प्राप्त कर स्थल से मिलान कर मापी पुस्तिका में मापी दर्ज कर भुगतान सुनिश्चित करेंगे।
23. एकरारनामा से पूर्व नियमानुसार Character Certificate and GST Clearance Certificate प्राप्त कर लेंगे। इसका प्रतिवेदन अधोहस्ताक्षरी को समर्पित करेंगे।
24. कार्य के कार्यान्वयन में JV के सभी भागीदार की भागीदारी निविदा में दिये गये JV Agreement के अनुरूप होनी चाहिए। यदि इसमें किसी भी प्रकार का फेरबदल हेतु सक्षम प्राधिकार से अनुमति प्राप्त करेंगे।
25. निविदा में यंत्र-संयंत्र एवं अभियंताओं के संग्रह में दिये गए शपथ के अनुसार एकरारनामा करने से पहले इनके कामजात की जांच कर लेंगे। कार्य स्थल पर यंत्र-संयंत्र एवं अभियंता की तैनाती सुनिश्चित करायेगे। अधोहस्ताक्षरी द्वारा निरीक्षण के क्रम यदि यंत्र-संयंत्र एवं अभियंता की तैनाती में कमी पायी जायेगी तो नियमानुसार संवेदक पर कार्रवाई सुनिश्चित किया जायेगा।
26. कार्यपालक अभियंता कार्यावदन आदेश प्राप्त होते ही संवेदक को अविलंब LOA (Letter of Acceptance) निर्गत करेंगे एवं CMBD की ITB की कंडिका 33.2 में निहित प्रावधान के आलोक में 15 दिनों के अन्दर Performance Security प्राप्त करते हुए एकरारनामा की कार्रवाई सुनिश्चित करेंगे। निर्धारित अवधि के अन्दर Performance Security जमा नहीं करने की स्थिति में ITB की कंडिका 34.2 के आलोक में कार्रवाई करते हुए अधीक्षण अभियंता के माध्यम से प्रस्ताव अधोहस्ताक्षरी को समर्पित करेंगे। विशेष परिस्थिति में निर्धारित अवधि के पश्चात एकरारनामा करने हेतु Proper Justification के साथ प्रस्ताव उचित माध्यम से समर्पित करेंगे एवं अधोहस्ताक्षरी के अनुमति के उपरान्त ही एकरारनामा करेंगे।
27. विभागीय पत्रांक-मु0अ0(अ0उ0)4515-01-792/2025 पार्ट-II-3571 अनु0, दिनांक 18.09.2025 के आलोक में पत्र प्राप्ति के 24 घंटे के भीतर Letter of Acceptance (LOA) संबंधित संवेदक को निर्गत करेंगे।

कृपया पत्र प्राप्ति की सूचना देंगे।

अनु0-यथा उपयुक्त।

जापांक- 1685/
प्रतिलिपि-

दिनांक- 19/9/25

विश्वासभाजन

मुख्य अभियंता-6

1. अपर मुख्य कार्यपालक पदाधिकारी-सह-सचिव, ब्रांडा, पटना को सूचनार्थ समर्पित।
2. अभियंता प्रमुख, ग्रामीण कार्य विभाग, पटना को सूचनार्थ समर्पित।
3. अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, मधुबनी को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित।
4. सहायक आई0टी0 मैनेजर को सूचनार्थ एवं संबंधित अधीक्षण अभियंता/कार्यपालक अभियंता को ई-मेल आई0डी0 पर अपलोड करने हेतु प्रेषित।

Maa Rajeshwari Construction Pvt. Ltd.

Director

Executive Engineer
Rural Works Department
Works Division, Jaynagar

29.05.25

Office Of The Executive Engineer
Rural Works Department, Works Division, Jaynagar, Madhubani.

Letter of Acceptance

Letter No. 1479

Date: 20.09.2025

From,

Executive Engineer
Rural Works Department
Works Division, Jaynagar

To,

M/S Maa Rajeshwari Construction Private Limited,
Rajeshwari Sadan, At-PO- Fulvariya, PS- Maker,
Dist- Saran, Bihar- 841416.

Dear Sir,

This is to notify you that Your Bid dated 08th Aug. 2025 for the execution of the Maintenance and repair of Package no.- MMGSUY-RRSMP/25-26 Jaynagar/06 (Tender I.D- 143341 BID ID- 626076) for the contract Price of Rupees 15,47,34,681=00 (Rupees Fifteen Crore Forty Seven lacs Thirty four thousand Six Hundred Eighty one) only as corrected and modified in accordance with the Instruction to Bidders is hereby accepted by the agency.

You are hereby requested to furnish total Performance Security including an additional Security for unbalanced bid in terms of ITB clause 27.4, for an amount of Rs. 55.660 Lacs (Rupees Fifty five lacs Sixty Six thousand) only, (Required Security Deposit 32.700 Lacs And Additional Performance Security 22.960 Lacs) within 15th days in accordance with the Conditions of Contract using for that purpose form in Section VIII Annex D and Sign the Contract, failing which action as stated in para 34.2 of ITB will be taken.

Yours faithfully,

Executive Engineer
Rural Works Department
Works Division, Jaynagar.

Maa Rajeshwari Construction Pvt. Ltd.

Director

Executive Engineer
Rural Works Department
Works Division, Jaynagar

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमण्डल, जयनगर

Email Id: rwdjannagar@gmail.com Mob No. 8986915802

पत्रांक-

जयनगर / दिनांक-

प्रेषक:-

ई० गो० जमील अबुल हसन
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, जयनगर

सेवा में,

मुख्य अभियंता-06
ग्रामीण कार्य विभाग
दरभंगा, बिहार

विषय:-

ग्रामीण कार्य विभाग कार्य प्रमण्डल, जयनगर के अधीन शीर्ष RRSMP (MMGSUY)
योजनान्तर्गत पथ निर्माण कार्य का वित्तीय बीड समर्पित करने के संबंध में।

महाशय,

उपर्युक्त विषय के संबंध में कहना है कि ग्रामीण कार्य विभाग कार्य प्रमण्डल, जयनगर के
अधीन शीर्ष RRSMP (MMGSUY) योजनान्तर्गत पथ निर्माण कार्य टेन्डर आई० डी०- 143341 का
वित्तीय बीड अग्रतर कार्रवाई हेतु समर्पित की जाती है।

अनु०- 01 अदद।

विश्वासभाजन

ह०

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, जयनगर

व्यापांक 1459 (31-30) जयनगर / दिनांक- 12/09/2018

प्रतिलिपि :- नोडल पदाधिकारी (MMGSUY), ग्रामीण कार्य विभाग, पटना को सूचनार्थ एवं
आवश्यक कार्रवाई हेतु समर्पित।

अनु०- 01 अदद।

Maa Rajeshwari Construction Pvt. Ltd.

Director

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, जयनगर

Executive Engineer
Rural Works Department
Works Division, Jaynagar

29.09.25

Office Memorandum No. 100/2024, Dated: 16 Nov 2024, Subject: MAA RAJESHWARI CONSTRUCTION PRIVATE LIMITED (MRCPL)
 Created By: HANU AGRAWAL
 Approved By: 16 Nov 2024 05:27 PM
 Issued To: MEMBERS OF THE BOARD
 Issued On: 2024-11-16 14:34:11

Subject: MAA RAJESHWARI CONSTRUCTION PRIVATE LIMITED (MRCPL) - 1st Additional Committee Report Special Secretary, NWRI, Bihar, Patna
 Name of Work: MAA RAJESHWARI CONSTRUCTION PRIVATE LIMITED
 Location: Patna

S. No.	Work Name	SCHEDULE OF WORK ITEM(S)		Quoted Rate in Figures and Words (Iteration 3)	
		Estimated Rate	Quoted Percentage	Rate	Amount
1	MAA RAJESHWARI CONSTRUCTION PRIVATE LIMITED - 1st Additional Committee Report	154734681.31	5.31	154734681.31	Fifteen Crore Forty Seven Lakh Thirty Four Thousand One Hundred and Eighty One
2	MAA RAJESHWARI CONSTRUCTION PRIVATE LIMITED - 2nd Additional Committee Report	154734681.31	0.50	154734681.31	Sixteen Crore Twenty Four Lakh Ninty Six Thousand Seven Hundred and Forty Four
3	MAA RAJESHWARI CONSTRUCTION PRIVATE LIMITED - 3rd Additional Committee Report	154734681.31	0.00	154734681.31	Sixteen Crore Thirty Four Lakh Eleven Thousand Eight Hundred and Fifty

Lowest Amount Quoted By: M/s MAA RAJESHWARI CONSTRUCTIONS PRIVATE LIMITED (154734681.31)

Handwritten signature and date: 13/10/24

Maa Rajeshwari Construction Pvt. Ltd.
Handwritten signature and date: 21/11/24
 Director

Handwritten signature and date: 21/11/24
 Executive Engineer
 Rural Works Department
 Works Division, Jaynagar

Handwritten signature and date: 29.09.25

BBO Summary Details
Tender Title: RRSMP/25-26 Jaynagar/06
Tender ID: 2025_RWD_143341_1

Sheet Name:

Sl No	Bidder Name	Amount	Bid Rank
1	MS MAJ RAJESHWARI CONSTRUCTIONS PRIVATE LIMITED (BID ID: 626076)	154734681.31	1
2	SATYA BUILDERS (BID ID: 626562)	162496744.72	2
3	M & S PAVING PRIVATE LIMITED (BID ID: 626565)	163111850.58	3

11/09/25
12/09/25

Maa Rajeshwari Construction Pvt. Ltd.

[Signature]
Director

11/09/25
31/09/25
Executive Engineer
Rural Works Department
Works Division, Jaynagar

नितेश
29.09.25

800 0040

Select At Par, Excess (+), Less (-)

Percentage

Select

Excess (+)

Less (-)

Price Sheet Page

Tender Inviting Authority: Engineer in-charge Additional Commissioner cum Special Secretary, RWD, Bilhar, Palna
Name of Work: RRSMP/25-26 Jainagar/06
Contract No:

Name of the Bidder

PRICE SCHEDULE		NUMBER #		TEXT #		TEXT #		NUMBER #		NUMBER #	
Sl. No.	Item Description	Quantity	Units	Estimated Rate	Units	Estimated Rate	Units	Quantity	Units	Estimated Rate	Units
1	Jaso MNGSY Khatwe Tol to Kauha Tak	4	5	6	5	6	5	4	5	6	5
2	Cleaning and grubbing - Cleaning and grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stocking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.08	Mq	75360.38							
3	Construction of Subgrade And Earthen Shoulders - Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1	109.50	Cum	244.73							
4	Pavement Quality Concrete (PQC) - Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement @ 400 kg per cum, coarse and fine aggregate conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing compound, finishing to lines and grades as per drawing	152.08	Cum	7534.22							
5	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC 8 fixing in position including casting and printing etc as per drawing and technical specification clause 1703										
6	Km stone	2.00	No	2838.91							
7	200 m stone	1.00	No	751.72							
8	Retro-reflectonized Traffic Signs Providing and erecting direction and place identification retro-reflectonized sign as per IRC 87 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 2 mm thick, with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701	0.96	Sqm	13623.01							
9	Providing and fixing of retro-reflectonized cautionary, mandatory and informatory sign as per IRC 87 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801										
10	500 mm equilateral & triangle	4.00	Nos	3321.54							
11	600 mm circular	4.00	Nos	4720.58							
12	600 mm x 450 mm rectangular	1.00	Nos	4577.35							
13	900 mm side octagon	2.00	Nos	8005.56							

Maa Rajeshwari Construction Pvt. Ltd.

Director

Executive Engineer

Rural Works Department
Works Division, Jainagar

14	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes					
15	Pedestrian Crossing (2 m in length and providing at 50 cm apart)	3.60	Sqm	778.40		2802.24
16	At Edge for New & Old CC Portion	73.00	Sqm	873.89		53793.97
17	Providing and fixing of typical MMSGY informative sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5mm size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	3.00	No	10322.14		30966.42
18	1% LABOUR CESS	1.00	Rs	13505.86		13505.86
19	Seigniorage Fee	1.00	Rs	16468.91		16468.91
20	18 % GST	1.00	Rs	248500.86		248500.86
21	6 YEAR MAINTENANCE COST	24.00	Quarterly	2308.33		55399.92
22	1% LABOUR CESS	1.00	Rs	554.00		554.00
23	18 % GST	1.00	Rs	10071.72		10071.72
24	Renewal Cost					
25	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Concrete Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes	73.00	Sqm	873.89		63793.97
26	1% LABOUR CESS	1.00	Rs	637.94		637.94
27	18 % GST	1.00	Rs	11597.74		11597.74
28	PMGSY Road To Jadav Tola Clearing and Grubbing - Cleaning and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.09	Ha	75360.38		6782.43
30	Construction of Subgrade And Earthen Shoulders - Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1	91.20	Cum	244.73		22319.38
31	Pavement Quality Concrete (PQC) - Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement @ 400 kg per cum, coarse and fine aggregate conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealer primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing compound, finishing to lines and grades as per drawing	158.32	Cum	7534.22		1192817.71
32	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC 8 facing in position including painting and printing, etc as per drawing and technical specification clause 1703					
33	Xm slope	2.00	No	2898.91		5797.82


Executive Engineer
 Rural Works Department
 Works Division, Jaynagar

Madheshwari Construction Pvt. Ltd.
 16/11/2024
 Director

34	200 m stone		1.00	No	791.78	791.78
35	Retro-reflectors Traffic Signs Providing and erecting direction and place identification retro-reflectors sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701 2.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701		0.96	Sqm	13223.01	13078.09
36	Providing and fixing of retro-reflectors cautionary, mandatory and informative sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701 2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 1701		3.00	Nos	3321.64	9964.92
37	600 mm equilateral & triangle		4.00	Nos	4720.59	18882.36
38	600 mm circular		1.00	Nos	4577.39	4577.39
39	600 mm x 450 mm rectangular		4.00	Nos	4577.39	18309.56
40	900 mm x 300 mm Hazard Marker		2.00	Nos	9005.56	18011.12
41	900 mm side octagon		16.00	Nos	684.63	10954.08
42	Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC 25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704		3.60	Sqm	776.40	2802.24
43	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes		76.00	Sqm	873.89	66415.64
44	Pedestrian Crossing (2 m in length and providing at 50 cm apart)					
45	At Edge for New & Old CC Portion					
46	Providing and fixing of typical MMSY informational sign board with Logo as per MORD specifications and drawing Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on bark on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1		3.00	No	10322.14	30966.42
47	1% LABOUR CESS		1.00	Rs	14224.51	14224.51
48	Seigniorage Fee		1.00	Rs	17064.42	17064.42
49	18 % GST		1.00	Rs	261673.24	261673.24
50	6 YEAR MAINTENANCE COST		24.00	Quarterly	2416.67	58000.08
51	1% LABOUR CESS		1.00	Rs	580.00	580.00
52	18 % GST		1.00	Rs	10544.40	10544.40
53	Renewal Cost					
54	Road Marking with Hot Applied Thermoplastic Compound with Reflectorisng Glass Beads on Concrete Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes		76.00	Sqm	873.89	66415.64

Executive Engineer
 Rural Works Department
 Works Division, Javindurga

Maa Rajeshwar Construction Pvt. Ltd.
 07/08/2019
 Director

55	1% LABOUR CESS	1.00	Rs	664.16	664.16
56	18 % GST	1.00	Rs	12074.36	12074.36
57	Mukhy Path Maha Vidhaly Kamalpur To Dal Tola Kamalpur Tah Clearing and grubbing - Clearing and grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E1	0.12	Ha	75360.38	9043.25
59	Construction of Subgrade And Earthen Shoulders - Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1	182.30	Cum	244.73	39719.63
60	Pavement Quality Concrete (PQC) - Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement @ 400 kg per cum, coarse and fine aggregate conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing compound, finishing to lines and grades as per drawing	225.40	Cum	7534.22	1684213.19
61	Reinforced cement concrete M15 grade Kilometre local stone of standard design as per IRC 8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703	2.00	No	2594.91	5189.82
62	Km stone	4.00	No	791.78	3167.12
63	200 m stone				
64	Retro-reflectonised Traffic Signs Providing and erecting direction and place identification retro-reflectonised sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701	0.96	Sqm	13623.01	13078.09
65	Providing and fixing of retro-reflectonised cautionary, mandatory and informatory sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm below ground level as per drawings and Technical Specification Clause 801	5.00	Nos	3321.64	16608.20
66	600 mm equilateral & triangle	2.00	Nos	4720.59	9441.18
67	600 mm circular	1.00	Nos	4577.39	4577.39
68	600 mm x 450 mm rectangular	4.00	Nos	4577.39	18309.56
69	900 mm x 300 mm Hazard Marker	1.00	Nos	9005.58	9005.58
70	900 mm side octagon	16.00	Nos	684.63	10954.08
71	Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC 25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704				
72	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes	3.60	Sqm	776.40	2802.24
73	Pedestrian Crossing (2 m in length and providing at 50 cm apart)	108.20	Sqm	873.89	94554.90
74	At Edge for New & Old CC Portion				

Maa Rajeshwari Construction Pvt. Ltd.

Director

Executive Engineer

Rural Works Department
Works Division, Jaynagar

75	Providing and fixing of typical MMGSY informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5mm size on back on lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	5.00	No.	10322.14	51810.70
76	1% LABOUR CESS				
77	Seigniorage Fee	1.00	Rs	19998.95	19998.95
78	18 % GST	1.00	Rs	24409.70	24409.70
79	6 YEAR MAINTENANCE COST	1.00	Rs	365811.19	365811.19
80	1% LABOUR CESS	24.00	Quarterly		
81	18 % GST	1.00	Rs	5616.67	134800.08
82	Renewal Cost	1.00	Rs	1348.00	1348.00
83	Road Marking with Hot Applied Thermoplastic Compound with Reflectorsing Glass Beads on Concrete Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorsing glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes	108.20	Sqm	873.89	94554.90
84	1% LABOUR CESS				
85	18 % GST	1.00	Rs	945.55	945.55
86	Dakhinwari Tola to Bhagiranathapatti	1.00	Rs	17190.08	17190.08
87	Cleaning and Grubbing - Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.12	Ha	75360.38	9043.25
88	Granular Sub-base with Well Graded Material(Grade I) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401	94.89	Cum	2949.83	279323.87
89	Water Bound Macadam Gr III - Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405	35.51	Cum	5040.52	173988.87
90	Pavement Quality Concrete (PQC) :- Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement @ 400 kg per cum, coarse and fine aggregate conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design transported to site laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing compound. Finishing to lines and grades as per drawing	238.25	Cum	7834.22	1779883.48
91	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC 8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703				
92	Km stone	2.00	No	2888.91	5797.82

Maa Rajeshwari Construction Pvt. Ltd.

4/12/2024
Director

Executive Engineer

Rural Works Department

93	200 m stone		2.00	No	791.78	1583.56
94	Retro-reflectised Traffic Signs Providing and erecting direction and place identification retro-reflectised sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701		0.96	Sqm	13623.01	13078.09
95	Providing and erecting a "W" metal beam crash barrier comprising of 3 mm thick corrugated sheet metal beam rail, 70 cm above road ground level, fixed on ISMC series channel vertical post, 150 x 75 x 5 mm spaced 2 m centre to centre, 1.8 m high, 1.1 m below ground/road level, all steel parts and filaments to be galvanised by hot dip process, all fittings to conform to IS 1367 and IS 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm, 330 mm long complete as per clause 810		160.00		3224.25	515850.00
96	Providing and fixing of retro-reflectised cautionary, mandatory and informative sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801					
97	600 mm equilateral & triangle		5.00	Nos	3321.64	16608.20
98	600 mm circular		2.00	Nos	4720.59	9441.18
99	600 mm x 450 mm rectangular		1.00	Nos	4577.39	4577.39
101	900 mm side octagon		1.00	Nos	9005.56	9005.56
102	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes					
103	Pedestrian Crossing (2 m in length and providing at 50 cm apart)		3.60	Sqm	778.40	2802.24
104	At Edge for New & Old CC Portion		110.00	Sqm	873.89	96127.90
105	Providing and fixing of typical MMSVY informative sign board with Logo as per MORD specifications and drawing Three MS Plates of 16 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All MS will be stove enamelled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1		5.00	No	10322.14	51610.70
106	1% LABOUR CESS		1.00	Rs	29734.07	29734.07
107	Seigniorage Fee		1.00	Rs	37290.95	37290.95
108	13 % GST		1.00	Rs	547350.47	547350.47
109	6 YEAR MAINTENANCE COST		24.00	Quarterly	3469.33	83263.92
110	1% LABOUR CESS		1.00	Rs	832.64	832.64
111	18 % GST		1.00	Rs	15137.40	15137.40
112	Renewal Cost					

Maa Kashiwan Construction Pvt. Ltd.

Director

Executive Engineer

Rural Works Department
Works Division, Jaynagar

113	Road Marking with Hot Applied Thermoplastic Compound with Reflectors Glass Beads on Concrete Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectors glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC-35. The finished surface to be level, uniform and free from streaks and holes	110.00	Sqm	873.89	96127.90
114	1% LABOUR CESS	1.00			
115	18% GST	1.00	Rs	961.28	961.28
116	Phent Chowk to Evan Mandal Tol	1.00	Rs	17476.05	17476.05
117	Cleaning and Grubbing - Cleaning and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.16	Ha	75360.38	12057.66
118	Construction of Subgrade And Earthen Shoulders :- Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	758.10	Cum	244.73	185529.81
119	Granular Sub-base with Well Graded Material(Grade II) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401	12.19	Cum	2485.69	30300.56
120	Water Bound Macadam Gr III :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	42.04	Cum	5040.52	211903.46
121	Prime Coat :- Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502	560.55	Sqm	55.31	31004.02
122	Tack Coat :- Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydroblow broom as per technical specification clause 503.	2734.58	Sqm	19.03	52039.06
123	Semi Dense Bituminous Concrete :- Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects	68.37	Cum	12912.76	882845.40
124	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC-8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703	2.00	No	2896.91	5797.82
125	Km stone	3.00	No	791.78	2375.34
126	200 m stone				
127	Retro-reflectors Traffic Signs Providing and erecting direction and place identification retro-reflectors sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701 2.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701	0.96	Sqm	13623.01	13078.09
128	Providing and erecting a "W" metal beam crash barrier comprising of 3 mm thick corrugated sheet metal beam rail, 70 cm above road/ground level, fixed on ISMC series channel vertical post, 150 x 75 x 5 mm spaced 2 m centre to centre, 1.8 m high, 1.1 m below ground/road level, all steel parts and filaments to be galvanised by hot dip process, all fittings to conform to IS 1367 and IS 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm, 330 mm long complete as per clause 810	160.00	M	3224.25	515880.00

Maa Rajeshwari Construction Pvt. Ltd.

Director

Executive Engineer
Rural Works Department
Works Division, Jaynagar

129	Road Markers/Road Stud with Lens Reflector - Providing and fixing of road stud 100 x 100 mm die cast in aluminium, resistant to corrosive effect of salt and grit, filled with lens reflectors, installed in concrete or asphaltic surface by drilling holes 30 mm upto a depth of 600 mm and bedded in a suitable bituminous grout or epoxy mortar, all as per BS 873 (Part 4) 1973	722.00	Nos	274.18	187957.96
130	Providing and fixing of retro-reflective cautionary, mandulatory and informatory sign as per IRC 07 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeling, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801				
131	600 mm equilateral & triangle	0.00	Nos	3321.64	19929.84
132	600 mm circular	4.00	Nos	4720.59	18882.36
133	600 mm x 450 mm rectangular	2.00	Nos	4577.39	9154.78
134	900 mm x 300 mm Hazard Marker	4.00	Nos	4577.39	18309.56
135	900 mm side octagon	2.00	Nos	9005.56	18011.12
136	Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC 25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	18.00	Nos	684.63	10954.08
137	Planting of Trees and their Maintenance for one Year - Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year	36.00	Each	1247.52	44910.72
138	Tree Guard With MS Iron - Providing and fixing MS Iron tree guard 60 cm dia and 2 metre high above ground level formed of 4 nos. (25 x 6 x mm) and 8 nos. (25 x 3 x mm) vertical MS riveted to 3 nos. (25 x 6 mm) iron ring in two halves bolted together with 8mm dia and 30 mm long bolts including painting two coats with paint of approved brand over a coat of priming, complete in all respect	38.00	Each	2346.13	84460.68
139	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes				
140	At Edge for BT Portion	144.40	Sqm	778.40	112400.96
141	Pedestrian Crossing (2 m in length and providing at 50 cm apart)	5.40	Sqm	778.40	4203.36
142	Providing and fixing of typical MMSY informatory sign board with Logo as per MORD specifications and drawing Three MS Plates of 1.6 mm thick. Top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	5.00	No	10322.14	51610.70
143	PARAPET REPAIR				
144	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	5.96	Cum	6268.49	37360.20
145	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	41.60	Sqm	221.00	9193.60
146	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	42.24	Sqm	128.70	5436.29
147	300MM Irrigation Pipe				

Maa Rajeshwari Construction Pvt. Ltd.

9/2/2020
Director

3/10/20
Rural Works Department
Works Division, Jalandhar
3/10/20

148	Providing and laying of a reinforced cement concrete pipe duct, 300 mm dia. across the road (new construction) extending from drain to drain in cuts and toe of slope to toe of slope in fills constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC 981997 bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC 98 - 1997 and approved drawings	20.00	RM	981.26	19625.20
149	1% LABOUR CESS	1.00	Rs	28051.88	28051.88
150	Seigniorage Fee	1.00	Rs	20221.72	20221.72
151	18 % GST	1.00	Rs	477263.06	477263.06
152	6 YEAR MAINTENANCE COST	24.00	Quarterly	27829.17	667900.08
153	1% LABOUR CESS	1.00	Rs	6679.00	6679.00
154	Seigniorage Fee	1.00	Rs	1760.02	1760.02
155	18 % GST	1.00	Rs	121741.02	121741.02
156	Renewal Cost				
157	Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.20 to 0.25kg per sqm on the prepared granular surface treated with Primer and cleaned with hydrioc broom as per technical specification clause 503	2734.58	Sqm	15.89	43452.48
158	Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects	88.38	Cum	12912.76	882716.27
159	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorizing glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC-35. The finished surface to be level, uniform and free from streaks and holes	144.40	Sqm	778.40	112400.96
160	1% LABOUR CESS	1.00	Rs	10385.70	10385.70
161	Seigniorage Fee	1.00	Rs	6293.63	6293.63
162	18 % GST	1.00	Rs	189944.83	189944.83
163	Narkatiya PMGSY Sadak to Arghawa Uttarwari Tola Tak				
164	Clearing and Grubbing - Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & slacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.28	Ha	75360.38	21100.91
165	Construction of Subgrade And Earthen Shoulders - Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1	1023.75	Cum	244.73	250542.34
166	Granular Sub-base with Well Graded Material (Grade II) - Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401	15.19	Cum	2485.69	37757.63

Maa Rajeshwari Construction Pvt. Ltd.

Director


Rural Works Department
Works Division, Jaynagar

167	Water Bound Macadam Gr III :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 60-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405	52.65	Cum	5040.62	265383.28
168	Prime Coat :- Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70 - 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502	702.03	Sqm	55.31	38829.28
169	Tack Coat :- Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydroloc broom as per technical specification clause 503	3314.06	Sqm	19.03	63066.56
170	Semi Dense Bituminous Concrete :- Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects	82.85	Cum	12612.79	1065922.17
171	Pavement Quality Concrete (PQC) :- Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement @ 400 kg per cum, coarse and fine aggregate conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing compound, finishing to lines and grades as per drawing	145.82	Cum	7534.22	1058639.96
172	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC 8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703	3.00	No.	2898.91	8656.73
173	Km stone	5.00	No.	791.78	3958.90
174	200 m stone				
175	Retro-reflectors Traffic Signs Providing and erecting direction and place identification retro-reflectors sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 2 mm thick, with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701.	0.96	Sqm	13623.01	13078.09
176	Providing and fixing of retro-reflectors cautionary, mandatory and informational sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm below ground level as per drawings and Technical Specification Clause 801				
177	600 mm equilateral & triangle	6.00	Nos	3321.84	19929.34
178	600 mm circular	4.00	Nos	4720.59	18882.36
179	600 mm x 450 mm rectangular	2.00	Nos	4577.39	9154.78
180	900 mm x 300 mm Hazard Marker	4.00	Nos	4577.39	18309.56
181	900 mm side octagon	2.00	Nos	9005.56	18011.12
182	Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC 25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	16.00	Nos	984.83	10954.08
183	Planting of Trees and their Maintenance for one Year :- Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, furring the tree guard and maintaining the plants for one year	44.00	Each	1247.52	54890.88

Maa Kaleshwari Construction Pvt. Ltd.
 07/05/2024
 Director


Exclusive Engineer
 Rural Works Department
 Works Division, Jayashankar
 23/09/2024


184	Tree Guard With MS Iron - Providing and fixing MS Iron tree guard 60 cm dia and 2 metre high above ground level formed of 4 nos. (25 x 6 mm) and 8 nos. (25 x 3 mm) vertical MS riveted to 3 nos. (25 x 6 mm) iron ring in two halves bolted together with 8mm dia and 30 mm long bolts including painting two coats with paint of approved brand over a coat of priming, complete in all respect	Each	44.00		2348.13	103229.72
185	Providing and laying of not applied thermoplastic compound 2.5 mm thick including reflecting glass beads @ 250 gms per sqm area. thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC-35. The finished surface to be level, uniform and free from streaks and holes					
186	At Edge for BT Portion	Sqm	175.00		778.40	136220.00
187	Pedestrian Crossing (2 m in length and providing at 50 cm apart)	Sqm	5.40		778.40	4203.36
188	At Edge for New & Old CC Portion	Sqm	70.00		873.89	61172.30
189	Providing and fixing of typical MGSY informational sign board with Logo as per MORD specifications and drawing Three MS Plates of 16 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All MS will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	No	3.00		10322.14	30966.42
190	PARAPET REPAIR					
191	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	Cum	5.96		8268.49	37360.20
192	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	Sqm	41.60		221.00	9193.60
193	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	Sqm	41.60		128.70	5353.92
194	300MM Irrigation Pipe					
195	Providing and laying of a reinforced cement concrete pipe duct 300 mm dia. across the road (new construction) extending from drain to drain in cuts and toe of slope to toe of slope in its constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC 981997 bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC, 98 - 1997 and approved drawings.	RM	20.00		981.26	19625.20
196	1% LABOUR CESS	Rs	1.00		34283.72	34283.72
197	Segregation Fee	Rs	1.00		39673.88	39673.88
198	18 % GST	Rs	1.00		630419.39	630419.39
199	6 YEAR MAINTENANCE COST	Quarterly	24.00		35048.08	841153.92
200	1% LABOUR CESS	Rs	1.00		8411.54	8411.54
201	Segregation Fee	Rs	1.00		2132.99	2132.99
202	18 % GST	Rs	1.00		153305.73	153305.73
203	Renewal Cost					
204	Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.20 to 0.25kg per sqm on the prepared granular surface treated with Primer and cleaned with hydrolic broom as per technical specifications clause 603	Sqm	3314.06		15.89	52660.41


 Executive Engineer
 Rural Works Department
 District, Bangalore

9/10/2019
 Director

205	Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects.	82.85	Cum	12912.76	1069822.17
206	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC-35. The finished surface to be level, uniform and free from streaks and holes.	175.00	Sqm	778.40	136220.00
207	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC-35. The finished surface to be level, uniform and free from streaks and holes.	70.00	Sqm	873.89	61172.30
208	1% LABOUR CESS	1.00	Rs	13198.75	13198.75
209	Seigniorage Fee	1.00	Rs	7527.67	7527.67
210	18 % GST	1.00	Rs	241326.23	241326.23
211	Mamohan Narar Road to Ghushkipatti Tak				
212	Cleaning and Grubbing :- Cleaning and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.36	Ha	75360.38	27129.74
213	Construction of Subgrade And Earthen Shoulders :- Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1	1380.15	Cum	244.73	337764.11
214	Granular Sub-base with Well Graded Material(Grade II) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401	26.16	Cum	2485.59	65025.65
215	Water Bound Macadam Gr III :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405	91.19	Cum	5040.52	459645.02
216	Prime Coat :- Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	1215.92	Sqm	55.31	67252.54
217	Tack Coat :- Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and celled with hydrioc broom as per technical specification clause 503	4556.36	Sqm	19.03	86707.53
218	Semi Dense Bituminous Concrete :- Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects	113.91	Cum	12912.76	1470892.49
219	Pavement Quality Concrete (PQC) :- Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 4.3 grade cement @ 400 kg per cum, coarse and fine aggregate conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing compound, finishing to lines and grades as per drawing	199.41	Cum	7534.22	1502398.81
220	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC 8 fixing in position including casting and piling, etc as per drawing and technical specification clause 1703				


 Executive Engineer
 Rural Works Department
 Works Division, Jammu


 Director

221	Km stone		3.00	No	2898.91	8696.73
222	200 m stone		6.00	No	791.78	4750.68
223	Retro-reflectonised Traffic Signs Providing and erecting direction and place identification retro-reflectonised sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701 2.3, fixed over aluminium sheeting, 2 mm thick, with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701		0.96	Sqm	13623.01	13078.09
224	Road Markers: Road Stud with Lens Reflector - Providing and fixing of road stud 100 x 100 mm die cast in aluminium, resistant to corrosive effect of salt and gnl, fitted with lens reflectors, installed in concrete or asphaltic surface by drilling holes 30 mm upto a depth of 600 mm and bedded in a suitable bituminous grout or epoxy mortar, all as per BS 873 (Part 4) 1973.		1203.00	Nos	274.18	329838.54
225	Providing and fixing of retro-reflectonised cautionary, mandatory and informatory sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701 2.3 fixed over aluminium sheeting, 1.5 mm thick, supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801					
226	600 mm equilateral & triangle		6.00	Nos	3321.64	19929.84
227	600 mm circular		4.00	Nos	4720.59	18882.36
228	600 mm x 450 mm rectangular		2.00	Nos	4577.39	9154.78
229	900 mm x 300 mm Hazard Marker		4.00	Nos	4577.39	18309.56
230	900 mm side octagon		2.00	Nos	9005.56	18011.12
231	Reinforced cement concrete M15 grade boundary pillars/focal stone of standard design as per IRC 25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704		16.00	Nos	684.63	10954.08
232	Planting of Trees and their Maintenance for one Year - Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year		60.00	Each	1247.52	74851.20
233	Tree Guard With MS Iron - Providing and fixing MS iron tree guard 60 cm dia and 2 metre high above ground level formed of 4 nos. (25 x 6 mm) and 8 nos. (25 x 3 mm) vertical MS riveted to 3 nos. (25 x 6 mm) iron ring in two halves bolted together with 8mm dia and 30 mm long bolts including painting two coats with paint of approved brand over a coat of priming, complete in all respect		60.00	Each	2346.13	140767.80
234	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes.					
235	At Edge for BT Portion		240.60	Sqm	778.40	187253.04
236	Pedestrian Crossing (2 m in length and providing at 50 cm apart)		5.40	Sqm	778.40	4203.36
237	At Edge for New & Old CC Portion		78.00	Sqm	873.89	68163.42
238	Providing and fixing of typical MMSY informatory sign board with Logo as per MORD specifications and drawing Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enamelled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700 1		3.00	No	10322.14	30566.42

Maa Keshwari Communication Pvt. Ltd.

22/05/2014
Director

Executive Engineer

Rural Works Department
Works Division, Jaynagar
590001

239	PARAPET REPAIR					
240	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	5.95	Cum	6288.46		37350.20
241	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	41.60	Sqm	221.00		9193.60
242	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	42.24	Sqm	128.70		5436.29
243	300MM Irrigation Pipe					
244	Providing and laying of a reinforced cement concrete pipe duct 300 mm dia. across the road (new construction), extending from drain to drain in cuts and toe of slope in fills, constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC 981997 bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC 98 - 1997 and approved drawings	20.00	RM	581.26		19625.20
245	1% LABOUR CESS	1.00	Rs	50463.05		50463.05
246	Seigniorage Fee	1.00	Rs	55856.66		55856.66
247	18 % GST	1.00	Rs	927472.53		927472.53
248	6 YEAR MAINTENANCE COST	24.00	Quarterly	47112.50		1130700.00
249	1% LABOUR CESS	1.00	Rs	11307.00		11307.00
250	Seigniorage Fee	1.00	Rs	2932.55		2932.55
251	18 % GST	1.00	Rs	206089.12		206089.12
252	Renewal Cost					
253	Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.20 to 0.25kg per sqm on the prepared granular surface treated with Primer and cleaned with hydrioc broom as per technical specification clause 503	4556.38	Sqm	15.89		72400.56
254	Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects	113.91	Cum	12912.76		1470892.49
255	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes	240.60	Sqm	778.40		187283.04
256	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes	78.00	Sqm	873.89		68163.42
257	1% LABOUR CESS	1.00	Rs	17987.40		17987.40
258	Seigniorage Fee	1.00	Rs	10487.23		10487.23
259	18 % GST	1.00	Rs	328898.55		328898.55
260	Mukhyamantri Sadak Se Teen Muhani Tak to 0.25					
261	Clearing and Grubbing - Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 1208.4	0.06	Ha	75360.38		4521.62

Executive Engineer
Rural Works Department
Works Division

Director

262	Construction of Subgrade And Earthen Shoulders :- Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1	06.00	Cum	244.73	16152.12
263	Pavement Quality Concrete (PQC) :- Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement @ 400 kg per cum, coarse and fine aggregate conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing compound, finishing to lines and grades as per drawing	114.57	Cum	7534.22	863156.59
264	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC 8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703	2.00	No	2229.91	5737.22
265	Km stone	1.00	No	791.72	791.72
266	200 m stone	0.56	Sqm	13623.01	13678.25
267	Retro-reflectors Traffic Signs Providing and erecting direction and place identification retro-reflectors sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701.				
268	Providing and fixing of retro-reflectors cautionary, mandatory and informative sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801				
269	600 mm equilateral & triangle	5.00	Nos	3321.64	16608.20
270	600 mm circular	4.00	Nos	4720.55	18882.26
271	600 mm x 450 mm rectangular	3.00	Nos	4577.39	13732.17
272	900 mm side octagon	2.00	Nos	9005.56	18011.12
273	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes.				
274	Pedestrian Crossing (2 m in length and providing at 50 cm apart)	3.60	Sqm	778.40	2807.24
275	At Edge for New & Old CC Portion	55.00	Sqm	873.89	48063.95
276	Providing and fixing of typical MIMGSY informative sign board with Logo as per MORD specifications and drawing Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	3.00	No	10322.14	30966.42
277	300MM Irrigation Pipe				

Maa Rajeshwari Construction Pvt. Ltd.

Director

Executive Engineer

Rural Works Department

Works Division, Jaynagar

278	Providing and laying of a reinforced cement concrete pipe duct 300 mm dia, across the road (new construction); extending from drain in cut and toe of slope to toe of slope in fills constructing head walls at both ends, thick layer of granular material over top and sides of RCC pipe as per IRC 981997 bedded on a 0.3 m minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC 98 - 1997 and approved drawings	20.00	PM	981.26	15625.20
279	1% LABOUR CESS				
280	Seigniorage Fee	1.00	P ₄	10722.81	10722.81
281	18 % GST	1.00	P ₅	12456.12	12456.12
282	6 YEAR MAINTENANCE COST	1.00	P ₆	157179.20	157179.20
283	1% LABOUR CESS	24.00	Quantity		
284	18 % GST	1.00	P ₅	2475.83	55259.32
285	Renewal Cost	1.00	P ₅	593.00	593.00
286	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC-35. The finished surface to be level, uniform and free from streaks and holes.			10780.74	10780.74
287	1% LABOUR CESS	55.00	Sqm	873.89	43563.95
288	18 % GST	1.00	P ₅	480.54	480.54
289	PMGSY SEMANIYA TOL To 0.8	1.00	P ₅	8732.03	8732.03
290	Cleaning and Grubbing :- Cleaning and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.08	Ha	75360.38	5022.23
291	Construction of Subgrade And Earthen Shoulders - Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	84.00	Cum	244.73	20557.32
292	Pavement Quality Concrete (PQC) - Construction of un-reinforced dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement @ 400 kg per cum, coarse and fine aggregate conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing compound, finishing to lines and grades as per drawing	145.82	Cum	7534.22	1098629.95
293	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC 8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703				
294	Km stone	2.00	No.	2888.91	5797.82
295	200 m stone	1.00	No.	791.78	791.78
296	Retro-reflectors Traffic Signs Providing and erecting direction and place identification retro-reflectors sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701	0.96	Sqm	13623.01	13078.09

Maa Kojeshwari Construction Pvt. Ltd.

Director

Executive Engineer
Rural Works Department

297	Providing and fixing of retro-reflectors cautionary, mandatory and informatory sign as per IRC 87 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeling, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of property designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801				
298	600 mm equilateral & triangle				
299	600 mm circular	4.00	Nos	3321.64	13286.56
300	600 mm x 450 mm rectangular	4.00	Nos	4725.56	18882.36
301	900 mm side octagon	2.00	Nos	4577.36	9154.78
302	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes	2.00	Nos	9025.56	18011.12
303	Pedestrian Crossing (2 m in length and providing at 50 cm apart)				
304	At Edge for New & Old CC Portion	3.60	Sqm	778.40	2892.24
305	Providing and fixing of typical MGSY informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	70.00	Sqm	873.89	61172.30
306	300MM Irrigation Pipe	3.00	No	10322.14	30966.42
307	Providing and laying of a reinforced cement concrete pipe duct, 300 mm dia, across the road (new construction), extending from drain to drain in cuts and toe of slope to toe of slope in fills, constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC 98:1997 bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC: 98 - 1997 and approved drawings.	20.00	RM	981.26	19625.20
308	1% LABOUR CESS	1.00	Rs	13188.23	13188.23
309	Seigniorage Fee	1.00	Rs	15824.37	15824.37
310	16 % GST	1.00	Rs	242810.34	242810.34
311	6 YEAR MAINTENANCE COST	24.00	Quarterly	3141.67	75400.08
312	1% LABOUR CESS	1.00	Rs	754.00	754.00
313	16 % GST	1.00	Rs	13707.72	13707.72
314	Renewal Cost				
315	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes	70.00	Sqm	873.89	61172.30
316	1% LABOUR CESS	1.00	Rs	811.72	811.72
317	16 % GST	1.00	Rs	11121.12	11121.12
318	Dhauli Tol Fulkaha Laxman Prasad & Co. Ghar to Nandoo Mahito Ke Ghar Agampur Tol				

Maa Rajeshwan Construction Pvt. Ltd.

27/08/2019
Director

Executive Engineer

Rural Works Department
Works Division, Jaypee Nagar

319	Cleaning and Grubbing - Cleaning and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.08	Ha	75360.38	6028.83
320	Construction of Subgrade And Earthen Shoulders - Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1	64.00	Cum	244.73	20557.32
321	Pavement Quality Concrete (PQC) - Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement @ 400 kg per cum, coarse and fine aggregate conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing compound, finishing to lines and grades as per drawing	145.82	Cum	7534.22	1098639.96
322	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC 8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703				
323	Km stone	2.00	No	2898.91	5797.82
324	200 m stone	1.00	No	791.78	791.78
325	Retro-reflectonised Traffic Signs Providing and erecting direction and place identification retro-reflectonised sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701	0.96	Sqm	13623.01	13078.09
326	Providing and fixing of retro-reflectonised cautionary, mandatory and informatory sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801				
327	600 mm equilateral & triangle	5.00	Nos	3321.64	16608.20
328	600 mm circular	4.00	Nos	4720.59	18882.36
329	600 mm x 450 mm rectangular	3.00	Nos	4577.39	13732.17
330	900 mm side octagon	2.00	Nos	9005.56	18011.12
331	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes				
332	Pedestrian Crossing (2 m in length and providing at 50 cm apart)	3.60	Sqm	778.40	2802.24
333	At Edge for New & Old CC Portion	70.00	Sqm	873.89	61172.30
334	Providing and fixing of typical MGSY informatory sign board with Logo as per MORD specifications and drawing Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	3.00	No	10322.14	30966.42

300MM Irrigation Pipe
Madhavji Wastewater Treatment Plant Ltd.
4728 3071/14
Director
Executive Engineer
Rural Works Department
Works Division, Jalgaon

336	Providing and laying of a reinforced cement concrete pipe duct 300 mm dia. across the road (new construction), extending from drain to drain in cuts and toe of slope to toe of slope in fills constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC 98/1997 bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC 98 - 1997 and approved drawings	20.00	RM	991.20	19625.20
337	1% LABOUR CESS				
338	Seigniorage Fee	1.00	Rs	13267.22	13267.22
339	18 % GST	1.00	Rs	15624.37	15624.37
340	6 YEAR MAINTENANCE COST	1.00	Rs	244046.38	244046.38
341	1% LABOUR CESS	24.00	Quality	3141.67	75400.08
342	18 % GST	1.00	Rs	754.00	754.00
343	Renewal Cost	1.00	Rs	13707.72	13707.72
344	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes	70.00	Sqm	873.99	61172.30
345	1% LABOUR CESS				
346	18 % GST	1.00	Rs	611.72	611.72
347	Ram Bilas Yadav Ke Ghar Se Mahendra Yadav Ghar Tak To 0.4	1.00	Rs	11121.12	11121.12
348	Cleaning and grubbing - Cleaning and grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E.I.	0.12	Ha	75360.38	9043.25
349	Box Culvert - Excavation for roadway in soil using manual means for carrying of cut earth to embankment side with a lift upto 1.5 m and lead upto 50 m as per Technical Specification Clause 302.3	72.19	Cum	96.35	6955.51
350	Construction of embankment with approved material deposited from road way cutting and excavation from drain and foundation of other structures and excavated with an average lead of 100 m graded and compacted to meet requirement of tables 300.1 and 300.2 as per technical specification clause 301.5 (including Royalty & Labour Cess)	43.31	Cum	75.69	3278.13
351	Construction of Subgrade And Earthen Shoulders - Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1	132.00	Cum	244.73	32304.36
352	Granular Sub-base with Well Graded Material (Grade I) - Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401	41.66	Cum	2649.93	122994.08
353	Water Bound Macadam Gr III - Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405	31.25	Cum	5042.52	157516.25
354	Pavement Quality Concrete (PQC) - Construction of unreinforced, dowel jointed, plain cement concrete pavement over a prepared sub-base with 43 grade cement @ 400 kg per cum, coarse and fine aggregate conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, secondary strip, dowel bar, tie rod, admixtures as approved, curing compound, finishing to top and surface as per drawing	224.98	Cum	7534.22	1695048.82

Executive Engineer

Rural Works Department
Road Works Division, Jaynagar

Director

355	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC 8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703					
356	Km stone					
357	200 m stone	2.00	No	2698.91		5737.32
358	Retro-reflectors Traffic Signs Providing and erecting direction and place identification retro-reflectors sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701 2.3 fixed over aluminium sheeting 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701	2.00	No	791.75		1583.56
359	Providing and fixing of retro-reflectors cautionary, mandatory and information sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701 2.3 fixed over aluminium sheeting 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801	0.96	Sqm	13623.21		13079.29
360	600 mm equilateral & triangle					
361	600 mm circular	5.00	Nos	3321.54		16608.20
362	600 mm x 450 mm rectangular	4.00	Nos	4720.59		18882.36
363	900 mm side octagon	2.00	Nos	4577.39		9154.78
364	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes	2.00	Nos	9023.59		18047.18
365	Pedestrian Crossing 2 m in length and providing at 50 cm apart					
366	At Edge for New & Old CC Portion	3.60	Sqm	771.42		2797.12
		110.00	Sqm	372.35		41057.30
367	Providing and fixing of typical MNGSY information sign board with Logo as per MORD specifications and drawing Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5mm size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes. Posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Appendix 1700.1	3.00	No	10022.14		30066.42
368	300MM Irrigation Pipe					
369	Providing and laying of a reinforced cement concrete pipe duct 300 mm dia. across the road (new construction), extending from drain to drain in cuts and toe of slope to toe of slope in fills constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC 58/1987 bedded on a 0.3 m thick layer of granular material free of rock pieces. Outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts. Joints to be made leak proof. Invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC 58 - 1987 and approved drawings.	20.00	Nm	86.71		1734.20
370	1% LABOUR CESS	1.00	%	1734.20		1734.20
371	Signature Fee	1.00	%	1734.20		1734.20
372	18 % GST	1.00	%	1734.20		1734.20

Maa Rajeshwari Construction Pvt. Ltd.

Director

Handwritten signatures and stamps at the bottom of the page.

373	6 YEAR MAINTENANCE COST		24.00	Quaterty	4933.33	118399.92
374	1% LABOUR CESS		1.00	Rs	1184.00	1184.00
375	18 % GST		1.00	Rs	21525.12	21525.12
376	Renewal Cost					
377	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC-35. The finished surface to be level, uniform and free from streaks and holes.		110.00	Sqm	873.89	96127.90
378	1% LABOUR CESS		1.00	Rs	961.28	961.28
379	18 % GST		1.00	Rs	17476.05	17476.05
380	PMGSY Road To Bagahi Tol Khaira Math					
381	Cleaning and grubbing - Cleaning and grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I		0.16	Ha	75360.38	12057.66
382	Construction of Subgrade And Earthen Shoulders :- Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1		169.00	Cum	244.73	41114.64
383	Pavement Quality Concrete (PQC) :- Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement @ 400 kg per cum, coarse and fine aggregate conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing compound, finishing to lines and grades as per drawing		291.64	Cum	7534.22	2197279.32
384	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC-8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703.		2.00	No	2898.91	5797.82
385	Km stone					
386	200 m stone		3.00	No	791.78	2375.34
387	Retro-reflectors Traffic Signs Providing and erecting direction and place identification retro-reflectors sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701.		0.96	Sqm	13623.01	13078.09
388	Providing and fixing of retro-reflectors cautionary, mandatory and informational sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801					
389	600 mm equilateral & triangle		5.00	Nos	3321.64	16608.20
390	600 mm circular		4.00	Nos	4720.59	18882.36
391	600 mm x 450 mm rectangular		3.00	Nos	4577.39	13732.17
392	900 mm side octagon		2.00	Nos	9005.56	18011.12

Maa Kaleshwari Construction Pvt. Ltd.
 Director

Executive Engineer
 Rural Works Department
 Works Division, Jaipur

393	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes.					
394	Pedestrian Crossing (2 m in length and providing at 50 cm apart)	3.60	Sqm	778.40		2802.24
395	AI Edge for New & Old CC Portion	140.00	Sqm	873.89		122344.60
396	Providing and fixing of typical MMSY informative sign board with Logo as per MORD specifications and drawing Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5mm size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enamelled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700 1	3.00	No	10322.14		30966.42
397	300MM Irrigation Pipe					
398	Providing and laying of a reinforced cement concrete pipe duct 300 mm dia, across the road (new construction), extending from drain to drain in cuts and toe of slope to toe of slope in fills, constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC 98/1997 bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC: 98 - 1997 and approved drawings	20.00	RM	981.20		19625.20
399	1% LABOUR CESS	1.00	Rs	25146.55		25146.55
400	Seigniorage Fee	1.00	Rs	31541.07		31541.07
401	18 % GST	1.00	Rs	46284.75		46284.75
402	0 YEAR MAINTENANCE COST	24.00	Quarterly	6291.67		151000.08
403	1% LABOUR CESS	1.00	Rs	1510.00		1510.00
404	18 % GST	1.00	Rs	27451.80		27451.80
405	Renewal Cost					
406	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes	140.00	Sqm	873.89		122344.60
407	1% LABOUR CESS	1.00	Rs	1223.45		1223.45
408	18 % GST	1.00	Rs	22242.25		22242.25
409	MMSY To Rajendra Babu Ke Dagan Tak to 1					
410	Clearing and grubbing - Clearing and grubbing Road Land (by manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of EA	0.19	Ha	75500.39		14318.47
411	Construction of Subgrade And Earthen Shoulders - Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1	204.00	Cum	244.73		49924.92

Maa Kaleshiwari Construction Pvt. Ltd.

425 30/1/19
Director

Executive Engineer

Rural Works Department

Works Division, Jaynagar

412	Pavement Quality Concrete (PQC) - Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement @ 400 kg per cum, coarse and fine aggregate conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing compound, finishing to lines and grades as per drawing	354.14	Cum	7534.22	2668168.67
413	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC 8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703				
414	Km stone				
415	200 m stone	2.00	No	2898.91	5797.82
416	Retro-reflectonised Traffic Signs Providing and erecting direction and place identification retro-reflectonised sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701.	4.00	No	791.78	3167.12
417	Providing and fixing of retro-reflectonised cautionary, mandatory and informatory sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801	0.96	Sqm	13623.01	13078.09
418	600 mm equilateral & triangle				
419	600 mm circular	5.00	Nos	3321.64	16608.20
420	600 mm x 450 mm rectangular	4.00	Nos	4720.59	18882.36
421	900 mm side octagon	3.00	Nos	4577.39	13732.17
422	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes.	2.00	Nos	9005.56	18011.12
423	Pedestrian Crossing (2 m in length and providing at 50 cm apart)				
424	At Edge for New & Old CC Portion	3.60	Sqm	778.40	2807.24
		170.00	Sqm	873.89	148561.30
425	Providing and fixing of typical MMGSY informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	3.00	No	10322.14	30966.42
426	300MM Irrigation Pipe				
427	Providing and laying of a reinforced cement concrete pipe duct 300 mm dia, across the road (new construction), extending from drain to drain in cuts and toe of slope to toe of slope in fills, constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC 981997 bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC 98 - 1997 and approved drawings	20.00	RM	981.26	19625.20

Maareshwari Construction Pvt. Ltd.

after 20 years
Director

Executive Engineer

Rural Works Department,
Works Division, Jaynagar

428	1% LABOUR CESS		1.00	Rs	30226.54	30226.54
429	Seigniorage Fee		1.00	Rs	38277.56	38277.56
430	18 % GST		1.00	Rs	566543.36	566543.36
431	6 YEAR MAINTENANCE COST		24.00	Quantity	7933.33	187799.22
432	1% LABOUR CESS		1.00	Rs	1822.30	1822.30
433	18 % GST		1.00	Rs	33305.76	33305.76
434	Renewal Cost					
435	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes		170.00	Sqm	873.89	148591.30
436	1% LABOUR CESS		1.00	Rs	1485.31	1485.31
437	18 % GST		1.00	Rs	27708.44	27708.44
438	PMGSY Road To Naya Tola (Cleaning and Grubbing - Cleaning and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I		0.25	Ha	75360.28	18340.30
440	Construction of Subgrade And Earthen Shoulders :- Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1		254.00	Cum	244.73	60000.22
441	Pavement Quality Concrete (PQC) :- Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement @ 400 kg per cum, coarse and fine aggregate conforming to IS 353, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, be rod, admixtures as approved, curing compound, finishing to lines and grades as per drawing		458.29	Cum	7534.22	342765.26
442	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC 8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703					
443	Km stone		3.00	No	2888.71	8666.13
444	200 m stone		4.00	No	757.75	3031.00
445	Retro-reflectorised Traffic Signs Providing and erecting direction and place identification retro-reflectorised sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701.		1.92	Sqm	18003.75	32718.15
446	Providing and fixing of retro-reflectorised cautionary, mandatory and informative sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm below ground level as per drawings and Technical Specification Clause 801					
447	600 mm equilateral & triangle		7.00	Nos	3321.84	23253.48

Maa Keshwari Construction Pvt. Ltd.

Director

Executive Engineer

Rural Works Department
Works Division, Jaunpur

448	600 mm circular	4.00	No	4720.59	18662.36
449	600 mm x 450 mm rectangular	4.00	No	4577.39	18309.66
450	900 mm x 300 mm Hazard Marker	2.00	No	4577.39	9154.78
451	900 mm side octagon	2.00	No	9065.56	18131.12
452	Reinforced cement concrete M15 grade boundary pillars local stone of standard design as per IRC 25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	6.00	No	584.63	5477.04
453	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes				
454	Pedestrian Crossing (2 m in length and providing at 50 cm apart)				
455	At Edge for New & Old CC Portion	3.60	Sqm	778.40	2802.24
456	Providing and fixing of typical MMSY informative sign board with Logo as per MORD specifications and drawing edges. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5mm size on back on lower most plate and flat iron frame of middle plate will be welded to 2 nos 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	220.00	Sqm	873.89	192255.80
457	PARAPET REPAIR		No	10322.14	30966.42
458	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	2.98	Cum	6268.49	18680.10
459	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	20.80	Sqm	221.00	4596.80
460	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	20.80	Sqm	128.70	2676.96
461	300MM Irrigation Pipe				
462	Providing and laying of a reinforced cement concrete pipe duct, 300 mm dia, across the road (new construction), extending from drain to drain in cuts and toe of slope to toe of slope in fills, constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC 981997 bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC: 98 - 1997 and approved drawings.	20.00	RM	961.25	19225.20
463	1% LABOUR CESS	1.00	Rs	39389.95	39389.95
464	Seigniorage Fee	1.00	Rs	51580.10	51580.10
465	18 % GST	1.00	Rs	725393.75	725393.75
466	6 YEAR MAINTENANCE COST	24.00	Quarterly	10975.00	263400.00
467	1% LABOUR CESS	1.00	Rs	2634.00	2634.00
468	18 % GST	1.00	Rs	47886.12	47886.12
469	Renewal Cost				


Maa Rajeshwari Construction Pvt. Ltd.


Director

Executive Engineer

Rural Works Department
Works Division

470	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC-35. The finished surface to be level, uniform and free from streaks and holes.	220.00	Sqm	873.89	192255.80
471	1% LABOUR CESS	1.00	Rs		
472	18 % GST	1.00	Rs	1922.56	1922.56
473	BASOPATTI MAIN ROAD TO BAIRA KARI YADAV'S HOUSE Cleaning and Grubbing - Cleaning and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	1.53	Ha	75390.38	115301.38
475	Scarifying - Scarifying the existing bituminous road surface to a depth of 150 mm and disposal of scarified material with a lift upto 3 m and lead upto 1000 m as per Technical Specification Clause 301.4.	6946.88	Sqm	31.58	219382.47
476	Construction of Subgrade And Earthen Shoulders - Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	6704.75	Cum	244.73	1640853.47
477	Granular Sub-base with Well Graded Material (Grade II) - Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	566.50	Cum	2485.69	1408143.39
478	Water Bound Macadam Gr III - Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	569.59	Cum	5040.52	2871025.79
479	Wet Mix Macadam (WMM) - Providing Laying spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill) carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100KN weight to achieve the desired density including lighting, barricading and maintenance of diversion, etc as per Tables 400.11 & 400.12 and Technical Specification Clause 406.	1950.56	Cum	4401.77	8585516.49
480	Prime Coat - Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	19505.63	Sqm	55.31	1078856.40
481	Tack Coat - Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydnoc broom as per technical specification clause 503.	19505.63	Sqm	19.03	371192.14
482	Tack Coat - Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.20 to 0.25 kg per sqm on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503.	19505.63	Sqm	15.89	309544.46
483	Bituminous Macadam - Providing and laying bituminous macadam with 100-120 TPH hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading premixed with bituminous binder, transported to site, laid over previously prepared surface with paver finisher to the required grade, level and alignment and rolled as per clauses 501.6 and 501.7 to achieve the desired compaction.	984.94	Cum	11297.54	11127399.05
484	Semi Dense Bituminous Concrete - Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects.	487.84	Cum	12912.76	6256773.25

Maa Rajeshwari Construction Pvt. Ltd.

 Director


 Executive Engineer
 Rural Works Department
 Works Division, Jaynagar
 12.9.2021

485	Pavement Quality Concrete (PQC) - Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement @ 400 kg per cum, coarse and fine aggregate conforming to IS 383 maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design, transported to the site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing compound, finishing to lines and grades as per drawing	834.20	Cum	7534.22	6285646.22
486	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC 8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703				
487	5th km stone	1.00	No	5464.31	5464.31
488	Nm stone	7.00	No	2999.85	20998.95
489	200 m stone	27.00	No	803.96	21706.92
490	Retro-reflectors Traffic Signs Providing and erecting direction and place identification retro-reflectors sign as per IRC 57 made of encapsulated lens type reflective sheeting vide Clause 1701 2.3, fixed over aluminium sheeting, 2 mm thick, with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701	4.80	Sqm	12885.40	61809.92
491	Providing and erecting a "M" metal beam crash barrier comprising of 3 mm thick corrugated sheet metal beam rail, 75 cm above road ground level, fixed on ISMC series channel vertical posts, 150 x 75 x 5 mm spaced 2 m centre to centre, 1.8 m high, 11 m below ground level, all steel parts and hardware to be galvanised by hot dip process, all fittings to conform to IS 1367 and IS 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 152 x 75 x 5 mm, 330 mm long complete as per clause 510	160.00		1024.25	163880.00
492	Road Markers Road Stud with Lens Reflector - Providing and fixing of road stud 100 x 100 mm die cast in aluminium, resistant to corrosive effect of salt and grit, fixed with lens reflectors, installed in concrete or asphaltic surface by drilling holes 30 mm into a depth of 600 mm and bedded in a suitable bituminous grout or epoxy mortar, all as per SS 671 (Part A) 1973	5150.00	No	174.75	898062.50
493	Providing and fixing of retro-reflectors cautionary, mandatory and information sign as per IRC 57 made of encapsulated lens type reflective sheeting vide Clause 1701 2.3 fixed over aluminium sheeting, 1.5 mm thick, supported on a mild steel angle iron post 75 mm x 75 mm x 5 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 501				
494	600 mm equilateral triangle	23.00	No	134.00	3082.00
495	600 mm circular	8.00	No	47.00	376.00
496	600 mm x 450 mm rectangular	11.00	No	40.00	440.00
497	900 mm x 300 mm Hazard Marker	12.00	No	40.00	480.00
498	900 mm side octagon	5.00	No	80.00	400.00
499	Reinforced cement concrete M15 grade boundary pillars local stone of standard design as per IRC 21, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	179.00	No	880.00	156420.00
500	Planting of Trees and their Maintenance for one Year - Planting of trees in the road side (Avenue trees) at 2.50 m dia holes, 1 m deep dug in the ground, mounding the soil with decayed farm yard sludge manure, planting the saplings, backfilling the trench, watering, during the tree guard and maintaining the plants for one year	259.00	Sq	3.00	777.00

Maa Kashiwan Cultivation Pvt. Ltd.

Director

Executive Engineer

Rural Works Department
Works Division,

522	Earth work in excavation for foundation of structures upto 3.0 m depth as per drawing and technical specification clause 1104	1117.35	Cum	307.15	44444.11
523	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-15 Grade	74.74	Cum	720.87	532287.76
524	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-20 Grade	229.59	Cum	8108.43	1581514.44
525	Supplying, fitting and placing HYSD bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202	16.07	MT	86593.49	1065543.28
526	Sub Structure				
527	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 PCC M-20 Grade	150.53	Cum	8108.43	1201546.27
528	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V) 20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7	320.00	Nos	259.02	82295.40
529	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204. RCC M-25 Grade	299.55	Cum	86593.03	2595599.25
530	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202	28.45	MT	66824.45	1894896.60
531	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 (With Sandy Materials)	404.85	Cum	3982.33	1624546.53
532	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8	169.71	Cum	3916.50	564659.22
533	Superstructure				
534	Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5. RCC M-30 Grade	152.28	Cum	9337.08	1421850.54
535	Supplying, fitting, and placing HYSD bar reinforcement in superstructure complete as per drawing and technical specifications Clauses 1002, 1010 and 1202	12.94	MT	68122.03	881499.07
536	Parapet Construction Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 (M20)	35.19	Cum	8108.43	283444.08
537	Painting on Parapet Wall (Black & White Strips) Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	245.12	Sqm	128.70	31546.34
538	Drainage spouts complete as per drawing and technical specifications Clause 1209	28.00	Nos	1236.84	34631.52
539	Providing and laying cement concrete wearing course M 30 grade including reinforcement complete as per drawing and technical specifications Clauses 800 and 1206.3	26.66	cum	13218.05	352383.21
540	Approach slab. Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5. RCC M-30 Grade	83.00	Cum	12743.18	802820.34
541	PCC M15 Ordinary grade (1:2:5) levelling course below approach slab complete as per drawing and technical specifications clauses 800 and 1211	31.50	Cum	7757.34	244356.21
542	Protection work				

Maa Rameshwar Construction Pvt. Ltd.

(Signature)
Director

(Signature)
Executive Engineer
Rural Works Department
Works Division, Jalandhar
591092

543	Earth work in excavation for foundation of structures upto 3.0 m depth as per drawing and technical specification clause 1104	918.70	Cum	397.76	365422.11
544	Providing and laying boulder apron for bed protection with stone boulders of minimum size and weight as per Table 1300 '1', no fragment weighing less than 25 kg laid dry complete as per drawing and technical specifications Clause 1301	113.76	Cum	4040.82	459683.68
545	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	23.07	Cum	7201.87	166147.14
546	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	140.64	Cum	8108.43	1140369.60
547	PARAPET REPAIR				
548	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	27.30	Cum	6268.49	171129.78
549	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	190.40	Sqm	221.00	42078.40
550	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	192.32	Sqm	128.70	24751.58
551	300MM Irrigation Pipe				
552	Providing and laying of a reinforced cement concrete pipe duct 300 mm dia, across the road (new construction), extending from drain to drain in cuts and toe of slope to toe of slope in fills, constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC 981997 bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC: 98 - 1997 and approved drawings.	30.00	RM	981.20	29437.80
553	Dismantling				
554	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 m as per Technical Specification Clause 202				
555	Cement Concrete	7.71	Cum	665.60	5131.78
556	Reinforced Cement Concrete	10.08	Cum	1564.61	15771.27
557	Dismantling of existing structures like culverts, bridges, retaining walls and other structures comprising of brick masonry, including disposal of unserviceable material and stacking the serviceable material with all lift and lead of 1000 m as per Technical Specification Clause 202				
558	Cement mortar	137.14	Cum	307.62	42187.01
559	Removing all types of Hume pipes and stacking including Earthwork and Dismantling of Masonry Works as per Technical Specification Clause 202				
560	Upto 600 mm dia Hume pipe	20.00	RM	258.14	5162.80
561	Above 600 mm to 900 mm dia Hume pipe	5.00	RM	349.05	1745.25
562	1% LABOUR CESS	1.00	Rs	778640.93	778640.93
563	Seigniorage Fee	1.00	Rs	795045.62	795045.62
564	18 % GST	1.00	Rs	14298800.34	14298800.34
565	6 YEAR MAINTENANCE COST	24.00	Quarterly	287204.17	6892900.08

Maa Rajeshwari Construction Pvt. Ltd.

Director

Executive Engineer
Rural Works Department
Works Division, Jangarh

566	1% LABOUR CESS		1.00	Rs	68929.00	68929.00
567	Seigniorage Fee		1.00	Rs	19418.68	19418.68
568	18 % GST		1.00	Rs	1256624.56	1256624.56
569	Renewal Cost					
570	Tack Coat Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.20 to 0.25kg per sqm on the prepared granular surface treated with Primer and cleaned with hydriloc broom as per technical specification clause 503.		19505.63	Sqm	15.89	309544.46
571	Semi-Dense Bituminous Concrete Providing and laying semi dense bituminous concrete with 100-120 TPII batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects.		487.64	Cum	12612.76	6256778.29
572	Road Marking with Hot Applied Thermoplastic Compound with Reflectorsing Glass Beads on Bituminous Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorsing glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes.		1030.00	Sqm	778.40	801752.00
573	Road Marking with Hot Applied Thermoplastic Compound with Reflectorsing Glass Beads on Concrete Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorsing glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes.		330.00	Sqm	873.89	288383.70
574	1% LABOUR CESS		1.00	Rs	76968.58	76968.58
575	Seigniorage Fee		1.00	Rs	44895.05	44895.05
576	18 % GST		1.00	Rs	1407369.97	1407369.97
Total In Figures						163411850.58
Quoted Rate in Figures						0.00
Quoted Rate in Words				Select		INR Zero Only

Maa Rajeshwari Construction Pvt. Ltd.

Executive Engineer

Rural Works Department
Works Division, Jaynagar

Director

21/10/21

29.09.21