

5th year Maintenance Bill

Sch. XLV—Form No. 134

62

[illegible]

① Restoration of Rainwater /			
Berm width	Slope	do	do
by Job.			
7 x	12 x	0.900 x 0.300	22.68 m ³
9 x	15 x	0.900 x 0.300	36.45 m ³
8 x	14 x	0.950 x 0.300	31.92 m ³
11 x	8 x	0.950 x 0.300	25.08 m ³
15 x	15 x	0.900 x 0.300	60.75 m ³
9 x	12 x	0.815 x 0.300	26.40 m ³
			Σ V = 203.28 m ³

(2) Making up of Revoms / Shouldy
Strengthening - do - do - all
- Job.

$15 \times 12 \times 0.900 = 162.00 \text{ m}^2$

Continuation

ABSTRACT OF 10ST

Sch. XLV—Form No. 134 66

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
(1/1) Restoration of Rainwater/Berms with Soil Trap (62)					
— do — do — all — Job.					
203.28 m ³ @ 380.55 / m ³					77361.00
(2/2) Making up of Berms/Shoulders					
Graveling Trap (62) — do					
— do — all — Job.					
1192.33 m ² @ 58.37 / m ²					69596.00
(3/3) Repair of pot holes filled					
With 75 mm Bit. Trap (63)					
— do — do — all — Job.					
14.93 m ³ @ 11601.50 / m ³					173210.00
(4/4) Patch Repair over pot holes					
With Mix Seal Surfacing					
— do — do — all — Job.					
199.07 m ² @ 298.13 / m ²					59348.00
(5/5) Maintenance of Barthen Drain					
Trap (63) — do — do — all					
— Job.					
1064.00 m ¹ @ 2.62 / m					2788.00
(6/6) Maintenance of Hump-pipe					
Culvert Trap (64) — do					
— do — all — Job.					
5.00 m ³ @ 1117.00 / m ³					5585.00

Continuation

387891.00

Sch. XLV—Form No. 134

68 B.F. = 390816.00

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
(i) ON BT portion.					
340.00 m ² @ 850.93/m ²					289316.00
(ii) ON pcc portion.					
106.40 m ² @ 953.99/m ²					101505.00
=) Sub total =					781637.00
(-) Less 0.11% below =					859.00
(=) Net Amount =					780778.00

[Signature]
Executive Engineer
Rural Works Department
Works Division, Jhansi Harpur

Material Statement				
(1) Earth				382.13 m ³
(2) 37.5 mm to 25 mm				3.17 m ³
(3) 25 mm to 5 mm				9.52 m ³
(4) 10 mm to 5 mm				5.29 m ³
(5) 5 mm and below				3.17 m ³
(6) Crushed Stone agg.				5.38 m ³
Prime coat (S.L.)				0.18 MT
Tack coat (R.S.L.)				0.100 MT
Bitumen				1.57 MT

Continuation