

WO Issu by E. in Chif, R.W.D., Bihar, Patna vide Letter No.2005 Anu Dated-28.05.2025

LOA Issu By EE, RWD, Raxaul, works Division, Raxaul vide Letter No. 1245 Dated-12-07-2025

1 MBD Agreement No. 03MBD/2025-26

2 Name of Scheme

3 Tender ID

141145 Package No.-MMGSY(AWSESH-SC)-RAXAUL-165

4 Name of Contractor

BHAGYA NARAYAN YADAV

5 Tender Amount

SL. No.	Block	Name of Road	Length (K.M)
1	Adapur	RWD Road to Ghamharia Khurd Anushuchit Jati Kanunia	2.530

Total Cost of Construction and Five Year Maintenance

35,229,283

17.06%

6 Percentage Less

7 Agreement Amount

Total Cost of Construction and Five Year Maintenance

29,219,167

8 Required Performance Security & Additional Performance Security

(A) Performance Security

(5%)

1,460,958

(B) Additional Performance Security

$(0.25 \times 5 + 0.50 \times 10 + 1 \times 2.06) = 8.310\%$

2,927,553

Total Performance Security & Additional Performance Security

4,388,511

9 Performance Security & Additional Performance Security deposited

10 Date of Start

11 Date of Completion

12 Maintenance Period

one year renewal coat and Six years routing maintenance after completion of construction.

BHAGYA NARAYAN YADAV
Vill Makari Mahuawa,
Po- Piprakothi, P.S- Piprakothi
Dist-East Champaran Pincode: 845429

Executive Engineer,
R.W.D. (M) Division,
Works Raxaul, Raxaul

Registration Department,
Government of Bihar

INDIA NON JUDICIAL
Other


First Party Name * : Not Applicable
Second Party Name * : BHAGYANARAYAN YADAV
Purchased By * : BHAGYANARAYAN YADAV
Certificate Number : BR038161421753682252954
Consideration Price : ₹0.00/-
Stamp Duty Paid : ₹1000.00/-
Registration Fee & Other Fees : ₹0.00/-
LLR & Proc Fee : ₹0.00/-
Miscellaneous Fees : ₹0.00/-
Discore SC : ₹0.00/-
Total Amount : ₹1000.00/- (One Thousand)



This stamp paper will only be valid if embossed below with special RED ink impression



Phone No:
Sold To/Issued To:
BHAGYANARAYAN YADAV
For Phon/ID Proof:
BHAGYANARAYAN YADAV



JUL-28-2025 11:30:03
₹ 0001000/-
38161421753762203208-00000390
3816142 1156

Agreement No. 08 MAY/2025-26 Date. 22/08/2025

This agreement, made the 22 August day of 2025,
Between EXECUTIVE ENGINEER, RURAL WORKS DEPARTMENT,
WORKS DIVISION, RAXAUL [name and address of Employer] (hereinafter
called "the Employer") of the one part, and Bhagya Narayan Yadav, Vill Makari
Mahuawa, P.O- Piprakothi, P.S-Piprakothi, Dist-East Champaran, Pincode- 845429 (BID
ID-616193) [name and address of Contractor] (hereinafter called "the Contractor")
of the other part). Whereas the Employer is desirous that the Contractor execute
Output and performance based Rural Road contract for the maintenance of Roads
Package No.- MMGSY(AWSESH-SC)-RAXAUL-165 (Tender ID-141145) (hereinafter
called "the Works") and the Employer has accepted the Bid by the Contractor for
the execution of such Works and the remedying of any defects therein, at a contract
price of Rs. 29219167.00 (Two Crore Ninty Two Lakh Ninteen Thousand One
Hundred and Sixty Seven Only).

BHAGYANARAYAN YADAV
Piprakothi (East Champaran)

22/8

Executive Engineer
R.W.D. (W) Division
Raxaul
22/8/25

NOW THIS AGREEMENT WITNESSETH as follows:

1. In the Agreement, words and expression shall have same meaning as are respectively assigned to them in the Conditions of Contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the works and remedy and defects therein in conformity in all aspects with provisions of the Contract.
3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the Works and the remedying the defects wherein the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.
4. There are following documents shall be deemed to form and read and construed as part of this Agreement, viz:
 - i) Letter of Acceptance
 - ii) Contractor's Bid
 - iii) Section VI- General Conditions.
 - iv) Section VII- Particular Conditions.
 - v) Section V-Technical Specifications (General and Supplementary Technical Specifications)
 - vi) Appendix A-Drawings.
 - vii) Section IV-works Schedule.
 - viii) Quality Plan for Output and Performance Based Contract as per Clause A 14.1 of the Technical Specifications.
 - ix) Appendices to the Contract.
 - x) Addenda issued during bid period.
 - xi) Any other relevant documents listed in the Particular Conditions together any post bid correspondence.

In witness whereof the parties thereto have caused this Agreement to be executed the day and year first before written.

The Common seal of

Was hereunto affixed in the presence of:

Signed, Sealed and delivered by the said

In the presence of:

Binding Signature of Contractor




Bhagyaa Narayan Yadav,


**Vill Makari Mahuawa, P.O- Piprakothi, P.S- Piprakothi
Dist-East Champaran Pincode:-845429**



Binding Signature of Employer



**Executive Engineer,
Rural Works Development,
Works Division, Buxar.**



बिहार सरकार
ग्रामीण कार्य विभाग

/पटना, दिनांक-04/12/25

पत्रांक:- BRRDA(HQ)MMGSY-398/25 -1584

प्रेषक,

ई० निर्मल कुमार,
अभियंता प्रमुख,
ग्रामीण कार्य विभाग।

सेवा में,

मुख्य अभियंता-5, मुजफ्फरपुर,
ग्रामीण कार्य विभाग।

विषय:- दिनांक-02.07.2025 को अपर मुख्य सचिव महोदय की अध्यक्षता में सम्पन्न निविदा समिति की बैठक की कार्यवाही प्रेषित करने के संबंध में।

महाशय,

उपर्युक्त विषय के संबंध में दिनांक-02.07.2025 को अपर मुख्य सचिव महोदय की अध्यक्षता में सम्पन्न निविदा समिति की बैठक की कार्यवाही की छायाप्रति नियमानुसार अग्रेतर कार्रवाई हेतु संलग्न कर भेजी जा रही है।
निविदा समिति की बैठक की कार्यवाही में अंकित निविदा का कार्य आवंटन आदेश निर्गत कर एक प्रति ज्ञापन लगाकर नोडल पदाधिकारी, MMGSY को e-mail के माध्यम से उपलब्ध कराना सुनिश्चित करें।
निर्धारित समय सीमा में निर्दिष्ट कार्य का पूरा किया जाना अनिवार्य है।

विश्वासभाजन

(निर्मल कुमार)

अभियंता प्रमुख

अनु०:- निविदा समिति की कार्यवाही की छायाप्रति।

ज्ञापक:- BRRDA(HQ)MMGSY-398/25 -1584

/पटना, दिनांक-04/12/25

प्रतिलिपि:- अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, मुजफ्फरपुर एवं मोतिहारी/कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, मुजफ्फरपुर पूर्वी-1, पकड़ीदयाल, रक्सौल एवं मोतिहारी को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित। IT Nodal, ग्रामीण कार्य विभाग/नोडल पदाधिकारी, e-advertisement-cum-e-tendering cell, ग्रामीण कार्य विभाग को विभाग के वेबसाइट पर अपलोड करने हेतु प्रेषित।

अनु०:- निविदा समिति की कार्यवाही की छायाप्रति।

अभियंता प्रमुख

BHAGYA N. MAIN YADAV
Piprahata (East Char)

Executive Engineer
P.W.D. (W) Division
Buxar

**बिहार सरकार
ग्रामीण कार्य विभाग**

दिनांक - 21/8/25 को विभागीय अपर मुख्य सचिव, ग्रामीण कार्य विभाग की अध्यक्षता में सम्पन्न निविदा समिति की बैठक की कार्यवाही:-

समिति हेतु नामित पदाधिकारी :-

- श्री दीपक कुमार सिंह, अपर मुख्य सचिव, ग्रामीण कार्य विभाग
श्री निर्मल कुमार, अभियंता प्रमुख, ग्रामीण कार्य विभाग
श्री जय किशोर ठाकुर, मुख्य अभियंता-5 (मुजफ्फरपुर), ग्रामीण कार्य विभाग
श्री आमीर नैय्यर, आंतरिक वित्तीय सलाहकार, ग्रामीण कार्य विभाग
2. बैठक में मुख्यमंत्री ग्राम संपर्क योजनांतर्गत e-tendering के माध्यम से प्राप्त की गयी निम्नवत् तालिका के क्रमांक-01 से 06 में अंकित निविदा के तकनीकी बीड पर सक्षम प्राधिकार की अध्यक्षता में गठित तकनीकी बीड मूल्यांकन समिति द्वारा तकनीकी बीड में योग्य घोषित किये गये निविदाकारों के वित्तीय बीड की तुलनात्मक विवरणी के आलोक में न्यूनतम दर उद्धृत करने वाले निविदाकार के वित्तीय बीड के प्रस्ताव पर विचार हेतु विभागीय निविदा समिति के समक्ष उपस्थापित किया गया, जिसकी विवरणी निम्नवत् तालिका "Summary of Financial Bids" के अनुरूप है।
- उपर्युक्त के संदर्भ में इस समिति द्वारा सम्यक विचारोपरांत तालिका में दर्जित न्यूनतम दर के निविदाकार (L1) के स्तम्भ "12" में निवेदित राशि पर स्तम्भ "13" के अनुसार निम्नवत् निर्णय लिया गया :-


Summary of Financial Bid												
Sl. No.	District	File No. BRDA /PO/ MGNREGS	Sl. No. & Date of Receipt	Sl. No. & Date of Publication	Package No./Tender ID	A.A. Amount (Rs.)	Est. Amt. (Rs.)	Total No. of Bidders/No. of Bidders Qualified in Tech. Bid	Name of Bidder for Technical Proposal (BID-01)	Quoted Rate (%)	Tender Awarded Amount (Rs.)	Remarks
1	2	3	4	5	6	7	8	9	10	11	12	13
1	Muzaffarpur	322/24	BWD/MGNREGS/SC/PO/ET/2025-26/04	01/04/2025 2025-26/04/07/08/2025	BWD/MGNREGS/SC/PO/ET/2025-26/04/07/08/2025 Tender ID: 2025_BWD_141144_11	780,350	71,76,434.14	3/3	Santa Family (616188)	-25.00	61647233.11 (Six Crore Thirty Eight Lakh Forty Seven Thousand Three Hundred and Thirty Three)	Approved as per lowest quoted rate i.e. 2.1
									Shiksha Kumar (617554)	-28.00		
									Sanjay Kumar Rana (617961)	-31.00		
2	Patna	232/24	BWD/MGNREGS/SC/PO/ET/2025-26/04	01/04/2025 2025-26/04/07/08/2025	BWD/MGNREGS/SC/PO/ET/2025-26/04/07/08/2025 Tender ID: 2025_BWD_141144_11	324,500	6,71,437.47	3/3	Shree Krishna Construction Pvt. Ltd. (617961)	-3.75	6649813.02 (Six Crore Eight Lakh Thirty Eight Thousand Four Hundred and Thirteen)	Approved as per lowest quoted rate i.e. 2.1
									S.S. Suman (617134)	-4.00		
3	Ranchi	117/23	BWD/MGNREGS/SC/PO/ET/2025-26/04	01/04/2025 2025-26/04/07/08/2025	BWD/MGNREGS/SC/PO/ET/2025-26/04/07/08/2025 Tender ID: 2025_BWD_141144_11	145,700	1,52,20,81.74	6/6	Shree Krishna Construction Pvt. Ltd. (617961)	-17.00	2921017.02 (Two Crore Twenty One Lakh Seventy One Thousand One Hundred and Sixty Seven)	Approved as per lowest quoted rate i.e. 2.1
									Shree Krishna Construction Pvt. Ltd. (617961)	-18.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-19.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-20.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-21.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-22.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-23.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-24.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-25.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-26.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-27.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-28.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-29.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-30.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-31.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-32.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-33.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-34.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-35.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-36.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-37.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-38.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-39.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-40.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-41.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-42.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-43.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-44.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-45.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-46.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-47.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-48.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-49.00		
									Shree Krishna Construction Pvt. Ltd. (617961)	-50.00		

**Executive Engineer
R.W.D. (W) Division
Ranchi**


Scanned with OKEN Scanner

11. अनुमोदित परिमाण विषय की दर से कम उद्धृत दर वाले निविदाकार के लिए Additional Performance Guarantee का प्रावधान पथ निर्माण विभाग की अधिसूचना संख्या-447(एत) दिनांक-16.01.2020 एवं विभागीय पत्रांक-292 (अनु०), दिनांक-17.01.2020 के आलोक में एकराजनामा के पूर्व संबंधित कार्यपालक अभियंता अनिवार्यतः जमा कराना सुनिश्चित करेंगे।
12. संबंधित कार्यपालक अभियंता, ग्रामीण कार्य विभाग सफल निविदाकार को 24 घण्टे के अन्दर Letter of Acceptance (LOA) निर्गत करते हुए इसकी प्रति संबंधित अधीक्षण अभियंता, संबंधित मुख्य अभियंता, अपर मुख्य कार्यपालक पदाधिकारी-सह-सचिव, BRDA एवं अभियंता प्रमुख को उपलब्ध कराना सुनिश्चित करेंगे।



(आमीर नैय्यर)
आंतरिक वित्तीय सलाहकार,
ग्रामीण कार्य विभाग,
बिहार, पटना।


(जय किशोर ठाकुर)
मुख्य अभियंता-5 (मुजफ्फरपुर),
ग्रामीण कार्य विभाग।


(निर्मल कुमार)
अभियंता प्रमुख,
ग्रामीण कार्य विभाग,
बिहार, पटना।


(दीपक कुमार सिंह)
सरकार के अपर मुख्य सचिव,
ग्रामीण कार्य विभाग,
बिहार, पटना।


BHAGYASHREE NARAIN YADAV
Piprekotli (East Champaran)


Executive Engineer
R.W.D. (W) Division
Raxaul
29/8/25


29/8/25

**OFFICE OF THE EXECUTIVE ENGINEER,
RURAL WORKS DEPARTMENT, WORKS DIVISION, RAXAUL**

(Letter of Acceptance)

Latter No. :- 1245

Date:- 12-07-2025

To,

Bhagya Narayan Yadav
Vill Makari Mahuawa,
P.o- Piprakothi, P.s- Piprakothi,
Dist-East Champaran Pincode:-845429


Dear Sir,

This is to notify that your Bid Dated-27-05-2025 for execution of the Bhagya Narayan Yadav, Vill Makari Mahuawa, P.o- Piprakothi, P.s-Piprakothi, Dist-East Champaran, Pincode- 845429 (BID ID-616193) (name of the contract and Identification number, as given in the Instructions to Bidders) Package No.- MMGSY(AWSESH-SC)-RAXAUL-165 (Tender ID-141145) for the Contract Price of Rs. 29219167.00 (Two Crore Ninty Two Lakh Ninteen Thousand One Hundred and Sixty Seven Only) (amount in words and figures), as Corrected and modified* in accordance with the Instructions to Bidders is hereby accepted by our Agency.

We note that as per bid, you do not intend to subcontract any component of work.

You are hereby requested to furnish Performance Security including an additional security for unbalanced bids in term of ITB Clause 27.4, for an amount of Rs. 4388511.00 (Rupees Forty three Lakh Eighty-Eight Thousands Five Hundred and Eleven Only) within 21 days in accordance with the Conditions of Contract using for that purpose form in Section VIII annex-D and sign the contract, failing which action as stated in Para 34.2 of ITB will taken.

Yours faithfully


12/07/25
Executive Engineer,
Rural Works Department
Works Division, Raxaul

I Delete "corrected and" or "and modified" if only of these action applies. Delete "as corrected and modified in accordance with the Instructions to Bidders" if corrections or modification have not been effected.


BHAGYA NARAYAN YADAV
Piprakothi (East Champaran)


29/08


29/08/25
Executive Engineer
R.W.D. (W) Division
Raxaul
29/8/25

**OFFICE OF THE EXECUTIVE ENGINEER,
RURAL WORKS DEPARTMENT, WORKS DIVISION, RAXAUL**

Issue of Notice to proceed with work

Latter No. :- 1540

Date:- 29/08/2025

To,

Bhagya Narayan Yadav
Vill Makari Mahuawa,
P.o- Piprakothi, P.s- Piprakothi,
Dist-East Champaran Pincode:-845429


Dear Sirs,

Pursuant to your furnishing the requisite performance security as stipulated in ITB Clause and signing of the contract for the construction of **Package No.- MMGSY(AWSESH-SC)-RAXAUL-165 (Tender ID-141145)** and one year renewal coat and Six years routing maintenance after completion of construction, you are hereby instructed to proceed with the execution of the said works in accordance with the contract documents. The arrangement of quality Control Lab with all required equipment is establishment at work site.

Yours faithfully


BHAGYA NARAYAN YADAV
Piprakothi (East Champaran)


29/08


Executive Engineer,
Rural Works Department,
Works Division, Raxaul
29/8/25

Percentage BOQ

Tender Inviting Authority: Authority: Engineer -In-Chief-Additional Commissioner-cum-Special Secretary, RWD, Bihar, Patna

Name of Work:MMGSY(AWSESH-SC)-RAXAUL-165

Contract No:

Name of the

Bidder/

Bidding

Firm /

Company :

Bhagya Narayan Yadav

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT With Taxes in	TOTAL AMOUNT In Words
1	RWD Road To Ghamharia Khurd To Anushuchit Jati Kanunia					
2	Setting Out Pillars :- Providing & Fixing of Working benchmark Pillars 01 nos. per km & 04 Nos. of reference pillars required for 1 Km. as per drawings given and direction of E/I	2.53	Km	13462.13	34059.19	INR Thirty Four Thousand & Fifty Nine and Paise Nineteen Only
3	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation , grass ,bushes ,shrubs , saplings and trees of girth upto 300mm , removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification - clause 201.1 and direction of E/I (By Manual Means) In area of non-thorny jungle	0.42	Hect.	75360.38	31651.36	INR Thirty One Thousand Six Hundred & Fifty One and Paise Thirty Six Only
4	Cutting of Trees including Cutting of Trunks, Branches and Removal of Stumps Cutting of trees, including cutting of trunks, branches and removal of stumps & roots, refilling, compaction of backfilling and stacking of serviceable material by manual means with all lifts as per Technical Specification Clause 201.7					

[Signature]
BHAGYA NARAIN YADAV
Pipakothi (East Champaran)

[Signature]
29/05

Executive Engineer
R.W.D. (W) Division
Bakailu

5	Girth above 300 mm to 600 mm	4.00	Each	352.90	1411.60	INR One Thousand Four Hundred & Eleven and Paise Sixty Only
6	Girth above 600 mm to 900 mm	3.00	Each	611.21	1833.63	INR One Thousand Eight Hundred & Thirty Three and Paise Sixty Three
7	Removal of Telephone/Electric Poles and Lines Removal of telephone/electric poles with wires including excavation and dismantling of foundation concrete and lines under the supervision of concerned department, disposal with all lifts and upto a lead of 1000 m and stacking the serviceable and unserviceable material separately as per Technical Specification Clause 202.	4.00	No	246.41	985.64	INR Nine Hundred & Eighty Five and Paise Sixty Four Only
8	Box Cutting :- Excavation for roadway in soil using manual means for carrying of cut earth to embankment site with a lift upto 1.5 m and lead upto 50 m as per Technical Specification Clause 302.3	189.71	Cum	96.35	18278.56	INR Eighteen Thousand Two Hundred & Seventy Eight and Paise Fifty Six Only
9	Construction of Embankment with Material Obtained from Roadway Cutting Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5.	113.83	Cum	74.20	8446.19	INR Eight Thousand Four Hundred & Forty Six and Paise Nineteen Only
10	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 100 m as per Technical Specification Clause 301.5	2316.69	Cum	147.61	341966.61	INR Three Lakh Forty One Thousand Nine Hundred & Sixty Six and Paise Sixty One Only
11	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	2676.39	Cum	239.97	642253.31	INR Six Lakh Forty Two Thousand Two Hundred & Fifty Three and Paise Thirty One Only
12	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m & 100 m as per Technical Specification Clause 303.1. (Including Royalty & Labour Cess).	3061.41	Cum	243.24	744657.37	INR Seven Lakh Forty Four Thousand Six Hundred & Fifty Seven and Paise Thirty Seven Only


BHAGYA NARAIN YADAV
Piprahathi (East Champaran)


29/8/25

Executive Engineer
R.W.D. (W) Division
Raxaul

29/8/25

13	Granular Sub-base with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. (For Grading II Material)	763.91	Cum	2461.03	1880005.43	INR Eighteen Lakh Eighty Thousand & Five and Paise Forty Three Only
14	WBM Grading 2 :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per Technical Specification Clause 405.	354.71	Cum	5145.71	1825234.79	INR Eighteen Lakh Twenty Five Thousand Two Hundred & Thirty Four and Paise Seventy Nine Only
15	WMM :- Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100kN weight to achieve the desired density including lighting, barricading and maintenance of diversion, etc as per Tables 400.11 & 400.12 and Technical Specification Clause 406.	700.68	Cum	4147.60	2906140.37	INR Twenty Nine Lakh Six Thousand One Hundred & Forty and Paise Thirty Seven Only
16	Prime Coat (Low Porosity) :- Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0kg/sqm using mechanical means as per Technical Specification Clause 502	4729.50	Sqm	55.33	261683.24	INR Two Lakh Sixty One Thousand Six Hundred & Eighty Three and Paise Twenty Four Only
17	Tack Coat:- Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25-0.30kg per sqm on the prepared granular surfaces treated with primer & cleaned with Hydraulic broom as per Technical Specification Clause 503.	4729.50	Sqm	19.04	90049.68	INR Ninety Thousand & Forty Nine and Paise Sixty Eight Only

[Signature]
BHAGYA NARAIN YADAV
Pipakothi (East Champaran)

[Signature]
29/08

[Signature] 29/08/25
Executive Engineer
R.W.D. (W) Division
Raxaul
[Signature] 27/8/25

18	Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509	4729.50	Sqm	302.49	1430626.46	INR Fourteen Lakh Thirty Thousand Six Hundred & Twenty Six and Paise Forty Six Only
19	Construction of un-reinforced, plain cement concrete pavement (M35 Grade) over a prepared sub base with 43 grade cement @ 400 kg per cum, coarse and fine aggregate conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form paver, spread, compacted and finished in a continuous operation including provision of 0.5 x 0.5 panel, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures as approved, curing compound, finishing to lines and grades as per drawing	569.21	Cum	7753.51	4413375.43	INR Forty Four Lakh Thirteen Thousand Three Hundred & Seventy Five and Paise Forty Three Only
20	Laying brick soling layer on prepared sub-grade with brick on end edging according to lines, graded and cross-section shown on the drawing filling joints with sand and earth, spreading 25 mm thick layer of earth over brick soling, watering and rolling the same with three wheel road roller 80-100 kN as per Technical Specification Clause 412	749.70	Sqm	500.49	375217.35	INR Three Lakh Seventy Five Thousand Two Hundred & Seventeen and Paise Thirty Five Only
21	TRAFFIC SIGNS, MARKINGS & OTHER ROAD APPURTENANCES					
22	Kilometre Stone					
23	Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703					
24	Ordinary Kilometer Stone (Precast)	3.00	Each	2977.07	8931.21	INR Eight Thousand Nine Hundred Thirty One and Paise Twenty
25	200 m stone (precast)	11.00	Each	804.16	8845.76	INR Eight Thousand Eight Hundred & Forty Five and Paise Seven

[Signature]
AGENCY

BHAGYA NARAIN YADAV
Pipraikothi (East Champaran)

[Signature]
29/08/25

Executive Engineer
R.W.D. (W) Division

[Signature]
29/08/25

26	(i) Providing and Fixing 'Logo' of PMGSY Project :- Providing and fixing of typical PMGSY Informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	4.00	Each	11035.87	44143.48	INR Forty Four Thousand One Hundred & Forty Three and Paise Forty Eight Only
27	Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701	396.00	per cm height	0.74	293.04	INR Two Hundred & Ninety Three and Paise Four Only
28	Boundary Pillar/Gaurd Post :- Reinforced cement concrete M15 grade boundary pillars/focal stone of standard design as per IRC:25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	156.00	No	704.69	109931.64	INR One Lakh Nine Thousand Nine Hundred & Thirty One and Paise Sixty Four Only
29	Rumble Strips : Provision of 15 nos rumble strips covered with premix bituminous carpet, 15-20 mm high at center, 250 mm wide placed at 1 m center to center at approved locations to control speed, marked with white strips of road marking paint.	10.13	Sqm	1080.89	10949.42	INR Ten Thousand Nine Hundred & Forty Nine and Paise Forty Two Only
30	Traffic Signs :- Providing and fixing of Retro reflective cautionary, mandatory and informatory sign board as per IRC :67 made of 1.5 mm thick MS steel duly stove white colour in front and gray colour on back with red reflective border of 65 mm width and required letters and figures with reflective tape engineering grade as per clause 1701.3.9 of MORD for rural road of required shade and colour supported and welded on 47mmx47mmx12swg sheet tube firmly fixed to the ground by mean of properly designed foundation with M15 grade cement concrete 450x450x600 mm, 600mm below ground level as per approved drawing clause 1701.2.2.					
31	600 mm equilateral & triangle, OR	11.00	Each	3999.17	43990.87	INR Forty Three Thousand Nine Hundred & Ninety and Paise Eighty

29/08

Executive Engineer
R.W.D. (W) Division

Raxaul 29/8/25

AGENCY
BHAGYA NARAIN YADAV
Pipraithi (East Champaran)

32	600 mm circular, OR	14.00	Each	5339.94	74759.16	INR Seventy Four Thousand Seven Hundred & Fifty Nine and Paise
33	600 mm x 450 mm rectangular, OR	7.00	Each	5202.70	36418.90	INR Thirty Six Thousand Four Hundred & Eighteen and Paise
34	900 mm side octagon, OR	2.00	Each	9446.72	18893.44	INR Eighteen Thousand Eight Hundred & Ninety Three and Paise
35	Hazard Board (900 mm x 300 mm)	44.00	Each	5202.70	228918.80	INR Two Lakh Twenty Eight Thousand Nine Hundred & Eighteen
36	Chevron Sign Boards, (Size: 600mm x 500mm)	36.00	Each	5519.42	198699.12	INR One Lakh Ninety Eight Thousand Six Hundred & Ninety Nine
37	Road Marking with Hot Applied Thermoplastic Compound with Reflectorisng Glass Beads on Concrete Surface :- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorisng glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes.	294.00	Sqm	879.72	258637.68	INR Two Lakh Fifty Eight Thousand Six Hundred & Thirty Seven and Paise Sixty Eight Only
38	Road Marking with Hot Applied Thermoplastic Compound with Reflectorisng Glass Beads on Bituminous Surface :- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorisng glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes.	212.00	Sqm	778.40	165020.80	INR One Lakh Sixty Five Thousand & Twenty and Paise Eighty Only
39	Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year	42.00	Each	1248.07	52418.94	INR Fifty Two Thousand Four Hundred & Eighteen and Paise Ninety Four Only
40	Cross Drainage Works					
41	Irrigation Pipe (300MM Dia)					

[Signature]
 AGENT
BHAGYA NARAIN YADAV
 Piprakothi (East Champaran)

[Signature]
 29/08

[Signature]
 29/08/25
 Raxaul
 29/08/25
 Raxaul (W) Division

42	Providing and laying of a reinforced cement concrete pipe duct, 300 mm dia, across the road (new construction), extending from drain to drain in cuts and toe of slope to toe of slope in fills, constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC:981997, bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC: 98 - 1997 and approved drawings.	80.00	RM	1066.81	85344.80	INR Eighty Five Thousand Three Hundred & Forty Four and Paise Eighty Only
43	Dismant					
44	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 m as per Technical Specification Clause 202.					
45	Cement Concrete	17.70	Cum	670.71	11871.57	INR Eleven Thousand Eight Hundred & Seventy One and Paise
46	Reinforced Cement Concrete	27.99	Cum	1697.74	47519.74	INR Forty Seven Thousand Five Hundred & Nineteen and Paise
47	Dismantling of existing structures like culverts, bridges, retaining walls and other structures comprising of brick masonry, including disposal of unserviceable material and stacking the serviceable material with all lift and lead of 1000 m as per Technical Specification Clause 202.					
48	Cement mortar	214.12	Cum	307.62	65867.59	INR Sixty Five Thousand Eight Hundred & Sixty Seven and Paise
49	Removing all types of Hume pipes and stacking including Earthwork and Dismantling of Masonry Works as per Technical Specification Clause 202.					
50	Above 600 mm to 900 mm dia Hume pipe	7.50	RM	349.05	2617.88	INR Two Thousand Six Hundred & Seventeen and Paise Eighty Eight
51	Box Culverts					
52	Foundation					

[Signature]
 BHAGYA NARAIN YADAV
 Piprahothi (East Champaran)

[Signature]
 29/8/25

[Signature]
 29/8/25
 R.W.D. (W) Division
 Raxaul

53	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material.	493.57	Cum	80.87	39915.01	INR Thirty Nine Thousand Nine Hundred & Fifteen and Paise One Only
54	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-15 Grade	61.57	Cum	7401.58	455715.28	INR Four Lakh Fifty Five Thousand Seven Hundred & Fifteen and Paise Twenty Eight Only
55	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-20 Grade	181.32	Cum	8027.57	1455558.99	INR Fourteen Lakh Fifty Five Thousand Five Hundred & Fifty Eight and Paise Ninety Nine Only
56	Supplying, fitting and placing HYSD bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202	1.02	MT	66393.54	67721.41	INR Sixty Seven Thousand Seven Hundred & Twenty One and Paise Forty One Only
57	Sub Structure					
58	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 PCC M-20 Grade	114.75	Cum	8300.42	952473.20	INR Nine Lakh Fifty Two Thousand Four Hundred & Seventy Three and Paise Twenty Only
59	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7	270.00	Nos	134.49	36312.30	INR Thirty Six Thousand Three Hundred & Twelve and Paise Thirty Only
60	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 RCC M-25 Grade	136.28	Cum	8854.48	1206688.53	INR Twelve Lakh Six Thousand Six Hundred & Eighty Eight and Paise Fifty Three Only
61	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202	12.26	MT	66601.74	816537.33	INR Eight Lakh Sixteen Thousand Five Hundred & Thirty Seven and Paise Thirty Three Only
62	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 (With Sandy Materials)	253.66	Cum	913.96	231835.09	INR Two Lakh Thirty One Thousand Eight Hundred & Thirty Five and Paise Nine Only
63	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8	157.05	Cum	3878.65	609141.98	INR Six Lakh Nine Thousand One Hundred & Forty One and Paise Ninety Eight Only
64	Superstructure					


BHAGYA NARAIN YADAV
 Piprakothi (East Chaurpura)


Executive Engineer
 R.W.D. (W) Division
 Raigarh

29/08/25
 29/08/25

65	Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 RCC M-30 Grade	66.64	Cum	9526.20	634825.97	INR Six Lakh Thirty Four Thousand Eight Hundred & Twenty Five and Paise Ninety Seven Only
66	Supplying, fitting, and placing HYSD bar reinforcement in superstructure complete as per drawing and technical specifications Clauses 1002, 1010 and 1202	6.41	MT	68118.39	436638.88	INR Four Lakh Thirty Six Thousand Six Hundred & Thirty Eight and Paise Eighty Eight Only
67	Parapet Construction Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 (M25)	12.14	Cum	9293.02	112817.26	INR One Lakh Twelve Thousand Eight Hundred & Seventeen and Paise Twenty Six Only
68	Painting on Parapet Wall (Black & White Strips) Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	86.72	Sqm	129.57	11236.31	INR Eleven Thousand Two Hundred & Thirty Six and Paise Thirty One Only
69	Drainage spouts complete as per drawing and technical specifications Clause 1209	28.00	Nos	927.82	25978.96	INR Twenty Five Thousand Nine Hundred & Seventy Eight and Paise
70	Approach slab(M 30) : Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 RCC M-30 Grade	14.07	Cum	12932.12	181954.93	INR One Lakh Eighty One Thousand Nine Hundred & Fifty Four and Paise Ninety Three Only
71	PCC (M15) (Below Approach Slab) : PCC M15 Ordinary grade (1:2.5:5) levelling course below approach slab complete as per drawing and technical specifications clauses 800 and 1211.	7.04	CUM	7473.76	52615.27	INR Fifty Two Thousand Six Hundred & Fifteen and Paise Twenty Seven Only
72	Protection work					
73	Earth work in excavation for foundation of structures upto 3.0 m depth as per drawing and technical specification clause 1104	112.22	Cum	80.87	9075.23	INR Nine Thousand & Seventy Five and Paise Twenty Three Only
74	Providing and laying boulder apron for bed protection with stone boulders of minimum size and weight as per Table 1300.1, no fragment weighing less than 25 kg laid dry complete as per drawing and technical specifications Clause 1301	27.60	Cum	4006.58	110581.61	INR One Lakh Ten Thousand Five Hundred & Eighty One and Paise Sixty One Only
75	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-15 Grade Curtain wall	5.60	Cum	7401.58	41448.85	INR Forty One Thousand Four Hundred & Forty Eight and Paise Eighty Five Only
76	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-20 Grade	34.12	Cum	8027.57	273900.69	INR Two Lakh Seventy Three Thousand Nine Hundred and Paise Sixty Nine Only
77	Hume Pipe Culverts(1000 mm)					
78	Earth work in excavation for foundation of structures upto 3.0 m depth as per drawing and technical specification clause 1104	49.64	Cum	80.87	4014.39	INR Four Thousand & Fourteen and Paise Thirty Nine Only

Executive Engineer
R.W.D. (W) Division
Bhagalpur

BHAGYA NARAIN YADAV
Pipakali (East Changanj)

79	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-15 Grade	6.53	Cum	7401.58	48332.32	INR Forty Eight Thousand Three Hundred & Thirty Two and Paise Thirty Two Only
80	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 ans 1204 (M20 (PCC 1:2.5:5))	27.68	Cum	8300.42	229755.63	INR Two Lakh Twenty Nine Thousand Seven Hundred & Fifty Five and Paise Sixty Three Only
81	Providing and laying RCC pipe NP-3 for culverts on first class bedding of PCC M10 material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling concrete and masonry works in head walls and parapets as per clause 1106 - 1000 mm Dia Pipe	7.50	RM	7838.55	58789.13	INR Fifty Eight Thousand Seven Hundred & Eighty Nine and Paise Thirteen Only
82	Painting on Parapet Wall (Black & White Strips) Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	20.64	Sqm	129.57	2674.32	INR Two Thousand Six Hundred & Seventy Four and Paise Thirty Two Only
83	Hume Pipe Culverts(600 mm)					
84	Earth work in excavation for foundation of structures upto 3.0 m depth as per drawing and technical specification clause 1104	33.39	cum	174.02	5810.53	INR Five Thousand Eight Hundred & Ten and Paise Fifty Three Only
85	Providing M15 (PCC 1:2.5:5) as levelling course in foundation :- Providing PCC M 15 (1:2.5:5) concrete for plain concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	7.10	cum	7401.58	52551.22	INR Fifty Two Thousand Five Hundred & Fifty One and Paise Twenty Two Only
86	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 ans 1204 (M15 (PCC 1:2.5:5))	30.33	cum	7963.18	241523.25	INR Two Lakh Forty One Thousand Five Hundred & Twenty Three and Paise Twenty Five Only
87	Providing and laying RCC pipe NP-3 for culverts on first class bedding of PCC M10 material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling concrete and masonry works in head walls and parapets as per clause 1106	20.00	m	3306.81	66136.20	INR Sixty Six Thousand One Hundred & Thirty Six and Paise Twenty Only
88	Painting on Parapet Wall (Black & White Strips) Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	24.96	Sqm	129.57	3234.07	INR Three Thousand Two Hundred & Thirty Four and Paise Seven Only
89	Parapet Repair					
90	Parapet Construction Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 ans 1204 (M25)	6.24	Cum	9293.02	57988.44	INR Fifty Seven Thousand Nine Hundred & Eighty Eight and Paise Forty Four Only

[Signature] 29/08/25
Executive Engineer
R.W.D. (W) Division
Rajshahi

[Signature] 29/08

[Signature]
BHAGYA NARAIN YADAV
Pipraichhi (East Champaran)

91	Painting on Parapet Wall (Black & White Strips) Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	47.28	Sqm	129.57	6126.07	INR Six Thousand One Hundred & Twenty Six and Paise Seven Only
92	5TH YEAR PERIODIC RENEWAL					
93	Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydriloc broom as per technical specification clause 503.	4054.50	Sqm	19.04	77197.68	INR Seventy Seven Thousand One Hundred & Ninety Seven and Paise Sixty Eight Only
94	Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects.	101.36	Cum	13712.34	1389882.78	INR Thirteen Lakh Eighty Nine Thousand Eight Hundred & Eighty Two and Paise Seventy Eight Only
95	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes. (Flexible Pavement)	212.00	Sqm	778.40	165020.80	INR One Lakh Sixty Five Thousand & Twenty and Paise Eighty Only
96	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes. (Rigid Pavement)	294.00	Sqm	879.72	258637.68	INR Two Lakh Fifty Eight Thousand Six Hundred & Thirty Seven and Paise Sixty Eight Only
97	Add Labour @ 1% on Construction Cost (A) :-	1.00	RS	269125.97	269125.97	INR Two Lakh Sixty Nine Thousand One Hundred & Twenty Five and Paise Ninety Seven Only
98	Add 10% S.F on Basic Materials Cost :-	1.00	RS	391876.42	391876.42	INR Three Lakh Ninety One Thousand Eight Hundred & Seventy Six and Paise Forty Two Only
99	Add GST @ 18% on Sub Total Construction Cost (including 1% Labour Cess & 10% S.F):-	1.00	RS	4963247.81	4963247.81	INR Forty Nine Lakh Sixty Three Thousand Two Hundred & Forty Seven and Paise Eighty One Only
100	1st Year Maintenance cost	1.00	Year	355352.00	355352.00	INR Three Lakh Fifty Five Thousand Three Hundred & Fifty Two Only


BHAGYA NALIN YADAV
 Piprakothi (East Chaurjuran)

Executive Engineer
R.W.D. (W) Division
 Rajahmundry

101	2nd Year Maintenance cost	1.00	Year	407772.26	407772.26	INR Four Lakh Seven Thousand Seven Hundred & Seventy Two and Paise Twenty Six Only
102	3rd Year Maintenance cost	1.00	Year	410751.00	410751.00	INR Four Lakh Ten Thousand Seven Hundred & Fifty One Only
103	4th Year Maintenance cost	1.00	Year	474534.00	474534.00	INR Four Lakh Seventy Four Thousand Five Hundred & Thirty
104	6th Year Maintenance cost	1.00	Year	285908.00	285908.00	INR Two Lakh Eighty Five Thousand Nine Hundred & Eight Only
105	7th Year Maintenance cost	1.00	Year	297227.00	297227.00	INR Two Lakh Ninety Seven Thousand Two Hundred & Twenty
106	Add Labour @ 1% on Maintenance Cost (A) :-	1.00	RS	22315.44	22315.44	INR Twenty Two Thousand Three Hundred & Fifteen and Paise Forty
107	Add 10% S.F on Basic Materials Cost :-	1.00	RS	27865.30	27865.30	INR Twenty Seven Thousand Eight Hundred & Sixty Five and Paise
108	Add GST @ 18% on Sub Total Maintenance Cost (Including 1% Labour Cess & 10% S.F):-	1.00	RS	410710.50	410710.50	INR Four Lakh Ten Thousand Seven Hundred & Ten and Paise Fifty Only
Total in Figures					35229283.34	INR Three Crore Fifty Two Lakh Twenty Nine Thousand Two Hundred & Eighty Three and Paise Thirty
Quoted Rate in Figures			Less ()	17.06%	29219168.00	INR Two Crore Ninety Two Lakh Nineteen Thousand One Hundred & Sixty Six Only
Quoted Rate in Words		INR Two Crore Ninety Two Lakh Nineteen Thousand One Hundred & Sixty Seven and				

[Signature]
BHAGYA NARAIN YADAV
Piprahothi (East Champaran)

[Signature]
Executive Engineer
R.W.D. (W) Division
Raxaul
27/01/25

[Signature]
27/01/25

**GOVERNMENT OF BIHAR
RURAL WORKS DEPARTMENT**

Office of the Engineer-in-Chief,
Rural Works Department, Bihar
5th floor, Visvesvaraya Bhawan, Nehru Path, Patna-800015

DETAILED NOTICE INVITING TENDER (through e-procurement mode only
<http://pmgsytendersbih.gov.in>)


for Construction and 06 year Routine Maintenance work (output and performance based) for Rural Road/Bridge under component of Mukhya Mantri Gram Sampark Yojana (AWSESH-SC).
Notice Inviting Tender: (No.-RWD/MMGSY(AWSESH-SC)/HQ/ET/2025-26/04)

1. Designation and Address of the Advertiser : Engineer-in-chief,
Rural Works Department, Govt. of Bihar
2. Date of Notice Inviting Tender : 02.05.2025
3. Period for download of Tender Document : From 19.05.2025 to 28.05.2025 up to 1500 hrs
4. Date, Time & Place of Pre-Bid meeting : Date 20.05.2025 at Concerned office of SE from 1100 hrs
5. Last Date & Time for uploading tender documents by bidder : Date 28.05.2025 till 1500 hrs.
<http://pmgsytendersbih.gov.in>
6. Date and time of opening of Technical Bid : Date 28.05.2025 Time 1530 hrs.
7. (i) Bid Security (EMD) and cost of BOQ shall be submitted Online. No other forms of Earnest Money (Bid Security) and cost of BOQ will be accepted. The Earnest Money deposited by the non-responsive bidder will be automatically refunded. In case the bid of non-responsive bidder is reconsidered whose EMD has been refunded automatically, will be collected and refunded manually in the shape of Fixed Deposit Receipt.
(ii) Bidders are required to upload an Affidavit regarding correctness of Information furnished with bid document. Original Affidavit regarding correctness of Information furnished with Bid document shall be submitted at the time of signing of agreement.
8. The Engineer-in-chief-cum-Additional Commissioner-cum-Special Secretary / Engineer-in-chief, Rural Works Department on behalf of Governor of Bihar invites bids for the works detailed below.

Project Scope & Duration:

- I. To undertake Construction and 06 years Routine Maintenance work (output and performance based) for Rural Road/Bridge for a period of 72 months under component of Mukhya Mantri Gram Sampark Yojana (AWSESH) on selected roads as described in para 9.
- II. Construction of road/bridge may include road safety measures, tree plantation at the end of slope of road within Right of Way, as per contract document. The time of completion for Construction of road/bridge, road safety measures, tree plantation shall be of total 12 months and for Routine Maintenance work (output and performance based) shall be of total 72 months. The total time to be given to the contractor for completing Construction of road/bridge, road safety measures, tree plantation and 06 years Routine Maintenance work (output and performance based) will be 72 months from the date of agreement.
- III. During 06 years Routine Maintenance work (output and performance based), the roads/bridges will be kept as per prescribed service level, to maintain road for traffic worthy. The Maintenance work (output and performance based) will also include cross drainage works, minor works on bridges and roads.
- IV. The Routine Maintenance work will be carried out under output and performance based for which the payment will be done quarterly.
- V. For Rapid Response of Routine Maintenance work each bidder must have a Rapid Road Repair Vehicle.


BHAGWATI NARAIN YADAV
Piprahata (East Champaran)


Executive Engineer
RWD. (W) Division
Raxaul

2025/05/02
RWD (W) Division
Patna

22/05

बिहार सरकार
ग्रामीण कार्य विभाग

पत्रांक-BRRDA(HQ)-MMGSY-152/25 - 804

/पटना, दिनांक-28/2/25

प्रेषक,

संजय कुमार, सहायक
संयुक्त सचिव,
ग्रामीण कार्य विभाग।

सेवा में,

महालेखाकार (लेखा एवं हकदारी),
बिहार, पटना।

विषय : योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परियोजना उप मुख्य शीर्ष-00-लघु शीर्ष-789-अनुसूचित जातियों के लिए विशेष घटक योजना-उप शीर्ष-0108 मुख्यमंत्री ग्राम संपर्क योजना (अवशेष), विपन्न कोष संख्या-37-4515-00-789-0108 के अन्तर्गत वित्तीय वर्ष 2025-26 के लिए बिहार राज्य के विभिन्न जिलों में संलग्न सूची के अनुसार कुल 820 अदद योजनाओं का निर्माण कार्य सन्निहित है। प्रत्येक योजना के लिए निर्माण (नये सतहीकरण कार्य सहित) एवं छः वर्षीय सतत् अनुरक्षण कार्य हेतु संलग्न सूची के स्तम्भ-15 में अंकित राशि के अनुरूप कुल राशि ₹107700.977 लाख (एक हजार सतहत्तर करोड़ सत्तानवे हजार सात सौ) मात्र की राशि के प्रशासनिक स्वीकृति प्रदान किये जाने के संबंध में।

महाराज,

मुख्यमंत्री ग्राम संपर्क योजना (अवशेष-अनुसूचित जाति) अन्तर्गत विभिन्न कार्य प्रमंडलों के अधीन वित्तीय वर्ष 2025-26 के लिए बिहार राज्य के विभिन्न जिलों में संलग्न सूची के अनुसार 820 (छः सौ बीस) अदद योजनाओं के निर्माण कार्य सन्निहित है। प्रत्येक योजना के लिए संलग्न सूची के स्तम्भ-10 में अंकित लम्बाई के निर्माण कार्य (नये सतहीकरण कार्य सहित) एवं छः वर्षीय सतत् अनुरक्षण कार्य हेतु अलग-अलग योजनाओं के लिए संलग्न सूची के स्तम्भ-15 में अंकित राशि के अनुरूप प्रशासनिक अनुमोदन प्रदान किया जाता है। प्रशासनिक स्वीकृति की कुल राशि ₹107700.977 लाख (एक हजार सतहत्तर करोड़ सत्तानवे हजार सात सौ) मात्र होता है।

2. विभागीय अपर मुख्य सचिव द्वारा दिनांक-28.04.25 को निम्न शर्तों के साथ इन योजनाओं की स्वीकृति प्रदान की गई है :-

- I. ब्राड के लिए निर्धारित प्रावधान/प्रक्रिया के आलोक में बजट प्रावधान के अंतर्गत राशि की निकासी की जायेगी।
- II. कार्यपालक अभियंता (PIU)का दायित्व होगा कि कार्यों को विशिष्टताओं/विशिष्टि के अनुरूप कार्यान्वित कराकर एकरारनामा एवं सुसंगत वित्तीय प्रावधानों के पालन उपरान्त पूर्णतः संतुष्ट होकर ही राशि की निकासी एवं व्यय करेंगे।
- III. इन योजनाओं के निर्माण एवं नये सतहीकरण कार्य (Road Edge Marking सहित) का भुगतान योजना शीर्ष-4515 एवं सतत् अनुरक्षण कार्य की राशि गैर योजना मद शीर्ष-3054 से भारित किया जायेगा।
- IV. प्रावधान की विशिष्टताओं के अनुसार निर्धारित समयावधि के अन्दर कार्य पूर्ण कराना सुनिश्चित किया जायेगा।
- V. योजना के कार्यान्वयन के क्रम में इनका निर्धारित निरीक्षण सरकार से निर्गत आदेशों में प्रावधानित सक्षम नियंत्री पदाधिकारियों द्वारा नियमित अंतराल पर अनिवार्य रूप से किया जायेगा तथा प्रतिवेदन अभिलेखित किया जायेगा।


EXECUTIVE ENGINEER
R.W.D. (W) Division
Patna

Executive Engineer
R.W.D. (W) Division
Patna

