



893
~~बिहार BIHAR~~

PAN- AAIIT5445L
Reg. - 1190066
GST No-10AAIIT5445L1Z

AZ 613114

AGREEMENT

रजिस्ट्री कचहरी, गोपालगंज^{लाइन-18/80}
Work has been allotted by Engineer-In-Chief-cum-Addl. Commissioner-cum-Spl. Secretary, RWD
Bihar Patna, vide letter no. 1523 dt. 01.07.2025

Below 20.21% on BOQ Rate

1. Agreement No.- 15./CMBD/2025-26
2. Estimated Cost Rs. 3,87,95,293.00 (Three crore eighty seven lac ninety five thousand two hundred ninety three only.)
3. Agreement value:- 3,09,54,765.00 (Three crore nine lac fifty four thousand seven hundred sixty five only)
4. Performance security Rs. 60.760 Lac. in shape of BG
5. Date of commencement of work: 03.07.2025
6. Date of completion of work: 02.07.2026

This agreement, made the..... 08..... day of July, 2025 Between Executive Engineer, R.W.D. Works Division, Hathua, of the one part, and M/s Tiwari Construction, At- Makshudpur, Post-Sasamusa, Distt- Gopalganj. Where as the Employer is desirous that Contractor execute Construction of Road and CD Works MMGSY(Awsesh-SC)/Hathua-170, Under- MMGSY(Awsesh-SC), Length-(3.450 k.m.) and the employer has accepted the bid by the contractor for the execution and completion of such works and the remedying of any defects there in at Contract Price of Rupees 3,09,54,765.00 (Three crore nine lac fifty four thousand seven hundred sixty five only). Construction Cost Rs. 2,60,01,849.00 (Two crore sixty lac one thousand eight hundred fifty nine) only. + Renewable Coat Cost Rs. 30,08,141.00 (Thirty lac eight thousand one hundred forty one) only + Maintenance cost Rs. 19,44,775.00 (Ninety lac forty four thousand seven hundred seventy five) only.

Sl. No.	Name of Road	Length (in km.)	Construction Cost	Renewable Coat Cost	Maintenance Cost	Total Cost.
1	PMGSY Road Near Dhalampur to Bhore Kataiya RCD Road.	2.150	15957937.00	2188025.00	1362017.00	19507979.00
2	Bhore Kataiya Road to Belwa Mishir	1.300	10043912.00	820116.00	582758.00	11446786.00
		3.450	26001849.00	3008141.00	1944775.00	30954765.00

M/s TIWARI CONSTRUCTION

Send new time

Partner

103
08.7.25

Ch. S. D. S. S.
Executive Engineer
R.M.D. Works Division
Hathua

NOW THIS AGREEMENT WITNESSETH AS FOLLOWS

1. In this Agreement, words and expression shall have the same meanings as are respectively as are respectively assigned to them in the condition of contract here in after referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the employer to the contractor as here in after mentioned, the contractor the works and remedy any defects there in conformity in all aspects with the provision of the contract.
3. The Employer here by covenants to pay contractor in consideration of the execution of the execution and completion of the works and the remedying the defects where in the contract price of such other sum as may become payable under the provisions the contract.
4. The following documents shall be deemed to form and be read and construct as part of this Agreement, Viz:-
 - I. Letter of Acceptance
 - II. Notice to proceed with the works
 - III. Contractor's Bid
 - IV. Contract Data
 - V. Special conditions of contract and general conditions of contract
 - VI. Specifications
 - VII. Drawings
 - VIII. Any other document listed in the contract date as forming part of the contract.

In witness where of the parties there to have caused this Agreement to be executed the day and year first before written.

The common seal of.....

In the presence of:-

Binding signature of employer..... M/s. TIWARI & HATHUA.....

Binding signature of contractor Sunit Kumar Tiwari


Executive Engineer

R.W.D. Works Division


Partner

Agreement on 20.21 % Below on B.O.Q. Rate SYNOPSIS OF AGREEMENT

Name of Works :- **Construction of Road and C.D. Works from MMGSY(Awsesh-SC)/Hathua-170, Under- MMGSY(Awsesh-SC), Length-(3.450 k.m.)**

Estimated Cost. : **3,87,95,293.00**

1. Ref. of NIT/PRNo. : **002641(RWD)-2025-26**
2. Agreement Value : **3,09,54,765.00 (Below 20.21%)**
3. Date of Tender : **28.05.2025**
4. Details of Earnest Money : **60.760 Lac. in shape of BG**
5. Date of Works Order : **03.07.2025**
6. Date of Completion : **02.07.2026**
7. Actual Date of Completion :
8. No. of Items Tender for : **84 Nos, & 84 Nos**

08/07/25
D.A.O.

R.W.D. Works Division
Hathua

08/07/25
Executive Engineer
R.W.D. Works Division
Hathua.

M/s TIWARI CONSTRUCTION
Suresh Tiwari
Partner